



Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:-[ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

NO:PWD/BN/TA/NIT/2025-26/- 20366-71  
To

Dated:-21.02.2026

The Executive Engineer, (IT Cell)  
Nirman Bhawan Nigam Vihar,  
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental Website.


Dear sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting Tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.


Encl: Notice Inviting Tender  
& Schedule of Quantity.

Yours faithfully,

  
Executive Engineer,  
Baijnath Division,  
HPPWD., Baijnath.

**Copy forwarded for information to:-**

1. The Superintending Engineer, JNR. Circle HPPWD., Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

  
Executive Engineer,  
Baijnath Division,  
HPPWD., Baijnath.



Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:-[ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

**"NOTICE INVITING TENDER"**

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **09.03.2026** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **07.03.2026** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **06.03.2026 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Preparation of Detailed estimate for Construction of Road from Utrala to Surahi Pass km 0/00-32/600 Stage-I (C/O road portion 13/00-19/00 i/c Bridge over Binwa Khad) (SH: Formation Cutting, R/wall, CD works, Kharanja Soling, Side drain, Road Safety Measures, Road Furniture and Bio Engineering km 13/00-19/00)	80,000/-	1,600/-	Rs.350/-	One Month
2	Reconstruction/Restoration of Baijnath Chobin Balander Road km 0/00 to 14/00 (Under OFC) (SH: Providing and laying Thermoplastic strip)	96,846/-	2,000/-	Rs.350/-	One Month
3	Restoration of rain damage on Barot to Nalhota road km 0/00 to 15/00 (SH: Maintenance of Earthen Shoulders b/w km 5/200 to 6/150 & 11/500 to 12/200)	99,000/-	2,000/-	Rs.350/-	One Month
4	Restoration of rain damages on various roads under Multhan Section (SH: Hiring of Hydraulic Excavator/JCB for removal of Snow/Slips dressing of road berms, filling depressions, clearance of drain and culvert)	99,000/-	2,000/-	Rs.350/-	One Month
5	Restoration of rain damage on Link road to Village Kuni Road km 0/00 to 1/600 (SH: C/O R/wall at RD 0/879.20 to 0/890.20 and 0/893 to 0/897)	98,514/-	2,000/-	Rs.350/-	Two-Months

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an undertaking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Baijnath Division.,  
H.P.PWD.,Baijnath.

For & On behalf of the governor of H.P.

**SCHEDULE OF QUANTITY**

1

Description of work	Qty	Unit	Rate		Estimated Cost- Earnest Money: -	One Month AMOUNT Rs. P
			Figure	Words		
<p>Work: Preparation of Detailed estimate for Construction of Road from Utrala to Surahi Pass Km 0/00-32/600 Stage-I (C/O road Portion 13/00-19/00 i/c Bridge over Binwa Khad )</p> <p>Information Cutting, R/wall, CD works, Kharanja Soling ,Side Drain ,Road Safety measures , road Furniture and Bio Engineering Km 13/00-19/00)</p>	1.000	Each	80000.00	Rupees Eighty Thousand Only	80000.00 1600.00	
<b>Total:-</b>						
Estimated rates Percentage in figures						80000.00
Estimated rates Percentage in words						

  
 Executive Engineer  
 Bajjnath Division  
 HPPWD Bajjnath

## SCHEDULE OF QUANTITY

Name of Work :- Reconstruction/ Restoration of Bajjnath Chobin Balandar Road km 0/00 to 14/000 ( under OFC.)  
(Sh.-Providing and laying Thermoplastic strip )

Estimate Cost: 96,846.00  
Earnest Money: 2,000.00  
Time Limit : One Month

2

### SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Road marking with hot applied thermoplastic compound with relectorising glass baord on bitumenous surface. Profviding and laying of hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @ 250 gms/sqm area thickness of 2.5mm is exelusive of surface applied glass beads as per IRC:35. The finished surface to be uniform and free from streaks and holes.complete in all respects as per the direction and entire satisfaction of Engineer-In Charge."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	122.25	Per Square meter	792.20	Rupees Seven Hundred Ninety Two And Paise Twenty Only	96,846.00
	<b>Quoted Percentage</b>					<b>96,846.00</b>

  
 Executive Engineer  
 Bajjnath Division  
 HPPWD Bajjnath

**SCHEDULE OF QUANTITY**

Estimate Cost: 99000.00  
 Earnest Money: 2000.00  
 Time Limit : One Month

Work: - Restoration of Rain Damage on Barot to Nalhota Road km 0/00 to 15/00 .  
 maintenance of Earthan Shoulders b/w km 5/200 to 6/150 & 11/500 to 12/200 )

**SCHEDULE OF WORKS**

Description of work	No.or Qty.	Unit	Rate to be entered by the		AMOUNT Rs. P
			Figures	Words	
Maintenance of Earthan Shoulders( Filling with fresh selected soil ) Making Uploss of material /irruglarties shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 ."The rate quoted shall deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, any other tax as applicable and imposed by the Government from time to time."	2475.00	Per Sqm	40.00	Rupees Forty Only	99,000.00
Estimated rates Percentage in figures					
Estimated rates Percentage in words					

Executive Engineer  
 Bajjnath Division  
 HPPWD Bajjnath

4

**SCHEDULE OF QUANTITY**

Name of Work:-Restoration of Rain Damages on various roads under Multhan Section  
 Estimated Cost:- Rs 99,000.00  
 Earnest Money:- Rs 2,000.00  
 (SH:Hiring of Hydraulic Excavator/JCB for removal of Snow/ slips dressing of road berms ,filling depressions ,  
 clearance of drain and culvert)

SR. No.	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				In Figure	Figures	
1	Hiring of Hydraulic Excavator/JCB cum loader having capacity of 0.9 Cum (zero point nine cubic meter ) in working condition urgently required for removal of snow , slips Boulder and debris etc from road surface upto any height , depth and lead including slips, boulders in all kind and classification of soil including rocky portion and saturated soil due to non-availability of departmental machinery any loss to the public/ private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of the JCB/ Excavator owner which shall have to be fully compensated by the contractor in all cases.it should be ensure that the output of machine should not be less than 20 cum per hour The fuel and operational staff for JCB/ Excavator shall be borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in charge. The rates are inclusive all taxes levy by the govt time to time including GST .	90.00	Per hour	1100.00	Rupees Eleven hundred only	99000.00
<b>Total:-</b>						<b>99000.00</b>
Quated rates Percentage in figures						
Quated rates Percentage in words						

Executive Engineer  
 Bajjnath Division  
 HPPWD Bajjnath

5

**SCHEDULE OF QUANTITY**

Name of work : Restoration of Rain Damage on Link Road to Village Kumi Road km 0/00 to 1/600.  
(SH: C/O R/wall at RD 0/879.20 to 0/890.20 and 0/893 to 0/897 ) .

Estimate Cost: 98,514.00/-  
Earnest Money: 2,000.00/-  
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.16	Per Cum	290.00	Rupees Two Hundred & Ninety Only	916.00
2	Providing and laying cement concrete 1:5:10(one cement five sand,ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size ) plums and curing complete including the cost of form work in <b>Retaining walls Breast walls</b> , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MOR.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge. including carriage of material within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	13.90	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	68,805.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.49	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	5,435.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	7.00	Each	290.00	Rupees Two Hundred & Ninety Only	2,030.00
5	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 ( M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogramme) per cubic metre in or under water including curing complete including pumping or bailing out water. dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.44	Per Cubic metre	6200.00	Rupees Six Thousand Two Hundred Only	21,328.00
<b>Quoted rates Percentage in Figures</b>						
<b>Quoted rates Percentage in words</b>						
<b>Total</b>						<b>98,514.00</b>

Executive Engineer  
Bajjnath Division  
HPPWD Bajjnath