



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/- 20358 - 63 Dated:-21.02.2026
To

The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental website.


Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.


Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.


Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **07.03.2026** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **06.03.2026 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **05.03.2026 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Restoration/Reconstruction on Utrala to Surahi Pass Road km 0/00 to 32/00 (SH: Hiring of Hydraulic Excavator/JCB for removal of slips dressing of road berms, filling depressions, clearance of drain and culvert portion) P.D.N.A	4,98,300/-	10,000/-	Rs.350/-	One Month
2	Restoration/Reconstruction on Langhoo to Jamrella Road Km 0/00 to 4/500 (SH: C/O E/wall at RD 1/980 to 2/027.40) P.D.N.A-2023	4,99,875/-	10,000/-	Rs.350/-	Two Months
3	Restoration/Reconstruction on Gowal Tikker to Mahesh Garh km 0/00 3/380 (SH: C/O cause way at RD 1/210, 1/435, 1/535, 1/275 and C/O Toe wall, catch pit at RD 0/450, 0/780, 1/520)	4,62,605/-	9,300/-	Rs.350/-	Two Months

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an undertaking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.
For & On behalf of the governor of H.P.

1

SCHEDULE OF QUANTITY

Name of Work:- Restoration / Reconstruction on Utrala to Surahi Pass Road km 0/00 to 32/00 .
 (SH: Hiring of Hydraulic Excavator/JCB for removal of slips dressing of road berms , filling depressions , clearance of drain and culvert portion) P.D.N.A

Estimated Cost:- Rs 4,98,300.00
 Earnest Money:- Rs 10,000.00

SR. No.	Description of work	No. or Qty.	Unit	Time:-		AMOUNT Rs. P
				In Figure	Rate	
1	Hiring of Hydraulic Excavator/JCB cum loader having capacity of 0.9 Cum (zero point nine cubic meter) in working condition urgently required for removal of snow , slips Boulder and debris etc from road surface upto any height , depth and lead including slips, boulders in all kind and classification of soil including rocky porridge and saturated soil due to non-availability of departmental machinery any loss to the public private property or any accident etc. happened during the course of hiring period/-execution shall be the absolute responsibility of the JCB/ Excavator owner which shall have to be fully compensated by the contractor in all bases.it should be ensure that the output of machine should not be less than 20 cum per hour The fuel and operational staff for JCB/ Excavator shall be borne by the contractor/ owner. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	453.00	Per hour	1100.00	Rupees Eleven hundred only	498300.00
Total:-		4				498300.00
Quated rates Percentage in figures						
Quated rates Percentage in words						

Executive Engineer
 Bajinath Division
 HPPWD Bajinath

2

SCHEDULE OF QUANTITY

Name of work -Restoration / Reconstruction on Langhoo to Jamrella Road km 0/00 to 4/500 .
(SH: (SH-C/O E/wall at RD 1/980 TO 2/027.40) P.D.N.A-2023

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	34.84	Per Cum	290.00	Rupees Two Hundred & Ninety Only	10,104.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	85.70	Per cubic metre	5600.00	Rupees Five Thousand Six Hundred Only	4,79,920.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3 8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	9.95	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	9,851.00
	Total					4,99,875.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

Executive Engineer
Bajmath Division
HPPWD Bajmath

SCHEDULE OF QUANTITY

Name of work :- Restoration /Reconstruction on Gawal Tikker to Mahesh Garh km 0/00 to 3/380 (SH :- C/O cause way at RD 1/210 , 1/435 , 1/535 , 1/275 and C/O Toe wall , catch pit at RD 0/450 ,0/780, 1/520 .

**Estimate Cost:4,62,605.00/-
Earnest Money:9,300.00/-
Time Limit : Two Months**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	89.19	Cum	290.00	Rupees Two Hundred & Ninety Only	25,865.00

3 (b)

2	<p>Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	2.95	Per cubic metre	5600.00	Rupees Five Thousand Six Hundred Only	16,520.00
3	<p>Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water -including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	14.20	Per Cubic metre	6100.00	Rupees Six Thousand One Hundred Only	86,620.00

