

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-MDI(P)E-Tender-NIT/2025-26- 17922-28 Dated:- 28/2/26

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 11.03.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 10.03.2026 upto 12:00 Noon.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Barot Mayot road Km 0/00 to 7/960. (PDNA-2023) (SH:- Removal of slips in various RDs from Km 0/00 to 7/960)	4,55,555.48	9200/-	350/-	One month
2	Restoration of rain damages on Thaltukhod Marh road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/00 to 0/020)	2,68,900.10	5400/-	350/-	One month
3	Restoration of rain damages on Thaltukhod Marh road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/020 to 0/030)	2,61,170.47	5200/-	350/-	One month
4	Restoration of rain damages on Thaltukhod Graman road Km 0/00 to 4/500. (PDNA-2023) (SH:- Construction of Retaining wall at RD 2/600 to 2/612)	4,30,921.35	8700/-	350/-	One month
5	Restoration of rain damages on Ropa Droon road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Causeway at RD 1/640 to 1/676)	4,91,533.93	9900/-	350/-	One month
6	Restoration of rain damages on Ropa Droon road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Causeway at RD 2/720 to 2/746.20)	4,87,694.34	9800/-	350/-	One month
7	Restoration of rain damages on Silhbudhani Sudhar Kathog road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Causeway at RD 2/550 to 2/581.20)	4,99,513.18	10000/-	350/-	One month
8	Restoration of Rain damages on Balh to Ropa road Km 0/00 to 5/100. (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 4/418 to 4/418.75)	4,71,995.17	9400/-	350/-	One month
9	Restoration of Rain damages on Balh to Ropa road Km 0/00 to 5/100. (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 0/150 to 0/165)	3,99,164.50	8000/-	350/-	One month

10	Restoration of Rain damages on Ropa Kathog road Km 0/00 to 5/00. (PDNA-2023) (SH:- Providing & Laying Kharanja Stone Soling in various RD's in Km 0/00 to 5/00)	4,75,310.06	9500/-	350/-	One month
11	Restoration of Rain damages on Ropa Kathog road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 0/615 to 0/630)	4,01,329.20	8000/-	350/-	One month
12	Construction of road Tikkan to Silhbudhani Km 0/0 to 16/100. (SH:- Improvement of Blind Curve and Narrow reaches in Km 7/255 to 7/315)	99,710.46	2000/-	350/-	One month
13	Construction of road Tikkan to Silhbudhani Km 0/0 to 16/100. (SH:- Improvement of Blind Curve and Narrow reaches in Km 7/315 to 7/372)	99,630.46	2000/-	350/-	One month
14	Restoration of rain damages on Padhar Nahuli road Km 0/00 to 14/500 (PDNA-2023) (SH:- Construction of Retaining wall at RD 14/015 to 14/035)	4,27,488.18	8500/-	350/-	One month
15	Restoration of rain damages on Banogi Chehar Chella road Km 0/00 to 5/00. (PDNA-2023) (SH:- Construction of Breast wall at RD 2/480 to 2/495)	1,89,270.26	3800/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Mandi Division No. I,
HPPWD, at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

1

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 455555.48
Earnest Money Rs:- 9200.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
Name of work: - Restoration of rain damages on Barot Mayot road 0/00 to 7/960(PDNA-2023) (Sub-Head:- Removal of slips in various RD's from Km 0/00 to 7/960)
Contact No. :
Bidder Name:

SCHEDULE OF WORKS						
Sr. No	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes including GST in Rs. P.	Total Amount with all taxes Including GST in words
1	Removal of landslids/slip clearance,Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and road upto 1000 metre as per technical specification 302.3.5 and 1611, including loading in to tipper/trucks and disposed of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in -Charge.	3192.40	Per Cubic Metre	142.70	455555.48	Rupees Four Lakh Fifty Five Thousand Five Hundred Fifty Five and Paise Forty Eight Only
Total in figure :					455555.48	Rupees Four Lakh Fifty Five Thousand Five Hundred Fifty Five and Paise Forty
Total in Words :					Rupees Four Lakh Fifty Five Thousand Five Hundred Fifty Five and Paise Forty Eight Only	

Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar. *ga...*

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 268900.10
 Earnest Money Rs:- 5400.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.

Name of Work:- Restoration of rain damages on Thaltukhod Math road km. 0/00 to 5/00. (PDNA -2023) (Sub Head:- Construction of Retaining wall at RD Km 0/00 to 0/020).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	22.60	Per cubic metre	491.80	11114.68	Rupees Eleven Thousand One Hundred Fourteen and Paise Sixty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	48.19	Per cubic metre	4870.50	234709.40	Rupees Two Lakh Thirty Four Thousand Seven Hundred Nine and Paise Thirty Nine Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	16.00	Each	282.50	4520.00	Rupees Four Thousand Five Hundred Twenty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	12.60	Per cubic metre	1472.70	18556.02	Rupees Eighteen Thousand Five Hundred Fifty Six and Paise Two Only
Total in figure :					268900.10	Rupees Two Lakh Sixty Eight Thousand Nine Hundred and Paise Nine Only
Total in Words :					Rupees Two Lakh Sixty Eight Thousand Nine Hundred and Paise Nine Only	

Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY


Estimated Cost Rs:- 261170.47
 Earnest Money Rs:- 5200.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of Work:- Restoration of rain damages on Thaltukhod Marh road km. 0/00 to 5/00. (PDNA -2023) (Sub Head:- Construction of Retaining wall at RD Km 0/020 to 0/030).

Contract No. :
 Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	19.60	Per cubic metre	491.80	9639.28	Rupees Nine Thousand Six Hundred Thirty Nine and Paise Twenty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203, P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded ,crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	48.68	Per cubic metre	4870.50	237095.94	Rupees Two Lakh Thirty Seven Thousand Ninety Five and Paise Ninety Four Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	12.00	Each	282.50	3390.00	Rupees Three Thousand Three Hundred Ninety Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	7.50	Per cubic metre	1472.70	11045.25	Rupees Eleven Thousand Forty Five and Paise Twenty Five Only
Total in figure :					261170.47	Rupees Two Lakh Sixty One Thousand One Hundred Seventy and Paise Forty Seven Only
Total in Words :					Rupees Two Lakh Sixty One Thousand One Hundred Seventy and Paise Forty Seven Only	


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 430921.35
 Earnest Money Rs:- 8700.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of Work:- Restoration of rain damages on Thaltukhod Graman road km. 0/00 to 4/500. (PDNA -2023). (Sub Head - Construction of Retaining wall at RD Km 2/600 to 2/612).
 Contract No. :
 Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	33.60	Per cubic metre	522.50	17556.00	Rupees Seventeen Thousand Five Hundred Fifty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	80.09	Per cubic metre	4951.80	396589.66	Rupees Three Lakh Ninety Six Thousand Five Hundred Eighty Nine and Paise Sixty Six Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	15.00	Each	283.70	4255.50	Rupees Four Thousand Two Hundred Fifty Five and Paise Fifty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.28	Per cubic metre	1512.10	12520.19	Rupees Twelve Thousand Five Hundred Twenty and Paise Nineteen Only
Total in figure :					430921.35	Rupees Four Lakh Thirty Thousand Nine Hundred Twenty One and Paise Thirty Five Only
Total in Words :					Rupees Four Lakh Thirty Thousand Nine Hundred	Twenty One and Paise Thirty Five Only

Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar

3

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 491533.93
Earnest Money Rs:- 9900.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, P.W.D. at Padhar.
Name of Work:- Restoration of rain damages on Ropa Droon road Km 0/00 to 5/00. (PDNA- 2023). (Sub Head:-Construction of Causeway at RD 1/640 to 1/676.

Contract No. :
Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials, including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	48.84	Per cubic metre	522.50	25518.90	Rupees Twenty Five Thousand Five Hundred Eighteen and Paise Ninety Only
2	Providing and laying boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulder weighing not less than 25Kg. Each as per drawing and technical specification clause 1301 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	79.68	Per cubic metre	2318.00	184698.24	Rupees One Lakh Eighty Four Thousand Six Hundred Ninety Eight and Paise Twenty Four Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	70.36	Per cubic metre	1512.10	106391.36	Rupees One Lakh Six Thousand Three Hundred Ninety One and Paise Thirty Six Only
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP, P.W.D specification. 100 mm spread thickness (finished work including materials and labour) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	20.84	Per cubic metre	994.00	20714.96	Rupees Twenty Thousand Seven Hundred Fourteen and Paise Ninety Six Only
5	Providing and Laying reinforced cement concrete in substructure complete as per drawing and technical specifications 802,804, 805, 804, 806, 807, 1202 & 1204. Plain cement concrete nominal mix 1:2:4 (one cement: two sand: four graded, crushed stone aggregate 20mm (twenty octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government, but excluding GST & including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	25.80	Per cubic metre	5977.15	154210.47	Rupees One Lakh Fifty Four Thousand Two Hundred Ten and Paise Forty Seven Only
Total in figure :					491533.93	Rupees Four Lakh Ninety One Thousand Five Hundred Thirty Three and Paise Ninety

Total in Words : Rupees Four Lakh Ninety One Thousand Five Hundred Thirty Three and Paise Ninety Three Only

Executive Engineer,
Mandi Division No. I,
HP, P.W.D. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 487694.34
 Earnest Money Rs:- 9800.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of Work:- Restoration of rain damages on Sihbudhani Sudhar Kathog road Km 0/00 to 5/00. (PDNA- 2023). (Sub Head:-Construction of Causeway at RD 2/720 to 2/746.20).
 Contract No. :
 Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause-305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials,including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	37.73	Per cubic metre	522.50	19713.93	Rupees Nineteen Thousand Seven Hundred Thirteen and Paise Ninety Three Only
2	Providing and laying boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulder weighing not less than 25Kg. Each as per drawing and technical specification clause 1301.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	76.03	Per cubic metre	2318.00	176237.54	Rupees One Lakh Seventy Six Thousand Two Hundred Thirty Seven and Paise Fifty Four Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical sepcification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	72.31	Per cubic metre	1512.10	109339.95	Rupees One Lakh Nine Thousand Three Hundred Thirty Nine and Paise Ninety Five Only
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.08	Per cubic metre	994.00	17971.52	Rupees Seventeen Thousand Nine Hundred Seventy One and Paise Fifty Two Only
5	Providing and Laying reinforced cement concrete in substructure complete as per drawing and technical specifications 802,804, 805, 804, 806, 807, 1202 & 1204. Plain cement concrete nominal mix 1:2:4 (one cement: two sand: four graded, crushed stone aggregate 20mm (twenty octroi, royalty, maikana, toll tax, sale tax or other taxes imposed by the Government, but excluding GST & including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.	27.51	Per cubic metre	5977.15	164431.40	Rupees One Lakh Sixty Four Thousand Four Hundred Thirty One and Paise Forty Only
Total in figure :					487694.34	Rupees Four Lakh Eighty Seven Thousand Six Hundred Ninety Four and Paise Thirty Four Only

Total in Words : Rupees Four Lakh Eighty Seven Thousand Six Hundred Ninety Four and Paise Thirty Four Only

Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 499513.18
 Earnest Money Rs:- 10000.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of Work:- Restoration of rain damages on Sihbudhami Sudhar Kathog road Km 0/00 to 5/00. (PDNA- 2023). (Sub Head:-Construction of Causeway at RD 2/550 to 2/581.20).
 Contract No. :
 Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	41.93	Per cubic metre	522.50	21908.43	Rupees Twenty One Thousand Nine Hundred Eight and Paise Forty Three Only
2	Providing and laying boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS 4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulder weighing not less than 25Kg. Each as per drawing and technical specification clause 1301 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	73.86	Per cubic metre	2318.00	171207.48	Rupees One Lakh Seventy One Thousand Two Hundred Seven and Paise Forty Eight Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	76.11	Per cubic metre	1512.10	115085.93	Rupees One Lakh Fifteen Thousand Eighty Five and Paise Ninety Three Only
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	19.53	Per cubic metre	994.00	19412.82	Rupees Nineteen Thousand Four Hundred Twelve and Paise Eighty Two Only
5	Providing and Laying reinforced cement concrete in substructure complete as per drawing and technical specifications 802,804, 805, 804, 806, 807, 1202 & 1204. Plain cement concrete nominal mix 1:2:4 (one cement: two sand: four graded, crushed stone aggregate 20mm (twenty octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government, but excluding GST & including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	28.76	Per cubic metre	5977.00	171898.52	Rupees One Lakh Seventy One Thousand Eight Hundred Ninety Eight and Paise Fifty Two Only
Total in figure :					499513.18	Rupees Four Lakh Ninety Nine Thousand Five Hundred Thirteen and Paise Eighteen Only
Total in Words :						Rupees Four Lakh Ninety Nine Thousand Five Hundred Thirteen and Paise Eighteen Only

Executive Engineer,
 Mandi Division No. I,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 471995.17
 Earnest Money Rs:- 9400.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.P.W.D. at Padhar.

Name of Work:- Restoration of rain damages on Balh to Ropa road km. 0/00 to 5/100. (PDNA -2023) at Dr. Daxi, the Property Damaged (32-10%). (Sub Head:- Construction of Retaining wall at R.D. 4/418 to 4/418.75)

Contract No.:

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials,including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	50.93	Per cubic metre	522.50	26610.93	Rupees Twenty Six Thousand Six Hundred Ten and Paise Ninety Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded ,crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	87.89	Per cubic metre	4844.40	425774.32	Rupees Four Lakh Twenty Five Thousand Seven Hundred Seventy Four and Paise Thirty Two Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	15.00	Each	279.10	4186.50	Rupees Four Thousand One Hundred Eighty Six and Paise Fifty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	10.20	Per cubic metre	1512.10	15423.42	Rupees Fifteen Thousand Four Hundred Twenty Three and Paise Forty Two Only
Total in figure :					471995.17	Rupees Four Lakh Seventy One Thousand Nine Hundred Ninety Five and Paise Seventeen Only
Total in Words :					Rupees Four Lakh Seventy One Thousand Nine Hundred Ninety Five and Paise Seventeen Only	

Executive Engineer,
 Mandi Division No.I,
 HP.P.W.D/ at Padhar

9

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 399164.50
Earnest Money Rs:- 8000.00
Time:- One month

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP PWD. at Padhar.
Name of Work:- Restoration of rain damages on Balh to Ropa road km. 0/00 to 5/100. (PDNA -2023 at R. D. 0/150 to 0/165).
Construction of Retaining wall at R.D. 0/150 to 0/165).
Contract No. :
Name of the Bidder/Bidding Firm/Company :
PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials, including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	33.60	Per cubic metre	522.50	17556.00	Rupees Thousand Five Hundred Fifty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses. 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	75.07	Per cubic metre	4817.30	361634.71	Rupees Three Lakh Sixty One Thousand Six Hundred Thirty Four and Paise Seventy One Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.00	Each	278.00	5004.00	Rupees Five Thousand Four Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	9.90	Per cubic metre	1512.10	14969.79	Rupees Thousand Nine Hundred Sixty Nine and Paise Seventy Nine Only
Total in figure :					399164.50	Rupees Three Lakh Ninety Nine Thousand One Hundred Sixty Four and Paise Only
Total in Words :					Rupees Three Lakh Ninety Nine Thousand One Hundred Sixty Four and Paise Fifty Only	

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 475310.06
 Earnest Money Rs:- 9500.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.
 Name of Work:- Restoration of rain damages on Ropa Kathog road km. 0/00 to 5/00. (PDNA -2023) (Sub Head - Providing & Laying Kharanja Stone Soling in various RD's in Km 0/00 to 5/00).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for seperately depending upon the classification of soil) complete as per H.P.W.D. Specifications, including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	3149.00	Per cubic metre	1.84	5794.16	Rupees Five Thousand Seven Hundred Ninety Four and Paise Sixteen Only
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour), including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	472.35	Per cubic metre	994.00	469515.90	Rupees Four Lakh Sixty Nine Thousand Five Hundred Fifteen and Paise Ninety Only
Total in figure :					475310.06	Rupees Four Lakh Seventy Five Thousand Three Hundred Ten and Paise Six Only
Total in Words :					Rupees Four Lakh Seventy Five Thousand Three Hundred Ten and Paise Six Only	

Executive Engineer,
 Mandi Division No.I,
 HP, PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 401329.20
 Earnest Money Rs:- 8000.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of Work:- Restoration of rain damages on Ropa Kathog road km. 0/00 to 5/00. (PDNA -2023)
 (Sub Head:- Construction of Retaining wall at RD Km 0/615 to 0/630).

Contract No. :
 Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	33.60	Per cubic metre	522.50	17556.00	Rupees Seventeen Thousand Five Hundred Fifty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	75.07	Per cubic metre	4845.80	363774.21	Rupees Three Lakh Sixty Three Thousand Seven Hundred Seventy Four and Paise Twenty One Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.00	Each	279.40	5029.20	Rupees Five Thousand Twenty Nine and Paise Twenty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	9.90	Per cubic metre	1512.10	14969.79	Rupees Fourteen Thousand Nine Hundred Sixty Nine and Paise Seventy Nine Only
Total in figure :					401329.20	Rupees Four Lakh One Thousand Three Hundred Twenty Nine and Paise Twenty Only
Total in Words :					Rupees Four Lakh One Thousand Three Hundred Twenty Nine and Paise Twenty Only	

Executive Engineer,
 Mandi Division No. I,
 HP.PWD. at Padhar, G.R. ---

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 99630.46
 Earnest Money Rs:- 2000.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of work :- Construction of Tikkan Silbudhani road Km 0/00 to 16/100.(Sub Head:- Improvement of Blind Curve and Narrow resches in Km 7/315 to 7/372).

Contract No. :
 Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate	TOTAL AMOUNT with all taxes excluding GST in	TOTAL AMOUNT with all taxes excluding GST in
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/ unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	562.70	Per cubic metre	201.06	113136.46	Rupees One Lakh Thirteen Thousand One Hundred Thirty Six and Paise Forty Six Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	22.51	Per cubic metre	600.00	-13506.00	Rupees Sixteen Thousand Seven Hundred Sixty Four Only.
Total in figure :					99630.46	Rupees Ninety Nine Thousand Six Hundred Thirty and Paise Forty Six Only
Total in Words :					Rupees Ninety Nine Thousand Six Hundred Thirty and Paise Forty Six Only	

Executive Engineer,
 Mandi Division No-1,
 HP. PWD, at Padhar *Gen.*

13

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs :- 99710.46

Earnest Money Rs :- 2000.00

Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP, PWD. at Padhar.						
Name of work :- Construction of road Tikkan to Silbudhani Km 0/00 to 16/100. (Sub Head:- Improvement of Blind Curve and Narrow reaches in Km 7/255 to 7/315).						
Contract No. :						
Bidder Name :						
<u>SCHEDULE OF WORKS</u>						
Sr. No.	Description of items	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	549.82	Per cubic metre	211.35	116204.46	Rupees One Lakh Sixteen Thousand Two Hundred Four and Paise Forty Six Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	27.49	Per cubic metre	600.00	-16494.00	Rupees Two Lakh Two Thousand Eight Hundred Fourteen only
Total in figure :					99710.46	Rupees Ninety Nine Thousand Seven Hundred Forty Six Only
Total in Words :						Ten and Paise Forty

Executive Engineer,
Mandi Division No-1,
HP, PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 427488.18
 Earnest Money Rs:- 8500.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of work :- Restoration of rain damages on Padhar Nahuli road km. 0/00 to 14/500. (PDNA -2023), (Sub Head:- Construction of Retaining wall at RD 14/015 to 14/035).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.80	Per cubic metre	522.50	22363.00	Rupees Twenty Two Thousand Three Hundred Sixty Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	74.31	Per cubic metre	4919.00	365530.89	Rupees Three Lakh Sixty Five Thousand Five Hundred Thirty and Paise Eighty Nine Only
3	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	1.91	Per cubic metre	5429.00	10369.39	Rupees Ten Thousand Three Hundred Sixty Nine and Paise Thirty Nine Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.00	Each	281.40	9567.60	Rupees Nine Thousand Five Hundred Sixty Seven and Paise Sixty Only
5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.00	Per cubic metre	1512.10	19657.30	Rupees Nineteen Thousand Six Hundred Fifty Seven and Paise Thirty Only
Total in figure :					427488.18	Rupees Four Lakh Twenty Seven Thousand Four Hundred Eighty Eight and Paise Eighteen Only
Total in Words :					Rupees Four Lakh Twenty Seven Thousand Four Hundred Eighty Eight and Paise Eighteen Only	

Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 189270.26
 Earnest Money Rs:- 3800.00
 Time:- One month

C/O
 Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of work :- Restoration of rain damages on Banogi Chehar Chella road km. 0/00 to 5/00. (PDNA - 2023). (Sub Head :- Breast Wall at R.D. 2/480 to 2/495).

SCHEDULE OF WORKS						TOTAL AMOUNT with all taxes excluding GST in words.
Sr. No.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	
1	25.05	Per cubic metre	522.50	13088.63	Rupees Thirteen Thousand Eighty Eight and Paise Sixty Three Only	
2	36.14	Per cubic metre	4783.10	172861.23	Rupees One Lakh Seventy Two Thousand Eight Hundred Sixty One and Paise Twenty Three Only	
3	12.00	Each	276.70	3320.40	Rupees Three Thousand Three Hundred Twenty and Paise Forty Only	
Total in figure :				189270.26	Rupees One Lakh Eighty Nine Thousand Two Hundred Seventy and Paise Twenty Six Only	
Total in Words :				Rupees One Lakh Eighty Nine Thousand Two Hundred Seventy and Paise Twenty Six Only		

Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.