

Enlistment OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG  
PH: 01907-222229 Fax: 222229 , e-mail : [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)

No.PW-KSG-E-Tenders/2024-

14507

Dated:- 25-2-2026

To

The Executive Engineer (IT) Cell,  
HPPWD, Nirman Bhawan, Nigam Vihar,  
Shimla-2.


Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

*Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 section 24 (i).*

Encl:- As above.

  
Executive Engineer,  
B&R Division,  
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG  
PH: 01907-222229 Fax: 222229 , E-mail : [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)  
Notice inviting tender**

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **06.03.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 05.03.2026** for which the application should reach in this office **upto 1.00 PM 05.03.2026**.


The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Churag to Chamanpur road Km. 0/00 to 4/00 (SH:- Removal of slips in Km. 0/220 to 3/380) under PDNA 2023	1,39,474/-	2,800/	One Month	350/-
2	R/R damages on Dawaru Talehan road Km. 0/00 to 5/00 (SH:- removal of slips, stone soling, C/o unlined & maintenance of earthen shoulder) under PDNA 2023	4,05,105/-	8,200/-	One Month	350/-

**TERMS & CONDITIONS:-**

- No tender form will be issued to those contractors who are not registered under HPGST Act.
- The Contractor/firm should be registered as or dealer GST NO.
- If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
- No tender form will be issued to those contractors who are not registered under EPF Act.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.

- The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
  9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


  
**Executive Engineer  
B&R Division  
HPPWD Karsog**

No. PW-E-Tender-NIT/2025-26-

14500-08

Dated:- 25-2-2025

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

  
**Executive Engineer,  
B&R Division,  
HP PWD Karsog**

Percentage Schedule of Quantity

Estimated Cost 139474  
Earnest Money 2800  
Time One Month

Name of Work:- R/R Damages on Churrag to Chamampur road Km. 0/00 to 4/00(SH:- Removal of slips in Km 0/220 to 3/380)Under PDNA 2023.

**Sub-Head and items of works.**

	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs.	Total Amount with all taxes Including GST In Rupees
1	1162.28	Per Cubic Meter	120.00	139474.00	Thirty Nine Thousand Four Hundred Seventy Four and Paise Zero Only
Total in Figures				139474.00	
Quoted Rate in Figures					
Quoted Rate in Words					

Executive Engineer,  
Karsog Division,  
CHPPWD, Karsog.


Percentage Bill Of Quantity

Estimated Cost 405105.00  
Earnest Money 8200  
Time One Month

Name of Work:- R/R Damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- Removal of slips, stone soling, C/O unlined drain & Maintenance of Earthen Shoulder) Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance.-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	825.53	Per Cubic Meter	120.00	99063	Rupees Ninety Nine Thousand Sixty Three and Paise Zero Only
2	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-graded to be paid for separately depending upon the classification or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	660.00	Per Square Meter	2.20	1452.00	Rupees One Thousand Four Hundred Fifty Two and Paise Zero Only
3	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PVD specifications as per direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidentals.	660.00	Per Square Meter	1.20	792.00	Rupees Seven Hundred Ninety Two and Paise Zero Only
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidation with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPVD specification. 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads, lifts and other incidentals.	99.00	Per Cubic Meter	2045.60	202514.00	Rupees Two Lakhs Two Thousand Five Hundred Fourteen and Paise Zero Only
5	Construction of unlined surface drain of average cross-section area 0.20 sqm (zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer-in-charge with in all lead and lifts and other incidentals.	2000.00	Per Running Meter	21.80	43600.00	Rupees Forty Three Thousand Six Hundred and Paise Zero Only
6	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2622.00	Per Cubic Meter	22.00	57684.00	Rupees Fifty Seven Thousand Six Hundred Eighty Four and Paise Zero Only
<b>Total in Figures</b>					<b>405105.00</b>	
<b>Quoted Rate in Words</b>						

Bill of Quantity approved for Rs. 405105.00  
Sr. No 334 for Years 2025-26

  
Executive Engineer,  
Karsog Division,  
CHPPWD, Karsog.