

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed **percentage rate** tender on form No. 6 and 7/8 are hereby invited by the **Executive Engineer (NH) Division HPPWD Nahan** on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **06-03-2026** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up **05-03-2026 04:00 PM**

The earnest money in the shape of FDR/TDR of any Bank in H.P. duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.


Sr. No.	Name of Work	Estimated Cost (inRs.)	Earnest Money	Time Limit	Cost of Form
1	2	3	4	5	6
1	Restoration of rain damages to Kala Amb Paonta Sahib Dehradun Road Km 46/00 to 103/00 (SH:- Repair of Pot holes in 55/321 to 55/341)	99904/-	2000/-	01Month	350/-
2	Restoration of rain damages to Kala Amb Paonta Sahib Dehradun Road Km 46/00 to 103/00 (SH:- Repair of Pot holes in 55/340 to 55/362)	99904/-	2000/-	01Month	350/-
3	Restoration of rain damages to Kala Amb Paonta Sahib Dehradun Road Km 46/00 to 103/00 (SH:- Repair of Pot holes in 55/300 to 55/321)	99904/-	2000/-	01 Months	350/-
4	A/R & M/o to Kala Amb Paonta Sahib Dehradun Road Km 46/00 to 103/00 (SH:- Providing fixing fire extinguisher in the office of Executive Engineer (NH) Division Nahan and office of NH Sub-Division HPPWD Dhaulakuan and Sarahan.	98400/-	2000/-	15 days	350/-

CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.

4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc.
before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD and others as published by the Govt. from time to time Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.



 Executive Engineer
 NH Division HPPWD
 Nahan
 Tele No. 01702-222202

For & on behalf of Governor of Himachal Pradesh

No. PW/NHD-NHN/TA-Tender Notice/ 2025-26: 5985-6014 **dated:-** 25/2/26.

Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.


 Executive Engineer
 NH Division HPPWD
 Nahan.


SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage to Kala Amb Paonta Sahib Dehradun road KM 46/00 to 103/00 on NH-07 (SH:- Repair of Pot Holes Km 55/321 to 55/341)

Estimated cost :- Rs.99904.00/- only
 Earnest Money :- RS.2000/-only
 Time Limit :- One Month

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate		Total Amount	Total Amount in word
				4	5		
1	Providing and applying tack coat with bitumen emulsion RS-1 using emulsion pressure distributor at the rate of 0.250 Kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.	140.00	Per Sqm	22.80	3192.00	Three thousand One hundred ninety two only	
2	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	5.60	Per Cubic metre	17269.95	96712.00	Ninety six thousand seven hundred and twelve only	
Total :-					99904.00	Ninety nine thousand nine hundred and four only	
Quoted Rate % (Percentage) in Figures							
Quoted Rate % (Percentage) in Words							

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.


 Executive Engineer
 NH Division
 HPPWD Nahan

76.2


SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage to Kala Amb Paonta Sahib Dehradun road KM 46/00 to 103/00 on NH-07 (SH):- Repair of Pot Holes Km 55/341 to 55/362)

Estimated cost :- Rs.99904.00/- only
 Earnest Money :- RS.2000/-only
 Time Limit :- One Month

Sr.No	Description of Item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word	
						7	8
1	2	3	4	5	6	7	8
1	Providing and applying tack coat with bitumen emulsion RS-1 using emulsion pressure distributor at the rate of 0.250 Kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.	140.00	Per Sqm	22.80	3192.00	Three thousand One hundred ninety two only	
2	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	5.60	Per Cubic metre	17269.95	96712.00	Ninty six thousand seven hundred and twelve only	
Total :-					99904.00	Ninety nine thousand nine hundred and four only	
Quoted Rate % (Percentage) in Figures							
Quoted Rate % (Percentage) in Words							

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.


 Executive Engineer
 NH Division
 HPPWD Nahau

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage to Kala Amb Paonta Sahib Dehradun road KM 46/00 to 103/00 on NH-07 (SH:- Repair of Pot Holes Km 55/300 to 55/321)

Estimated cost :-

Rs.99904.00/- only

Earnest Money :-


RS.2000/-only

Time Limit :-

One Month

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	Providing and applying tack coat with bitumen emulsion RS-I using emulsion pressure distributor at the rate of 0.250 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.	140.00	Per Sqm	22.80	3192.00	Three thousand One hundred ninety two only
2	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filter, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	5.60	Per Cubic metre	17269.95	96712.00	Ninety six thousand seven hundred and twelve only
Total :-					99904.00	Ninety nine thousand nine hundred and four only
Quoted Rate % (Percentage) in Figures		(+)/(-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.


 Executive Engineer
 NH Division
 HPPWD Nahan

SCHEDULE OF QUANTITY

Name of Work:- A/r & M/O to Kala Amb Paunta Sahib
Dehradun Road on (New NH-07) Km 46/00 to 103/00. (SH:-
Providing and Fixing Fire Extinguisher in the Office of Executive
Engineer NH Division Nahan & o/o NH Sub-Division Dhaulakuan,
Sarahaan & Kafota.

Estimated cost :-

Rs.98400.00/-/- only

Earnest Amount

2000.00/-

Time Limit :-

15 Days

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	Providing and fixing Powder fire extinguisher (Stored Pressure Type) duly ISI Marked ABC Powder complete with squeeze grip release valve, discharge ypoipe locking arrangement pressure gauge, operational manual bracket with two screw and sleeve including all leads, lifts and carriage of materials, fixing / installation at various location in this Division, as per the direction and entire satisfaction of Engineer-in-charge.	3	Each No	8200.00	98400.00	Ninty EightThousand and Four Hundred Only
					Total Amount	98400.00/-
						(+) / (-)

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.



Executive Engineer
NH Division
HPPWD Nahan

565/4