

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender- Publication/2025-26- 9665-74

Dated:- 11-2-2026

To


The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest.


DA: - Notice Inviting Tender.
(41 Nos. Works)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Copy to Account Branch in this office.
Copy to Drawing Branch in this office.
Notice Board.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed **Percentage rate** tenders on form "**6&8**" are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **20.02.2026 upto 01.30 PM** and will be opened on the same day at **3.00 PM** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 19.02.2026** and tender form will be issued on dated **20.02.2026 upto 11:30 AM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Restoration of rain damages on Ner Dhangu and link road from Chandyal to Saayah via SC Basti Saayah km 0/00 to 2/500. (SH:- Providing and laying CC paver block in km 2/151 to 2/157.50).	95801	2000	350	Two Months	"D"
2	C/o Play Ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH: C/o PCC drain in 1:3:6 at RD 0/0 to 0/042)	98550	2000	350	Two Months	"D"
3	A/R & M/O TCCC building at SLBSGMC&H at Nerchowk (SH: Balance work of C/o Ramp along with railing) Job No.II.	88932	1800	350	Two Months	"D"
4	A/R & M/O Division office building HPPWD Nerchowk, Tehsil Balh Distt Mandi HP. (SH:- C/O Gate for Division office building HPPWD Nerchowk).	97632	2000	350	Two Months	"D"
5	A/R & M/O various roads under Nerchowk Sub-Division. (SH:- Providing and fixing of sign board/ direction information sign board of size 450 X 600mm rectangular) (Job-I)	95000	2000	350	One Month	"D"
6	Restoration of rain damages on various road under Rewalsar Sub Division HPPWD Rewalsar. (Sardhwar Section). (SH:- Removal of slips, dressing of berm in various reaches).	99500	2000	350	Two Months	"D"
7	Restoration of rain damages on various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc).	95700	2000	350	Two Months	"D"
8	C/o Play Ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH: C/o wire crte R/wall at RD 0/025 to 0/035)	87206	1800	350	Two Months	"D"
9	Restoration of rain damages on various roads under the jurisdiction of Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of material for removal of slips and patch work and other various work) Ratti Section.	99200	2000	350	Two Months	"D"
10	A/R & M/O various Buildings in the campus of Shri Lal Bahadur Shastri Medical College & Hospital at Nerchowk (SH: Hirin gof JCB and Tipper for carriage of stones/ debris/muck/ unserviceable material/ dismantled material etc.).	55400	1200	350	Two Months	"D"

11	Restoration of damages caused due to laying of H.D.P.E.Pipe line on Mandi Gagail Chailchowk Janjehali Chatri Rana Ka Bag road KM 0/0 to 16/190 (SH: Dressing of road berms at RD 12/500 to 14/000 and C/o road shoulders at RD 10/500 to 11/015) (Deposit)	96848	2000	350	Two Months	"D"
12	Restoration of rain damages on various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section). (SH:- Construction of unlined surface drain in various reaches).	98820	2000	350	Two Months	"D"
13	Restoration of rain damages on Behna Chanol Malori road km 0/0 to 3/500. (SH:- Removal of slips at RD 0/200 to 0/360). (MC Deposit)	76492	1600	350	Two Months	"D"
14	A/R & M/O various roads under Nerchowk Sub-Division. (SH:- Providing and fixing of sign board/ direction information sign board of size 900X 600mm rectangular) (Job-II)	99000	2000	350	Two Months	"D"
15	A/R & M/O TCCC building at SLBSGMC&H at Nerchowk (SH: Balance work of C/o Ramp along with railing) Job No.III.	80862	1700	350	Two Months	"D"
16	Restoration of rain damages on Khakhryana to Kaphara via Kufri road km 0/0 to 2/105. (Sub Head:- Construction of Retaining wall in PCC 1:5:10 at RD 0/955 to 0/960.30).	99917	2000	350	Two Months	"D"
17	Preparation of working estimate for C/o Ayurvedic Health Centre Building at Halyater , Tehsil Balh, Distt. Mandi and Preparation of contour site plan for construction of Tribal Hostel building at Rewalsar, Tehsil Balh, Distt. Mandi (HP).	60000	1200	350	Two Months	"D"
18	Annual Repair & Maintenance of Shri Lal Bahadur Shastri Govt. Medical College & Hospital Nerchowk, Mandi HP. (SH:- Providing and laying Epoxy Flooring O.T. No.3 of 6th floor for Robotic Surgery Room) Job No.I	98667	2000	350	Two Months	"D"
19	Construction of Gutkar to Shiv Gufa road in Muhal Otta km 0/0 to 2/00. (SH:- P/L water bound macadam G-II and cement concrete from RD 0/135 to 0/170). VKY Deposit.	91690	1900	350	Two Months	"D"
20	Restoration of damages caused due to laying of H.D.P.E.Pipe line on Mandi Gagail Chailchowk Janjehali Chatri Rana Ka Bag road KM 0/0 to 16/190 (SH: C/o unlined surface drain in KM 11/500 to 12/730) (Deposit)	99630	2000	350	Two Months	"D"
21	Restortion of rain damages on various roads under Chakkar Sub Division, HPPWD Nerchowk (SH: Hiring of Tipper with lift system for carriage of muck/ debries and shifting of material etc.) (Gagal Section).	99200	2000	350	Two Months	"D"
22	A/R & M/O TCCC building at SLBSGMC&H at Nerchowk (SH: Balance work of C/o Ramp along with railing) Job No.I.	99644	2000	350	Two Months	"D"
23	Construction of Gutkar to Shiv Gufa road in Muhal Otta km 0/0 to 2/00. (SH:- P/L water bound macadam G-II and cement concrete from RD 0/100 to 0/135). VKY Deposit.	94668	1900	350	Two Months	"D"
24	A/R & M/O Atal Medical Research University (AMRU) in the campus of Shri Lal Bahadur Shastri Govt.Medical College and Hospital, Nerchowk, Mandi (HP) (SH: Repair of Dome).	99947	2000	350	Two Months	"D"
25	A/R & M/O Atal Medical Research University (AMRU) in the campus of Shri Lal Bahadur Shastri Govt.Medical College and Hospital, Nerchowk, Mandi (HP) (SH: Painting Distempering and Repair work in 2nd floor	99746	2000	350	Two Months	"D"

	Dome abd 3rd Floor ENT Lobby).					
26	RRD on various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tractor with trolly for carriage of muck/ debris and shifting of materials etc.) (Gagal Section).	97350	2000	350	Two Months	"D"
27	Restoration of rain damages on various roads under Chakkar Sub Division. (SH:- Providing dual directional delinators for road side with plastic head unbreakable at neck).	98700	2000	350	Two Months	"D"
28	Restoration of rain damages on various roads under Chakkar Sub Division. (SH:- Providing high intensity Engineer Grade prismatic sheeting).	97850	2000	350	Two Months	"D"
29	RRD on Tanda-Kohla-Tikkari-Kawalkot Sidhkothi (via Baba Balak Nath Mandir) Thapla Gobhol Galoo road km 0/0 to 5/150. (SH:- Prepration of working estimate of additional work).	98500	2000	350	Two Months	"D"
30	Annual Repair & Maintenance of Shri Lal Bahadur Shastri Govt. Medical College & Hospital Nerchowk, Mandi HP. (SH:- Providing and laying Epoxy Flooring O.T. No.3 of 6th floor for Robotic Surgery Room) Job No.II	97677	2000	350	Two Months	"D"
31	Restoration of rain damages on Galma Manjhyali road km 0/0 to 9/0. (SH:- C/O R/wall at RD 2/750 to 2/754).	97398	2000	350	Two Months	"D"
32	Restoration of rain damages on Ratti to Randhara road km 0/0 to 9/00. (SH:- C/O PCC R/wall at RD. 3/410 to 3/414).	99381	2000	350	Two Months	"D"

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. Only two tenders shall be issued to each contractor.
4. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
5. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
6. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNT Sr.No. 77 for the year 2025-26

Vol No. 1

DRAFT SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain damages on Ner Dhangu and link road from Chandyal to Saayah via SC Basti Saayah km. 0/00 to 2/500 (SH:- Providing and laying CC Paver block in km. 2/151 to 2/157.50).

Estimated Cost:-	95801.00
Earnest Money Cost:-	2000.00
Time:- One Month	

Sr. No.	Item Description	Quantity	Unit	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic metre	5	6	7 Rupees Six Thousand Five Hundred EightyEight Only
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadan specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.63	Per cubic metre	2427.00	6383.00	8 Rupees Six Thousand Three Hundred EightyThree Only
3	Providing and laying Plain/ reinforcement cement concrete in foundation/ substructure as per drawing and technical specification clause 802, 803, 1202 and 1203 PCC nominal mix 1:2:4 (1 cement: 2 sand: 4 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.36	Per cubic metre	5810.00	7902.00	9 Rupees Seven Thousand Nine Hundred Two Only
4	Providing and laying Plain/ reinforcement cement concrete in foundation/ substructure as per drawing and technical specification clause 802, 803, 1202 and 1203 PCC nominal mix 1:3:6 (1 cement: 3 sand: 6 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.51	Per cubic metre	5247.00	18417.00	10 Rupees Eighteen Thousand Four Hundred Seventeen Only

<p>5 Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper mbedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.</p>	35.10	Per square metre	1610.00	56511.00	Rupees FiftySix Thousand Five Hundred Eleven Only
<p style="text-align: center;">TOTAL:-</p>				95801.00	Rupees Ninety Five Thousand Eight Hundred One Only

Self Schedule of quantity checked approved for Rs. 95,801/- only (Rs. Ninety Five Thousand Eight Hundred one only)


 Executive Engineer
 Nerchowk Division
 P.P.W.D. Nerchowk

DMIT Sr.No. 175 for the year 2025-26


Page No. 2

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Play ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH:- C/O PCC drain in 1:3:6 at RD. 0/0 to 0/042)

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts as per direction of Engineer-in-Charge.	28.56	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	8197.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded, crushed stone aggregate)curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	17.22	Per cubic meter	5247.00	Rupees Five Thousand Two Hundred Forty Seven only	90353.00
TOTAL:-						98550.00

Self Schedule of quantity checked & approved for Rs. 98,550/- only.
(Rs. Ninety Eight Thousand Five Hundred Fifty only).


Executive Engineer
Nerchowk Division
APPWD-Nerchowk

DRAFT Sr.No. 88 for 2025-26

Page No. 5

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O TCCC building at SLBSGMC&H at Nerchowk (SH:- Balance work of C/O Ramp along with railing) Job No. 2.

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Providing and laying 12 mm (Twelve millimetre) cement plaster of mix 1:4 (1 cement : 4 fine sand) including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	275.21	Per Square Metre	238.20	Rupees Two Hundred ThirtyEight and Paise Twenty Only	65555.00
2	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, kg railings, brackets, gates and similar works including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	157.79	Per kg	148.15	Rupees One Hundred FourtyEight and Paise Fifteen Only	23377.00
TOTAL:-						88932.00

*Self schedule of quantity checked & approved for Rs. 88,932/only
C.Ps. Eighty Eight Thousand Nine Hundred Thirty Two only*

[Signature]
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT Sr. No. (167) for the year 2025-26

22.03.24

DRAFT SCHEDULE OF QUANTITY


Name of work:- A/R & M/O Division office building HPPWD Nerchowk, Tehsil Balh, Dist. Mandi (HP) (SH:- C/O gate for division office building HPPWD Nerchowk).

Estimated Cost:-	97632.00
Earnest Money:-	2000.00
Time:- One Month	

S. No.	Description of item	Quantity	Unit	Rate with all taxes excluding GST		Amount
				In figure	In words	
1	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead in cement mortar including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.28	Per cum	1011.75	Rupees One Thousand Eleven and Paise Seventy Five only	2307.00
2	Dismantling steel work inbuilt up sections inangles, tees, flats and channels including all gusset plates, bolts, nuts, cuttingrivets, welding etc. including dismembering and stacking within 50 metres lead including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	146.62	Per sqm	2.35	Rupees Two and Paise Thirty Five only	345.00
3	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.12	Per cum	267.10	Rupees Two Hundred Sixty Seven and Paise Ten only	299.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement: 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.16	Per kg	5090.15	Rupees Five Thousand Ninety and Paise Fifteen only	814.00
5	Sourced rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level, masonry work (first sort), in cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.2	Per cum	7589.00	Rupees Seven Thousand Five Hundred Eighty Nine and Paise Zero only	24285.00

6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	73.07	Per sqm	85.80	Rupees Eighty Five and Paise Eighty only	6269.00
7	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, kg railings, brackets, gates and similar works including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	376.84	Per sqm	127.20	Rupees One Hundred Twenty Seven and Paise Twenty only	47934.00
8	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement: 3 coarse sand), cost of required Centering complete. 1:1.5:3 (1 cement: 1.5 coarse sand): 3 graded stone aggregate 20mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.89	Per cum	7475.80	Rupees seven Thousand Four Hundred Seventy Five and Paise Eighty only	14129.00
9	Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	15.75	Per sqm	79.35	Rupees Seventy Nine and Paise Thirty Five only	1250.00
TOTAL:-						97632.00

Draft schedule of quantity checked & approved for Rs. 97,632/- only
(Rs. Ninety seven Thousand Six Hundred Thirty Two & only)


 Executive Engineer
 Nerchowk Division
 PPWD Nerchowk

DMIT NO. (178) FOR THE YEAR 2025-26

Job No. 5

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O various roads under Nerchowk Sub - Division (SH:- Providing and fixing of sign board / direction information sign board of size 450 X 600mm rectangular)(Job I)

Estimated cost :- Rs. 95,000/-
Earnest Money :- Rs. 2000/-
Time Limit Two month

Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Providing and fixing of 0.27 sqm (zero point twenty seven square metre) in rectangular of retro-reflectorised cautionary, mandatory and informatory sign board as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting 1.5 mm (one point five millimetre) thick supported on a mild steel angle iron post 50 mm x 50 mm x 5 mm (fifty into fifty into five millimetre) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm (two hundred fifty into two hundred fifty into three hundred x six hundred) millimetre below ground level as per drawings and Technical Specification Clause 801 as per direction of entire satisfaction on Engineer-in-Charge.	19	5000.00	Ruppes five thousand paise nil only	Each	95000.00
Total:-						95000.00

Draft schedule of quantity approved for Rs. 95,000/- (Rupees Ninety Five thousand) only

Assistant Engineer,
Chakkar Sub-Division
H.P.W.D Nerchowk

Executive Engineer,
Nerchowk Division,
H.P.W.D Nerchowk.

DIT Sano (134) for the year 2005-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various road under Rewalsar Sub Division HPPWD Rewalsar.
 (Sardhwar Section) (SH:- Removal of slip, dressing of berm in various reaches)

Estimated Cost:- 99500.00
 Earnest Money :- 2000.00
 Time :- One Month

S.N	Description of Item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P	In word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	775.00	104.00	Rupees One hundred four and paise zero only.	Per Cubic Metre	80600.00
2	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1350.00	14.00	Rupees Fourteen and paise zero only.	Per square Metre	18900.00
Total						99500.00

Draft schedule of Quantity approved for ₹ 99500/- only.
 (Rs. Ninety Nine thousand Five hundred only)

[Signature]
 Assistant Engineer,
 Rewalsar Sub-Division,
 H.P.P.W.D. Rewalsar.

[Signature]
 Executive Engineer,
 HPPWD Division,
 HPPWD Nerchowk

Job No. 6

DMIT Sr. No. (160) for the year 2025-26


Job No 7

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkar Sub Division, HPPWD Nerchowk (Gagal Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	87.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	95700.00
TOTAL:-						95700.00

Draft schedule of quantity checked & approved for Rs. 95,700/- only (Rs. Ninety Five Thousand seven hundred only)




[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNT Sr.No. (172) for the year 2025-26

Job No. 8

Name of work:- Construction of Play ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH:- C/O wire crate R/wall at RD. 0/025 to 0/035)

DRAFT SCHEDULE OF QUANTITY

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	29.5	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	8467.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmX100mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.34	Per cubic meter	2880.00	Rupees Two Thousand Eight Hundred Eighty only	78739.00
TOTAL:-						87206.00

Draft schedule of quantity checked & approved for Rs 87,206/- only (Rs. Eighty seven thousand Two Hundred sixty only)

Executive Engineer
Nerchowk Division
PPWD Nerchowk

DMIT sr.No. 192 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under the jurisdiction of Chakkur Sub Division, HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of material for removal of slips and patch work and other various work) Ratti Section.

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				In figure	In words	
1	Hiring of Tipper for carriage of premixed material for patchwork and shifting of patchwork material including carriage of excavated earth/ material generated during clearance of drain and removal of slips tipper having capacity of 5.50 cum per trip and minimum 70 km. of trip per day. The contractor/ owner of tipper shall bear the expensive of P.O.L. charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer-in-Charge with in all lead and lifts.	31.00	Per Day	3200.00	Rupees Three Thousand Two Hundred Only	99200.00
TOTAL:-						99200.00

Draft schedule of quantity checked & approved for Rs. 99,200/- only (Rs. Ninety Nine Thousand Two Hundred only)

A.E.

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

Page No. 9

DNT No (25) FOR THE YEAR 2025-26

date No. 10

Draft Schedule of Quantity

Estimated Cost:- 55400.00
 Earnest Money:- 1200.00
 Time:- One Month

Name of work:- A/R & M/O various Buildings in the campus of Shri Lal Bahadur Shastri Medical College & Hospital at Nerchowk.
 (SH: Hiring of JCB and Tipper for carriage of stones/debris/ muck/unserviceable material/dismantled material etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	30.00 Hour	1100.00	Rupees One Thousand only	Per Hour	33000.00
2	Hiring of Tipper 5.5 cum capacity having lift system for carriage of earth/ debris, boulder and other construction materials from various location etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	7.00 days	3200.00	Rupees Three Thousand Two Hundred only	Per day	22400.00
Total:-						55400.00

Draft schedule of quantity approved to Rs. 55400/- (Rupees Fifty Five Thousands Four Hundred) only.

[Signature]
 PWD/-e

Executive Engineer,
 Nerchowk Division,
 PWD, Nerchowk.

DNT, Sr. No. (187) for the year 2025-26

Job No. 11

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of damages caused due to laying of H.D.P.E. Pipe line on Mandi Gagal Chailchowk Janjahlai Chattri Rana Ka Bag road km. 0/0 to 16/190 (SH:- Dressing of road berms at RD. 12/500 to 14/000 & C/O road shoulders at RD. 10/500 to 11/015) (Deposit).

Estimated Cost:-	96848.00
Earnest Money:-	2000.00
Time:-	One Month

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3600.00	Per Sqm	14.00	Rupees Fourteen only	50400.00
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table 300.0 with lead upto 1000 m as per technical specification clause 303.1 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	103.00	Per Cum	450.95	Rupees Four Hundred Fifty and Paise Ninety Five only	46448.00
TOTAL:-						96848.00

draft schedule of quantity checked & approved for Rs. 96,848/- only (Rs. Ninety six Thousand Eight Hundred Forty Eight only)

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNIT Sr.No. (158) for the year 2025-26

Lab No. 12

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various roads under Chakkar Sub-Division, HPPWD Nerchowk (Gagal Section) (SH:- Construction of unlined surface drain in various reaches).

Estimated Cost:- 98820.00
 Earnest Money:- 2000.00
 Time:- Two Months

S. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			Figure	Words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions to the requirement of clause 301 and 309. Excavated material to be used in embankment as per Technical Specification complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1220.00	81.00	Rupess Eighty One only	Per Running Metre	98820.00
Total:-						98820.00

*Isaaf schedule of quantity checked & approved for Rs. 98,820/- only
 Rs. Ninety Eight Thousand Eight Hundred Twenty only*

Assistant Engineer,
 Chakkar Sub-Division
 H.P.P.W.D. Nerchowk

Executive Engineer
 Nerchowk Division
 H.P.P.W.D. Nerchowk

Job No. 13

DNT S/N. (184) for the year 2028-26

Draft Schedule of Quantity

Estimated Cost:- Rs. 76492.00
Earnest Money:- Rs. 1600.00
Time:- One month

Name of work:- Restoration of Rain Damages on Behana Chanol Malori Road km 0/00 to 3/500
Sub Head:- Removal of Slips at R.D. 0/200 to 0/360) (M.C. Deposit)

Sr. No.	Description of item	Qty.	Rate with all taxes including		Unit	Amount
			In Figure	GST in Rs. P In Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto any height and carriage of material upto any lead, lift and other incidental complete in all respect as per Technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge.	731.98 Cum	104.50	Four and paise fifty only	Per cubic metre	76492.00
Total:-						76492.00

Draft schedule of quantity checked & approved for Rs. 76,492/- only
(Rs. Seventy six Thousand Four Hundred Ninety Two only)

Assistant Engineer,
Chakkar Sub-Division
H.P.P.W.D Ner Chowk

Executive Engineer,
Nerchowk Division,
H.P.P.W.D. Nerchowk.

DWN No. (176) FOR THE YEAR 2015-26

Job No. 14

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- AR & M/O various roads under Nerchowk Sub - Division (SH:- Providing and fixing of sign board / direction information sign board of size 900 X 600mm rectangular)(Job II)

Estimated cost :- Rs. 99,000/-
Earnest Money :- Rs. 2000/-
Time Limit Two month

Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Providing and fixing of 0.54 sqm (zero point twenty seven square metre) in rectangular of retro-reflected cautionary, mandatory and informatory sign board as per I.R.C:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting 1.5 mm (one point five millimetre) thick supported on a mild steel angle iron post 50 mm x 50 mm x 5 mm (fifty into fifty into five millimetre) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm (two hundred fifty into two hundred fifty into three hundred x six hundred) millimetre below ground level as per drawings and Technical Specification Clause 801 as per direction of entire satisfaction on Engineer-in-Charge.	3	5500.00	Rupees five thousand five hundred paise nil only	Each	99000.00
1		18				
Total:-						99000.00

[Signature]
Assistant Engineer,
Chakkar Sub-Division
H.P.P.W.D Ner Chowk

[Signature]
Right schedule of quantity approved for Rs. 99,000/-. (Rupees Ninety Nine thousand) only

[Signature]
Executive Engineer,
Nerchowk Division
D.P.P.W.D Nerchowk

DMIT Sr. No. (30) for 2028-28

Job No. 14

DRAFT SCHEDULE OF QUANTITY

Name of Works:- A/R & M/O TCCC building at SLBSGM&H at Nerchowk (SH:- Balance work of C/O Ramp along with railing) Job No. 3.

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, kg railings, brackets, gates and similar works including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	191.84	Per kg	148.15	Rupees One Hundred FourtyEight and Paise Fifteen Only	28421.00
2	Finishing walls with Acrylic Smooth exterior paint of required shade of approved brand i.e. Apex of Asian Paints or equivalent : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface upto all heights including cost of scaffolding and other arrangements etc. complete in all respects including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	275.21	Per Square Metre	190.55	Rupees One Hundred Ninety and Paise FiftyFive Only	52441.00
TOTAL:-						80862.00

Do not Schedule of quantity checked approved for Rs. 80,862 only
 Rs. Eighty Thousands Eight Hundred Sixty Two only

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

Draft Sr. No. (138) for the year 2025-26

Tab No. 16

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Khakhryana to Kaphara via Kurri road km. 0/0 to 2/105.
 (Sub Head :- Construction of Retaining wall in P.C.C. 1:5:10 at RD. 0/955 to 0/960.30)

Estimated Cost:- 99917.00
 Earnest Money :- 2000.00
 Time :- Two Months

S No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.82	287.00	Rupees Two hundred eighty seven and paise zero only	Per Cubic Metre	3392.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	16.82	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only	Per Cubic Metre	92124.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	7.00	287.00	Rupees Two hundred eighty seven and paise zero only	Each	2009.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	2.17	1102.50	Rupees One thousand one hundred two and paise fifty only	Per Cubic Metre	2392.00
		Total				99917.00

Draft Schedule of quantity approved for ₹ 99917 only.
 (Rs. Ninety Nine Thousand Nine Hundred Seventy only)

Executive Engineer,
 HPPWD Division,
 HPPWD Narnhowa

DNIT SRN^o 156 For The Year 2025-26

E/ Cost = ₹ 60000/-
E/ Money = ₹ 1200/-
Time = 1 month


Job No. 17

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Preparation of Working estimate for C/O Ayurvedic health centre Building at Halvater, Tehsil Balh, Distt. Mandi and preparation of contour site plan for construction of Tribal hostel building at Rewalsar, Tehsil Balh, distt. Mandi (H.P.)

Sr.No	Description of item	Qty.	Unit	Rate	Amount
1	Preparation of Working estimate of whole project as per Architectural Drawing for the C/O Ayurvedic health centre building at Halvater, Tehsil Balh, Distt. Mandi (H.P.) with W.S.& S.I. and Development of Site etc. The Job shall also include supplying detailed estimate as per analysis of rates based on HPSR 2020 /market rates for all the items appearing in the estimate. The work shall also include supplying the estimate in triplicate and approval of the same in divisional office / Circle office /CE office complete as per directions of Engineer-in-charge.	1 Job	Per Job	35000.00	₹ 35,000
2	Preparation of contour site plan of the land proposed for construction of Tribal Hostel building at Rewalsar, Tehsil Balh, Distt. Mandi, with the help of total station. The contours shall be drawn at one or two metre Contour intervals clearly showing boundary lines electric lines, roads, trees and other special features in the enclosed area. The work shall also include supplying the Contour Plan in triplicate and a soft copy in autocad file complete as per directions of Engineer-in-charge.	One Job	Per Job	25000.00	₹ 25,000
Total					₹ 60,000

Draft schedule of Quantity approved for ₹ 60,000/- only
(Rs. Sixteen Thousand only)


Assistant Engineer,
Rewalsar Sub-Division,
H.P.P.W.D. Rewalsar.


Executive Engineer
Nerchowk Division
HP PWD Nerchowk

Job No. 18

DNIT Sr.No. 32 For the year 2023-24


Draft Schedule of Quantity

Estimated Cost:-Rs. 98667.00
Earnest Money:- Rs. 2000.00
Time:- Two Month

Name of work:-Annual Repair & Maintenance of Shri Lal Bahadur Shastri Govt. Medical College & Hospital Nerchowk, Mandi HP
(SH:-Providing and laying Epoxy Flooring O.T. No. 3 of 6th floor for Robotic Surgery Room) Job No. 1

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount	
			In Figure	In words			
1	Providing and laying 2mm thick Anti static Epoxy Flooring (Make :-Asian/Berger or Equivalent) typically involve multilayer system and its complete specification. Primer applied to the prepare surface provides adhesion and durability and top coat chemical resistance and finish including covering 75mm and 4 mm thick self leveling compound with mixing adhesive for make the zero level floor including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	19.94	Per square metre	4948.20	Rupees Five Hundred Forty Four and paise twenty three only	Per square metre	98667.00
Total						98667.00	

Draft schedule of quantity checked & approved for Rs. 98,667/- only
(Rs. Ninety Eight Thousand six hundred sixty seven only)


Executive Engineer
HP, PWD, Division,
Nerchowk.

DRAFT Sr. No. 190 for 2025-26

for No. 19


DRAFT SCHEDULE OF QUANTITY

Name of Work:- Construction of Gutkar to Shiv Gufa road in Mahal Otta km. 0/0 to 2/000 (SH:- P/L water bound macadam G-II and cement concrete from RD. 0/135 to 0/170) (VKV Deposit).

Estimated Cost:-	91690.00
Earnest Money:-	1900.00
Time:- One Month	

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.39	Per Sqm	2240.00	Rupces Fourteen only	25514.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.39	Per Cum	5810.00	Rupces Four Hundred Fifty and Paise Ninety Five only	66176.00
TOTAL:-						91690.00

Draft schedule of quantity checked & approved for Rs. 91,690/- only (Rs. Ninety one Thousand six Hundred Ninety only)


 Executive Engineer
 Nerchowk Division
 MPPWD Nerchowk

DWT SR. No. 185 for the year 2025-26

Vol No. 20


DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of damages caused due to laying of H.D.P.E. Pipe line on Mandi Gagal Chailchowk Janjehali Chattri Rana Ka Bag road km. 0/0 to 16/190 (SH:- C/O unlined surface drain in km. 11/500 to 12/730) (Deposit).

Estimated Cost:-	99630.00
Earnest Money:-	2000.00
Time:-	One Month

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in all type of soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1230.00	Rmt	81.00	Rupees Eighty One only	99630.00
TOTAL:-						99630.00

1230 schedule of quantity checked & approved for Rs. 99,630/only (Rs. Ninety Nine Thousand six Hundred Thirty only)


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNIT SR.No. (183) for the year 2025-26

Sheet No. 21

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkar Sub-Division, HPPWD Nerchowk (SH:- Hiring of Tipper with lift system for carriage of muck/debris and shifting of material etc.) (Gagal Section).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. The Tipper should work minimum 8.00 hours (Eight hours) from 9:00 AM to 5:00PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver, repair work shall have to be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	31.00	Per Day	3200.00	Rupces Three Thousand Two Hundred Only	99200.00
TOTAL:-						99200.00

Draft schedule of quantity checked & approved for Rs. 99,200/only (Rupees Ninety Nine Thousand Two Hundred only)

ac
Assistant Engineer,
Chakkar Sub-Division
HPPWD Nerchowk

ac
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Job No 22

DNT Sr. No. 88 for 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O TCCC building at SLBSGMC&H at Nerchowk (SH:- Balance work of C/O Ramp along with railing) Job No. 1.

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				Rate with all taxes including GST in Rs. P.	In words	
1	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, kg railings, brackets, gates and similar works including cartage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	672.59	Per kg	148.15	Rupees One Hundred FourtyEight and Paise Fifteen Only	99644.00
TOTAL:-						99644.00

Soft schedule of quantity checked & approved for Rs 99,644/only (As Ninety Nine Thousand six Hundred forty four only)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT Sr. No. (188) for 2025-26

Page No. 23


DRAFT SCHEDULE OF QUANTITY

Name of Work:- Construction of Gulkar to Shiv Gufa road in Mihal Ota km. 0/0 to 2/000 (SH:- P/L water bound macadam G-II and cement concrete from RD. 0/100 to 0/135) (VKV Deposit).

Estimated Cost:-	94668.00
Earnest Money:-	1900.00
Time:- One Month	

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.76	Per Sqm	2240.00	Rupees Fourteen only	26342.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.76	Per Cum	5810.00	Rupees Four Hundred Fifty and Paise Ninety Five only	68326.00
TOTAL:-						94668.00

Draft schedule of quantity checked & approved for Rs. 94,668 only (Rs. Ninety Four Thousand Six Hundred sixty eight only)


Executive Engineer
Nerchowk Division
PPVVD Nerchowk

DVT Sr. No. 27 for the year 2025-26

Sl. No. 24

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O Aal Medical Research University (AMRU) in the campus of Shri Lal Bahadur Shastri Govt. Medical College & Hospital, Nerchowk, Mandi (HP) (SI:- Repair work of Dome).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Providing and fixing, in position Wall paneling with ACP sheets 3mm thick of approved colour and shade including framework with concealed G.I. section for wall paneling using board of required thickness fixed on the 'W' profile (0.55 mm thick) having a knurled web of 51.55 mm and two flanges of 26 mm each with lips of 10.55 mm, placed @ 610 mm C/C in perimeter channel having one flange of 20 mm and another flange of 30 mm with thickness of 0.55 mm and web of length 27 mm. Perimeter channel is fixed on the floor and the ceiling with the nylon sleeves @ 610 mm C/C with fully threaded self-tapping dry wall screws. Board is fixed to the 'W' profile with 25 mm countersunk ribbed head screws @ 200 mm C/C., all complete as per the drawing & directions of engineer-in-charge, the joints of the boards are finished with specially formulated jointing compound and 48mm wide jointing tape to provide seamless finish including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	30.18	Per Square Metre	3311.70	Rupees Three Thousand Three Hundred Eleven and Paise Seventy Only	99947.00
TOTAL:-						99947.00

Draft schedule of quantity checked & approved for Rs. 99,947/- only (Rs. Ninety Nine Thousand nine hundred forty seven only)

[Signature]
 Executive Engineer
 Nerchowk Division
 PWD Nerchowk

Job No. 25

DNIT Sr. No. 299 for 2015-16

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O Ayal Medical Research University (AMRU) in the campus of Shri Lal Bahadur Shastri Govt. Medical College & Hospital, Nerchow k. Mandi (HP) (SH):- Painting, Distemping and Repair work in 2nd floor Dome & 3rd floor ENT Lobby).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
<p>Estimated Cost:- 99746.00 Earnest Money:- 20000.00 Time:- Two Months</p>						
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick plain edge gypsum plain board of Saint Gobain or equivalent, conforming to IS: 2095- (Part J) : 2011 (Board with BIS Certification marks) including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	24.18	Per Square Metre	1532.06	Rupees One Thousand Five Hundred Thirty Two and Paise Six Only	37045.00
2	Distemping on ceiling/sloping surfaces with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (Two or more coats) upto 10.00m height complete in all respects including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	154.12	Per Square Metre	122.3	Rupees One Hundred Twenty Two and Paise Thirty Only	18849.00
3	Distemping on ceiling/sloping surfaces with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (Two or more coats) upto all height complete in all respects including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	166.43	Per Square Metre	76.75	Rupees Seventy Six and Paise Seventy Five Only	12774.00

4	Distemping on walls surfaces with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (Two or more coats) complete in all respects including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	50.01	Per Square Metre	70.85	Rupees Seventy and Paise EightyFive Only	3543.00
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete in all respects including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	26.23	Per Square Metre	16.60	Rupees Sixteen and Paise Sixty Only	435.00
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete in all respects including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	50.41	Per Square Metre	136.85	Rupees One Hundred ThirtySix and Paise EightyFive Only	6899.00
7	Providing and fixing, in position Wall panelling with ACP sheets 3mm thick of approved colour and shade including framework with concealed G.I. section for wall paneling using board of required thickness fixed on the 'W' profile (0.55 mm thick) having a knurled web of 51.55 mm and two flanges of 26 mm each with lips of 10.55 mm, placed @ 610 mm C/C in perimeter channel having one flange of 20 mm and another flange of 30 mm with thickness of 0.55 mm and web of length 27 mm. Perimeter channel is fixed on the floor and the ceiling with the nylon sleeves @ 610 mm C/C with fully threaded self-tapping dry wall screws. Board is fixed to the 'W' profile with 25 mm countersunk ribbed head screws @ 200 mm C/C., all complete as per the drawing & directions of engineer-in-charge, the joints of the boards are finished with specially formulated jointing compound and 48mm wide jointing tape to provide seamless finish including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	6.10	Per Square Metre	3311.70	Rupees Three Thousand Three Hundred Eleven and Paise Seventy Only	20201.00
TOTAL:-						99746.00

Staff schedule of quantity checked & approved for Rs. 99,746/- only (Rs. Ninety Nine Thousand seven hundred forty six only)

[Signature]
 Executive Engineer
 Ketchowk Division
 PPMWD, Ketchowk

DRAFT SCHEDULE OF QUANTITY (199) for the year 2025-26

Vol No. 26

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division, HPPWD Nerchowk. (SH:- Hiring of Tractor with trolly for carriage of muck/ debris and shifting of materials etc.) (Gagal Section).

Estimated Cost:-	97350.00
Earnest Money:-	2000.00
Time:-	Two Months

S. No.	Description of item	Qty.	Rate with all taxes including		Unit	Amount
			GST in Figure	Rs. P. Words		
1	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	59.00	1650.00	Rupess One Thousand Six Hundred Fifty only	Per day	97350.00
Total:-						97350.00

Draft schedule of quantity checked & approved for Rs. 97,350/- only (Rs. Ninety seven Thousand Three Hundred Fifty only).

(Signature)
(Signature)
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNIT Sr. No. (203) for the year 2025-26

Job No. 27


Draft Schedule of Quantity

Estimated Cost:- 98700.00
Earnest Money:- 2000.00
Time:- Two Month

Name of work:- Restoration of rain damages on various roads under Chakkar Sub Division
Sub Head:- Providing dual directional delinators for road side with plastic head un breakable at neck .

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing dual directional delinator made out of 18 guage (Eighteen guage) MS rectangular pipe of size 25x68mm (twenty five into sixty eight millimetres) and of length 600mm (six hundred millimetre). Pipes stove enamelled and baked to 120 C (one hundred twenty degree centigrade) or powder coated. Head made out of ABS plastic rectangular moulded with flat face provided with high intensity prismatic reflectors of colour white/yellow/red of size 100x125mm (one hundred into one hundred twenty five millimetres) with additional 2 (two) reflective strips of 20mm (twenty five millimetres) wide make green light for road side with plastic head unbreakable neck including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	94.00 Sqm.	1050.00	Rupees One Thousand Fifty and paise nil only	Sqm.	98700.00
Total:-						98700.00

Draft schedule of quantity checked & approved for Rs. 981700/- only
(Rs. Ninety Eight Thousand Seven Hundred only).


Executive Engineer,
Nerchowk Division,
HP PWD Nerchowk

DNIIT Sr. No. (267) for the year 2025-26

Lab No. 28

Draft Schedule of Quantity

Estimated Cost:- 97850.00
Earnest Money:- 2000.00
Time:- Two Month

Name of work:- Restoration of rain damages on various roads under Chakkar Sub Division
(Sub Head:- Providing high intensity Engineer Grade prismatic sheeting)

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing high intensity Engineer grade prismatic sheeting on the front side of existing W- Metal beam crash barrier size 300X450mm in yellow and white colour at site including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	103.00 Sqm.	950.00	Rupees Nine Hundred Fifty and paise nil only	Sqm.	97850.00
Total:-						97850.00

Draft schedule of quantity checked & approved for Rs. 97,850/- only
(Rs. Ninety seven Thousand Eight Hundred Fifty only).

Executive Engineer,
Merchowsk Division,
HP. RWD, Merchowsk

Job No. 29

DMIT S.N.No. (198) for the year 2005-06


DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Tanda-Kohla -Tikkari -Kawalkot Sidhkothi (Via Baba Balak Nath Mandir) Thapla Gobhol Galoo road Km 0/0 to 5/150. (Sub Head :- Preparation of working estimate of additional work)

Estimated Cost:- 98500.00
Earnest Money :- 2000.00
Time :- One Month

S.N	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Job work for preparation of working estimate of additional work such as Cross-drainage work, Retaining Walls, Breast Walls & other necessary provision taken in the estimate, preparation of working estimate duly approved from the Circle Office & Chief Office. Three sets of working estimate and soft copies in the form of Compact Disc (C.D.) complete as per directions of Engineer in charge.	1	98500.00	Rupees Ninety Eight Thousand Five Hundred and paise zero only.	Per Job	98500.00
					Total	98500.00

Soft estimate of quantity checked & approved for Rs. 98,500/- only (Rs. Ninety Eight Thousand Five Hundred only).


Executive Engineer,
HBPWD Division
Berhampur

DMIT Sr. No. (34) for the year 2025-26

Lab No. 30

Draft Schedule of Quantity

Estimated Cost:-Rs. 97677.00

Earnest Money:- Rs. 2000.00

Time:- Two Month

Name of work:-Annual Repair & Maintenance of Shri Lal Bahadur Shastri Govt. Medical College & Hospital Nerchowk, Mandi HP

(SH:-Providing and laying Epoxy Flooring O.T. No. 3 of 6th floor for Robotic Surgery Room) Job No. II

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount	
			In Figure	In words			
1	Providing and laying 2mm thick Anti static Epoxy Flooring (Make :-Asian/Berger or Equivalent) typically involve multilayer system and its complete specification. Primer applied to the prepare surface provides adhesion and durability and top coat chemical resistance and finish including coving 75mm and 4 mm thick self leveling compound with mixing adhesive for make the zero level floor including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	19.74	Per square metre	4948.20	Rupees Five Hundred Forty Four and paise twenty three only	Per square metre	97677.00
Total							97677.00

Draft schedule of quantity checked & approved for Rs. 97,677/- only (Rs. Ninety seven Thousand six Hundred seventy seven only)


Executive Engineer,
HP PWD Division,
Nerchowk.

DNIT Sr.No. (109) for the year 2025-26
DRAFT SCHEDULE OF QUANTITY

Job No 31

Name of Work:- Restoration of rain damages on Galma Manjhyali road km. 0/00 to 9/00 (SH:- C/O R/wall at RD. 2/750 to 2/754).

Estimated Cost:- 97398.00
Earnest Money Cost:- 2000.00

Sr. No.	Item Description	Quantity	Unit	Time:- One Month		
				Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earthwork in excavation for foundation of structures upto 3 mtr. depth as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling in trenches with excavated suitable material, ordinary soil including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic metre	287	861.00	Rupees Two Hundred TwentyFour Only
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:6:12 (1 cement: 6 sand: 12 graded stone aggregate 40mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.88	Per cubic metre	3250	9360.00	Rupees Nine Thousand Three Hundred Sixty Only
3	Random Rubble stone masonry in cement mortar (1:6) (One cement: Six sand) for sub structure complete as drawing and technical specification of Ministry of Rural road Development for Rural road clauses 702, 704, 1202 and 1204 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.22	Per cubic metre	3840	46925.00	Rupees Fourty Six Thousand Nine Hundred TwentyFive Only
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (1 cement: 4 sand: 8 graded stone aggregate 40mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.76	Per cubic metre	5000	8800.00	Rupees Eight Thousand Eight Hundred Only

Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.95	Per cubic metre	2250	24638.00	Rupees TwentyFour Thousand Six Hundred ThirtyEight Only
6 Back-filling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.40	Per cubic metre	1102.50	4851.00	Rupees Four Thousand Eight Hundred FiftyOne Only
TOTAL:-				97398.00	Rupees NinetySeven Thousand Three Hundred NinetyEight Only

I draft schedule of quantity checked & approved for Rs. 97,398/only (Rs. Ninety seven Thousand Three Hundred Ninety Eight only).

eeel

Executive Engineer
Nerchowk Division
HPPWD-Nerchowk

DMIT Sr. No. 191 for the year 2025-26

Job No. 32

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ratti to Randhara road km. 0/0 to 9/000 (SH:- C/O PCC R/wall at RD. 3/410 to 3/414).

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in		Amount
				Rs. P.	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	2778.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.32	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	89676.00
3	Providing Weep holes in Brick masonry/ Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1 (V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	2296.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.20	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	4631.00
TOTAL:-						99381.00

Draft schedule of quantity checked & approved for Rs. 99,381/only (Rs. Ninety Nine Thousand Three hundred Eighty one only).

Executive Engineer
Nerchowk Division
PPWD Nerchowk