Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2025-2026- 25362-63 Dated:- 27/2/26

To

The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.

Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .

Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

1. Date of receipt of application for tender forms:- 06-03-2026 10:00 AM upto 12:00 PM
2. Dated of Issue /sale of tender forms:- 06-03-2026 12:00 PM upto 4:00 PM
3. Date of receipt of tender:- 07-03-2026 .up to 10:30 AM
4. Date of opening of tender:- 07-03-2026 up to 11:00 AM

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O to various residential Qtrs. Under Kasumpti Sub-Division Shimla-9 (SH:- Supplying of material to Sub-Division No. VIII Parimahal Section Shimla-9).	99651/-	2000/-	350/-	30 days	Class-D
2	A/R & M/O to various residential Qtrs. Under Kasumpti Sub-Division Shimla-9 (SH:- Supplying of material to Sub-Division No. VIII Parimahal Section Shimla-9).	99989/-	2000/-	350/-	30 days	Class-D
3	Restoration and rain damages on HIPA road Km. 0/00 to 0/450 (SH:- Disposal of muck white washing on side drain & Parapits).	95700/-	1800/-	350/-	30 days	Class-D
4	Restoration of rain damages on Dharech to Khangna to Kawanti road Km. 0/000 to 8/700 (SH:- C/O R/Wall at RD. 0/930 to 0/945) (Under PDNA).	440653/-	8800/-	350/-	30 days	Class-D
5	Restoration of rain damages on Baldeyan to Shenal road Km. 0/00 to 4/720 (SH:- Construction of retaining wall at RD. 1/012 to 1/026) (Under PDNA).	499670/-	10000/-	350/-	30 days	Class-D
6	Restoration of rain damages on Baldeyan to Shenal road Km. 0/00 to 4/720 (SH: - Construction of retaining wall at RD. 2/360 to 2/375) (Under PDNA).	499850/-	10000/-	350/-	30 days	Class-D
7	C/O Zila Parishad Bhawan at Sanjauli Dhalli bye Pass (SH:- Providing and fixing MS steel ornamental fencing & prepainted sheet there in).	91897/-	1900/-	350/-	30 days	Class-D
8	Restoration of rain damages on Shimla to Mandi road Km. 0/00 to 22/00 (SH:- Widening & Improvement of road RD. 17/390 to 17/465(Under PNDA).	307125/-	6100/-	350/-	30 days	Class-D
9	Special repair to Police Barracks for 40 Nos. NGO GD-II at Bn. Head Quarter at Junga (SH:- Special repair thereof) (Balance Work).	33522/-	700/-	350/-	30 days	Class-D
10	C/O Zila Parishad Bhawan at Sanjauli Dhalli Bye Pass (SH: - Providing and fixing MS steel fencing with preprinted sheet there in front side).	91994/-	1800/-	350/-	30 days	Class-D
11	R/R Damages on Mashobra to Bhaikalty road Km. 0/00 to 18/00 (SH: - C/O R/Wall at RD. 3/915 to 3/931.40)(Under PDNA).	499844/-	9997/-	350/-	30 days	Class-D
12	A/R & M/O various type-I to VI Qtrs. at mehli Shimla-9 (SH:- Providing roof painting due block-3 & 4 transit accommodation at Mehli Shimla.	99998/-	2000/-	350/-	30 days	Class-D
13	A/R & M/O various type-I to type-VI Qtrs. at Mehli Shimla-9 (SH: - Providing and fixing Cup-Board in Type-IV set No.15 at Mehli Shimla (H.P).	92018/-	1800/-	350/-	30 days	Class-D
14	A/R & M/O to Shoghi Mehli Junga Sadhupul road Km. 12/375 to 48/925 (SH:- Providing and fixing of road studs (Hill side) at RD 23/450 to 24/300).	97890/-	2000/-	350/-	30 days	Class-D
15	A/R & M/O to Shoghi Mehli Junga Sadhupul road Km. 12/375 to 48/925 (SH: - Providing and fixing of road studs (Valley side) at RD 23/450 to 24/300).	97110/-	2000/-	350/-	30 days	Class-D
16	C/O link road from Durgapur to Banedi road Km. 0/00 to 2/700 (SH: - Preparation of Geo referenced Digital Map and collection data for FRA.	70000/-	1500/-	350/-	30 days	Class-D
17	A/R & M/O various type-I to VI GAD at Kasumpti Shimla-9 (SH:- Providing and fixing Cupboard and change of damaged wooden flooring in type-VI set No.6 at Kasumpti Shimla-6).	94643/-	1800/-	350/-	30 days	Class-D
18	A/R & M/O various type-I to VI GAD at Kasumpti Shimla-9 (SH:- Providing and fixing Cupboard in type-III set No.5 set No.23 accommodation set No.4,5 at Mehli Shimla (Balance work).	99116/-	2000/-	350/-	30 days	Class-D
19	C/O link road from Craignano to Sadhora via sharei to Koti Resort road Km. 0/00 to 2/500 (SH: - Preparation of Geo referenced Digital Map and collection data for FRA).	70000/-	1500/-	350/-	30 days	Class-D
20	A/R & M/O various type –III & IV GAD at Kasumpti Shimla-9 (SH:- Repair work in Kitchen in type-III-125, Repair od drain with type-V (Set No. 19 to 22) approach and Providing and fixing Grating etc under Kasumpti Sub-Division).	99623/-	2000/-	350/-	30 days	Class-D
21	Restoration of rain damages on Shimla Mandi road in Km. 6/00 to 22/00 (SH:- C/O B/Wall at RD 20/615 to 20/626) (Under PDNA).	495160/-	9900/-	350/-	30 days	Class-D
22	Restoration of rain damages on Shimla to Mandi road Km. 6/000 to 22/000 (SH:- C/O B/Wall at RD 20/630 to 20/637) (Under PDNA).	468298/-	9400/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.
14.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2025-2026- 25364-78 Dated :- 27/12/25

Copy forwarded to:-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Dsitt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.

Estimated Cost: Rs 99651.00

Earnest Money :- 2000.00

Time:- One Month.

Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Parimahal Section Shimla-9).

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	In words	Unit	Amount
1	Supplying of Black Nails size 20mm complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6.00	Kgs.	350.00	Rupees Three Hundred Fifty Only	Per Kilo-gram	2100.00
2	Nails 20m	6.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	1320.00
3	Nails 25m	6.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	1320.00
4	Nails 40mm to 100mm	6.00	Kgs.	145.00	Rupees One Hundred Forty Five Only	Per Kilo-gram	870.00
5	C.P. iron sliding door bolt 200x16mm	8.00	Nos	330.00	Rupees Three Hundred Thirty Only	Each	2640.00
6	C.P iron sliding door bolt 250x 16mm	5.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	1900.00
7	C.P. iron sliding door bolt 300x 16mm	5.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	2250.00
8	Iron door spring	5.00	Nos	395.00	Rupees Three Hundred Ninety Five Only	Each	1975.00
9	Hydraulic door closer (Heavy)	7.00	Nos	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Each	12950.00
10	Drawer lock (Godrej)	8.00	Nos	270.00	Rupees Two Hundred Seventy Only	Each	2160.00
11	C.P.Tel Mixer ESS ESS Premium range	6.00	Nos	5760.00	Rupees Five Thousand Seven Hundred Sixty Only	Each	34560.00
12	PVC Seat Cover for EVOC.	4.00	Nos	897.00	Rupees Eight Hundred Ninety Seven Only	Each	3588.00
13	PVC Seat Cover for Anglo Indian with Hinges.	4.00	Nos	850.00	Rupees Eight Hundred Fifty Only	Each	3400.00
14	S.S. Greating 110mm (Heavy) with frame.	6.00	Nos	158.00	Rupees One Hundred Fifty Eight Only	Each	948.00
15	Gate Valve 20mm (Heavy)	3.00	Nos	850.00	Rupees Eight Hundred Fifty Only	Each	2550.00
16	Glass Corner Shelf for Tuffon Glass with S.S. Railing & Brackets	8.00	Nos	1890.00	Rupees One Thousand Eight Hundred Ninety Only	Each	15120.00
17	S.S Curton Rod 12" Long S.S. 304 Grade	8.00	Nos	925.00	Rupees Nine Hundred Twenty Five Only	Each	7400.00
18	CP/ Gyser connection pipe 19"	8.00	Nos	325.00	Rupees Three Hundred Twenty Five Only	Each	2600.00
	TOTAL						99651.00

T/s No. 25023241 21/9/26 Amounting to Rs. 102429/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.

Estimated Cost: Rs 99989.00

Earnest Money :-2000.00

Time:- One Month.

Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Parimahal Section Shimla-9).

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	In words	Unit	Amount
1	Sink Mixer heavy duty make ESS ESS Premium Range	8.00	Nos	4848.00	Rupees Four Thousand Eight Hundred Forty Eight Only	Each	38784.00
2	CP Bib Cock Delux long body make ESS ESS premium Range	12.00	Nos	1790.00	Rupees One Thousand Seven Hundred Ninety Only	Each	21480.00
3	Teflon Tape roll	8.00	Nos	140.00	Rupees One Hundred Forty Only	Each	1120.00
4	Zet L type	5.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	3250.00
5	Fastner 4" complete set	3.00	Nos	70.00	Rupees Seventy Only	Each	210.00
6	Nariyal Broom/ Phool Broom with clamp	8.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	960.00
7	Sliding door bolt 250mm stainless steel heavy duty	12.00	Nos	1950.00	Rupees One Thousand Nine Hundred Fifty Only	Each	23400.00
8	CPVC solution large pack	12.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	5400.00
9	White Cement packing	5.00	kg	45.00	Rupees Forty Five Only	kg	225.00
10	C.P Angle cock make ESS ESS Premium Range	4.00	Nos	1290.00	Rupees One Thousand Two Hundred Ninety Only	Each	5160.00
							99989.00

T/S No. 25025-26 21-2 26 dated 2-1-26 Amounting to Rs. 102330/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

CONDITION:-

1 Rates should be quoted for all heighus including all leads and lifts.

2 Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.	Estimated Cost:-95700.00
Name of Work :- Restoration and Rain damages on HIPA road km 0/00 to 0/450 (SH:- Disposal of muck , white washing on side drain & Parapits)	Earnest Money :- 1800.00
	Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Disposal of muck excavated Earth /Removal of Slipes/ Malba/Similar unservicible, dismantle or waste materials by mechanical transport including loading, unloading & disposal up to all leads & lifts including arranging the dumping site at its own cost all taxes etc the payment shall be made for dumping site by contrector for dumping site arranged by the contractor at private property or Govt. land as per the direction of Engineer-in- Charge.	270.00	Cum	300.00	Rupees Three Hundred Only	Per Cubic Meter	81000.00
2	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	500.00	Sqm	29.40	Rupees Twenty Nine and Paise Forty Only	Per Square Meter	14700.00
	Quoted rates Percentage in words						
	G.Total						95700.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual

T/s No 25105-66 dated 21-2-26 Amounting to Rs. 98571/-

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., .

Estimated Cost:- 4,40,653.00

Name of Work :- Restoration of Rain damages on Dharech to Khangna to Kawanti road Km 0/000 to 8/700. (SH:- C/O R/Wall at Rd 0/930 to 0/945).

Earnest Money :- 8,800.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	36.90	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	11993.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	7.65	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	3060.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6:12 (One cement:Six sand: Twelve graded stone agg.40mm nominal size).	7.65	Cum	3600.00	Rupees Three Thousand Six Hundred Only	Per Cubic Metre	27540.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate20 mm(Twenty milimetre) nominal size).	78.45	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic Metre	376560.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	40.00	Rmt	200.00	Rupees Two Hundred Only	Per Running meter	8000.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	11.25	Cum	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	13500.00
						Total	**440653.00**
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:- 4,99,670.00

Name of Work:--Restoration of Rain damages on Baldheyan to Shenal road km. 0/00 to 4/720. (SH:- Construction of retaining wall at Rd. km1/012 to 1/026)(UNDER PDNA)

Earnest Money :10,000 .00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	20.00	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	6500.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	5.00	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	2000.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. a) Cement Mortar 1:6:12(1one cement: six sand: twelve graded stone agg.40mm nominal size).	5.00	Cum	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	17000.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate20 mm(Twenty milimetre) nominal size).	98.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	450800.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	13.00	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	13650.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	54.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	9720.00
						Total	**499670.00**
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

DNIT approved for Rs.4.99,670/- Only (Rupees Four Lac ninety nine Thousand six hundredseventy only) vide DNIT Register Sr.No. 546 the financial year 2025-26..T/S No 25198.99 dated 242/26 amounting to Rs. 5,14,660/-

1. Rates should be quoted for all heights including all leads and lifts.

2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use in work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HP PWD Division.
Kasumpti Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER Kusumpti DIVISION H.P.P.W.D.SHIMLA-3.

Estimated Cost:-91897.00

Name of Work :- Construction of Zila Parishad. Bhawan at Sanjauli Dhalli bye (SH:- Providing and fixing MS Steel ornamantal fancing & prepainted sheet there in)

Earnest Money :- 1900.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit.	Amount
1	Steel work welded in built up sections. framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings. framed guards bars ladders. railing. brackets and similar work. in or as per direction of the Engineer- in - Charge .	679.52	Kgs.	105.00	Rs One hundred and five only	Per Kilogram	71350.00
2	Providing and fixing 0.47mm to 0.50mm thick (Zero point thirty seven milimeter) thick prepainted steel both side green in partition with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic ting of 20 microns over 5 microne primer coating to back coat of polyster of 5 microns over a microns primer i/c fixing with self drilling screws 55mm size with prepainted it and rubber washer complete with all accessories as required as per the directions of Engineer-in-Charge make TATA Dura shine.	15.22	Sqm	1350.00	Rs One thousand three hundred fifty only	Per Square Metre	20547.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	91897.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division
Kasumpti Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.

Estimated Cost:-3,07,125.00

Name of Work :- Restoration of Rain damages on Shimla to Mandi road Km 0/00 to 22/00 (SH:- Widening & Improvement of road Rd 17/390 to 17/465(UNDER PDNA)

Earnest Money :- 6100.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Cutting in earth work in all heights in all kinds of soil including saturated soils comprising of Pick work , jumper work and blasting work both in soft and hard rock , with chiseling and wedging out of rock (where blasting in Prohibted) and their intermediate classification of soils including dewatering wherever required setting out true to the required by Engineer - in charge at site according to the HPP.WD specifications of 1990 volume - 1 and sorting of useful and un- useful materials and stacking the same in all lead and lifts and transporation of the un-useful materils for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materilas in acquired width of the road or on approved dumping site / sites through all modes of transportaing inscluding head loads , animal loads , machinery materils tools , equipment and safety measures and other incidental necessery to complets the work by mechanical means and / or labour (if any required) the cost of useful materials such as stones shingles aggergate and statrs shallbe slotedout and stacking along road side 13.09 cum stine will be recovered @ 300/- cum which shall not be blasting work which shall be proportinately increases decreases as the quality of earth work increase in alll cases recovered from the contractor at the rate of per cubic metere shall be effected any loss to the public and private property durinng the case of execution shall be absolute responsibility of contractor which shall have to be duly compensated by him in all respects.	975.00	Cum	315.00	Rupees Three Hundred Fifteen Only	Per Cubic Metre	307125.00
	Quoted rates Percentage in words						
	G.Total						307125.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual

T/s No. 25200-02 dated 24-2-26 Amounting to Rs. 3163391/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.	Estimated Cost:- 33,522.00
Name of Work :- Special repair to Police Barracs for 40 Nos NGO GDEII at Bn Head Quarter at Junga (SH:- Special repair thereof).(Balance Work).	Earnest Money :- 700.00
	Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	319.26	Kg	105.00	Rupees One Hundred Five Only	Per Kilogramme	33522.00
						Total	**33522.00**
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., | **Estimated Cost:- 91994=00**

Name of Work :- C/O Zila Parishad bhawan at Sanjuali Dhalli bye Pass (SH:- | **Earnest Money : 1800=00**

(SH:- Providing and fixing MS steel fencing with prepainted sheet there in Front side | **Time:- One Month.**

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Steel work welded in built up sections, framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work. ornamental work.	649.52	Kg	110.00	Rs one hundred and five only	Per kilo gramme	71447.20
2	Providing and fixing 0.47 to 50mm (Zero point forty seven to fifty milimeter) thick prepainted steel liner in partition with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic ting of 20 microns over 5 microne primer coating to back coat of polyster of 5 microns over a microns primer i/c fixing with self drilling screws 55mm size with prepainted it and rubber washer complete with all accessories as required as per the directions of Engineer-in-Charge. Tata make .	15.22	Sqm	1350.00	Rs one thousand thre hundred only	Per square Metre	20547.00
						Total	**91994.20**

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-

T/s No 10792-93 dated 22/9/23 Amounting to Rs. 94754/-

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY.

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:- 499844.00

Name of Work :- R/R Damages on Mashobra to Bhaikalty Road Km 0/00 to 18/00 (SH :- C/O R/Wall at RD 3/915 to 3/931.40 (Under PDNA)

Earnest Money :- 9997.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	69.54	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	22601.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	7.71	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	3084.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a)PCC 1:6:12 (40 mm aggregate)	7.71	Cum	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	26214.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a)PCC 1:4:8 aggregate20 mm(Twenty milimetre) nominal size).	95.25	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	438150.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 HPSR 2009 Item No 12.14 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.30	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	2415.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	41.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	7380.00
					Total		**499844.00**

(T/S No 224192 Dated 12-2-25 Amount to Rs.....T /S Amount 514839.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-

Executive Engineer,
HP PWD Division
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.

Name of Work :- A/R & M/O various Type I to Type-VI Qtrs at Melhi Shimla-9. (SH:- Providing Roof painting due Block 3 & 4 Transit accommodation at Melhi Shimla

Estimated Cost:-99998.00
Earnest Money :- 2000.00
Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1.00	Applying Modrent solution on GI Sheet for preparation of surface for painting @ 5 liters /100 Sqm of surface and rubbing the solution with brush including throughly cleaning the surface of all oil grease sirt and other foreign matter priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	799.98	Sqm	50.00	Rupees Fifty Only	Per Square Meter	39999.00
2.00	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarlied on undecorated wall surfaces (two coats) to give an even shade and final finish after throughly leaning the surface to remove all dirt, dust and other foreign matter etc. including sand paper smooth complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	799.98	Sqm	75.00	Rupees Seventy Five Only	Per Square Meter	59998.50
p	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	99997.50

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

T/s No 250687 dated 25-2-26 Amounting to Rs. 2102998/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.

Estimated Cost:92018.00

Earnest Money :- 1800.00

Time:- One Month.

Name of Work :- A/R & M/O various Type I to Type-VI Qtrs at Melhi Shimla-9. (SH:- Providing and Fixing Cup boards in Type - IV set No 15 at Melhi Shimla (H.P)

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1.00	Providing and fixing HDMR Board including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 19mm thick.	26.98	Sqm	2300.00	Rupees Two Thousand Three Hundred Only	Per Square meter	62054.00
2.00	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	4.25	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	5738.00
3.00	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 6mm thick	7.00	Sqm	650.00	Rupees Six Hundred Fifty Only	Per Square Meter	4550.00
4.00	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.41	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Metre	4190.00
5.00	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of matrials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	31.00	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	2015.00
6.00	Providing and fixing magnetic Catchers ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	20.00	Nos	55.00	Rupees Fifty Five Only	Each	1100.00
7.00	Providing and fixing bright SS Handles , ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. 125 mm	20.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	5000.00
8.00	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	29.40	Sqm	45.00	Rupees Forty Five Only	Per Square Meter	1323.00

9.00	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enemal paint.	29.40	Sqm	70.00	Rupees Seventy Only	Per Square Meter	2058.00
10.00	Painting **one coats**(excluding priming coat) on previously painted wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters sand papering and stopping . including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint	66.50	Sqm	60.00	Rupees Sixty Only	Per Square Metre	3990.00
P	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	92018.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

T/s No. 25088-89 dated 25-2-26 Amounting to Rs. 94779/-

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.	Estimated Cost:- 97,890.00
Name of Work :- A/R & M/O to Shoghi Mehli Junga Sadhupul road Km 12/375 to 48/925 (SH:- Providing and Fixing of Road Studs (Hill side) at RD 23/450 to 24/300).	**Earnest Money :- 2,000.00**
	Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and Fixing cat eye make (3m) of size 100x20mm made of heavy duty body shall be molded dual ASA/Acyclic Styrene Acrylonitrile or HP/High impact polystyreaon on ABS having electronically welded micro prisnatics lens with abrasion resistant coating as approved by Engineer-in-Charge. The road stud shall support a load of 13635 bt tesdted in accordance with ASTMD4280. The slope of retro reflective surface shall be 35+/-5degree to hences. The reflective panel on both side with at least 12cm of each area side. Te luminance intesity should be as pac the specification ASTM as recommended in BS-S873 part 41973 as per approved sample and manufacture by the Engineer-in-Charge including carriage of material within all leads and lifts the rate are inclusive of octroi, rayality, malkana GST, toll tax, sale tax or other taxes imposed by the Government.	251.00	Nos	390.00	Rupees Three Hundred Ninety Only	Per Each	97890.00
						Total	**97890.00**
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.	Estimated Cost:- 97,110.00
Name of Work :- A/R & M/O to Shoghi Mehli Junga Sadhupul road Km 12/375 to 48/925 (SH:- Providing and Fixing of Road Studs (Valley side) at RD 23/450 to 24/300).	Earnest Money :- 2,000.00
	Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and Fixing cat eye make (3m) of size 100x20mm made of heavy duty body shall be molded dual ASA/Acyclic Styrene Acrylonitrile or HP/High impact polystyreaon on ABS having electronically welded micro prisnatics lens with abrasion resistant coating as approved by Engineer-in-Charge. The road stud shall support a load of 13635 bt tesdted in accordance with ASTMD4280. The slope of retro reflective surface shall be 35+/-5degree to hences. The reflective panel on both side with at least 12cm of each area side. Te luminance intesity should be as pae the specification ASTM as recommended in BS-S873 part 41973 as per approved sample and manufacture by the Engineer-in-Charge including carriage of material within all leads and lifts the rate are inclusive of octroi, rayality, malkana GST, toll tax, sale tax or other taxes imposed by the Government.	249.00	Nos	390.00	Rupees Three Hundred Ninety Only	Per Each	97110.00
						Total	**97110.00**
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.

Estimated Cost:-70000.00
Earnest Money :- 1500.00
Time:- One Month.

Name of Work :- C/O link road from Durga pur to Banedi road Km 0/00 to 2/700 (SH:- Preparation of Geo referenced Digital Map and collection data for FRA

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Preparation of Geo reference digitial map and collecting of the data for proposed site including field visit preparation of KMI files with Geo coordinates along with marking of habitations to be benefited by construction of project and dumping area of proposed site . Making the aligement in soft copy and submission in hard copy . Processing the case for preparation of forest diversion under forest conservation ACT 2006 (FRA for short) including preparation of revenue paper for land acquire in thee projects & collection of other field data and all relevant document formats mandatory required to be attached with thee case as per latest requirement of of ministry of environment and forest conservation Govt of India letter No. 11-9/98 FC (PT) dated 3 rd august 2009 dehrudun after getting the joint inspection of site including computer typing of six copy to the case biniding complete and gating in through from DFO including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accuately filling in all the formats documents online submission rectifying observations and receiving approvals in all respects as per the direction and complete citification of user Agency and forest Department the rates are inclusive of octop royalty malkans tool GST or other taxes imposed by the govermnent including carriage of all equipments with in all leads and lifts as per direction of Engineer - in charge .	1.00	per case	70000.00	Rs Seventy thousand only	Per Job	70000.00
	Quoted rates Percentage in words G.Total						70000.00

DNIT approved for Rs.70,000/- Only vide DNIT Register Sr.No. 557 the T/s No. 25104-05 dated 25-2-26 Amounting to Rs. 72100/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.	Estimated Cost:94643.00
Name of Work :- A/R & M/O various Type-I to Type-VI GAD at Kasumpti, Shimla-9. (SH:- Providing and fixing Cupboard and change of damaged wooden flooring in Type VI set No .6 at kasumpti Shimla - 9	Earnest Money :-1800.00 Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1.00	Providing and fixing 19mm thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	8.79	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	11867.00
2.00	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 9mm thick	1.87	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Meter	1777.00
3.00	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	17.57	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Metre	14935.00
4.00	Providing and fixing magnetic Catchers ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.00	Nos	55.00	Rupees Fifty Five Only	Each	220.00
5.00	Providing and fixing SS Handles , ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. 120 mm	8.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	2000.00
6.00	Providing and fixing PVC Tucker tap section including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	24.44	Rmt	55.00	Rupees Fifty Five Only	Per Running metre	1344.00

7.00	Providing and fixing HDF Decorative laminated coir board German floor AC -4 32.8 mm thick placed on cushion of 2 mm thick expanded polythene foam 100 micron thick polythene under layer including boader of required shade and colour complete in all respect as per specifications of architcural drawing no .254 of job no 3977 including carriage of materials in all leads and lifts	25.00	Sqm	2500.00	Rupees Two Thousand Five Hundred Only	Per Square Metre	62500.00
nar	Quoted rates Percentage in words						
						G.Total	94643.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

T/s No 25090-91 dated 25-2-26 Amounting to Rs. ~~9748~~ 97,483/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.	Estimated Cost:- Rs. 99116.00
Name of Work :- A/R & M/O various Type-I to Type-VI GAD at Kasumpti, Shimla-9. (SH:- Providing and fixing Cupboard in Type - IIIset No - 5 set No -23 accommodation set No 4 , 5 at Melhi shimla (Balance work)	Earnest Money :2000.00 Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1.00	Providing and fixing 19mm thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	39.49	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	53312.00
2.00	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	18.99	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Metre	16142.00
3.00	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 6 mm thick	12.50	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	7500.00
4.00	Providing and fixing square edged cover fillets (Beading) 19mm x 6mm section including mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Ist ClassDeodar wood.	85.10	Rmt	65.00	Rupees Sixty Five Only	Per Running Metre	5532.00
5.00	Providing and fixing magnetic Catchers ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	30.00	Nos	55.00	Rupees Fifty Five Only	Each	1650.00
6.00	Providing and fixing SS Handles , ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. 125 mm	30.00	Nos	170.00	Rupees One Hundred Seventy Only	Each	5100.00
7.00	Applying priming coat over new concrete and plaster based surfaces after and i/c preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting including carriage of mateirals in all leads and lifts as per directions of the Engineer-in-Charge. (a)Ready mixed paint brushing cement primer.	91.48	Sqm	38.00	Rupees Thirty Eight Only	Per Square Metre	3476.00

8.00	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt,dust and other foreign matter including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint	91.48	Sqm	70.00	Rupees Seventy Only	Per Square Metre	6404.00
vis	Quoted rates Percentage in words						
						G.Total	99116.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 2596-97 dated 25-2-26 Amounting to Rs. 102090/-

Executive Engineer,
Kasumpti Division,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.

Estimated Cost:-70000.00

Name of Work :- C/O link road from Craignano to Sadhora via sharei to Koti Resort road Km 0/00 to 2/500 (

Earnest Money :- 1500.00

SH:- Preparation of Geo referenced Digital Map and collection data for FRA

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Preparation of Geo reference digitial map and collecting of the data for proposed site including field visit preparation of KMI files with Geo coordinates along with marking of habitations to be benefited by construction of project and dumping area of proposed site . Making the aligement in soft copy and submission in hard copy . Processing the case for preparation of forest diversion under forest conservation ACT 2006 (FRA for short) including preparation of revenue paper for land acquire in thee projects & collection of other field data and all relevant document formats mandatory required to be attached with thee case as per latest requirement of of ministry of environment and forest conservation Govt of India letter No. 11-9/98 FC (PT) dated 3 rd august 2009 dehrudun after getting the joint inspection of site including computer typing of six copy to the case biniding complete and gating in through from DFO including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accuately filling in all the formats documents online submission rectifying observations and receiving approvals in all respects as per the direction and complete citification of user Agency and forest Department the rates are inclusive of octop royalty malkans tool GST or other taxes imposed by the governnent including carriage of all equipments with in all leads and lifts as per direction of Engineer - in charge .	1.00	per case	70000.00	Rs Seventy thousand only	Per Job	70000.00
	Quoted rates Percentage in words	G.Total					70000.00

T/s No. 95102.03 dated 25.2.26 Amounting to Rs. 72600/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual

Executive Engineer.
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.	Estimated Cost:99623.00
Name of Work :- A/R & M/O various Type-III & Type-IV GAD at Kasumpti, Shimla-9. (SH:- Repair work in kitchen in Type - III-125, Repair od Drain with Type -V(set no 19 to 22) approcach and Providing and fixing Grating etc under Kasumpti sub - Division)	Earnest Money :- 2000.00 Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1.00	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)For thickness of tiles 10 mm to 25 mm	15.78	Sqm	55.00	Rupees Fifty Five Only	Per Square Meter	868.00
2.00	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Of area 3 sq. metres and below	1.00	Nos	300.00	Rupees Three Hundred Only	Each	300.00
3.00	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	15.78	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square Meter	19725.00
4.00	Providing and fixing 15 mm mixer for kitchen sink with top / bottom swinging spout make ESSco or Equivalent make including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00
5.00	Providing and fixing one hole basin mixing Faucet make ESSCO or Equivalent make including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00
6.00	Providing and fixingwall mixing faucet including carriage of in all leads and lifts as per directions of the Engineer-in-Charge. Make ESSCO	1.00	Nos	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00
7.00	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings including carriage of materials in all leads as per directions of the Engineer-in-Charge. (a) Flat back (i) 550mmx400mm Make ESSCO or Equivalent	1.00	Nos.	2600.00	Rupees Two Thousand Six Hundred Only	Each	2600.00

8.00	Providing and fixing 32 mm (thirty two milimetre) dia C.P. brass waste for wash basin or sink complete within all leads, lifts of materials and other incidentals. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	1.00	Nos.	450.00	Rupees Four Hundred Fifty Only	Each	450.00
9.00	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. Make ESSCO or Equivalent make .	1.00	Nos.	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Each	3250.00
10.00	Providing and fixing wire gauge in shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestorcy windows including bright finished black enamelled iron hinges with necessary screws. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	2.00	Sqm	300.00	Rupees Three Hundred Only	Per Square Meter	600.00
11.00	Disposal of muck /denris/ excavated earth upto site approved by Municipal Corporation surrounding Shimla upto all leads and lifts as per directions of the Engineer-in-Charge.	26.32	Cum	620.00	Rupees Six Hundred Twenty Only	Per Cubic Metre	16318.00
12.00	Steel work welded in built up section/ framed work , including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	266.25	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilogram	27956.00
13.00	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enemal paint.	11.25	Sqm	70.00	Rupees Seventy Only	Per Square Meter	788.00
14.00	Providing and fixing copper osidised fittings (iron) butts hinges 75x47x1.70 mm	8.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	960.00
15.00	Providing and fixing chicken mesh in wall with wood screws and nails including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	15.78	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Metre	3945.00
16.00	Dubbing out an old irregular walls average 10mm thick with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) cement mortar 1:5 (One cement: Five sand).	15.78	Sqm.	280.00	Rupees Two Hundred Eighty Only	Per Square Metre	4418.00

17.00	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)Cement Mortar 1:6 (one Cement: six Sand).	15.78	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Metre	3945.00
	Quated rates Percentage in figures						
kul	Quoted rates Percentage in words						
						G.Total	99623.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

T/s No 25092-93 dated 25-2-26 Amounting to Rs. 1026121

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:-495160.00

Name of Work :-Restoration of rain damages on Shimla to Mandi road Km 6/000 to 22/000 (SH:-C/O B/Wall at RD 20/615 to 20/626) (Under PDNA)

Earnest Money :-9900.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting in earth work in all depths and heights in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and carriage of all labour , machinery , materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labor (if any required the cost of all useful materials such as stones shingles aggregate and stats shall be slotedout and stacking along road side cum stone will be recovered @ 300 /- Cum Which shall be blasting work which shall be proportionately increase decreases as the quantity of the earth work increase decrease in all cases recovered from the contractor at	44.00	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	14300.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical	4.00	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1600.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6:12(1one cement: six sand: twelve graded stone agg.40mm nominal size).	4.00	Cum	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	13600.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate 40 mm(Forty milimetre) nominal size).	99.000	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	455400.00

5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including hauling of materials in all leads and lifts as per the same satisfaction and directions of the Engineer-in-Charge.	57.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running Meter	10260.00
					Total		**495160.00**

D/N R. NO 677/S No. 15027-28 dt 11-11-23

Amt to Rs 510015/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts. Including head load
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
Shimla Division No.I,
HP PWD-Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., .

Estimated Cost:- 4,68,298.00

Name of Work :- Restoration of Rain damages on Shimla to Mandi road Km 6/000 to 22/000. (SH:- C/O B/Wall at Rd 20/630 to 20/637).(Under PDNA).

Earnest Money :- 9,400.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Estimated Rate In words	Unit	Amount
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	58.87	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	19133.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to	4.48	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1792.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6:12 (One cement:Six sand: Twelve graded stone agg.40mm nominal size).	4.48	Cum	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	15232.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:3:6(One cement: three sand:six graded stone aggregate20 mm(Twenty milimetre) nominal size).	76.02	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Metre	425712.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	30.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	5400.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	0.98	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	1029.00
						Total	**468298.00**
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla