



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Telephone No: 01782-233017

e-mail: ee-ram-hp@nic.in

No. PW/ RMP/TA-I/Publication/2025- 12311

Dated:- 13-2-26

To


The Executive Engineer (IT Cell),  
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of tender Notice.

Enclosed please find herewith the tender Notice of various works as given in the tender inviting tender for uploading on department website as per notified by the Govt. of H.P. letter No. PBD-B-A0(3)/8/2025-300858 dated 13.11.2025 as the works mentioned in the tender Notice are urgent nature and public interest.

DA: - As above.

Executive Engineer,  
B&R Division HPPWD,  
Rampur.



## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Telephone No: 01782-233017  
e-mail: ee-ram-hp@nic.in

### NOTICE INVITING TENDER

Sealed item rate tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD, Rampur Distt. Shimla (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class so as to reach in this office on **20.02.2026** upto 10:30 A.M. and will be opened on the same day at 11:00 A.M. in the presence of contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **19.02.2026** between 10:00 A.M. to 2:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **19.02.2026** between 02:00 PM to 5:00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, B&R Division, HP. PWD, Rampur Bushahr Distt. Shimla H.P. must accompany with the tender form. Ambiguous/Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer, B&R Division, HP.PWD, Rampur Bushahr reserve the right to reject/accept any offer of tender without assigning any reasons.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of tender form	Time limit
1	R/R damages on Kyao Koot Kinfi road Km. 0/000 to 13/450 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 0/000 to 13/450)	98,750/-	2,000/-	350/-	One month
2	R/R damages on Ganvi Fancha road Km. 0/000 to 9/500 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 0/000 to 9/500)	98,750/-	2,000/-	350/-	One month
3	R/R damages on Samej Sarpara road Km. 0/000 to 13/450 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 0/000 to 13/450)	98,750/-	2,000/-	350/-	One month
4	R/R damages on Pajidhar Chandi Branda road Km. 0/000 to 10/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 0/000 to 10/000)	98,750/-	2,000/-	350/-	One month
5	R/R damages on Samej Sarpara road Km. 0/000 to 13/450 (SH:- Supplying and stacking at site approved crushed sand at various RDs in Km. 3/000 to 13/450)	98,800/-	2,000/-	350/-	One month
6	R/R damages on Rampur Gaura Mashnoo road Km. 0/000 to 30/500 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of	98,750/-	2,000/-	350/-	One month

	snow/slips in Km. 0/000 to 30/500)				
7	R/R damages on Jhakhari Khadkhag road Km. 0/000 to 5/445 (SH:- Hiring of Dumper for carriage of muck/debris from Km. 0/000 to 5/445)	96,000/-	2,000/-	350/-	One month
8	R/R damages on Jhakhari Khadkhag road Km. 0/000 to 5/445 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 0/000 to 5/445)	98,750/-	2,000/-	350/-	One month
9	R/R damages on various roads under Gaura Section (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of berms & clearance of blocked side drain in various roads under Gaura section)	98,750/-	2,000/-	350/-	One month
10	R/R damages on Rampur Guara Mashnoo road Km. 0/000 to 30/500 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 22/000 to 30/500)	98,750/-	2,000/-	350/-	One month
11	R/R damages on Rattanpur Uchi Shah Dofda road Km. 0/000 to 16/700 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of berms & clearance of blocked side drain in Km. 10/000 to 16/780)	98,750/-	2,000/-	350/-	One month
12	R/R damages on Pajidhar Chandi Branda road Km. 0/000 to 10/000 (SH:- Supplying and stacking a site approved crushed sand at various RDs in Km. 0/000 to 10/000)	98,800/-	2,000/-	350/-	One month
13	R/R damages on Labana Sadana road Km. 0/000 to 8/000 (SH:- Supplying and stacking a site approved crushed sand at various RDs in Km. 1/000 to 8/000)	99,756/-	2,000/-	350/-	One month
14	R/R damages on RSBTN road Km. 27/000 to 80/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 27/000 to 40/000)	98,750/-	2,000/-	350/-	One month
15	R/R damages on RSBTN road Km. 27/000 to 80/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 40/000 to 53/000)	98,750/-	2,000/-	350/-	One month
16	R/R damages on RSBTN road Km. 27/000 to 80/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 53/000 to 70/000)	98,750/-	2,000/-	350/-	One month
17	R/R damages on Kashadhar Darkali road Km. 0/000 to 22/700 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips at various RDs)	98,750/-	2,000/-	350/-	One month
18	R/R damages on Anu Munish road Km. 0/000 to 11/000 & Dandol Kasha road Km. 0/000 to 13/280 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips at various roads)	98,750/-	2,000/-	350/-	One month
19	R/R damages on Mashnoo Taklech road Km. 12/000 to 48/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips in Km. 12/000 to 30/000)	98,750/-	2,000/-	350/-	One month

20	R/R damages on various roads in Bahli section under Sub Division Taklech (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips at various RDs)	98,750/-	2,000/-	350/-	One month
21	A/R & M/O Jeori Ganvi road Km. 0/000 to 11/000 (SH:- White washing of guard stone, hill side rock etc. in Km. 3/000 to 11/000)	99,756/-	2,000/-	350/-	One month
22	Recovery and restoration on Jeori Tayawal Doknoo road Km. 0/000 to 1/400 (SH:- C/O R/wall in PCC 1:4:8 between Km. 0/360 to 0/375).	3,71,660/-	7,500/-	350/-	One month
23	Recovery and restoration on Nanan Dharali road Km. 0/000 to 4/000 (SH:- C/O R/wall in RR masonry between Km. 1/930 to 1/945)	3,37,436/-	6,800/-	350/-	One month
24	Recovery and restoration of Uchi Shah Dofda road Km. 0/000 to 16/780 (SH:- C/O PCC drain from Km. 7/035 to 7/065 and R/wall on various RDs)	4,95,277/-	10,000/-	350/-	One month
25	A/R & M/O PWD Residence P-67 Type-III Qtr. at Nogli (SH:- Painting and distemping works)	92,719/-	2,000/-	350/-	One month
26	Repair of staff room of Rani Ratna Kumari Memorial Govt. Sr. Sec. School Nogli in Tehsil Rampur Distt. Shimla (SH:- Dismantling & repair of plastering works and roof band works)	96,397/-	2,000/-	350/-	One month

**Terms and conditions:-**

1. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.
2. The contractor will produce show their enlistment/renewal documents at the time of obtaining tender form.
3. Latest Income tax and sale tax clearance certificates as well as Pan Number and GST number must be attached with the application failing which tender documents will not be issued.
4. The tender forms will be issued to only those contractors who have not more than two works in hand in any of HP.PWD. Circles.
5. The contractor will have to submit the proof. of registration under Employees Providing Funds & Miscellaneous provision Act. 1952 at the time of tender. Failure to observe this condition shall render the tender of the contractor liable to summary rejection.

Executive Engineer,  
Rampur Division (B&R),  
HPPWD, Rampur Bsr.

No: - RMP/Tender/2025 12312-13

Dated:- 13-2-26

Copy forwarded for information:-

1. The Superintending Engineer 11<sup>th</sup> Circle HPPWD, Shimla.
2. Copy to Notice Board.


Executive Engineer,  
Rampur Division (B&R),  
HPPWD, Rampur Bsr.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Kyao Koot Kinfli road Km 0/000 to13/450.  
 (SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow at Km 0/000 to 13/450).

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.P.W.D., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Ghanvi Fancha road Km 0/000 to9/500.  
 (SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow at Km 0/000 to 9/500).

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 G.P.PWD., Rampur.


## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Samej Sarpara road km 0/000 to 13/450.

(SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/Slips on various Rds from km 0/000 to 13/450)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
<b>Quoted rate in figures</b>					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in words</b>					+/-	.....%


  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Pajidhar Chandi Branda road Km 0/000 to 10/000.  
 (SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow at Km 0/000 to 10/000).

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 MP.PWD., Rampur.


**SCHEDULE OF QUANTITY**

Estimated cost :- **98,800.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**Name of Work:-** R/R Damages on Samej Sarpara road kn 0/000 to 13/450.

(SH:- Supplying and stacking at site approved crushed sand at various Rd's in km 3/000 to 13/450)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts and proper stacking at site complete as per the direction of Engineer-in-charge	76.00	Per Cubic metre.	1,300.00	(Rs One Thousand Three Hundred and paise zero)only	98,800.00
<b>Total:-</b>						<b>98,800.00</b>
<b>Quoted rate in figures</b>		+/-	(.....)	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.P.WD., Rampur.


## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- 2,000.00  
 Time allowed:- One Month

**NAME OF WORK:** -R/R Damages on Rampur Gaura Mashnoo road km 0/000 to 30/500.

(SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/Slips/land slide from km 0/000 to 30/500)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.W.D., Rampur.


## SCHEDULE OF QUANTITY

Estimated cost :- **96,000.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One month**

**Name of Work:-R/R Damages on Jhakri Khadkhag road km 0/000 to 5/445**

(SH:- Hiring of ~~tipper~~ <sup>dumper</sup> for carriage of muck/debris from km 0/000 to 5/445).

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring <del>tipper</del> <sup>dumper</sup> of heavy Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absulte responsibility of the contractor/ on onwer tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in-charge.	12.00	Per Day	8,000.00	(Rs. Eight Thousand and piase zero)	96,000.00
					<b>Total:-</b>	<b>96,000.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 HP.PWD., Rampur.


## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- 2,000.00  
 Time allowed:- One Month

**NAME OF WORK:** -R/R Damages on Jhakri Khadkhag road km 0/000 to 5/445.

(SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/Slips/land slide from km 0/000 to 5/445

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on various roads under Guara Section  
 (SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips/snow, dressing of berms & clearance of blocked side drain in various roads under Gaura section)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.PWD., Rampur.


## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- 2,000.00  
 Time allowed:- One Month

**NAME OF WORK:** -R/R Damages on Gaura Mashnoo Road km 0/000 to 30/500

(SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips/snow, land slide from km 22/000 to 30/500)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hundred fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Rattanpur uchi Shah Dofda Road km 0/000 to 16/700  
 (SH :- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips/snow, dressing of berms & clearance of blocked side drain in km 10/000 to 16/780)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One thousand two hunderd fifty oand paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
	<b>Quoted rate in figures</b>	+/-	.....	.....%		
	<b>Quoted rate in words</b>					


  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.P.W.D., Rampur.

**SCHEDULE OF QUANTITY**

Estimated cost :- **98,800.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**Name of Work:-** R/R Damages on Pajishar Chandi Branda road km 0/000 to 10/000.  
 (SH:- Supplying and stacking at site approved crushed sand at various Rd's in km 0/000 to 10/000)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts and proper stacking at site complete as per the direction of Engineer-in-charge	76.00	Per Cubic metre.	1,300.00	(Rs One Thousand Three Hundred and paise zero)only	98,800.00
<b>Total:-</b>						<b>98,800.00</b>
<b>Quoted rate in figures</b>		+/-	(.....)	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.W.D., Rampur.


**SCHEDULE OF QUANTITY**

Estimated cost :- **98,800.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**Name of Work:-** R/R Damages on Laban Sadana road kn 0/000 to 8/000.

(SH:- Supplying and stacking at site approved crushed sand at various Rd's in km 1/000 to 8/450)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts and proper stacking at site complete as per the direction of Engineer-in-charge	76.00	Per Cubic metre.	1,300.00	(Rs One Thousand Three Hundred and paise zero)only	98,800.00
<b>Total:-</b>						<b>98,800.00</b>
<b>Quoted rate in figures</b>		+/-	(.....)	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.P.WD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Rohru Sungari Bahli Taklech Nogli Road km 27/000 to 80/000.  
 (SH :- Hiring of JCB/Excavator cum loader for removal of slips/Snow in km 27/000 to 40/000)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
		+/-	.....	.....%		
<b>Quoted rate in figures</b>						
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 AP PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Rohru Sungari Bahli Taklech Nogli Road km 27/000 to 80/000.  
**CH :-** Hiring of JCB/Excavator cum loader for removal of slips/Snow in km 40/000 to 53/000)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
		+/-	.....	.....%		
<b>Quoted rate in figures</b>						
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 HP.PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Rohru Sungari Bahli Taklech Nogli Road km 27/000 to 80/000.  
 (SH :- Hiring of JCB/Excavator cum loader for removal of slips/Snow in km 53/000 to 70/000)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.P.W.D., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Kashadhar Darkali Road km 0/000 to 23/700.  
 (SH :- Hiring of JCB/Excavator cum loader for removal of slips/Snowat various RDs)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Anu Munish Road km 0/000 to 11/000 & Dandol Kasha Road km 0/000 to 13/280  
 (SH :- Hiring of JCB/Excavator cum loader for removal of slips/Snow at various RDs)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on Mashnoo Taklech Road km 12/000 to 48/000  
 (SH :- Hiring of JCB/Excavator cum loader for removal of slips/Snow in km 12/000 to 30/000)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


Executive Engineer,  
 Rampur Division (B&R)  
 MP PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**  
 Earnest money :- **2,000.00**  
 Time allowed:- **One Month**

**NAME OF WORK:** -R/R Damages on various road in Bahli Section under Sub Division Taklech.  
 (SH :- Hiring of JCB/Excavator cum loader for removal of slips/Snow in various RDs)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour	1,250.00	Rs One Thousand Two Hundred Fifty and paise zero	98,750.00
					<b>Total:-</b>	<b>98,750.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.W.D., Rampur.

**SCHEDULE OF QUANTITY**

Estimated cost:- **99,756.00**  
 Earnest money **2,000.00**  
 Time **One Month**

Name of work:- A/R & M/O Jeori Ganvi road km 0/000 to 11/000.  
 (SH:- White Washing of guard stone, hill side rock etc. in km 3/000 to 11/000.)

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	White washing two coats in parapet walls, white pati on hill side rock and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications clause 1915 including carriage of material within all leads and lifts and as per HPPW Specification of 1990 volume-I and as per direction of Engineer-in-	2109.00	per square metre	47.3	(Rs. Fourty Seven and paise Thirty)only	99,756.00
<b>Total:-</b>						<b>99,756.00</b>
<b>Quoted rate in figures</b>		+/-	(.....)	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.WD., Rampur.


## SCHEDULE OF QUANTITY

Estimated cost:- **3,71,660.00**  
 Earnest money **7,500.00**  
 Time **Two Months**

**Name of work:- Recovery and Restoration on Jeori Tayawal Doknoo road km 0/000 to 1/400 in Tehsil Rampur Distt Shimla.**  
**(SH:- Construction of R/Wall in PCC(1:4:8) between km 0/360 to 0/375)**

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hardd rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock( where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	13.50	Per Cubic metre	350.00	(Rs. Three Hundred Fifty and paise zero) only	4,725.00
2	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 305-1 including setting out, construction of shoring and bracin , removal of stumps and other deleterious material and disposal in all lead and lift including dressisng of sides and bottom and back filling in trenches with excavated suitable material . All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out of rock( where blasting is prohibited) as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	9.60	per cubic metre	559.10	(Rs. Five Hundred Fifty Nine and paise Ten)only	5,367.00

	Providing and laying cement concrete 1:4:8 (1 cement : 4 sand :8 Graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in foundation and plinth in breast and retaining walls etc. including carriage of material within all leads and lifts and as per HP.PWD. specifications of 1990 volume-I and as per direction of Engineer-in-charge.	49.50	Per Cubic metre	6249.00	(Rs. Six thousand Two Hundred Fourty Nine and paise zero) only	3,09,326.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8 including carriage of material within all leads and lifts. including all leads and lifts as per directions of Engineer in Charge.	13.50	per cubic metre	1885.60	(Rs.One Thousand Eight Hundred Eighty Five and paise Sixty) only	25,456.00
5	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.63	Sqm	426.00	(Rs.Four Hundred Twenty Six and paise Zero) only	6,658.00
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C grade M 10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 Including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of Engineer- in Charge.	2.39	per cubic metre	7252.00	(Rs. Seven Thousand Two Hundred Fifty Two and paise zero) only	17,332.00
7	Supplying and installation of delinators (road way indicators, hazard markers, object markers) 80-100 cm high above ground level, painted blk and white in 15 cm wide strips, fitted with 80x100 mm rectangular or 75 mm dia circular reflectorised panels at top, buried or passed into ground and conforming to IRC-79 and drawings.including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.00	Each	559.10	(Rs.Five Hundred Fifty Nine and paise Ten) only	2,796.00
<b>Total:-</b>						<b>3,71,660.00</b>
<b>Quoted rate in figures</b>		+/-	(.....)	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 HP PWD., Rampur.


**SCHEDULE OF QUANTITY**

Estimated cost:- **3,37,436.00**  
 Earnest money **6,800.00**  
 Time **Two Months**

**Name of work:- Recovery and Restoration on Nanan Dharali road km 0/000 to 4/000 in Tehsil Rampur Distt Shimla (Under PDNA).  
 (SH:- Construction of R/Wall in RR Masonry between km 1/930 to 1/945)**

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hardd rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock( where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolte responsibility of the contractor which shall have to be duly compensated by him in all cases.	35.63	Per Cubic metre	350.00	(Rs. Three Hundred Fifty and paise zero) only	12,471.00
2	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 305-1 including setting out, construction of shoring and bracin , removal of stumps and other deleterious material and disposal in all lead and lift including dressisng of sides and bottom and back filling in trenches with excavated suitable material . All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out of rock( where blasting is prohibited) as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolte responsibility of the contractor which shall have to be duly compensated by him in all cases.	5.70	per cubic metre	559.10	(Rs. Five Hundred Fifty Nine and paise Ten)only	3,187.00

3	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement: five sand : ten graded crushed stone aggregate) 40 mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	1.86	Per Cubic meter	5523.00	(Rs. Five thousand Five Hundred Twenty Three and paise zero) only	10,273.00
4	Random Rubble Masonry work In cement mortar 1:6 (1 cement : 6 sand ) in foundation & super-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203..including carriage of material with in all leads and lifts as per direction of Engineer-In-Charge.	43.31	Per Cubic metre	6574.00	(Rs. Six Thousand Five Hundred Seventy Four and paise zero) only	2,84,720.00
5	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.63	Sqm	426.00	(Rs.Four Hundred Twenty Six and paise Zero) only	6,658.00
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C grade M 10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 Including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of Engineer- in Charge.	2.39	per cubic metre	7252.00	(Rs. Seven Thousand Two Hundred Fifty Two and paise zero) only	17,332.00
7	Supplying and installation of delinators (road way indicators, hazard markers, object markers) 80-100 cm high above ground level, painted blk and white in 15 cm wide strips, fitted with 80x100 mm rectangular or 75 mm dia circular reflectorised panels at top, buried or passed into ground and conforming to IRC-79 and drawings.including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.00	Each	559.05	(Rs.Five Hundred Fifty Nine and paise Five) only	2,795.00
<b>Total:-</b>						<b>3,37,436.00</b>
<b>Quoted rate in figures</b>		+/-	(.....)	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 HP.PWD., Rampur.


### SCHEDULE OF QUANTITY

Estimated cost:-	4,95,277.00
Earnest money	10,000.00
Time	Two Months

**Name of work:- Recovery and Restoration of Uchi Shah Dofda road km 0/000 to 16/780. (SH:- Construction of PCC drain from km 7/035 to 7/065 and retaining walls on various RDs)**

Sr. No	Description of items	Quantity	Unit	Rate ( In figure)	Rate (In Word)	Amount
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock( where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates & slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	39.00	Per Cubic metre	350.00	(Rs. Three Hundred Fifty and paise zero) only	13,650.00

	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C grade M 10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 Including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of Engineer- in Charge.	37.44	per cubic metre	7252.00	(Rs. Seven Thousand Two Hundred Fifty Two and paise zero) only	2,71,515.00
3	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS;280 and IS;4826 in 100mm x 100mm mesh(woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 Kg. each as per drawing and technical specifications Clause 1301. including all leads and lifts as per directions of Engineer in Charge.	65.66	per cubic metre	3200.00	(Rs Three thousand Two Hundred and paise zero)only	2,10,112.00
<b>Total:-</b>						<b>4,95,277.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						


  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.PWD., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost:- **92,719.00**  
 Earnest money **2,000.00**  
 Time **One Month**

Name of work:- A/R & M/O PWD Residence P-67 Type-111 Quater at Nogli.  
 (SH:- Painting and distempering works)

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Repair to Plaster of thickness 12mm to 20mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing pastering the wall surface with white cement based polymer modified self suring mortar, including disposal of rubbish, all complete as per the direction of Engineer-in-Charge.	95.28	Per Square metre.	450.00	(Rs. Four Hundred Fifty and paise zero)	42876.00
2	Applying Biria white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per HP. PWD. specifications of 1990 volume-1 including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge	95.28	Per Square metre	110.00	(Rs. One Hundred Ten and paise zero)	10481.00
3	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade within all leads and lifts and carriage of material complete as per direction of the Engineer-in charge.	281.16	Per Square metre	140.00	(Rs. One Hundred Forty and paise zero)	39362.00
					<b>Total:-</b>	<b>92,719.00</b>
<b>Quoted rate in figures</b>		+/-	.....	.....%		
<b>Quoted rate in words</b>						

  
 Executive Engineer,  
 Rampur Division (B&R)  
 P.P.WD., Rampur.

## SCHEDULE OF QUANTITY


Estimated cost:-	96,397.00
Earnest money	2,000.00
Time	One Month

**NAME OF WORK:- Repair of Staff room of Rani Ratna Kumari Memorial Govt. Sr.Sec School Nogli tehsil Rampur Distt. Shimla HP**

(SH:- Dismantling & repair of plastering works and roof band works).

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Dismantling roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials within 20 Metres lea including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	0.75	per cubic metre	1,050.00	(Rupees One Thousand Fifty)only	788.00
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately), with in all leads and lifts as directed by Engineer-in- Charge.: Second class Deodar wood. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	0.11	per cubic metre	1,46,515.00	(Rupees One Lac Forty Six Thousand Five hundred fifteen ) only	16,117.00
3	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	2.61	per Sqm	4,050.00	(RupeesFour Thousand Fifty) only	10,571.00

	Centering and shuttering including strutting, propping etc. and removal of form for					
	Lintels, beams, plinth beams, girders, bressumers and cantilevers . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	22.44	per Sqm	525.25	(Rupees Five hundred Twenty five and paisa Twenty Five) only	11,787.00
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	247.64	Kg	125.00	(Rupees One Hundred Twenty five) Only	30,955.00
6	Providing and laying in position specified grade of reinforced Cement concrete, excluding the coat of centering, dhuttering, finidhing and reinforcement- all work up to plinth levle 1:2:4 (1 cement : 2 coarse sand): 4 graded stone aggregate 20mm nominal size) including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	2.27	per Sqm	7,500.00	(RupeesSeven Thousand Five hundred)Only	17,025.00
7	15mm cement plaster on the rough side of singile of half brick wall of mix 1:4 (1: cement: 4: fine sand) including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	166.50	per Sqm	220.00	(Rupees Two hundred Twenty) only	36,630.00
					<b>Total:-</b>	<b>96,397.00</b>
	<b>Quoted rate in figures</b>	+/-	(.....)	.....%		
	<b>Quoted rate in words</b>					

  
 Executive Engineer,  
 Rampur Division (B&R)  
 H.P.W.D., Rampur.