Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **20-02-2026 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **18-02-2026 up to 4:00** P.M and the application for issue of tender form shall be received on **18-02-2026 up to 12.00 Noon.**

The earnest money in the shape of NSC/FDR/Saving account of the Post office Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	Restoration of Rain Damages in Chambi to Dharamshala road (MDR-45) KM 0/00 to 12/800.(S.H:-C/o Wire Crate Wall with C,C, Pusta at RD 11/858.70 to 11/860.	98,276.00	2,000.00	One Month	350/-
2	A/R and M/O Garoh Garh Matti Road km 0/000 to 2/500.(S.H:-Clearing and Grubbing road land,C/O Earthen shoulder and Maintenance drain Between Km 0/000 to 1/800 .	99,861.00	2,000.00	One Month	350/-
3	Recovery of Reconstruction of Prai Sadhu Road Km 0/00 to 1/00.(S.H:-C/o 0.75 mtr Span culvert with Drain at RD 0/105.	91,589.00	2,000.00	One Month	350/-
4	Balance work of Dramman to Dhukhru Road km 0/00 to 0/690 (S.H:-C/o 1.00 mtr Span culvert with Drain at RD 0/030.	94,468.00	2,000.00	One Month	350/-
5	C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work) (S.H:-C/o 900 MM Hume Pipe culvert at RD 0/600.	98,533.00	2,000.00	One Month	350/-
6	Annual repair and maintenance of various roads Under Shahpur Division in Distt Kangra H.P. (S.H:-Writing letters and Painting etc	97,211.00	2,000.00	One Month	350/-
7	Balance work of Dramman to Dhukhru Road km 0/00 to 0/690 (S.H:-C/o 1.00 mtr Span culvert with Drain at RD 0/030.(Laying of Slab and C/o Catchpit)	98,603.00	2,000.00	One Month	350/-
8	C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work) (S.H:-C/o Wing Wall at RD 0/057.50 to 0/060 and 0/063.30 to 0/065.80	92,974.00	2,000.00	One Month	350/-
9	Balance work of Dramman to Dhukhru Road km 0/00 to 0/690 (S.H:-C/o 1.00 mtr Span culvert with Drain at RD 0/030.(Providing and laying 60 mm thick Interlocking Paver	92,400.00	2,000.00	One Month	350/-
10	C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work) (S.H: Formation Cutting at RD 0/073 to 0/081 and C/o Wing Wall at RD 0/056.50 to 0/057.50 and 0/065.80 to 0/066.80	47,432.00	2,000.00	One Month	350/-
11	Repair and maintenance HPPWD Rest House Shahpur Distt Kangra HP. (S.H: Providing and Laying water proofing, Brick work, Plastering and Repair of Manhole Cover etc in HPPWD Rest House Set no.5.	99,813.00	2,000.00	One Month	350/-
12	C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work) (S.H:-Formation Cutting at RD 0/00 to 0/073.	99,892.00	2,000.00	One Month	350/-
13	Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur Distt Kangra H.P. (S.H:-Providing and Laying wooden florring etc in Executive Engineer Office Room.	86,464.00	2,000.00	One Month	350/-
14	Restoration of Rain Damages in Chambi to Dharamshala road (MDR-45) KM 0/00 to 12/800.(S.H:-C/o Wire Crate Wall with C,C, Pusta at RD 11/857 to 11/858.80	98,393.00	2,000.00	One Month	350/-
15	Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur Distt Kangra H.P. (S.H:-Providing and Laying wpc in Executive Engineer Offie Room.	89,401.00	2,000.00	One Month	350/-

16	A/R and M/O Salli to Khari bhei road km 0/00 to 8/720.(S.H:- Clearing and Grubbing road land, C/O Earthen shoulder and unlined drain between KM 4/00 to 5.000	97,517.00	2,000.00	One Month	350/-
17	Balance work of Mini Secretariat at Shahpur,Tehsil Shahpur ,Distt. Kangra (H.P).(S.H:-P/L 1:1.5:3 and P/L HYSD)	98,950.00	2,000.00	One Month	350/-
18	Balance work of Mini Secretariat at Shahpur,Tehsil Shahpur ,Distt. Kangra (H.P).(S.H:-P/L CC 1:4:8 and CC 1:1.5:3.	99,399.00	2,000.00	One Month	350/-
19	Restoration of Rain damages on various roads under Darini Sub- Division.(S.H:-Hiring of Excavator cum loader under Darini Section.	99,000.00	2,000.00	One Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.
(on behalf of Governor of Himachal Pradesh)

No.PWD/SD/Tender/NIT/2025-26/- 9405-14 **Dated:** 11/2/26

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. Notice Board

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

Sr no-347

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98276.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.

SUB-HEAD :- C/o Wire Crate wall with C.C.Pusta at RD 11/858.70 to 11/860.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	5.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1820.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	6.45	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34701.00
3	Providing and laying of boulder apron or gabin walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royality, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	17.90	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	61755.00
					TOTAL :-	98276.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure.)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(2)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99861.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - A/R and M/O Garoh Garh Matti Road km 0/000 to 2/500.

SUB-HEAD : - Clearing and Grubbing road land,C/O Earthen shoulder and Maintenance drain Between Km 0/000 to 1/800 .

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidenta The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.50	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	11220.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	4860.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Square metres	35721.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	1800.000	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running Metre	52920.00
					TOTAL :-	*99861.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

3

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 91589.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Months

NAME OF WORK :- Recovery of Reconstruction of Pral Sadhu Road Km 0/00 to 1/00.

SUB-HEAD :- C/o 0.75 mtr Span culvert with Drain at RD 0/105.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	6.97	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	2440.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.24	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per Cubic metre	28191.00
3	Providing and laying machinery mixed and vibrated concrete for plain cement (VI-) nominal mix 1:2.5:5 on ground or under water curing complete for4 fourteen days, in cradle bedding for hume pipe including pumping or bailing out water, dewatering for all depths and any quantum of water including removable of slush wish may arise as per drawing and M.O.R.D technical specification section 800,900 and 1100 as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.120	5850.00	Rupees Five Thousand Eight Hundred Fifty Only	Per Cubic metre	18252.00
4	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	1.950	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic metre	11993.00

1	2	3	4	5	6	7
5	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royality, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	292.50	105.00	Rupees One Hundred Five Only	Per koligram	30713.00
				TOTAL :-		91589.00
		(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in words)				
	Quated Rate in Words (%)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 94468.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Balance work of Dramman to Dhukhru Road km 0/00 to 0/690

SUB-HEAD :- C/o 1.00 mtr Span culvert with Drain at RD 0/030.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	31.35	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	10973.00
2	Providing and Laying mechanically mixed and vibrated plain Cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1 :5 :10 (One cement into five sand into ten graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.96	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	4128.00
3	Providing and laying concrete mechanically mixed and vibrated PCC M-15(Fifteen) grade 1:2.5:5 in foundation (one cement: two point five sand :five graded stone aggregate 40mm(forty millimeter) nominaal size for plain/reinforced concrete in sub structure or similar works complete as per drawings and technical specification clause 802,803,1202 and 1203 and curing complete including the cost of form work and hauling of materail in all leads and lifts as per the entire satisfication and direction of Engineer in charge.	9.610	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic metre	52855.00

1	2	3	4	5	6	7
4	roviding and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals The rates are inclusive of octroi, royality malkana toll tax, sale tax or other taxes imposed by the Government	1.570	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic metre	10048.00
5	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royality, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	156.80	105.00	Rupees One Hundred Five Only	Per koligram	16464.00
					TOTAL :-	*94468.00*
		(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in words)				
	Quated Rate in Words (%)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(5)

SCHEDULE OF QUANTITY

ESTIMATED	₹	98533.00
EARNEST MONEY	₹	2000.00
TIME LIMIT		One Month

NAME OF WORK :- C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work)

SUB-HEAD : - C/o 900 MM Hume Pipe culvert at RD 0/600.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	15.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5320.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.94	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	4465.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	10.02	5550.00	Rupees Five Thousand Five Hundred Fifty Only	Per cubic metre	55611.00

4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete M-15 (M- fifteen) nominal mix 1:2½:5 (one cement is to two and half sand is to five graded crushed stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen) days , in cradle bedding for hume pipe including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying concrete complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification section 800,900 and 1100 as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	1.10	*5850.00*	Rupees Five Thousand Eight Hundred Fifty Only	Per cubic metre	*6435.00*
5	Providing and laying (to level or slope) 900mm dia (nine hundred millimetre) diametre reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.10	*3450.00*	Rupees Three Thousand Four Hundred Fifty Only	Per Running metre	24495.00
6	Fillling in foundation trenches for marshy soil as per drawing and technical specification Clause 305.3.9 complete as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	6.66	*239.10*	Rupees Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	*1592.00*
7	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	0.10	*6150.00*	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	*615.00*
					TOTAL :-	***98533.00***
		(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Figure (%)					
		(Amount to be quoted by the contractor in words)				
	Quated Rate in Words (%)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(6)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97211.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Annual repair and maintenance of various roads Under Shahpur Division in Distt Kangra H.P.

SUB-HEAD :- Writing letters and Painting etc

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Removing dry or oil bound distempering water proofing Ena mel paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	86.40	11.15	Rupees Eleven And Paise Fifteen Only	Per Square metres	963.00
2	Applying priming coat over new steel & other metal surfaces after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrapers and sand paper complete. With ready mixed priming paint brushing red lead,Red-oxide/zinc oxide chrome. as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	86.40	38.95	Rupees Thirty Eight And Paise Ninety Five Only	Per Square metres	3365.00
3	Painting two costs (excluding priming cost on new steel and other metal surfaces eith enamel paint brushin to give an even shade including cleaning the surface of all dirt, dust and other foregin matters :– Enamel paint other than white :–as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	86.40	53.85	Rupees Fifty Three And Paise Eighty Five Only	Per Square metres	4653.00
4	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately ,Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royality, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.					0.00
(i)	Block letters/figures	23100.00	1.70	Rupees One And Paise Seventy Only	Per letter per centimetre hight	39270.00
(ii)	Indian(letters/figures)	30600.000	1.60	Rupees One And Paise Sixty Only	Per letter per centimetre hight	48960.00
					TOTAL :-	***97211.00***
		(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in words)				
	Quated Rate in Words (%)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(7)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98603.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Balance work of Dramman to Dhukhru Road km 0/00 to 0/690

SUB-HEAD : - C/o 1.00 mtr Span culvert with Drain at RD 0/030.(Laying of Slab and C/o Catchpit)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals The rates are inclusive of octroi, royality malkana toll tax, sale tax or other taxes imposed by the Government	8.120	6400.00		Per Cubic metre	51968.00
2	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royality, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	189.00	105.00	Rupees One Hundred Five Only	Per koligram	19845.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure using plain cement concrete 1:4:8 (one cemnet is to four sand is to eight graded crushed stone) aggregate 40 mm nominal size including curing complete including the cost of form work in or underwater including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying underwater complete for all heights/ depths as per drawing and MORD technical specification section clauses 802, 803, 1202 & 1203 engineer in charge and carriage of material within all leads and lips and other incidentals the rate including octroi royalty GST or other taxes imposed by the government.	5.64	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per Cubic metre	26790.00
					TOTAL :-	***98603.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED	₹	92974.00
EARNEST MONEY	₹	2000.00
TIME LIMIT		One Month

NAME OF WORK **:-** **C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work).**

SUB-HEAD **:-** **C/O Wing wall at RD 0/057.50 to 0/060 and 0/063.30 to 0/065.80.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	11.30	*350.00*	Rupees Three Hundred Fifty Only	Per cubic metre	*3955.00*
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, including the cost of centering, shuttering and finishing 1:5:10 (one cement isto five coarse sand) isto ten graded stone aggregate 40 mm (forty milimetres) nominal size) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	17.60	*4350.00*	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	*76560.00*
3	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.80	*850.00*	Rupees Eight Hundred Fifty Only	Per cubic metre	*4080.00*

4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate as including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.00	350.00	Rupees Three Hundred Fifty Only	Each	4200.00
5	Construction of Embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1and 300.2 as per techniad specification Clause 301.5 as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	17.48	239.10	Rupees Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	4179.00
					TOTAL :-	**92974.00**
	Quated Rate in Figure (%)			**(Amount to be quoted by the contractor in Figure)**		
	Quated Rate in Words (%)			**(Amount to be quoted by the contractor in words)**		

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(9)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 92400.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- 'Balance work of Dramman to Dhukhru Road km 0/00 to 0/690

SUB-HEAD :- C/o 1.00 mtr Span culvert with Drain at RD 0/030.(Providing and laying 60 mm thick Interlocking Paver Block)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	84.000	1100.00		Per square metre	92400.00
					TOTAL :-	92400.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

10

SCHEDULE OF QUANTITY

ESTIMATED ₹ 47432.00
EARNEST MONEY ₹ 1000.00
TIME LIMIT One Month

NAME OF WORK :- C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit work)

SUB-HEAD :- Formation cutting at RD 0/073 to 0/081and C/o Wing wall at RD 0/56.50 to 0/057.50 & 065.80 to 0/066.80

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of matereials within all leads and lifts and other incidentals The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	35.84	270.00	Rupees Two Hundred Seventy Only	Per cubic metre	9677.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	4.52	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1582.00

3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, including the cost of centering, shuttering and finishing 1:5:10 (one cement isto five coarse sand) isto ten graded stone aggregate 40 mm (forty milimetres) nominal size) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.04	*4350.00*	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	*30624.00*
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.92	*850.00*	Rupees Eight Hundred Fifty Only	Per cubic metre	*1632.00*
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	*350.00*	Rupees Three Hundred Fifty Only	Each	*2100.00*
6	Construction of Embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1and 300.2 as per techniacl specification Clause 301.5 as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	7.60	*239.10*	Rupees Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	*1817.00*
					TOTAL :-	***47432.00***

	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**

Executive Engineer,
Shahpur Division,

(11)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99813.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Repair and maintenance HPPWD Rest House Shahpur Distt Kangra HP

SUB-HEAD :- Providing and Layingfwater proofing, Brick work ,Plastering and Repair of Manhole Cover etc in HPPWD Rest House Set no.5.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying water proofing of RCC slab with liquicrete 151 as Acrlic Polymade binding with cement, providing Fibre mesh and liqucrete RTU as Two components Acrylic base Modified cementation water proofing coat system complete and ornamental moulding in side of gutter complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.82	535.40	Rupees Five Hundred Thirty Five And Paise Forty Only	Per Killograme	3651.00
2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 12 mm thickness (weight not less than 20 kg/ sqm)	0.88	1295.65	Rupees One Thousand Two Hundred Ninety Five And Paise Sixty Five Only	Per square metre	1140.00
3	Providing and fixing 3D WALL Paper decorative colours of approved brands and as per the directionof Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	11.36	2300.00	Rupees Two Thousand Three Hundred Only	Per square metre	26128.00
4	Repair of Door and Window including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.00	850.00	Rupees Eight Hundred Fifty Only	Per square metre	3400.00
5	Providing and laying water proofing of RCC slab with liquicrete 151 as Acrlic Polymade binding with cement, providing Fibre mesh and liqucrete RTU as Two components Acrylic base Modified cementation water proofing coat system complete and ornamental moulding in side of gutter complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	23.19	526.95	Rupees Five Hundred Twenty Six And Paise Ninety Five Only	Per square metre	12220.00
6	Providing and laying in position cement conctete ofspecified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) Engineer- In charge, including entire carriage of material within all leads, lifts and other incidentals.The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.70	5850.00	Rupees Five Thousand Eight Hundred Fifty Only	Per cubic metre	4095.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
7	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand), inside cement plaster 12 mm thick with cement mortar 1:3 (1 cement ; 3 cparse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design With Sewer bricks conforming to IS : 4885 complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.00	9692.30	Rupees Nine Thousand Six Hundred Ninety Two And Paise Thirty Only	Each	29077.00
8	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) With F.P.S (non modular) bricks complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.23	6296.15	Rupees Six Thousand Two Hundred Ninety Six And Paise Fifteen Only	Per cubic metre	1448.00
9	15mm (Fifteen milimetres) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty milimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	30.26	225.50	Rupees Two Hundred Twenty Five And Paise Fifty Only	Per square metre	6824.00
10	Providing and fixing on wall face 100mm (One hundred milimetres) diametres P.V.C. rain water pipes of working pressure 4kg (four / six kilogramme) per square centimetre of finolex / Relience / vectus/ prince pipe for rain water pipe fixed with approved adhesive including filling the joints complete within all leads, lifts of materials and other incidentals, and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	20.00	310.50	Rupees Three Hundred Ten And Paise Fifty Only	Per running metre	6210.00
11	Providing and fixing 15 mm nominal bore C.P. brass angle valve of Continental series of Jaquar / classik series of Hindware /Floral series of Cera & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS:8931 complete within all leads, lifts of materials and other incidentals, and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	910.00	Rupees Nine Hundred Ten Only	Each	1820.00
12	Providing and fixing C.P. brass long nose bib jaquar / classik series of Hindware /Floral series of Cera & Hindon cock of approved quality conforming to IS standards and weighing not less than 810 gms complete within all leads, lifts of materials and other incidentals, and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	750.00	Rupees Seven Hundred Fifty Only	Each	1500.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
13	Providing and fixing concealed complete as directed by Engineer- In-Charge, including entire carriage of material within all leads, lifts and other incidentals.75 mm diameter complete within all leads, lifts of materials and other incidentals, and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	2300.00
					Total:-	99813.00
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(2)

SCHEDULE OF QUANTITY

ESTIMATED ₹ 99892.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT One Month

NAME OF WORK :- **C/o Ambulance road from Main road to Dhiman Basti ward No-04 (Rajiyal).(Deposit Work)**

SUB-HEAD :- **Formation cutting at RD 0/00 to 0/073.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of matereials within all leads and lifts and other incidentals The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	369.97	*270.00*	Rupees Two Hundred Seventy Only	Per cubic metre	*99892.00*
					TOTAL :-	***99892.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(13)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 86464.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur . Distt Kangra H.P.

SUB-HEAD :- Providing and Laying wooden florring etc in Executive Engineer Offie Room.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.44	24.35	Rupees Twenty Four And Paise Thirty Five Only	Per square metre	157.00
2	Providing and fixing 8 mm thick frameless toughened glass of approved brand and manufacture, including as per direction of Engineer-in- charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.01	3550.00	Rupees Three Thousand Five Hundred Fifty Only	Per square metre	10686.00
3	Providng and Laying MDF board 12mm thickness in flooring with acoustic /thermal foam backing ,over prepared base including 12 mm thickness insulation foam fixing and aligment finishing and making good including all accessories decorative colours of approved brands and as per the directionof Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	30.50	1400.10	Rupees One Thousand Four Hundred And Paise Ten Only	Per square metre	42703.00
4	Providing & fixing 14mm (fourteen millimetre) (WPC (Wood Plastic Composites) Panelling/Lining(7.7" x 116"=2.95 x .20 Mtr. Make of approved side and brand of area 7.7" x 116" =2.95 x 0.20 Mtr. =0.590 Sqm for interior side including cutting and fixing in position. The WPC also not easy to deform, moisture proof , insect and fire resistance in all type of decorative colours of approved brands and as per the directionof Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.63	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per square metre	32918.00
					Total:-	86464.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figuro)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer.
Shahpur Division,
HPPWD Shahpur

14

Srno-345

(2)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98393.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT Two Months

NAME OF WORK :- Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.

SUB-HEAD :- C/o Wire Crate wall with C.C.Pusta at RD 11/857 to 11/858.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	5.10	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1785.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	6.35	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34163.00
3	Providing and laying of boulder apron or gabin walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royality, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.10	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	62445.00
					TOTAL :-	98393.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(15)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 89401.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur . Distt Kangra H.P.

SUB-HEAD :- Providing and laying wpc panling etc in Executive Engineer Offie Room.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing and fixing plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-in- charge (Frame work shall be paid for separately) 12mm thick commercial ply conforming to IS : 1328 BWR type within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	29.13	920.05	Rupees Nine Hundred Twenty And Paise Five Only	Per square metre	26801.00
2	Painting two coats (excluding priming coat) on new wood and wood based surface under coat with enamel and finishing coating with flat oil paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter, sand papering and stopping:- With paint other than white, including as per direction of Engineer-in- charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	54.93	85.10	Rupees Eighty Five And Paise Ten Only	Per square metre	4675.00
3	Providing and fixing 3D WALL Paper decorative colours of approved brands and as per the directionof Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	11.00	2300.00	Rupees Two Thousand Three Hundred Only	Per square metre	25300.00
4	Providing & fixing 14mm (fourteen millimetre) (WPC (Wood Plastic Composites) Panelling/Lining(7.7" x 116"=2.95 x .20 Mtr. Make of approved side and brand of area 7.7" x 116" =2.95 x 0.20 Mtr. =0.590 Sqm for interior side including cutting and fixing in position. The WPC also not easy to deform, moisture proof , insect and fire resistance in all type of decorative colours of approved brands and as per the directionof Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.50	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per square metre	32625.00
					Total:-	**89401.00**
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

16

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97517.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Salli to Khari bhei road km 0/00 to 8/720.

SUB-HEAD :- Clearing and Grubbing road land,C/O Earthen shoulder and unlined drain between KM 4/00 to 5.000

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental.s per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government	0.56	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	12566.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.s per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government	3800.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Squre metre	27930.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1939.50	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	57021.00
					TOTAL :-	97517.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer.
Shahpur Division,
HPPWD Shahpur

17

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98950.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Balance work of Mini Secretariat at Shahpur,Tehsil Shahpur ,Distt. Kangra (H.P).

SUB-HEAD : - P/L 1:1.5:3 and P/L HYSD)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals The rates are inclusive of octroi,royality malkana toll tax, sale tax or other taxes imposed by the Government	6.480	6450.00	Rupees Six Thousand Four Hundred Fifty Only	Per Cubic metre	41796.00
2	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royality, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	583.20	98.00	Rupees Ninety Eight Only	Per koligram	57154.00
					TOTAL : -	***98950.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(18) (18)

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99399.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Balance work of Mini Secretariat at Shahpur,Tehsil Shahpur ,Distt. Kangra (H.P).

SUB-HEAD :- P/L CC 1:4:8 and CC 1:1.5:3

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure using plain cement concrete 1:4:8 (one cemnet is to four sand is to eight graded crushed stone) aggregate 40 mm nominal size including curing complete including the cost of form work in or underwater including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying underwater complete for all heights/ depths as per drawing and MORD technical specification section clauses 802, 803, 1202 & 1203 engineer in charge and carriage of material within all leads and lips and other incidentals the rate including octroi royalty GST or other taxes imposed by the government.	6.41	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per Cubic metre	30448.00
2	roviding and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals The rates are inclusive of octroi, royality malkana toll tax, sale tax or other taxes imposed by the Government	10.690	6450.00	Rupees Six Thousand Four Hundred Fifty Only	Per Cubic metre	68951.00
					TOTAL :-	99399.00

Draft schedule of quantity approved for Rs -99399/- only.

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(19)

SCHEDULE OF QUANTITY

ESTIMATED	₹	99000.00
EARNEST MONEY	₹	2000.00
TIME LIMIT		One Month

NAME OF WORK **:-** **Restoration of Rain damages on various roads under Darini Sub- Division.**

SUB-HEAD **:-** **Hiring of Excavator cum loader under Darini Section.**

S No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	*90.00*	*1100.00*	Rupees one thousand and or hundred only	Per Hour	*99000.00*
					TOTAL :-	***99000.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur