



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- cc-sol-hp@nic.com

No.PW-SD/CB-Tender/-2025-26-

16473-77

Dated: 04/09/26

To

✓ The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID: cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Exigency

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

| Sr.No. | Tender Schedule | Dates | Time |
|--------|-----------------------------------------------------------|------------|-----------------|
| 1 | The last date for receipt of application for tender form. | 09.02.2026 | Upto 3.00 P.M. |
| 2 | The last date sale of tender forms. | 10.02.2026 | Upto 4.00 P.M. |
| 3 | The date for receipt of tender forms. | 11.02.2026 | Upto 10.30 P.M. |
| 4 | The date of opening of tender | 11.02.2026 | At 11.00 A.M. |


The tender shall be received upto 10.30 A.M. on 11.02.2026 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

| Sr. No | Name of work | Estimated Cost (Rs.) | Earnest Money (Rs.) | Time | Cost of Form |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|---------------------|---------------|--------------|
| 1. | A/R & M/O various roads under B&R Solan division (SH: hiring of vehicle to carry out inspection of various roads by SQM/NQM/TPQM/EE/AE for monitoring of ongoing works and inspections during rainy seasons under Solan division) | 496684/- | 10,000 | Seven Month | Rs.350/- |
| 2 | Restoration of rain damages on Kandaghat Hathon road km 0/0 to 6/0 under PDNA (SH: Construction of PCC V shape open surface drain at RD 1/700 to 2/100) | 384324/- | 7700 | Two Month | Rs.350/- |
| 3. | Restoration of rain damages on Kandaghat hathon road km 0/0 to 6/0 under PDNA (SH: Construction of PCC V shape drain in km 1/400 to 1/700) | 358170/- | 7200 | Two Month | Rs.350/- |
| 4. | Construction of mediation rooms/chambers of top floor of Judicial court complex at Solan (Deposit work) (SH: Balance work of providing and fixing wood work, flooring and painting work etc.0 | 354016/- | 7100 | Two Month | Rs.350/- |
| 5. | Construction of jeepable road from Manlog to Chaura km 0/0 to 0/270 under MNP (SH: F/C, CD work, WBM, Gr-II, Gr-III, Tarring, parapets and V shape drain in km 0/0 to 0/270)(SW: Formation of cutting in km 0/0 to 0/270) | 258861/- | 5200 | One Month | Rs.350/- |
| 6. | Annual repair and maintenance of various roads under Oachghat sub-division (SH: Supplying and stacking of VI pot seal bag cold mix) Job -2 | 419400/- | 9000 | One Month | Rs.350/- |
| 7. | Restoration of rain damages on Solan Meenus road km 2/0 to 9/300 (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain and tipper for carriage of debris, slips and dump at specified sites) | 210000/- | 4200 | Two Month | Rs.350/- |
| 8 | A/R & M/O PWD rest house at Kandaghat Distt. Solan (SW: Providing sanitation services by deployment of one beldar/sweeper/ part time worker | 99898 | 2000 | Twelve Months | Rs.350/- |
| 9 | Restoration of rain damages on various roads under Oachghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain and tipper for carriage of debris, slips and dump at specified sites in Gaura section) | 197400/- | 4000 | Two Months | Rs.350/- |

| | | | | | |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|---------------|----------|
| 10 | A/R & M/O PWD rest house at Solan Dist. Solan (SW: Providing sanitation services by deployment of one beldar/sweeper/ part time worker | 99898 | 2000 | Twelve Months | Rs.350/- |
| 11 | Restoration of rain damages on kufri Chail Kandaghat road km 2/0 to 57/0 (SH: Supplying/stacking/ crusher. Coarse sand for smooth plying of vehicles in snow bound reaches from km 2/0 to 50/0) | 196700/- | 4000 | Two Months | Rs.350/- |
| 12 | Construction of parking project for Municipal Corporation Solan near Thodo Gound word No. 7 Solan Tehsil & Dist. Solan (Deposit work) (SH: Vetting of structural drawing) | 350000/- | 7000 | One Month | Rs.350/- |

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.



 Executive Engineer
 B&R Division
 HPPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No.PW-SD/CB-Tender/20025-26- 16473-77 Dated: 04/02/26. are of emergent nature of work and in public interest the as per the provision at Sr. No. 5(I to IV) of Govt. Notification No PBW(B) A(3)1/2020 dated 27.05.2021.

Dated:- 04/02/26

Place:- Solan


Executive Engineer
B&R Division
HPPWD, Solan


SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 4,96,684.00
EARNEST MONEY ₹ 10,000.00
TIME ALLOWED Seven Months

N.O.W. :- A/R & M/O various Roads under B&R Solan Division (SH :- Hiring of vehicle to carry out inspection of various roads by SQM/NQM/TPQM/EE/AE for monitoring of ongoing works and inspections during rainy seasons under Solan Division)

| Sr. No. | Description of item | Quantity | Rate (Rs.) | Rate in Words | Amount (Rs.) |
|---------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|-------------|-------------------------------------------------|----------------------|
| 1 | Hiring of inspection vehicle (Diesel/Petrol) such as Bolero or equivalent with driver for official use by the Public Works Department (PWD), including all maintenance, repairs, and POL (Petrol, Oil & Lubricants) charges, for road inspection and monitoring works. The Vehicle must be in good running condition, not older than 5 years with Minimum seating capacity of 5 persons and with Air conditioning preferred. All the Fuel and lubricants to be provided by the contractor/vehicle provider. The Driver must possess a valid driving license and maintain a neat appearance and courteous behavior. All liabilities including driver wages, overtime, road tax, insurance, maintenance, and repair of vehicle to be borne by the vehicle provider. | 7.00 | ₹ 48,750.00 | Fourty Eight Thousands Seven Hundred Fifty Only | ₹ 3,41,250.00 |
| 2 | Fixed Monthly Charges @ 1500 km (8 Hours Daily Service) | 2650.00 | ₹ 23.00 | Twenty Three only | ₹ 60,950.00 |
| 3 | Extra Per Km when Hired for more than prescribed km | 292.00 | ₹ 185.00 | One Eighty Five Only | ₹ 54,020.00 |
| 4 | Extra Rate per Hours when hired for more than prescribed Hours | 72.00 | ₹ 562.00 | Five Hundred and Sixty Two Only | ₹ 40,464.00 |
| | Extra for Night halt if any | | | | |
| TOTAL | | | | | ₹ 4,96,684.00 |
| Total in Words :- | | Rupees Ninety Four Thousands Nine Hundred and Nineteen Only | | | |
| Quoted Percentage rate upto Three Digits :- | | (+)/(-) | | | |

- Conditions :-
- All the repair / maintenance shall be borne by the contractor.
 - Any Accident/ mishap/damage during the course of execution shall be borne by contractor


 Executive Engineer
 B&R HPPWD Division
 Solan

Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in words | | Amount |
|-------------------|---------------------|------|------|------------------|------------------|------------|
| | | | | Figures | Estimated Cost:- | |
| Job No. 29 | | | | Estimated Cost:- | | 384324.00 |
| | | | | Earnest Money:- | | 7700.00 |
| | | | | Time limit:- | | Two months |

Name of Work :- Restoration of rain damages on Kandaghat Hathon road Km.0/00 to 6/00 under PDNA (SH:- Construction of PCC V shape open surface drain at Rd.1/700 to 2/100)

| | | | | | | | |
|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----------------|---------|------------------------------------|--------------------|------------------|
| 1 | Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases. | 100.00 | Per Cubic Meter | 392.00 | Rupees Hundred Two Only | Three Ninety | 39200.00 |
| 2 | Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40 mm (fourty millimeters nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORR Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and other incidental charges. | 20.00 | Per Cubic Meter | 4253.00 | Rupees Thousand Hundred Three Only | Four Two Fifty | 85060.00 |
| 3 | Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORR Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals | 54.00 | Per Cubic Meter | 4816.00 | Rupees Thousand Hundred Only | Four Eight Sixteen | 260064.00 |
| Total:- | | | | | | | 384324.00 |

Quoted Percentage rate upto Three Digits :-

Rupees Three Lakhs Eighty Four Thousand Three Hundred Twenty Four Only

(+)/(-)

Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|--------------------------------------------------------------------------------------------------------------------------------------|---------------------|------|------|-------------------|-------|------------|
| | | | | Figures | words | |
| Job No. :- 23 | | | | Estimated Cost :- | | 358170.00 |
| | | | | Earnest Money :- | | 7200.00 |
| | | | | Time limit :- | | Two months |

Name of Work :- Restoration of rain damages on Kandaghat Hathon road Km.0/00 to 6/00 under PDNA (SH:- Construction of PCC V shape open surface drain with grating at Rd.1/400 to 1/700)

| | | | | | | | |
|---|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------------|---------|------------------------------------|--------------------|----------|
| 1 | Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases. | 75.00 | Per Cubic Meter | 392.00 | Rupees Hundred Two Only | Three Ninety | 29400.00 |
| 2 | Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40 mm (fourty millimeters nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORC Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges. | 15.00 | Per Cubic Meter | 4253.00 | Rupees Thousand Hundred Three Only | Four Two Fifty | 63795.00 |
| 3 | Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORC Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals. | 40.50 | Per Cubic Meter | 4816.00 | Rupees Thousand Hundred Only | Four Eight Sixteen | 195048.0 |

| | | | | | | |
|------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----------------|-------|------------------------------------------------|-----------|
| 4 | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges. | 780.00 | Per Kilogram | 89.65 | Rupees NINE and Sixty Five Paise Only | 69927.00 |
| Total:- | | | | | | 358170.00 |
| Rupees Three Lakhs Fifty Eight Thousand One Hundred Seventy Only | | | | | | |
| Quoted Percentage rate upto Three Digits :- | | | | | | |
| | | | | | | |

T/S No.271 for the year 2025-26
 Sr. No. 460 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-------------------|---------------------------------------------------|---------------------------------------------------------------------------|-----------|
| | | | | Figures | words | |
| <p>Job No. :- 4</p> <p>Name of work :- Construction of Mediation rooms/ Chambers of Top floor of Judicial Court complex at Solan (Deposit work) (SH:- Balance work of providing and fixing wood work, flooring and painting work etc.)</p> | | | | | | |
| 1 | Providing Sal wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc.as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges. | 0.377 | Per Cubic Meter | 91310.90 | Rupees Ninety One Thousand Three Hundred Ten and Paise Ninety Only | 34424.00 |
| 2 | Providing and fixing 4mm thick burl ply of standard quality and of approved shade & design wall lining w/c fixing with approved adhesive, but jointing and nails & screws complete (Base frame work to be measured & paid for separately) as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges. | 127.42 | Per square meter. | 2343.74 | Rupees Two Thousand Three Hundred Forty Three and Paise Seventy Four Only | 298639.00 |
| 3 | Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges. | 127.42 | Per square meter. | 111.52 | Rupees One Hundred Eleven and Paise Fifty Two Only | 14210.00 |
| 4 | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/ litre complete as per HP.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges | 127.42 | Per Square Meter | 52.92 | Rupees Fifty Two and Paise Ninety Two Only | 6743.0 |
| Total:- | | | | | | |
| | | | | Rupees Three Lakhs Fifty Four Thousand Sixteen On | | |
| Quoted Percentage rate upto Three Digits :- | | | | (+)/(-) | | |

T/S No. 276 for the 2025-26
Sr. No. 462 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Draft Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|-----------------------------------------------------------------------------------------------------------|---------------------|------|------|-------------------|-------|-----------|
| | | | | Figures | words | |
| Job No. 5 | | | | | | |
| | | | | Estimated Cost: - | | 258861.00 |
| | | | | Earnest Money: - | | 5200.00 |
| | | | | Time limit: - | | One Month |

Name of work :- Construction of Jeepable road from Manlog to Chaura Km.0/00 to 0/270 under MNP (SH: - FC, CD work, WBM G-I, G- II, G-III, Tarring, parapets and V shape drain in Km.0/00 to 0/270) (SW: - Formation of cutting in Km.0/00 to 0/270)

| | | | | | |
|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----------------|------------------------------------------------------------------------|------------------|
| 1 | Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site according to the HP.PWD. specification and sorting out useful and un-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). The recovery for stones, whether useful or not, for 49.37 Cum (Forty Nine point Thirty Seven cubic metre) in all cases, @ rupees 300/- only (Rupees three hundred only) per cubic meter shall be affected on pro-rata basis in each running bill plus / minus contractor premium. Any loss to the public and private property during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. | 1481.07 | Per Cubic Meter | 174.78 Rupees One Hundred Seventy Four and Paise Seventy Eight Only | 258861.00 |
| Total:- | | | | | 258861.00 |

Rupees Two Lakhs Fifty Eight Thousand Eight Hundred Sixty One Only

T/S No. 277 for the 2025-26
Sr. No. 463 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 258861.00 only.

Executive Engineer
B&R Division, HP.PWD. Solan.

Draft Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|-------------------------------------|-----------|
| | | | | Figures | words | |
| Name of Work :- Annual repair and maintenance of various roads under Oachghat Sub Division (SH:- Supplying and stacking VI pot seal bag cold mix) (Job No.2) | | | | | | |
| 1 | Supplying and stacking of potseal bag of 25 kg cold mix bituminous premix of grade equivalent or more than Bituminous concrete material upto all leads and lifts in the premises of the concerned sub-divisional office store as per direction of Engineer-in-charge. | 600.00 | Each | 699.00 | Rupees Six Hundred Ninety Nine Only | 419400.00 |
| Total:- | | | | | | 419400.00 |
| Rupees Four Lakhs Nineteen Thousand Four Hundred Only | | | | | | |

Sr. No. **466** for the year 2025-26

Draft Schedule of Quantity approved for Rs. 419400.00 only.

Executive Engineer
 B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 2,10,000.00
EARNEST MONEY ₹ 4,200.00

TIME ALLOWED Two Months

Name of Work :- Restoration of rain damages on Solan Meenus road Km.2/00 to 9/300 (SH :- Hiring of Excavator Cum Loader for removal of Debris, slips, clearance of unlined drain and tipper for carriage of debris, slips and dump at specified sites)

| Sr. No. | Description of item | Quantity (Hours) | Rate (Rs.) in Figures | Rate in words | Unit | Amount |
|---------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|-----------------------|------------------------------------|---------------------------|----------------------|
| 1 | Hiring of excavator cum loader for removal of snow, removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator, POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge. | 120.00 | 1050.00 | Rupees Thousand Only | One Rupees Fifty per Hour | 126000.00 |
| 2 | Hiring of tipper for removal of snow/ slips with minimum capacity of 5.5 cum per trip. minimum 6 hours per day. The contractor / owner of tipper shall bear the expenses of POL charges, repair of machinery. Any accident and other damages to private and government property occur during working hour is the whole responsibility of contractor and disposal within all leads, lifts as per the direction of Engineer - in - charge. | 20.00 | ₹ 4,200.00 | Rupees Thousand Two Hundred Only | Four Per Day | ₹ 84,000.00 |
| TOTAL | | | | | | Rs. 210000.00 |
| Total in Words :- | | | | Rupees Two Lakhs Ten Thousand Only | | |
| Quoted Percentage rate upto Three Digits :- | | (+) / (-) | | | | |

Sr. No. 467 for the year 2025-26

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.
5. Hiring charges shall be payable only after signing of agreement and completion of work as per the directions of Engineer-in-charge.

Executive Engineer
B&R HPPWD Division
Solan

Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|--------------------------------------------------|---------------------|------|------|---------|------------------|-----------|
| | | | | Figures | words | |
| Job No 8 | | | | | Estimated Cost:- | 99898.00 |
| | | | | | Earnest Money:- | 2000.00 |
| | | | | | Time:- | 12 Months |

Name of work :- A/R & M/O PWD Rest House at Kandaghat, Distt. Solan (SW :- Providing sanitation services by deployment of one beldar / sweeper / Part time worker)

| | | | | | | |
|----------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|---------|------------|----------------------------------------------------------|-----------------|
| 1 | Sweeping in and around the Rest house including cleaning and washing of floors out side and inside rest house, wash room, kitchen, drain by deploying labour (Timing of labour shall be 7.30 AM to 10.00 AM and 4.00 PM to 6.30 PM at specified places i.e. five hours per day or one thousand eight hundred twenty five hours per annum i.e. 1 Job) as per direction of Engineer in Charge including carriage of all labour, equipment and material to various location through all modes of transportation in all lead, lift and other incidental charges. | 1.000 | Per Job | 99898.00 | Rupess Thousand Hundred Ninety Eight Only | 99898.00 |
| Total :- | | | | | | 99898.00 |
| Total in Words :- | | Rupess Ninety Nine Thousand Eight Hundred Ninety Eight Only | | | | |
| Percentage rate to be quoted by the contractor :- | | | | (+) / (-) | | |

Sr. No. 468 for the year 2025-26

Executive Engineer,
B&R Division, HP.PWD.
Solan.

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 1,97,400.00
EARNEST MONEY ₹ 4,000.00
TIME ALLOWED Two Months

Name of Work :- Restoration of rain damages on Various roads under Oachghat Sub Division (SH :- Hiring of Excavator Cum Loader for removal of Debris, slips, clearance of unlined drain and tipper for carriage of debris, slips and dump at specified sites in Gaura Section)

| Sr. No. | Description of item | Quantity (Hours) | Rate (Rs.) in Figures | Rate in words | Unit | Amount |
|----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------|-----------------------|---------------------------------------|-----------------|----------------------|
| 1 | Hiring of excavator cum loader for removal of snow, removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator, POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge. | 112.00 | 1050.00 | Rupees One Thousand Fifty Only | Rupees per Hour | 117600.00 |
| 2 | Hiring of tipper for removal of snow/ slips with minimum capacity of 5.5 cum per trip, minimum 6 hours per day. The contractor / owner of tipper shall bear the expenses of POL charges, repair of machinery. Any accident and other damages to private and government property occur during working hour is the whole responsibility of contractor and disposal within all leads, lifts as per the direction of Engineer - in - charge. | 19.00 | ₹ 4,200.00 | Rupees Four Thousand Two Hundred Only | Per Day | ₹ 79,800.00 |
| TOTAL | | | | | | Rs. 197400.00 |
| Total in Words :- | | Rupees One Lakh Ninety Seven Thousand Four Hundred Only | | | | |
| Quoted Percentage rate upto Three Digits :- | | (+)/(-) | | | | |

Sr. No. 469 for the year 2025-26

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any accident/ mishap/damage during the course of excavation shall be borne by contractor.
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.
5. Hiring charges shall be payable only after signing of agreement and completion of work as per the directions of Engineer-in-charge.

Executive Engineer

Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------|--------------------------------------------------------------------|------------------------------------------------|-----------------|
| | | | | Figures | words | |
| Job No. 10 | | | | Estimated Cost: - | | 99898.00 |
| | | | | Earnest Money: - | | 2000.00 |
| | | | | Time: - | | Twelve months |
| <p>Name of work :- A/R & M/O PWD Rest House at Solan , Distt. Solan (SH :- Providing sanitation services by deployment of one beldar / sweeper / Part time worker)</p> | | | | | | |
| 1. | Sweeping in and around the circuit house / Rest house including cleaning and washing of floors out side and inside rest house, wash room, kitchen, drain by deploying labour (Timing of labour shall be 7.30am to 10.00am and 4.00pm to 6.30pm at specified places i.e. five hours per day or one thousand eight hundred twenty five hours per annum i.e. 1 Job) as per direction of Engineer in Charge including carriage of all labour, equipment and material to various location through all modes of transportation in all lead, lift and other incidental charges. | 1.000 | Per Job | 99898.00 | Rupees Ninety Nine Thousand Hundred Eight Only | 99898.00 |
| Total :- | | | | | | 99898.00 |
| Total in Words | | | | Rupees Ninety Nine Thousand Eight Hundred Ninety Eight Only | | |
| Percentage rate to be quoted by the contractor :- | | | | (+) / (-) | | |

Sr. No. for the year 2025-26


 Executive Engineer
 B&R Division. HP.PWD. Solan.

91

SCHEDULE OF QUANTITY

ESTIMATED COST INR 1,96,700.00
EARNEST MONEY INR 4,000
TIME ALLOWED Two Months

Name of Work :- RR Damages on Kufri Chail Kandaghat Road km 25/000 To 57/000 (SH :- Supplying / Stacking Crusher/coarse sand for smooth plying of vehicles in snow bound reaches from km 25/000 to 50/000)

| Sr. No. | Description of item | Quantity (Cum) | Rate (Rs.) in Figures | Rate in words | Unit | Amount |
|----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|-----------------------|-------------------------------------------------|----------------|-------------------|
| 1 | Supplying and stacking clean crusher/coarse sand at site of work which should be hard durable chemically inert , clean free from adherent coating particles or organic matter and should not contain impurities like leaves , dirt , dust and deletrious materials , salt or other materials in such form and quality so as to effect adversely its durability. The amount of deletrious substance shall not exceed 4% in case of silt , sand fine dust complete in all respect in stacks , loading and unloading including carriage of materials in all leads , lifts and as per direction of Engineer-in-charge. | 140.00 | ₹ 1,405.00 | Rupees One Thousands four Hundred and five Only | Rupees per Cum | ₹ 1,96,700.00 |
| TOTAL | | | | | | Rs. 196700 |
| Quoted Percentage rate upto Three Digits :- | | (+) / (-) | | | | |

Conditions :-

1. Rates should be quoted for all heights including all leads and lifts.
2. The contractor shall procure all the materials conforming to the **MORD** specifications at his own risk and cost.
3. Sample of all the materials to be used on work shall be got approved from the Engineer-in-charge in advance before actual use of work and any or all of the materials which are available as per Indian standards in the market should confirm to Bureau of Indian Standards.

Executive Engineer
B&R HPPWD Division
Solani

Schedule of Quantity

| Sr. No. | Description of work | Qty. | Unit | Rate in | | Amount |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------|-----------|----------------------------------------------|------------------|
| | | | | Figures | words | |
| Name of work:- Construction of Parking Project for Municipal Corporation Solan near Thodo Ground ward No.7 Solan Teh. & Distt. Solan (HP) (Deposit work) (SH:-Vetting of Structural Drawing) | | | | | | |
| Job No. :- 119 | | | | | | |
| Earnest Money :- 7000.00 Time limit :- One Months | | | | | | |
| 1 | Consultancy services for preparation of detailed structural design drawings for C/o Parking Project for Municipal Corporation Solan near Thodo Ground including vetting/ proof checking from independent institutions like NIT/IT/ PEC/NITTR /BHU . its approval from the competent authority of HPPWD and providing services to the satisfaction of Engineer-in-charge. | 1.000 | Per Job | 350000.00 | Rupees Three Laks Fifty Thousand Only | 350000.00 |
| Total:- | | | | | Rupees Three Laks Fifty Thousand Only | 350000.00 |
| Quoted Percentage rate upto Three Digits :- | | | | | | |

Sr. No. 473 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD. Solan.