

HIMACHAL PRADESH  
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

11636

Dated:-24-2-2026

To,


The Executive Engineer  
IT Cell Nirman Bhawan Nigam Vihar  
HP PWD Shimla

Subject: \_

Regarding NIT for uploading on HP PWD website .


Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 11 Nos copy of Schedule of quantity.

  
Executive Engineer  
Tanda Division HP PWD  
at Nagrota Bagwan

## CERTIFICATE

Certified that the tenders of works, called vide  
this office letter No. PW-DT-NIT-2025-26- 11637-51 Dated:-24-2-2026  
are urgent nature.

  
Executive Engineer  
Tanda Division HP PWD  
at Nagrota Bagwan

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Scaled item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, H.P. PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 03.03.2026 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 02.3.2026 up to 4:00 P.M. and the application for issue of tender form shall be received on 28.02.2026 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Repair of Guest House at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit work (SH: Providing and fixing pre-painted Sheet work etc. (part-I))	98348.00	2000.00	One Month
2	Annual Repair and Maintenance of Various roads under HP PWD Sub-Division Nagrota Bagwan in Distt. Kangra HP (SH: White washing, painting dressing of berms and writing letters etc.)	98611.00	2000.00	Two Months
3	Special Repair to Auditorium Building at Dr. R.P. G.M.C. Tanda in Distt. Kangra HP Deposit Work (SH: Demolishing of brick work, Cement concrete work, Granite work, Glass panes and ceiling work etc.)	86020.00	1750.00	One Months
4	Construction of Shed and Boundary wall near Dead House at Dr. R.P. Govt. Medical college Tanda in Distt. Kangra HP Deposit work (SH: Construction of Shed & Boundary wall part-I)	78742.00	1600.00	One Months
5	Repair of Robotic Surgery Area at Dr. R.P. Govt. Medical College Tanda Distt. Kangra HP Deposit work (SH: Providing and fixing Vinyl Flooring in O.T. 2 <sup>nd</sup> Part-I)	65975.00	1350.00	One Months
6	Special Repair of Labour Room Adjuent area, Galley & Corridor etc at Dr. R.P. Govt. Medical College Tanda Distt. Kangra HP Deposit Work (SH: Providing and applying painting work etc ( Part- I))	85818.00	1750.00	One Months
7	Repair to Guest House Building at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Plaster work Painting work & Other Civil Work etc (Part-I))	66024.00	1350.00	One Months
8	Construction of Toilet Block Outside adult ICU at Dr. R.P. Govt. Medical college Tanda in Distt. Kangra HP Deposit Work (SH: Construction of Civil Work ( Part-I))	99986.00	2000.00	One Months
9	Construction of Paraclinical Block at Dr. R.P. Govt Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Construction of Aluminium Partition at Dianonds Lab (Part-I))	64067.00	1300.00	One months
10	Construction of Toilet Block Outside adult ICU at Dr. R.P. Govt. Medical college Tanda in Distt. Kangra HP Deposit Work (SH: Construction of Civil Work and W.S. & S.I. etc. ( Part-II))	99718.00	2000.00	One Months
11	Construction of Sarai Bhawan at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit work (SH: Balance work of lift Portion)	55970.00	1120.00	One months

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan

**HIMSUCHANA AVAM & JAN SAMPARK**

(On behalf of Governor of Himachal Pradesh)

No. PW/NBD/TA/Tender/NIT/2025-26- **11637-51** Dated/ **24-2-2026**  
Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Executive Engineer IT Cell Shimla HP PWD Shimla
3. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD, Palampur.
4. The Deputy Commissioner, Kangra at Dharamshala
5. All the S.E./E.E.s under North Zone
6. The Sub-Divisional Officer(C) Nagrota Bagwan.
7. All the Assistant Engineer under this Division
8. The Drawing /Accounts Branch in this office
9. Notice Board

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan


### Schedule of Quantity

ESTIMATED COST:- ₹ 98348.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair to Guest House Building at Dr. R.P. Govt. Medical College Tanda in Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Plaster work, Painting work & Other Civil work etc. (Part-I)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 0.60mm (Zero point Sixty millimeters) thick prepainted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimeters) dia metre with prepainted lmpet and rubber washers complete with all accessories as required including carriage of materials within all leads, lifts and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	27.00			Per Square metre	
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials within all leads, lifts and other incidentals	607.50			Per kilogram	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagawan.


**SCHEDULE OF QUANTITY**

ESTIMATED COST: - ₹ 98611.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Annual repair and maintenance of various roads under HPPWD Sub-Division Nagrota Bagwan in Distt. Kangra (H.P.).

SUB HEAD:- *White washing, painting dressing of berms and writing letters etc;*

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	White washing with lime to give an even shade :on old work of approved brand and manufacture of required colour to give an even shade completed as whire required directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	2500.00	3	5	Per Square metre	7
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety liter / Ten square metre)of approved brand and manufacture complete as per drawings, design and HPPWD eighty liter / Ten square metre)of approved brand and manufacture complete as per drawings, design and HPPWD technical specifications as pre directed by the Engineer-Incharge including entire carriage of materials within all leads, lifts and other incidentals.	55.00	35.60	5	Per Square metre	7
3	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc: on concrete work complete as per drawings, design and HPPWD technical specifications as pre directed by the Engineer-Incharge including entire carriage of materials within all leads, lifts and other incidentals.	5000.00	5000.00	5	Per letter per centi-metred height	7
4	Writing letters or figures on any surface with black japan paint (stops, comas, hyphens and the like not to be measured and paid separately) in Block letters/figures complete as per drawings, design and HPPWD technical specifications as pre directed by the Engineer-Incharge including entire carriage of materials within all leads, lifts and other incidentals.	1310.00	1310.00	5	Per square metre	7
5	Making up less of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead (Maintenance of Earthen shoulder (filling with fresh selected soil) as per technical specification Clause 1903, as per directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	350.00	350.00	5	Per square metre	7
6	Painting two coats (excluding priming coat) on previously painted concrete/ masonry/plastered surfaces with enamel paint of approved brand and manufacture for use on floors to give an any shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering as required, including entire carriage of materials within all leads, lifts and other incidentals.			5	Per square metre	7
<b>TOTAL:-</b>						

  
 Executive Engineer,  
 H.P.P. W.D Division,  
 Tanda at Nagrota Bagwan.

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 860  
 EARNEST MONEY :- ₹ 17  
 TIME LIMIT : ONE MO

**NAME OF WORK :-** Special Repair to Auditorium Building at Dr. R.P.G.M.C Tanda in Dist. Kangra (H.P.) **DEPOSIT WORK.**

**SUB-HEAD :-** Demolishing of brick work, Cement Concrete work, Granite work, Glass panes and Ceiling work etc;

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material upto any lead complete as per drawing including carriage of material as directed by the Engineer-in-Charge, within all leads, lifts and other incidentals.	3	4	5	6	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	0.90			Per cubic metre	
3	Providing and fixing 18mm (Eighteen millimetres) thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20mm (Twenty millimetres) thick base cement mortar 1:4 (One cement : Four coarse sand), joints treated with white cement, mixed with matching pigment including single/double moulding, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc; complete upto all floor level including carriage of material within all leads, lifts and other incidentals, as per approved specifications architectural drawing, design and as directed by the Engineer-in-charge.	1.35			Per cubic metre	
4	Providing and fixing 5.5mm (Five point five millimetres) thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.00			Per square metre	
5	Providing and fixing 12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit complete, as directed by the Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	31.50			Per square metre	
		11.64			Per square metre	
<b>TOTAL :-</b>						

  
 Executive Engineer,  
 H.P.P. W.D. Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 78741  
EARNEST MONEY :- ₹ 160  
TIME LIMIT : ONE MO.

**Name of Work:-** Construction of Shed and Boundary Wall Near Dead House at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Construction of Shed & Boundary wall (Part-1)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m Ordinary rock complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other	1.21			Per Cubic metre	
2	Providing and laying 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.21			Per Cubic metre	
3	Providing and laying 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.50			Per Cubic metre	
4	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of putlogs, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/ m <sup>2</sup> complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	25.00			Per Square metre	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	200.00			Per Kilogram	
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	118.25			Per Kilogram	
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/ 10 sqm over an under coat of primer applied @ 0.80 lit/ 10 sqm of approved brand and manufacture complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	16.45			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST :- ₹ 65975.00  
EARNEST MONEY :- ₹ 1350.00  
TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of Robotic Surgery Area at Dr. R.P. Govt. Medical College Tanda Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and fixing Vinyl Flooring in O.T. 2<sup>nd</sup> (Part-I)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 2mm (Two millimetres) thick heavy duty homogeneous vinyl Flooring (ROBUST) plain or coloured, carpet or mosaic/metallic finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	22.75	Square metres			
<b>Total:-</b>						

  
Executive Engineer,  
HP PWD Division,  
Tanda at Nagrota Bagwan.

### Schedule of Quantity

**Name of Work:-** Special Repair of Labour Room Adjacent area, Gallery & Corridor etc at Dr. R.P. Govt. Medical College Tanda Dist. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Providing and applying painting work etc. (Part-~~1~~ 2)

ESTIMATED COST :- ₹ 8581.92  
 EARNEST MONEY :- ₹ 1750.00  
 TIME LIMIT : ONE MONTH

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	749.00			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm (One millimetres), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	298.00			Per Square metre	
3	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	749.00			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST: - ₹ 66024.00  
 EARNEST MONEY: - ₹ 1350.00  
 TIME LIMIT: ONE MONTH

**Name of Work:-** Repair to Guest House Building at Dr. R. P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Plaster work, Painting work & Other Civil work etc. (Part-1)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	15mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering above floor two level to floor three level including arrises, internal rounded angles, channfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	15.56			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	207.00			Per Square metre	
3	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	118.88			Per Square metre	
4	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade Old work (Two or more coats applied @ 1.43 lit/ 10 sqm) over existing cement paint surface complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	324.92			Per Square metre	
5	Painting One or more coats on old work with synthetic enamel paint of approved brand and manufacturer of required colour to give an even shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	121.54			Per Square metre	
<b>Total:-</b>						

Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST: - ₹ 99986.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Construction of Toilet Block outside Adult ICU at Dr. R.P. Govt. Medical College Tanda in Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Construction of Civil Work. (Part-1)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and laying cement concrete 1:2:4 (1 cement: 2 sand : 4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of centring and shuttering in Foundation and plinth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.63			Per Cubic metres	
2	Providing Centring and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bresssumers and cantilever complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.60			Per Square metres	
3	Providing mild steel/Tor steel reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	111.30			Per Kilograms	
4	Brick work using common burnt clay building bricks in Superstructure in Second Class Bricks Cement Mortar 1:6 (1 Cement : 6 Sand) Second Class Bricks complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.04			Per Cubic metres	
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.00			Per Square metres	
6	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/ paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	77.69			Per Kilograms	
7	Providing and Fixing 12mm thick both side Pre Laminated Water Proof Particle board of Tesa / Centaur / Kitlam etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.15			Per Square metres	
8	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and	1.08			Per Square metres	
9	Providing and fixing 300 x16 mm (Three hundred into sixteen millimetres) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Numbers	

3

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
10	Providing and fixing 200x10mm (Two hundred into ten millimetres) size aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	12 Numbers			Each	
11	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade: with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each	
i	125 mm (One hundred twenty five millimetres)	4 Numbers			Each	
ii	100mm (One hundred millimetres)	4 Numbers			Each	
12	Providing and fixing 200 mm (Two hundred millimetres) bright finished brass hard drawn hooks and eyes complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each	
13	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
14	Providing and fixing 1st quality ceramic glazed floor tiles of size 300x450mm conforming to IS : 15622 (thickness to be specified by the manufacturer ) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	15.00 Square metres			Per Square metre	
Total:-						

### Schedule of Quantity

ESTIMATED COST :- ₹ 64067.00  
 EARNEST MONEY :- ₹ 1300.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Construction of Paraclinic Block at Dr. R.P. Govt. Medical College Tanda in Dist. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Construction of Aluminium Partition at Diamonds Lab (Part-1)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount	
			In fig	In words			
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions. i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	123.20			Per Square metre		
2	Providing and fixing 5.5mm (Five point five millimetres) thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	8.70			Square metres		
<b>Total:-</b>						Per Square metre	

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

**Name of Work:-** Construction of Toilet Block outside Adult ICU at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Construction of Civil Work and W.S. & S.I etc. (Part-II)

ESTIMATED COST :- ₹ 99718.  
 EARNEST MONEY :- ₹ 2000.  
 TIME LIMIT : ONE MON


Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sq.m including pointing the joints with white cement and matching pigments etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.16	Square metres		Per Square metre	
2	15mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering above floor two level to floor three level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	39.35	Square metres		Per Square metre	
3	Applying Bitla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	39.35	Square metres		Per Square metre	
4	Finishing wall with weather proof exterior grade emulsion of approved design (Apxultima) or its equarnted on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	39.53	Square metres		Per Square metre	
5	Providing and fixing 0.60mm thick preprepared steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with preprepared iron J or L hooks, bolts and nuts 6mm dia metre with preprepared limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	9.00	Square metres		Per Square metre	
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	202.50	Kilograms		Per Kilogram	
7	Providing and fixing plain multipurpose cement board/High pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid separately) 6 mm thick Cement fiber board as per IS: 14862 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other	6.25	Square metres		Per Square metre	
8	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers		Each	
9	Providing and fixing Flat back 630mmx450mm vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers		Each	

3

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
10	Providing and fixing 32mm dia rubber plug for sink / wash basin complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each	
11	Providing and fixing 100mm sand cast iron grating for gully, floor or Nahni trap complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
12	Providing and fixing 600mm x 450 mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. Brass screws and washers complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
13	Providing and fixing 600mm x 120 mm glass shelf with C.P. Brass bracket and guard rail complete, fixed to wooden plugs with C.P. Brass screws complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
14	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden cleats with C.P. Brass Small (160mm size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
15	Providing and fixing 15mm nominal bore chromium plated ISI marked No. 8934 fancy btb tap E58 or equivalent complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
16	Providing and fixing 15mm diameters brass angle valve without nuts as per approved drawing and design directed by the Engineer-in-charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5 Numbers			Each	
17	Providing and placing water tank make P.V.C. SINTEX having capacity of 1000 liters each tank necessary fittings including over flow pipe scour pipe etcetera and pads required for inlet and outlet and inside painting ball valve with cover and locking arrangements including painting of good quality complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1000.00 Litre			Per Litre	
18	Providing and fixing 110mm dia on wall face PVC (D-Plast) rain water pipes of working pressure not less than 4.5 Kg/sqm including filling the joints with approved adhesive complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	20.00 Running metres			Per Running meter	
19	Providing and fixing on wall faces PVC (D-Plast) accessories for rain water pipes including filling the joints with approved adhesive complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.					
i	PVC 85* bend 110mm dia.	2 Numbers			Each	
ii	PVC shoe 110mm dia.	1 Numbers			Each	
20	Providing and fixing Polyethylene-Aluminium Polyethylene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes testing of joints complete as per direction of the Engineer-in-charge. Concealed work, including cutting chases and making good the wall etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	10.00 Running metres			Per Running meter	
i	15mm nominal bore/diameters.	10.00 Running metres			Per Running meter	
ii	20 mm nominal bore/diameters.	10.00 Running metres			Per Running meter	

Sr. No.	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
10	Providing and fixing 32mm dia rubber plug for sink / wash basin complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each	
11	Providing and fixing 100mm sand cast iron grating for gully, floor or Nahni trap complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
12	Providing and fixing 600mm x 450 mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. Brass screws and washers complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
13	Providing and fixing 600mm x 120 mm glass shelf with C.P. Brass bracket and guard rail complete, fixed to wooden plugs with C.P. Brass screws complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
14	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden cleats with C.P. Brass Small (160mm size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
15	Providing and fixing 15mm nominal bore chromium plated ISI marked No. 8934 fancy bib tap E58 or equivalent complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
16	Providing and fixing 15mm diameters brass angle valve without nuts as per approved drawing and design directed by the Engineer-in-charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5 Numbers			Each	
17	Providing and placing water tank make P.V.C. SINTEX having capacity of 1000 liters each tank necessary fittings including over flow pipe scour pipe etcetera and pads required for in let and out let and inside painting ball valve with cover and locking arrangements including painting of good quality complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1000.00 Litre			Per Litre	
18	Providing and fixing 110mm dia on wall face PVC (D-Plast) rain water pipes of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	20.00 Running metres			Per Running meter	
19	Providing and fixing on wall faces PVC (D-Plast) accessories for rain water pipes including filling the joints with approved adhesive complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
i	PVC 85* bend 110mm dia.	2 Numbers			Each	
ii	PVC shoe 110mm dia.	1 Numbers			Each	
20	Providing and fixing Polyethylene-Aluminium Polyethylene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes testing of joints complete as per direction of the Engineer-in-charge. Concealed work, including cutting chases and making good the wall etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	10.00 Running metres			Per Running meter	
i	15mm nominal bore/diameters.	10.00 Running metres			Per Running meter	
ii	20 mm nominal bore/diameters.	10.00 Running metres			Per Running meter	

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
21	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour, 15 mm nominal bore with 45 cm length complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5 Numbers			Each	
22	Providing and fixing white vitreous china flat back or wall corner type tipped front urinal basin of 430X260X350 mm and 340X102X265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required One urinal basin with 5 litre white P.V.C. automatic flushing cistern complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
23	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75X50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Granite Stone of approved shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.75 Square metres			Per Square metre	
Total:-						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST:- ₹ 55970.00  
 EARNEST MONEY :- ₹ 1120.00  
 TIME LIMIT : ONE MONTH

Name of Work:- Construction of Sarai Bhawan at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)  
 Sub Head:- Balance work of Lift Portion.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.52			Per Cubic metre	
2	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels granite of any colour and shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.64			Per Square metre	
3	Providing and Laying Stone soiling under floor complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.58			Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.58			Per Cubic metre	
5	Providing and laying water proofing of Reinforced cement concrete (RCC) slab with liquicrete 151 as Acrylic Polyamide binding with cement, providing Fibre mesh and liquerete RTU as Two components Acrylic base Modified cementation water proofing coat system complete and ornamental moulding in side of gutter complete as directed by Engineer-In-charge, including entire carriage of material within all leads, lifts and other incidentals.	2.87			Per Square metre	
6	Centering and shuttering including strutting, propping etc. and removal of form for :Suspended floors, roofs, landings, balconies and access platform complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.29			Per Square metre	
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajias, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.95			Per Cubic metre	
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Cold twisted bars complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	113.40			Per Kilograms	
9	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.29			Per Square metre	
10	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	64.10			Per Square metre	
11	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats on new work complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	64.10			Per Square metre	

5

