

Himachal Pradesh
Public Works Department

NO.PW.TH.D./CB-tender/2025-26 - 19439-55

Dated:- 24-1-2026

To


✓ The Executive Engineer, (IT Cell)
O/O Engineer-in- Chief,
H.P.P.W.D., NirmnBhawan, Shimla-2

Subject:- Publication of Tender notice.

Sir,


I am enclosing herewith Notice Inviting Tender for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW (B) A (3) 1/2020 dated 16th July 2021.

As the work mentioned in the tender notice are urgent in nature and in public interest.


Executive Engineer,
TheogDivision, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- The Deputy Commissioner, Shimla Distt. Shimla H.P
- The Superintending Engineer, 4th circle H.P.P.W.,D , Shimla-3.
- The Sub-divisional officer© Theog.
- The municipal Council Theog.
- Block development officer, Theog block.
- All the Assistant Engineer working under this divison
- Superintendent Gr-II (Estt.) in this division.
- Drawing branch in this office.
- Notice Board


Execdutive Engineer,
TheogDivision, B&R,
H.P.P.W.D., Theog

**Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER**

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **19.02.2026 up to 11.00 A.M.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **18.02.2026 up to 4.00 P.M.** and the application for issue of tender form shall be received on **17.02.2026 up to 4.00 P.M.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	EMD (Rs.)	Cost of form (Rs)	Time Allowed
1	2	3	4	5	6	7
1	A/R & M/O Sainj Deha Chopal Road Km 0/0 to 20/740 (SH:- C/O Unlined surface drain in Km 10/00 to 20/740)	Theog	2,06,400/-	4,200/-	350/-	One Month
2	A/R & M/O to PWD office Building at Theog (SH:- C/O shed for DG set and repair of Boundary wall and providing of stair for record room)	Theog	4,29,052/-	8,583/-	350/-	One Month
3	R/R of Rain Damages on Bala to Kishor Road Km 0/0 to 8/00 (SH:- C/O wire crate B/wall at RD 7/500 to 7/520)	Theog	4,98,995/-	10,000/-	350/-	One Month
4	R/R Rain Damages on Bala Kiashor via Deothi Road 0/0 to 1/600 (SH:- C/O RCC B/wall at RD 0/510 to 0/540)	Theog	2,83,320/-	6,000/-	350/-	One Month
5	R/R Damages on Balaghar Tihanadhar Kalna Road Km 0/0 to 24/500 (SH:- C/O PCC B/wall at RD 7/355 to 7/375)	Theog	2,55,560/-	5,112/-	350/-	One Month
6	A/R & M/O Chhaila Sainj Neripul Yashwant Nager Solan Road Km 0/0 to 18/435 (SH:- Providing and Laying Patch work by providing 25 mm thick Bituminous concrete in Km 0/00 to 3/00)	Theog,	4,37,017/-	8,800/-	350/-	One Month
7	C/O Sarion to Gowai via Bhalech Jadeog Road Km 0/0 to 8/00 (SH:- Formation cutting in earth work at RD 3/330 to 4/00)	Theog,	4,85,889/-	10,000/-	350/-	One Month
8	C/O Chalai to GSSS Kot Shilaroo Km 0/0 to 1/300 (SH:- Formation cutting in earth work at RD 0/0)	Theog	4,99,660/-	10,000/-	350/-	One Month

	to 1/300) Balance work					
9	R/R Rain Damages on Bala Kiashor via Deothi Road 0/0 to 1/600 (SH:- C/O RCC R/wall at RD 0/555 to 0/570)	Theog,	4,89,597/-	9,800/-	350/-	One Month
10	R/R Rain Damages on Balaghar Tihanadhar Kalna Road km 0/0 to 24/500 (SH:- C/O RCC R/wall at RD at RD 8/880 to 8/892)	Theog	3,00,509/-	6,050/-	350/-	One Month
11	R/R Rain Damages on Kargoli Nallah to Deha Road Km 0/0 to 8/00 (SH:-C/O RCC R/wall at RD 2/534 to 2/540)	Theog	99,122/-	2,000/-	350/-	One Month
12	R/R Damages on Dhamandri Jais Road Km 0/0 to 6/150 (SH:- C/O B/wall wire create for protection house at Km 3/370 to 3/386)	Theog,	2,80,616/-	5,612/-	350/-	One Month
13	R/R Rain Damages on Kelvi Gadhakuffer Road Km 0/0 to 3/200 (SH:- C/O PCC R/wall at RD 3/045 to 3/060)	Theog	4,89,423/-	10,000/-	350/-	One Month
14	R/R Damages on Sandhu Talash Bago Road Km 0/0 to 3/120 (SH:- C/O B/wall at RD 3/060 to 3/074 and 2/520 to 2/545)	Theog	4,99,528/-	10,000/-	350/-	One Month
15	R/R Damages on Chhaila Sainj Neripul Yashwant Nager Solan Road Km 0/0 to 14/435 (SH:- C/O wire create B/wall at RD 3/390 to 3/405)	Theog	1,62,638/-	3,253/-	350/-	One Month
16	R/R Rain Damages on Sainj Deha Chopal Road Km 0/0 to 20/740 (SH:- Removal of land slide slips in Km 10/135 to 19/790)	Theog	4,98,652/-	10,000/-	350/-	One Month
17	R/R Damages on Balaghar Tihanadhar Kalna Road Km 0/0 to 24/500 (SH:- C/O wire create R/wall at RD 24/028 to 24/040.50)	Theog	3,58,109/-	7,200/-	350/-	One Month
18	R/R Damages on Chhaila Ghoond Banari Road Km 0/0 to 20/615 (SH:- C/O PCC R/wall at RD 18/340 to 18/360)	Theog	2,59,939/-	5,200/-	350/-	One Month
19	R/R of Rain Damages on Various Road Under Theog Sub-Division (SH:- Hiring of Excavator - cum-Loader /Tipper for removal of snow/ slips and surface dressing in various Roads under fagu section)	Theog	4,98,000/-	10,000/-	350/-	One Month
20	R/R Rain Damages on Chhaila Mohari Road Km 0/0 to 11/00 (SH:- C/O PCC R/wall at RD 3/540 to 3/559)	Theog	4,49,818/-	9,000/-	350/-	One Month
21	A/R & M/O Rain Shelter at Sainj on Chhaila Sainj Neripul Yashwant Nager Solan Road (SH:- Steel work , roofing painting etc)	Theog	1,27,133/-	2,550/-	350/-	One Month
22	C/O Dhatti to Manlog via Teer Road Km 0/0 to 3/0 (SH:- C/O PCC B/wall at Rd 0/890 to 0/906)	Theog	2,39,382/-	4,788/-	350/-	One Month
23	R/R Damages on Nangel Devi Naleha Road Km 0/0 to 5/00 (SH:- C/O B/wall at RD 1/550 to 1/563)	Theog	1,87,023/-	3,741/-	350/-	One Month
24	A/R & M/O on Chhaila, Shalowa, tikker up to Ghoond Road Km 0/0 to 12/585 (SH:- Unlined surface drain at RD 6/500 to 12/585 & removal of slips)	Theog	4,99,420/-	9,988/-	350/-	One Month


25	R/R Rain Damages on Thanola Nallah to Kiari Road Km 0/0 to 2/00 (SH:- C/O B/wall at RD 0/825 to 0/845)	Theog	2,26,922/-	4,550/-	350/-	One Month
26	Extention of Ground by Providing R/wall and fencing over wall in Gove Degree College at Theog (SH:- C/O R/wall & Fencing over it)	Theog	4,99,615/-	10,000/-	350/-	One Month
27	R/R Damages of Forest Coleny to Chikhar Pump House Road Km 0/0 to 6/400 (SH:- C/O R/wall at RD 5/630 to 5/641.70 Balance work and proposed B/wall at RD 4/415 to 4/435)	Theog	4,99,860/-	10,000/-	350/-	One Month

- The contractors are required to be produce a copy of their PAN No. GST and should also produce a copy of enlistment /renewal letter.
- Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act, 1952 at the time of tender. Failure to observe this condition shall render the tender of contractor liable to summary rejection.


 Executive Engineer.
 Theog Division B&R,
 H.P.P.W.D Theog.

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW/THD/CB/Tender/2025-26 12439-50 dt 24-01-2026 are of emergent nature in exigency of public interest.


Executive Engineer,
Theog Division, B&R,
H.P.W.D., Theog

Schedule of Quantity

Estimated Cost: 206400/-
Earnest Money: 4200/-
Time: One month

Name of Work - A/R&M/O Sainj Deha Chopal Road km 0/0 to 20/740 (SH:- C/o Unlined surfacee drainin km 10/00 to 20/740)

Sr. No.	Description of Items	QTY.	Rate		Unit	Amount
			in fig	in words		
1	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site (Mechanical Means)	6450.00	32.00	Rupees Thirty Two Only	P/rmt	206400
					Total:-	206400.00
				% above/Below/ as per DNIT amount		
	Quoted Rate(InFig)					
	Quoted Rate(InWords)					

Executive Engineer,
Theog Division,
HP.PWD. Theog.

SCHEDULE OF QUANTITY

Estimated Cost 429052/-
 Earnest Money 8583.00
 Time One Months

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	5.36	240.1	Rupees Two Hundred Forty and Paise Ten Only		P/cum	1287
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge.(1.2.4)	1.70	6500	Rupees Six Thousand Five Hundred Only		P/cum	11050
3	Providing and laying cement concrete 1.4:8(One cement Four sand Eight graded cured/broken stone aggregate 40mm) (forty millimeters nominal size) mechanically mixed and curing complete, excluding cost of form work in foundation and plinth, including carriage of material all leads and lifts and as per direction of the Engineer-in-Charge	5.40	4700	Rupees Four Thousand Seven Hundred Only		P/cum	25380
4	Brick work using common burnt clay building bricks in Foundation and plinth in c.m. 1:4 (1 cement 4sand) second class bricks including carriage of material all leads and lifts and as per direction of the Engineer-in-Charge	10.94	8800	Rupees Eight Thousand Eight Hundred Only		P/cum	96272
5	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement mortar 1:4 (1 cement 4 and) including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	85.00	390	Rupees Three Hundred Ninety Only		P/cum	33150
6	Providing and fixing loulded hand rail of M.S. hollow pipe 50mm dia welded in straight length over M.S. flat at top of vertical balusters including one coat of red oxide priming coat complete (M.S. flat & balusters of railings shall be measured & paid separately including all leads and lifts as per direction of the Engineer-in-Charge	45.00	465.8	Rupees Four Hundred Sixty Five and Paise Eighty Only		P/Rmt.	20961
6.1	Steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts and as per direction of Engineer in Charge.			Rupees NIL Only			0
7	In gratings framed guard bars, ladders, railing, brackets and similar works including carriage of Material with in all leads and lifts as per the direction of Engineer in charge	1624.55	103	Rupees One Hundred Three Only		Kg	167329

Name of work:- A/R & M/O to PWD Office Building at Theog (SH:- C/o shed for DG set and repair of Boundary Wall and providing of stair for Record Room.)

8	Prepainted steel sheet in roofing over steel trusses of Kolermetal or equivalent prepainted single skin trapezoidal profile sheeting 0.60mm thickness having 1060 mm cover with (overall width 1126 mm)28 mm crest depth at 353.2 centre to centre crest distance. There will be two ribs at the centre for stiffening having crest depth of 2.5 mm. the main crest width at top of 25 mm &at lower 81 mm base metl of cold rolled steel coil with zinc coating. Top coat with regular modified polyester coating of approved shade and balancing reverse coat with polyester paint. Fixing of steel shall be with self drilling and self tapping screw of size 5.5 mm dia &Prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 including. carriage of Material with in all leads and lifts as per the direction of Engineer in-charge	5.50	1450	Rupees One Thousand Four Hundred Fifty Only	P/sqm	7975
9	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick prepainted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating 1/2 fixing with prepainted iron J or L hooks, bolts & nuts 6mm dia & prepainted G.I limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charges-including carriage of Material with in all leads and lifts as per the direction of Engineer in-charge	4	550	Rupees Five Hundred Fifty Only	P/Rmt.	1925
10	Supplying and fixing expended metal to wood or steel members in partitions etc.including all leads and lifts as per the direction of Engineer-in-Charge.	51.56	625	Rupees Six Hundred Twenty Five Only	P/sqm	32225
11	Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within all Leads and lifts or as per the direction of Engineer in - Charge of 20 metres with	43.00	415	Rupees Four Hundred Fifteen Only	P/sqm	17845
12	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of Material with in all leads and lifts as per the direction of Engineer in-charge	43.00	110	Rupees One Hundred Ten Only	P/sqm	4730
13	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equariled on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete including carriage of Material with in all leads and lifts as per the direction of Engineer in-charge	43.00	105	Rupees One Hundred Five Only	P/sqm	4515
14	Supplying & fixing glass panes, with putty and nails wherever necessary including removal of old broken glass.	4.64	950	Rupees Nine Hundred Fifty Only	P/sqm	4408
Total						429052
				Quoted rate in figure/(%-----)		
				Quoted rate in words		

Executive Engineer,
Theog Division,

5

DNIT

Estimated Cost Rs.255560

Earnest Money:5200/

Time: One months

Name of work:- R/R Damages on Balghar Tihanadhar Kaina road km 0/0 to 24/500 (SH:- C/O PCC B/wall at RD 7/355 TO 7/375.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	74.60	220.00	Rupees Two Hundred Twenty Only	Per cubic meter	16412
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	52.40	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	229428
3	Providing and fixing weapholes in bnck masonry/stone masonry plain RCC aburment.B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts as per direction of the Engineer -in -Charge.	36.00	270.00	Rupees Two Hundred Seventy Only	Per running meter	9720
						255560

DNIT approved for Rs 255560/- only
 vide Sr No 83 for the year 2024-25
 123

Executive Engineer,
 Theog Division,
 HP.PWD, Theog

SCHDEULE OF QUANTITY

Estimated Cost 437017

Earnest Money:-8800

Time One Month

Name of work:- A/R &M/O Chhaila Sainj Neripul Yashwant Nager Solan Road km 0/0 to 18/435 (SH:-Providing and laying Patch Work by providing 25mm thick Bituminous concrete in Km. 0/00 to 3/00).

Sr No	Description of items	Quantity	Unit	Rate	Amount
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1150.85	Per Sqm	17.25	19852.00
2	Providing and laying 25mm thick Bituminous Concrete with 100-120 (One Hundred to One hundred Twenty) TPH batch type hot mix plant producing an average output of 75 (Seventy Five) tonnes per Hour using crushed aggregates of specified aggregates of specified grading, premixed with bituminous binder (V.G-10) @ 5.5 (Five point five) per cent of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORT&H specification clause No. 509 complete in all respects and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	28.77	Per Cum	14500.00	417165.00
Total:-					437017.00
Quoted Rate in Fig					% above/below /at par
Quoted Rate in Words					



 Executive Engineer
 B&R Division, HP. PWD.
 Theog

SCHEDULE OF QUANTITY

Estimated Cost: 485889/-
Earnest Money: 10000 /-
Time: one month

Name of work: C/O Sarion to Gowai via Bhalech Jadeog Road km 0/0 to 8/00(SH:-Formation cutting in earth work at RD3/330 to 4/00)

Sr. No.	Sub Head and Item of work	Qty.	Rate		Unit	Amount
			4	5		
1	2 Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in-charge at site, according to the HP.PWD. specification of 1990 volume-1 and sorting of useful and unuseful materials and stacking the same in all lead and left and transportation of the unuseful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping sites/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to complete the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials such as stones, shingles, aggregate and slates etc. shall be sorted out. The recovery of 33.97 cum useful stone during the course of execution shall be made @300/cum on prorata basis Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect including all leads and lifts as per direction of the Engineer-in-Charge	3397.35	143.02	Rupees One Hundred Forty Three and Paise Two Only	P/cum	485889.00
					TOTAL:-	485889.00
					% above/Below/at par DNIT amount	
					Quoted Rates in Fig	
					Quoted Rates in Words	



 Executive Engineer,
 Theog Division,
 HP.PWD, Theog.

SCHEDULE OF QUANTITY

Estimated Cost: 499660/-
 Earnest Money: 10000 /-
 Time: one month

Name of work: C/O Chalai to GSSS Kot Shilaroo km 0/0 to 1/300SH:-Formation cutting in earth work at RD/0/0 to 1/300) Balance

Sr No.	Sub Head and Item of work	Qty.	Rate	Unit	Amount
1	<p>2</p> <p>Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP.PWD. specification of 1990 volume-1 and sorting of useful and unuseful materials and stacking the same in all lead and left and transportation of the unuseful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles, aggregate and slates etc. shall be sorted out. The recovery of 59.30 cum useful stone during the course of execution shall be made @300/cum on prorata basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge</p>	2965.34	168.50	Rupees One Hundred Sixty Eight and Paise Fifty Only	499660.00
				TOTAL:-	499660.00
				% above/Below/at par DNIT amount	
	Quoted Rates in Fig				
	Quoted Rates in Words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog.


10

Schedule Of Quantity

Estimated Cost: 300509/-
Earnest Money: 6050 /-
Time: One month

Name of Work - R/R Rain Damages on Balghar Tihanadhar Kalna Road km 0/0 to 24/500 C/O RCC R/Wall at RD8/880 to 8/892)

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
			in fig	in words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	27.36	280.00	P/cum	7661.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size)	56.04	4900.00	P/cum	274596.00
3	Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	20.00	270.00	Each	5400.00
4	Back stone Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	12.24	1050.00	P/cum	12852.00
				Total:-	300509.00
				(% above/below / at Par)	
				Quoted Rates (In Fig)	
				Quoted Rates (In Words)	


 Executive Engineer
 Theog Division
 HP PWD Theog

11

2

Schedule Of Quantity

Estimated Cost 99122/-
Earnest Money 2000 /-
Time: One month

Name of Work - R/R Rain Damages on Kargoli Nallah to Deha Road km 0/0 to 8/00 SH: - C/O RCCR/Wall at RD2/534 to 2/540)

Sr No.	Description of Items	QTY.	Rate	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge (Ordinary Soil)	12.66	in feg 270.00	P/cum	3418.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge (1.4.8) 25 mm nominal size)	17.88	4900.00	P/cum	87612.00
3	Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts as per direction of the Engineer-in-Charge	10.00	242.15	Each	2422.00
4	Back Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	5.40	1050.00	P/cum	5670.00
				Total:-	99122.00
				Quoted Rates (In Fig)	
				Quoted Rates (In Words)	
				(% above/below / at Par)	

Executive Engineer
Theog Division
HP PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs - 280616
 Earnest Money 5612 00
 Time One Months

Name of work:- R/R Damages on Dhamandri Jais Road Km 0/0 to 6/150 (SH:- C/O B/wall wire create for protection house at Km 3/370 to 3/386)

Sr No	Description of item	QTY	Rate in fig	Rate		Unit	Amount
				Rate in words			
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	60.80	200.10	Rupees Two Hundred and Paise Ten Only	P/Cum	12166.08	
2	Providing and laying boulder laid in wire crates with 4mm dia G.I wire conforming to IS 2883 and IS 4826 in 100 mm mesh (woven diagonally) i/c 10 percent extra for laps and joints laid with stone boulder weighing not less than 25 kg each as per drawing and technical specification clauses 130 i/c all leads and lifts as per direction of the Engineer-in-Charge)	91.00	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	P/Cum	268450.00	
Total							
							280616.08

Quoted rate in figer+ / (%.....)

Quoted rate in words


Executive Engineer,
 Theog Division,
 HP.PWD. Theog

Schedule of Quantity

Estimated Cost 489423/-
Earnest Money: 10000/-
Time: One month

Name of Work - R/R Rain Damages on Kelvi Gadhakuffer Road km 0/0 to 3/200(SH:- C/O PCC RWall at RDs 3/045 to 3/060)

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
			in feg		
			in words		
1	Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopess and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge	44.10	180.00	P/cum	7938.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	35.40	220	P/cum	7788.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1.4:8) 25 mm nominal size)	92.84	4800.00	P/cum	445632.00
4	Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts as per direction of the Engineer-in-Charge	48.00	250.00	Each	12000.00
5	Back stone Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	15.30	1050.00	P/cum	16065.00
				Total:-	489423.00
			% above/Below/ as per DNIT amount		
	Quoted Rate(InFig)				
	Quoted Rate(InWords)				



 Executive Engineer
 Theog Division
 HP.PWD Theog

14

SCHEDULE OF QUANTITY

Estimated Cost 499528/-
 Earnest Money 10000.00
 Time: One Months

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge-specification clause 1603.1	63.53	148.00	Rupees One Hundred Forty Eight Only	P/Cum	9402.44	
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge	42.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	8992.20	
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge (1.4.8)	98.44	4725.00	Rupees Four Thousand Seven Hundred Twenty Five Only	P/Cum	465129.00	
4	Providing weepholes in brick masonry/ stone masonry / plin RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe 1/c all leads and lifts as per directions of the Engineer - in Charge	66.00	242.50	Rupees Two Hundred Forty Two and Paise Fifty Only	Each	16005.00	
Total							499528.64
							Quoted rate in fig. + / (%-----)
							Quoted rate in words


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

15

SCHEDULE OF QUANTITY

Estimated Cost Rs - 162638/-
Earnest Money 3253 00
Time One Months

Sr No	Description of Item	QTY	Rate in fig	Rate		Unit	Amount
				Rate in words	Rate in fig		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	20.92	280.00	Rupees Two Hundred Eighty Only	P/Cum	5857.60	
2	Providing and laying boulder laid in wire crates with 4mm dia G.I. wire conforming to IS 2880 and IS 4826 in 100 mm mesh (woven diagonally) 1/4 10 percent extra for laps and joints laid with stone boulder weighing not less than 25 kg each as per drawing and technical specification clauses 130 1/c all leads and lifts as per direction of the Engineer-in-Charge)	46.80	3350.00	Rupees Three Thousand Three Hundred Fifty Only	P/Cum	156780.00	
Total							162638.00


Executive Engineer,
Theog Division,
HP.PWD. Theog

16

Schedule of Quantity

Estimated Cost: 498652 /-

Earnest Money: 10000 /-

Time: One month

Name of Work: R/O Rain damages on Sainj Deha Chopal Road km 0/0 to 20/740(SH):- Removal of land slide slips in km/RD 10/135 to 19/790

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means i/c cutting and trimming of slapes and disposal of cut material with lift upto 1.50 mtrs. And lead upto 100 mtr. As per technical specification: 302.3.5 and 1611 all leads and lifts as per direction of Engineer-in-Charge.	5540.58	in feg 90.00	P/cum	498652.2
				Total:-	498652.00
				% above/Below/ as per DNIT amount	

Executive Engineer
Theog Division
HP PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost 259939/-
Earnest Money 5200 00

Time One Months

Name of work:- R/R Damages on Chhaila Ghoond Banari Road Km 0/0 to 20/615 (SH:- C/O PCC R/wall at RD 18/340 to 18/360)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305 1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	65 20	214 10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	13959.32
2	Providing and Laying concrete 1 4 8 (1 cement 4 sand 8 graded stone aggregate 20 mm Nomonal size) on open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge	52 40	4550 00	Rupees Four Thousand Five Hundred Fifty Only	P/Cum	238420.00
3	Providing and fixing weapholes in brick masonry plain RCC abument B/wall & R/wall with 110 mmm dia (4 Kg Cm2 pressure) PVC pipe etc all leads and lift as per directions of the Engineer - in Charge	36.00	210 00	Rupees Two Hundred Ten Only	P/Each	7560.00
Total						259939.00
			Quoted rate in figer+/(%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog


19

SCHEDULE OF QUANTITY

Estimated Cost: 498000/-
Earnest Money: 10000/-
Time Three month

Name of Work:- Restoration of rain damages on Various Road under Theog sub division (SH:-Hiring of Excavator-Cum Loader/Tipper for removal of snow/slips and surface dressing in Various Roads under Fagu Section)

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of earth cutting / excavating machineries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machineries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	260.00	1050.00	Hrs	273000 00
2	Hiring of full size Tipper 5 50 cum/10 tons loading capacity, self-unloading system on daily basis (for eight hour daly in good condition including the charges of POL Repair ad maintenance and wages of Driver/Operator for lifting of excavated earth/stone slips, drain and disposal of the same in all leads and lifts including disposal of the same in all leads and lifts including carriage of material and as per HPPWD specification of 1990 Vol I and as per the direcion of Engineer in Charge at site)	50.00	4500.00	P/day	225000.00
				Total	498000.00
					% above/Below/as per DNIT amount
					Quoted Rate In Fig
					Quoted Rate In Words



Executive Engineer,
Theog Division,
HP PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs . 127133/-
Earnest Money 2550/-
Time. One Month

Name of work :- A/R & M/O Rain Shelter at Sainj on Chhaila Sainj Neripur Yashwant Nagar solan road (SH:- Steel work, roofing painting etc)

Sl.N	Description of item	Qty	Unit	Rate	Rate	Amount
1	Steel work welded in built up sections/ framed work, including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer - in - Charge	3	4	5	5	6
1	Providing and fixing 0.60 mm thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with pre-painted iron J or L hooks bolts and nuts 6mm dia metre with pre-painted impet and rubber washers complete with all accessories as required as per the direction of engineer - in - charge	564.53	Kg	107.45	Rupees One Hundred Seven and Paise Forty Five Only	60659
2	Providing and fixing 0.60 mm thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with pre-painted iron J or L hooks bolts and nuts 6mm dia metre with pre-painted impet and rubber washers complete with all accessories as required as per the direction of engineer - in - charge	31.41	Sqm	1076.50	Rupees One Thousand Seventy Six and Paise Fifty Only	33813
3	Providing and fixing ridges or hips 60cm overall with 0.60mm thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating plus back coat of polyester of 5 microns over 5 microns primer coating including fixing with screws pre-painted iron J or L hooks, bolts and nuts 6mm diameter with pre-painted GI Impet and bitumen washers complete with all accessories as required complete including all leads and lifts as per direction of the Engineer - in - Charge	7.50	Rmt	620.00	Rupees Six Hundred Twenty Only	4650
4	Providing and fixing MS BP sheet 2.00 mm thick in eaves board / facial/ soffits / ceiling including cutting fixing and welding to steel rnf members and applying a coat of red lead primer complete as per the instruction of Engineer - in - charge (basec members of steel work shall be measured and paid separately).	9.78	Sqm	1993.00	Rupees One Thousand Nine Hundred Ninety Three Only	19492
5	Applying priming coat over new steel and other metal based surface after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting with ready mixed paint brushing wood primer pink with all leads and lifts as per the direction of Engineer-in-charge	71.81	Sqm	33.30	Rupees Thirty Three and Paise Thirty Only	2391
6	Painting two coats excluding priming coat on wood and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter with enamelled paint including in with ready mixed paint other than white with in all leads and lifts as per the direction of Engineer-in-charge	71.81	Sqm	85.35	Rupees Eighty Five and Paise Thirty Five Only	6129
					Total	127133
					% Above/below	
					Quoted Rates in Fig	
					Quoted Rates in Words	


 Executive Engineer
 Theog Division
 HPPWD Theog

SCHEDULE OF QUANTITY

Estimated Cost 239382/-
 Earnest Money 4788 00
 Time One Months

Name of work:- C/O Dathi to Manlog via Teer Road Km 0/0 to 3/0 (SH:- C/O PCC B/wall at RD 0/890 to 0/906)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in fig.		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge specification clause 1603.1	44.00	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	P/Cum	6545.00	
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	21.60	220.00	Rupees Two Hundred Twenty Only	P/Cum	4752.00	
3	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge 1 48	46.88	4700.00	Rupees Four Thousand Seven Hundred Only	P/Cum	220336.00	
4	Providing weepholes in brick masonry/ stone masonry plain reinforcement concrete abutment wing wall R/wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing with in all leads and lifts as per directions of the Engineer-in-Charge)	32.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	7748.80	
Total							239382.00
Quoted rate in figer+ /-(%.....)							
Quoted rate in words							


 Executive Engineer,
Theog Division,
HP.PWD. Theog


SCHEDULE OF QUANTITY

Estimated Cost 187023
 Earnest Money 374100
 Time: One Months

Name of work:- R/R Damages on Nangal Devi to Naleha Road Km 0/0 to 5/00 (SH:- C/O B/wall at RD 1/550 to 1/563)

92

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge specification clause 1603.1	33.34	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	P/Cum	4959.33
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	13.23	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	2832.54
3	Providing and laying concrete 1:4:8 (1 cement 4 sand 6 graded stone aggregate 40 mm nominal size) in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge	36.23	4800.00	Rupees Four Thousand Eight Hundred Only	P/Cum	173904.00
4	Providing weepholes in brick masonry/ stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia (4kg per Cm2 pressure) PVC pipe approved brand i/c all leads and lifts as per directions of the Engineer - in Charge	22.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	5327.30
Total						187023.17
			Quoted rate in figer+ / . (% -----)			
			Quoted rate in words			


 Theog PWD Engineer,
 Theog Division,
 HP.PWD. Theog


24

SCHEDULE OF QUANTITY

Estimated Cost 499420
Earnest Money 998800
Time: One Months

Name of work:- A/R & M/O on Chhailla , Shalowa , Tikker up to Ghoond Road Km 0/0 to 12/585 (SH:- Unlined surface drain at RD 6/500 to 12/585 & removal of slips)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Construction of Unlined Surface Drain of average cross -Sectional area 0.40 sqm in soil to specified lines , grades levels and dimensions Excavated material to be used in embankment with a lifts upto 3 m and lead of 0 m (Average) lead 25 m as per Technical specification Clauses.	6500.00	32.00	Rupees Thirty Two Only	P/Rmt	208000.00	
2	Removal of land slide slip clearance. Removal of slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materials with in lift up to 1.50 mtr And lift up 1000 mtrs.As per technical specification 302.3.5 and 1611.	3238.00	90.00	Rupees Ninety Only	P/Cum	291420.00	
Total							
			Quoted rate in figer+ /-(%.....)			499420.00	
			Quoted rate in words				


Executive Engineer,
Theog Division,
HP.PWD. Theog

95

[Handwritten signature]

Schedule Of Quantity

Estimated Cost 226922/-
Earnest Money: 4550 /-
Time: One month

Name of Work: R/R Rain Damages on Thanola Nallah to Kiri Road km 0/0 to 2/00(SH-C/O BWall at RD 0/825 to 0/845)

Sr No.	Description of Items	QTY.	Rate	in words	Unit	Amount
1	Excavation in Hilly areas in soil by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20 mtr As per technical specification clause 1603 1 including in all leads and lifts as per direction of Engineer-in-Charge	21.80	180.00	Rupees One Hundred Eighty Only	P/cum	3924.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge (Ordinary Soil)	13.40	220.00	Rupees Two Hundred Twenty Only	P/cum	2948.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge (1.6.12) 40 mm nominal size	5.72	4000.00	Rupees Four Thousand Only	P/cum	22880.00
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702.704.1202 and 1204 Random rubble masonry in cement mortar 1.6 including all leads and lifts as per direction of the Engineer-in-Charge (1.6)	49.40	3800.00	Rupees Three Thousand Eight Hundred Only	P/cum	187720.00
4	Back Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	9.00	1050.00	Rupees One Thousand Fifty Only	P/cum	9450.00
				Total:-		226922.00
		Quoted Rates (In Fig)		(% above/below / at Par)		
		Quoted Rates (In Words)				

[Handwritten signature]
Executive Engineer
Theog Division
HP PWD Theog


26

Schedule Of Quantity

Estimated Cost 499615/-
Earnest Money: 10000 /-
Time: One month

Name of Work: -Extension of Ground by Providing R/Wall and fencing over Wall in Govt Degree College at Theog (SH:-C/O R/Wall & Fencing over it))

Sr. No.	Description of Items	QTY.	Rate	in feg	in words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	40.13	220.00		Rupees Two Hundred Twenty Only	P/cum	8828.60
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge (1:2:4) 25 mm nominal size	1.35	7000.00		Rupees Seven Thousand Only		9450.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm nominal size	92.50	5000.00		Rupees Five Thousand Only	P/cum	462500.00
4	Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts as per direction of the Engineer-in-Charge	32.00	250.00		Rupees Two Hundred Fifty Only	Each	8000.00
5	Back Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	10.32	1050.00		Rupees One Thousand Fifty Only	P/cum	10836.00
					Total:-		499615.00
							(% above/below / at Par)
							Quoted Rates (In Fig)
							Quoted Rates (In Words)



Executive Engineer
Theog Division
HP PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost 499860/-
 Earnest Money 10000 00
 Time One Months

Name of work:- R/R Damages on Forest Colony to Chikhar Pumphouse Road Km 0/0 to 6/400 (SH:- C/O R/wall at RD 5/630 to 5/641.70 Balance work and proposed B/wall at Rd 4/415 to 4/435)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge specification clause 1603.1 with in all leads and lifts as per the direction of the Engineer - in Charge	32.20	148.00	Rupees One Hundred Forty Eight Only	P/Cum	4765.60
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge	16.60	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	3554.06
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802.803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge (1:4.8)	98.44	4725.00	Rupees Four Thousand Seven Hundred Twenty Five Only	P/Cum	465129.00
4	Providing weepholes in brick masonry/ stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe 1/c all leads and lifts as per directions of the Engineer - in Charge	47.00	242.50	Rupees Two Hundred Forty Two and Paise Fifty Only	Each	11397.50
5	Back Filling Behind the retaining wall all leads and lifts as per directions of the Engineer - in Charge	11.93	1258.50	Rupees One Thousand Two Hundred Fifty Eight and Paise Fifty Only	P/Cum	15013.91
Total						
						Quoted rate in fig +/- (%-----)
						Quoted rate in words


 Executive Engineer,
Theog Division,
HP.PWD. Theog