Himachal Pradesh
Public Works Department

No-PW/Ksli/CB/Tender /2025-26- 18493-18500 Dated:- 20/02/2026

To

The Executive Engineer, (I.T. cell)
HPPWD, nirman Bhwan, Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on departmental site.

Sir,

Enclosed please find herewith the tender notice of works as given in the Notice inviting Tenders for uploading on departmental web site as per Notification of the Pr. Secretary (PW) to the Govt. of H.P. No. PBW-(B)A((3)1/2024 dated 03.01.2024 & PWD-B-A)(3)/8/2025-300858 dated 09.10.2025 as the work mentioned in the tender notice are urgent in nature and public interest.

DA:- As Above.

Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

Copy to Superintending Engineer, 3rd Circle, HPPWD, Solan for information please.

Copy to All the AE working under this Division for information .
Copy to AB/DB of this office for information.

Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

Scanned with OKEN Scanner

Himachal Pradesh
Public Works Department
" Notice Inviting Tenders"

The Executive Engineer HPPWD Kasauli Distt solan HP on behalf of Governor of HP invites the tender on the form 6 for below mentioned work from the eligible and approved contractors/Firms registered with HPPWD Department.

Job No.	Name of Work	Tentative Cost	Earnest Money	Time allowed	Cost of Form
1	R/R damages on Dharampur Kiyard road in Km 0/00 to 6/510 (SH;- P/L WBM-G-III in patch work and repair of pot holes by providing 20 mm thick premix carpet in patch work in km 3/190 to 3/780) under PDNA	494853/-	9900/-	Two Months	500/-
2	R/R damages on Dharampur Kiyard road in Km 0/00 to 6/510 (SH;- P/L WBM-G-III in patch work and repair of pot holes by providing 20 mm thick premix carpet in patch work in km 2/010 to 3/190) under PDNA	498640/-	10000/-	Two Months	500/-
3	R/R damages on Dharampur Kiyard road in Km 0/00 to 6/510 (SH;- P/L WBM-G-III in patch work and repair of pot holes by providing 20 mm thick premix carpet in patch work in km 3/830 to 4/765) under PDNA	499193/-	10000/-	Two Months	500/-
4	R/R damages on Dharampur Kiyard road in Km 0/00 to 6/510 (SH;- P/L WBM-G-III in patch work and repair of pot holes by providing 20 mm thick premix carpet in patch work in km 4/765 to 5/640) under PDNA	499451/-	10000/-	Two Months	500/-
5	R/R damages on Gharer Patta road in km 15/00 to 30/00(SH:- C/o B/wall in Km 21/505 to 21/550) Under PDNA	498411/-	10000/-	Two Months	500/-
6	R/R damages on Gharer Patta road in km 15/00 to 30/00(SH:- Hiring of JCB/ loader cum excavator along with tipper for removal of slips in km 15/00 to 30/00) under PDNA	485200/-	10000/-	Two Months	500/-
7	R/R damages Trashadi to Pedi road in Km 0/00 to 3/00(SH:- supply of BC on various reaches to rectify the damages portion between kM 0/00 to 0/700) Under PDNA	489579/-	9792/-	One Month	500/-
8	R/R damages Trashadi to Pedi road in Km 0/00 to 3/00(SH:- supply of BC on various reaches to rectify the damages portion between kM 1/00 to 1/800) Under PDNA	495731/-	9915/-	One Month	500/-
9	R/R damages on Shaid Suresh Marg in Km 0/00 to 4/525(SH:- Hiring of JCB for removal of slips, C/o of unlined drain , berm dressing and hiring of tipper for shifting of earh in KM 0/200 to 0/450 & 3/500 to 4/250) Under PDNA	98400/-	2000/-	Two Months	500/-
10	R/R damages Kharyana to Rano Pul road in Km 0/00 to 2/500(SH:- Supply of BC on various reaches to rectify the damages portion between KM 1/700 to 2/500) Under PDNA	496134/-	10000/-	One Month	500/-
11	R/R damages Kharyana to Rano Pul road in Km 0/00 to 2/500(SH:- Supply of BC on various reaches to rectify the damages portion between KM 1/00 to 1/700) Under PDNA	496537/-	10000/-	One Month	500/-
12	R/R damages Kharyana to Rano Pul road in Km 0/00 to 2/500(SH:- Supply of BC on various reaches to rectify the damages portion between KM 0/00 to 1/00) Under PDNA	489982/-	9800/-	One Month	500/-
13	R/R damages on Shilora Khurad to Shillu Kalan Tipra Naryal road in Km 0/00 to5/345 (SH:- C/o both side wing wall of HPC at RDs 2/630) Job No-2 under PDNA	499269/-	10000/-	Two Months	500/-
14	R/R damages on Shilora Khurad to Shillu Kalan Tipra Naryal road in Km 0/00 to5/345 (SH:- C/o both side wing wall of HPC at RDs 2/630) Job No-1 under PDNA	452463/-	9000/-	Two Months	500/-
15	R/R damages on Shilora Khurad to Shillu Kalan Tipra Naryal road in Km 0/800 to5/345 (SH:- C/o both side wing wall of HPC at RDs 2/630) Job No-3 under PDNA	490889/-	9800/-	Two Months	500/-

Scanned with OKEN Scanner

16	R/R damages on Shilora Khurad to Shillu Kalan Tipra Naryal road in Km 0/800 to5/345 (SH:- C/o both side wing wall of HPC at RDs 2/630) Job No-4 under PDNA	466276/-	9300/-	Two Months	500/-
17	R/R damages on Dharampur to Thadi road km 0/00 to 4/150 (SH:- Hiring of Excavator cum loader along with tipper for remvaol of slips, C/o unlined drain opening of catchpits and disposal of muck etc from km 0/00 to 4/150)	384000/-	7680/-	One Month	500/-
18	R/R damages on Sanawar Gate to Mandodhar via Shillar Pathia road km 0/00 to 3/500(SH:- P/L 80MM thick inter lock paver block from RD 0/870 to 0/970 and 1/182 to 1/197) Under PDNA	481609/-	9800/-	Two Months	500/-
19	R/R damages on Sanawar Gate to Mandodhar via Shillar Pathia road km 0/00 to 3/500(SH:- P/L 80MM thick inter lock paver block from RD 1/197 to 1/255,1/580 to 1/636.50) Under PDNA	479515/-	9800/-	Two Months	500/-
20	R/R damagews on Kimmughat Chakki mod road km 0/00 to 16/380(SH:- P/L 80 mm thick paver block from RD 0/075.50 to 0/161 and from RD 0259.70 to ~~0274~~ 0/274.70) Under PDNA	~~497317~~ 497364	10000/-	Two Months	500/-

Date and time of receipt of application for tender form:- **05.03.2026 . up to 12.30 PM**
Issue of tender form **05.03.2026 up to 5.00 PM**
Date and time receipt of tender :- **06.03.2026 up to 10.30 AM**
Date and time opening of tender:- **06.03.2026 11.00APM**

Executive Engineer,
Kasauli Division,
HPPWD Kasauli
(On behalf of the Governor of HP.

Scanned with OKEN Scanner

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	

DRAFT SCHEDULE OF QUANTITY

Job No. :-

R/R Damages

Estimated Cost: -	494853.00
Earnest Money: -	9900.00
Time limit : -	Two Month

Name of Work :- ~~A/R & M~~/O to Dharampur to Kiyarad road in Km. 0/00 to 6/510. (SH:- P/l WBM G-III in patch work and repair to pot holes by providing 20mm thick premix carpet in patch work in km. 3/190 to 3/780). Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting by mechnical means of crushed stone aggregate size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) Grading-III 75mm (seventy five millimetres) consolidated thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. (eight to one hundred) static roller in stages to proper grade and camber, including applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point one eight cubic metres) per ten square metres and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	38.40 m3	Per cubic meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	99036.00
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface by providing tack coat 20mm (twenty millimeters) thick premix carpet and seal coat type B as per specification clause 1904.2, (one thousand nine hundred four point two), 503 (Five hundred three) and 508.1 (five hundred eight point one) of MORD specification, and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts and all incidental charges.	1228.10 m2	Per Square meter.	322.30	Rupees Three Hundred & Twenty Two - Paise Thirty Only	395817.00
						494853.00

1 in Words Rupees Four Lakh Ninety Four Thousand Eight Hundred & Fifty Three Only

% above/below to the DNIT amount i.e. Rs.

T/S No. for the year 2025-26

DNITNo. for the year 2025-26

Draft Schedule of Quantity approved for Rs. 494853.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

r.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	498640.00
Earnest Money: -	10000.00
Time limit : -	Two Month

R/R Damages

Name of Work :- ~~A/R & M/O~~ to Dharampur to Kiyarad road in Km. 0/00 to 6/510. (SH:- P/l WBM G-III in patch work and repair to pot holes by providing 20mm thick premix caarpet in patch work in km. 2/010 to 3/190). Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting by mechnical means of crushed stone aggregate size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) Grading-III 75mm (seventy five millimetres) consolidated thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. (eight to one hundred) static roller in stages to proper grade and camber, including applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point one eight cubic metres) per ten square metres and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	43.88 m3	Per cubic meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	113169.00
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface by providing tack coat 20mm (twenty millimeters) thick premix carpet and seal coat type B as per specification clause 1904.2, (one thousand nine hundred four point two), 503 (Five hundred three) and 508.1 (five hundred eight point one) of MORD specification, and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts and all incidental charges.	1196.00 m2	Per Square meter.	322.30	Rupees Three Hundred & Twenty Two - Paise Thirty Only	385471.00
						498640.00
	Rupees Four Lakh Ninety Eight Thousand Six Hundred & Fourty Only					
1 in Words						
	% above/below to the DNIT amount i.e. Rs.					

T/S No. for the year 2025-26
DNITNo. for the year 2025-26

Draft Schedule of Quantity approved for Rs. 498640.00 only

Executive Engineer
B&R Division, HP.PWD.
Kangra

Scanned with OKEN Scanner

o	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	

DRAFT SCHEDULE OF QUANTITY

Job No. :-

R/R Damages

Estimated Cost:-	499193.00
Earnest Money:-	10000.00
Time limit :-	Two Month

3

Name of Work :- ~~A/R & M/O~~ to Dharampur to Kiyarad road in Km. 0/00 to 6/510. (SH:- P/l WBM G-III in patch work and repair to pot holes by providing 20mm thick premix carpet in patch work in km. 3/830 to 4/765). Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting by mechnical means of crushed stone aggregate size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) Grading-III 75mm (seventy five millimetres) consolidated thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. (eight to one hundred) static roller in stages to proper grade and camber, including applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point one eight cubic metres) per ten square metres and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	23.10 m3	Per cubic meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	59576.00
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface by providing tack coat 20mm (twenty millimeters) thick premix carpet and seal coat type B as per specification clause 1904.2, (one thousand nine hundred four point two), 503 (Five hundred three) and 508.1 (five hundred eight point one) of MORD specification, and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts and all incidental charges.	1364.00 m2	Per Square meter.	322.30	Rupees Three Hundred & Twenty Two - Paise Thirty Only	439617.00
						499193.00

l in Words Rupees Four Lakh Ninety Nine Thousand One Hundred & Ninety Three Only

% above/below to the DNIT amount i.e. Rs.

T/S No. for the year 2025-26

DNITNo. for the year 2025-26

Draft Schedule of Quantity approved for Rs. 499193.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

Sr.No	Description of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount

Job No. :-

DRAFT SCHEDULE OF QUANTITY

Estimated Cost: -	499451.00
Earnest Money: -	10000.00
Time limit : -	Two Month

Name of Work :- ~~A/R & M/O~~ R/R Danazu to Dharampur to Kiyarad road in Km. 0/00 to 6/510. (SH:- P/l WBM G-III in patch work and repair to pot holes by providing 20mm thick premix carpet in patch work in km. 4/765 to 5/640). Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount
1	Providing, laying, spreading and compacting by mechnical means of crushed stone aggregate size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) Grading-III 75mm (seventy five millimetres) consolidated thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. (eight to one hundred) static roller in stages to proper grade and camber, including applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point one eight cubic metres) per ten square metres and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	22.95 m3	Per cubic meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	59189.00
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface by providing tack coat 20mm (twenty millimeters) thick premix carpet and seal coat type B as per specification clause 1904.2, (one thousand nine hundred four point two), 503 (Five hundred three) and 508.1 (five hundred eight point one) of MORD specification, and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts and all incidental charges.	1366.00 m2	Per Square meter.	322.30	Rupees Three Hundred & Twenty Two - Paise Thirty Only	440262.00
						499451.00

1 in Words Rupees Four Lakh Ninety Nine Thousand Four Hundred & Fifty One Only

% above/below to the DNIT amount i.e. Rs.

T/S No. for the year 2025-26

DNITNo. for the year 2025-26

Draft Schedule of Quantity approved for Rs. 499451.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	498411.00
Earnest Money: -	10000.00
Time limit : -	Two Month

5

Name of Work :- R/R damages to Patta Gharade road in Km. 15/00 to 30/300. (SH: C/o PCC B/Wall at Rd 2/505 to 2/550). Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	61.75 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	17136.00
2	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (fourty milimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two,eight hundred three,one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge	100.70 m3	Per cubic meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven Paise Twenty Only	456896.00

Scanned with OKEN Scanner

3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	80.00 No.	Each.	304.74	Rupees Three Hundred & Four · Paise Seventy Four Only	24379.00
						498411.00
1 in Words		Rupees Twenty Four Thousand Three Hundred & Seventy Nine Only				
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 601 for the year 2025-26
DNITNo. 648 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 498411.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

	AMOUNT
Estimated Cost: -	485200.00
Earnest Money: -	2000.00
Time Limit: -	One months.

(6)

ne of work:-R/R of Rain Damages on Gharer Patta road Km 15/00 to 30/300. (SH:-Hiring of JCB/loader cum-excavator along with tipper for Removal of slips in 15/00 to 30/300) Under PDNA

o.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999 . quantity of excavated / removed material should not be less than 28 cum / per hour.	332.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	365200.00
2	Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge , including carriage of all labour equipment and material to various locations through all modes of transportion in all leads and lifts and all incidental charges.	30.00	Per day	4000.00	Rupees two thousands two hundred and sixteen only	120000.00
	Total :-					485200.00

Total in Words **Rupees Four Lakh Eighty Five Thousand Two Hundred Only**

Draft Schedule of Quantity Recommended for approval for Rs. **485200.00** **only.**

Assistant Engineer,
B&R Sub Division,HP.PWD. Chandi

Sr. No. **for the year 24-25**

Draft Schedule of Quantity approved for Rs. 485200.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	489579.00
Earnest Money: -	9792
Time Limit: -	One month.

Name of Work: R/o rain damages on Trasadi to Perri road in KM 0/00 to 3/00 (SH :- Supply of bituminous concrete (BC) on various reaches to rectify the damages portion between KM 0/00 to 0/700 under PDNA.)

Sl. No.	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
1	Prime Coat (i) Low Porosity Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base i/c cleaning of road surface and spraying primer @ 0.70-1.00 kg/m2 using mechanical means as per Technical Specification Clause 502.	1100.00	m2	59.85	Rupees Fifty Nine - Paise Eighty Five Only	65835.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1100.00	m2	20.80	Rupees Twenty - Paise Eighty Only	22880.00
3	Supply of bituminous concrete materials mixed in 100-120 TPH batch type hot mix plant producing ann average output of 75 tonnes pr hour using crushed aggregate of specified grading ie. aggregate Grading II (13.2 to 10 mm thirty per cent, 10-5mm twenty five per cent, 5mm and below forty three per cent of volume of aggregate premixed with bituminous binder @ 5.4 to 5.5 per cent of total weight of mix, nd filler @ 2 per cent of weight of aggregates, complete in all respect at hot mix plant site as per MORTH Specification and as per direction of Engineer-in-Charge.	75.00	Tonne	5344.85	Rupees Five Thousand Three Hundred & Fourty Four - Paise Eighty Five Only	400864.00
	Total :-					489579.00

Total in Words **Rupees Four Lakh Eighty Nine Thousand Five Hundred & Seventy Nine Only**

Draft Schedule of Quantity Recommended for approval for Rs. **489579.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. for the year 25-26

Draft Schedule of Quantity approved for Rs. 489579.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	495731.00
Earnest Money: -	9915
Time Limit: -	One month.

Name of Work: R/o rain damages on Trasadi to Perri road in KM 0/00 to 3/00 (SH :- Supply of bituminous concrete (BC) on various reaches to rectify the damages portion between KM 1/000 to 1/800 under PDNA.)

Sl. No.	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
1	Prime Coat (i) Low Porosity Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base i/c cleaning of road surface and spraying primer @ 0.70-1.00 kg/m2 using mechanical means as per Technical Specification Clause 502.	1110.00	m2	59.85	Rupees Fifty Nine - Paise Eighty Five Only	66434.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1110.00	m2	20.80	Rupees Twenty - Paise Eighty Only	23088.00
3	Supply of bituminous concrete materials mixed in 100-120 TPH batch type hot mix plant producing ann average output of 75 tonnes pr hour using crushed aggregate of specified grading ie. aggregate Grading II (13.2 to 10 mm thirty per cent, 10-5mm twenty five per cent, 5mm and below forty three per cent of volume of aggregate premixed with bituminous binder @ 5.4 to 5.5 per cent of total weight of mix, nd filler @ 2 per cent of weight of aggregates, complete in all respect at hot mix plant site as per MORTH Specification and as per direction of Engineer-in-Charge.	76.00	Tonne	5344.85	Rupees Five Thousand Three Hundred & Fourty Four - Paise Eighty Five Only	406209.00
	Total :-					495731.00

Total in Words **Rupees Four Lakh Ninety Five Thousand Seven Hundred & Thirty One Only**

Draft Schedule of Quantity Recommended for approval for Rs. **495731.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. for the year 25-26

Draft Schedule of Quantity approved for Rs. 495731.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	98400.00
Earnest Money: -	1968.00
Time Limit: -	Two month.

Name of work: - Restoration of rain damages on Shahid Sudesh Marg in Km 0/00 to 4/525 (SH :- Hiring of JCB / loader cum-excavator for Removal of slips and hiring of Tipper for shifting of earth etc between KM 0/200 to 0/450 and KM 3/500 to 4/250 under PDNA .)

Sl. No.	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999 . quantity of excavated / removed material should not be less than 28 cum / per hour.	64.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	70400.00
2	Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge , including carriage of all labour equipment and material to various locations through all modes of transportion in all leads and lifts and all incidental charges.	7.00	Per day	4000.00	Rupees two thousands two hundred and sixteen only	28000.00
	Total :-					98400.00

Total in Words **Rupees Ninety Eight Thousand Four Hundred Only**

Draft Schedule of Quantity Recommended for approval for Rs. **98400.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. **for the year 25-26**

Draft Schedule of Quantity approved for Rs. 98400.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	496134.00
Earnest Money:-	9923
Time Limit: -	One month.

10

Name of Work: R/o rain damages on Kharyana to Ranoput road KM 0/00 to 2/500 (SH :- Supply of bituminous concrete (BC) on various reaches to rectify the damages portion between KM 1/700 to 2/500 under PDNA.)

Sl. No.	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
1	Prime Coat (i) Low Porosity Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base i/c cleaning of road surface and spraying primer @ 0.70-1.00 kg/m2 using mechanical means as per Technical Specification Clause 502.	1115.00	m2	59.85	Rupees Fifty Nine - Paise Eighty Five Only	66733.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1115.00	m2	20.80	Rupees Twenty - Paise Eighty Only	23192.00
3	Supply of bituminous concrete materials mixed in 100-120 TPH batch type hot mix plant producing ann average output of 75 tonnes pr hour using crushed aggregate of specified grading ie. aggregate Grading II (13.2 to 10 mm thirty per cent, 10-5mm twenty five per cent, 5mm and below forty three per cent of volume of aggregate premixed with bituminous binder @ 5.4 to 5.5 per cent of total weight of mix, nd filler @ 2 per cent of weight of aggregates, complete in all respect at hot mix plant site as per MORTH Specification and as per direction of Engineer-in-Charge.	76.00	Tonne	5344.85	Rupees Five Thousand Three Hundred & Fourty Four - Paise Eighty Five Only	406209.00
	Total :-					496134.00

Total in Words Rupees Four Lakh Ninety Six Thousand One Hundred & Thirty Four Only

Draft Schedule of Quantity Recommended for approval for Rs. **496134.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. for the year 25-26

Draft Schedule of Quantity approved for Rs. 496134.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	496537.00
Earnest Money: -	9931
Time Limit: -	One month.

Name of Work: R/o rain damages on Kharyana to Ranopul road KM 0/00 to 2/500 (SH :- Supply of bituminous concrete (BC) on various reaches to rectify the damages portion between KM 1/000 to 1/700 under PDNA.)

Sl. No.	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
1	Prime Coat (i) Low Porosity Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base i/c cleaning of road surface and spraying primer @ 0.70-1.00 kg/m2 using mechanical means as per Technical Specification Clause 502.	1120.00	m2	59.85	Rupees Fifty Nine - Paise Eighty Five Only	67032.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1120.00	m2	20.80	Rupees Twenty - Paise Eighty Only	23296.00
3	Supply of bituminous concrete materials mixed in 100-120 TPH batch type hot mix plant producing ann average output of 75 tonnes pr hour using crushed aggregate of specified grading ie. aggregate Grading II (13.2 to 10 mm thirty per cent, 10-5mm twenty five per cent, 5mm and below forty three per cent of volume of aggregate premixed with bituminous binder @ 5.4 to 5.5 per cent of total weight of mix, nd filler @ 2 per cent of weight of aggregates, complete in all respect at hot mix plant site as per MORTH Specification and as per direction of Engineer-in-Charge.	76.00	Tonne	5344.85	Rupees Five Thousand Three Hundred & Fourty Four - Paise Eighty Five Only	406209.00
	Total :-					496537.00

Total in Words **Rupees Four Lakh Ninety Six Thousand Five Hundred & Thirty Seven Only**

Draft Schedule of Quantity Recommended for approval for Rs. **496537.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. **for the year 25-26**

Draft Schedule of Quantity approved for Rs. 496537.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

(12)

Job No.

	AMOUNT
Estimated Cost: -	489982.00
Earnest Money: -	9800
Time Limit: -	One month.

Name of Work: R/o rain damages on Kharyana to Ranopul road KM 0/00 to 2/500 (SH :- Supply of bituminous concrete (BC) on various reaches to rectify the damages portion between KM 0/000 to 1/00 under PDNA.)

Sl. No.	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
1	Prime Coat (i) Low Porosity Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base i/c cleaning of road surface and spraying primer @ 0.70-1.00 kg/m2 using mechanical means as per Technical Specification Clause 502.	1105.00	m2	59.85	Rupees Fifty Nine - Paise Eighty Five Only	66134.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1105.00	m2	20.80	Rupees Twenty - Paise Eighty Only	22984.00
3	Supply of bituminous concrete materials mixed in 100-120 TPH batch type hot mix plant producing ann average output of 75 tonnes pr hour using crushed aggregate of specified grading ie. aggregate Grading II (13.2 to 10 mm thirty per cent, 10-5mm twenty five per cent, 5mm and below forty three per cent of volume of aggregate premixed with bituminous binder @ 5.4 to 5.5 per cent of total weight of mix, nd filler @ 2 per cent of weight of aggregates, complete in all respect at hot mix plant site as per MORTH Specification and as per direction of Engineer-in-Charge.	75.00	Tonne	5344.85	Rupees Five Thousand Three Hundred & Fourty Four - Paise Eighty Five Only	400864.00
	Total :-					489982.00

Total in Words **Rupees Four Lakh Eighty Nine Thousand Nine Hundred & Eighty Two Only**

Draft Schedule of Quantity Recommended for approval for Rs. **489982.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. for the year 25-26

Scanned with OKEN Scanner

13

DRAFT SCHEDULE OF QUANTITY

Job No. -

Estimated Cost: -	499269.00
Earnest Money: -	10000.00
Time: -	Two Months

Name of Work :- R/R Damages on Shillora Khurad to Shillu Kalan Tipra Naryal road in km 0/00 to 5/345 (SH:- C/O both side Wing Wall of HPC at RDs 2/630) Under PDNA Job No. 2

Sr. No	Description of work	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	167.70	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	46537.00
2	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	96.76	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	439019.00

Scanned with OKEN Scanner

3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1,204.3.7, including carriage of all labour equipment and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	45.00	No	304.74	Rupees Three Hundred & Four Paise Seventy Four Only	13713.00
	Total:-					499269.00
	Rupees Four Lakh Ninety Nine Thousand Two Hundred & Sixty Nine Only					

T/S No. for the year 2025-2026
Sr. No. 615 for the year 2025-2026

Executive Engineer
B&R Division, HP PWD, Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost: -	452463.00
Earnest Money: -	9000.00
Time: -	Two Months

Name of Work :- R/R Damages on Shillora Khurad to Shillu Kalan Tipra Naryal road in km 0/00 to 5/345 (SH:- C/O both side Wing Wall of HPC at RDs 2/630) Under PDNA Job No. 1.

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	54.60	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	15152.00
3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	85.50	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	387931.00

Scanned with OKEN Scanner

3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	40.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	12190.00
4	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	33.60	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six Paise Eighty Five Only	37190.00
	Total:-					**452463.00**
	Rupees Four Lakh Fifty Two Thousand Four Hundred & Sixty Three Only					

T/S No. **for the year 2025-2026**
Sr. No. 614 **for the year 2025-2026**

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	

15

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	~~466276.00~~ 490889.00
Earnest Money: -	9800.00
Time limit : -	Two Month

Name of Work :- R/R damages to Shilora Khurd to Shillu Kalan Tipra Naryal road in Km. 0/800 to 5/345. (SH:- C/o both side wing wall of HPC at Rd 2/630). Job No-3.Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	16.28 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	4518.00
2	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (fourty milimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two,eight hundred three,one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge	91.20 m3	Per cubic meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	413793.00
3	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	47.40 m3	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	52465.00

Scanned with OKEN Scanner

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	66.00 No.	Each.	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	20113.00
						490889.00
1 in Words		Rupees Twenty Thousand One Hundred & Thirteen Only				
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 584 for the year 2025-26
DNITNo. 604 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 466276.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	466276.00
Earnest Money: -	9300.00
Time limit : -	Two Month

Name of Work :- R/R damages to Shilora Khurd to Shillu Kalan Tipra Naryal road in Km. 0/800 to 5/345. (SH:- C/o both side wing wall of HPC at Rd 2/630). Job No-4.Under PDNA.

Sr.No	Description of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	16.80 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	4662.00
2	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (fourty milimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two,eight hundred three,one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge	81.60 m3	Per cubic meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	370236.00
3	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 40mm (forty milimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	5.51 m3	Per Cubic Meter	5297.65	Rupees Five Thousand Two Hundred & Ninety Seven - Paise Sixty Five Only	29190.00

16

Scanned with OKEN Scanner

S.No	Description of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount
4	Providing and laying (to level or slope) reinforced cement concrete pipe NP2- 900 mm (nine hundred milimeter) diameter for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement isto two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets as per technical specification clause 1108(one thousand one hundred eight), or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	5.00 mtr	Per Running Meter	3902.60	Rupees Three Thousand Nine Hundred & Two - Paise Sixty Only	19513.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	33.60 m3	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	37190.00
6	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	18.00 No.	Each.	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	5485.00
						466276.00
		Rupees Five Thousand Four Hundred & Eighty Five Only				
	l in Words					
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 585 for the year 2025-26
DNITNo. 605 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 466276.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

D.N.I.T

Name of work :- R/R damages to Dharampur Thadi road km 0/00 to 4/150 (SH: Hiring of Excavator cum loader along with tipper for removal of slips, c/o unlined drain, opening of catchpits & disposal of muck etc from km 0/00 to 4/150) under PDNA

Estimated cost :- Rs. 3,84,000/- only
Earnest Money :- Rs. 7680 /- only
Time limit :- One Month

S.No	Sub heads and items of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic metre) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORTH specification and the direction of Engineer-in-Charge.	240.00	Per hour	1100.00	Rupees One thousand one hundred only	264000.00
2	Hiring of tipper which shall include all expenses on a/c establishment , POL, repair, and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per directions of Engineer in charge including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges	30.00	per day	4000.00	Rupees four thousand only	120000.00
					Total=	**384000.00**

Assistant Engineer
Kasauli Sub- Division (B&R)
HPPWD Kasauli

Executive Engineer
Kasauli Division (B&R)
HPPWD Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	481609.00
Earnest Money: -	9600.00
Time limit : -	Two Month

Name of Work :- R/R damages to Sanawar Gate to Mandodhar via Shillar Pathai road in km. 0/00 to 3/500. (SH:- P/L 80mm thick interlocking paver blocks from Rds 0/870 to 0/970 and 1/182 to 1/197) Under PDNA

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing and Laying of Interlocking Concrete Blcok Pavements having thickness 80 mm (eighty milimeters) as per drawing and Technical Specification Clause 1504, as per direction of Engineer in Charge including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	386.40	Per Square mete	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	481609.00
	Total :-					481609.00

in Words Rupees Four Lakh Eighty One Thousand Six Hundred & Nine Only

% above/below to the DNIT amount i.e. Rs.

T/S No. 626 for the year 2025-26
DNITNo. 681 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 481609.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

19

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	479515.00
Earnest Money: -	9600.00
Time limit : -	Two Month

Name of Work :- R/R damages to Sanawar Gate to Mandodhar via Shillar Pathai road in km. 0/00 to 3/500. (SH:- P/L 80mm thick interlocking paver blocks from Rds 1/197 to 1/255 and 1/580 to 1/636.50) Under PDNA

Sr. No	Description of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (eighty milimeters) as per drawing and Technical Specification Clause 1504, as per direction of Engineer in Charge including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	384.72	Per Square mete	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	479515.00
	Total :-					479515.00

in Words Rupees Four Lakh Seventy Nine Thousand Five Hundred & Fifteen Only

% above/below to the DNIT amount i.e. Rs.

T/S No. 625 for the year 2025-26
DNITNo 680 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 479515.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost:-	497364.00
Earnest Money:-	9900.00
Time:-	Two Months

Name of Work :- R/R Damages on Kimmughat Chakki mour road in km 0/00 to 16/380 (SH:- P/L Interlocking tiles pavement 80mm thick at RDs 0/075:50 to 0/161 and 0/259:70 to 0/274.70) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	17.09	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine - Paise Fourty Five Only	69034.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504, as per HP PWD. specification 1990 [illegible] (One) including carriage of all labour equipment and material to various location through all modes of transportation in all leads [illegible] including all incidental charges and as per direction of engineer in charge.	321.60	Per Square Meter	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	400842.00
3	Providing and laying plain concrete in RCC grade M 20 (twenty) Nominal mix 1:2:4 (one [illegible] and crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	4.68	Per Cubic Meter	5873.40	Rupees Five Thousand Eight Hundred & Seventy Three - Paise Fourty Only	27488.00
	Total:-				**Rupees Four Lakh Ninety Seven Thousand Three Hundred & Sixty Four Only**	497364.00

T/S No. 620 for the year 2025-2026
Sr. No. 659 for the year 2025-2026

Executive Engineer
B&R Division, HPPWD, Kasauli

Scanned with OKEN Scanner