Himachal Pradesh
Public Works Department

No.PW/Ksli/CB/Tender /2025-26- 17683-90 dated 04/02/2026

To

The Executive Engineer, (IT Cell)
HPPWD Nirman Bhawan, (Nigam Vihar)

Subject:- Publication of Tender Notice on department site.

Sir,

Enclosed please find herewith the tender notice of works as given in the Notice inviting Tenders for uploading on department web site as per Notification of the Pr.Secretary (PW) to the Govt. of H.P. No.PWD-(B)A0(3)8/2025-300858 dated 09.10.2025 as the work mentioned in the tender notice are urgent in nature and Public interest.

DA:- As Above

Executive Engineer,
Kasauli Division
HPPWD Kasauli

Copy to The Superintending Engineer, 3rd Circle, HPPWD, Solan for information Please.

Copy to All the AE working under this Division for information.

Copy to AB/DB of this office for information.

Executive Engineer,
Kasauli Division
HPPWD Kasauli

Scanned with OKEN Scanner

Exigency Certificate

It is Certified that the tenders which were invited vide this office NIT NO.PW/Ksli/CB/Tenders/2025-26-17683-90 dated 04.02.2026 are tp emergent nature of work and in Public Interest.

Place:-Kasauli

Executive Engineer
Kasauli Division
HPPWD Kasauli

Scanned with OKEN Scanner

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER
(Exigency)

Sealed percentage rate tenders on **Form No. 6 , 7&8** are hereby invited by the **Executive Engineer Kasauli Division, HPPWD, Kasauli** for the following works on behalf of the Governor of Himachal Pradesh for the following works from registered contractors of appropriate class enlised in HPPWD, whose registrations stood renewed as per revised instructions and also registered dealers under the himachal Pradesh General Sakes Tax act, 1968 The Improvement dates of tender are as under:-

Sr No	Tender Schedule	Date	Time
1	Receipt of application for tender forms	10 02 2026	Upto 3.00 PM
2	Issue of Tender Forms	11 02 2026	Upto 5 00 PM
3	Receipt of Tenders	12 02 2026	Upto 11 00 AM
4	Opening of Tenders	12 02 2026	At 11 30 AM

The tender Shall be received upto **11.00AM on 12.02.2026** and will be opened on the same day at 11 30AM in the presence of office against cash payment as shown below (Non-refundable)during the working hours The earnest money in the shape of National Saving Certificate, FDR/Account/Sving account in any of the post office/Nationalized Bank in H P duly intending Contractors or their authorized representatives who may like to be present The tender from can be had from this pledged in favour of Executive Engineer, (B&R) Division, HPPWD, Kasauli must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected The offier of the tender hall be kept open for 120days The Executive Engineer reserves the right to reject the tender without assigning any reason

Job No.	Name of Work	Tentative Cost	Earnest Money	Time allowed	Cost of Form
1	R/R damages on Sukhi Johari Kanda Katal Ka Bag road in Km. 0/00 to 15/500.(SH:- C/O R/wall at Rds. 14/213.50 to 14/235)Under PDNA.	4,89,886/-	9800/-	Two Months	350/-
2	R/R damages on Chandi Ghyan road in Km. 0/00 to 5/600.(SH:- Repair of damages portion by P/L 80mm thick Interlocking Tiles Pavement at Various Rds.)Under PDNA.	4,68,735/-	9400/-	Two Months	350/-
3	R/R damages on Chandi Ghyan road in Km. 0/00 to 5/600.(SH:- ROFD at Various reaches and P/L Hume Pipe Culvert at Rds. 5/160)Under PDNA.	4,88,568/-	9800/-	Two Months	350/-
4	R/R damages on Chandi Ghyan road in Km. 0/00 to 5/600.(SH:- C/O R/Wall at Rds. 5/255 to 5/267)Under PDNA.	4,98,713/-	10000/-	Two Months	350/-
5	R/R damages on Himatpur Dabli Kheel (Basholu road)in Km. 0/00 to 6/135.(SH:- C/O R/Wall at Rds. 2/200 to 2/235)Under PDNA.	4,98,232/-	10000/-	Two Months	350/-
6	R/R damages on Garkhal Shaktighat Shamaghat road in Km. 0/0 to 7/00.(SH:- C/O R/Wall in PCC at Rds. 5/985 to 6/00)Under PDNA	3,99,911/-	8000/-	Two Months	350/-
7	R/R damages on Garkhal Gunai road in Km. 0/00 to 9/710.(sH:- C/O R/Wall in PCC at Rds. 3/725 to 3/733)under PDNA.	4,95,296/-	9900/-	Two Months	350/-
8	R/R damages on Garkhal Gunai road in Km. 0/00 to 9/710.(SH:- C/O R/Wall in PCC at Rds. 3/743 to 3/754)Under PDNA.	4,92,565/-	9900/-	Two Months	350/-

Terms &Conditions:-

1. Tender form shall be issued to those contractors who have owned machinery like JCB/Tipper. The application without ownership charges of JCB/Tipper will not be accepted.
2. The tender from will not be issued to those contractor whose performance has been found unsatisfactory.
3. The contractor should have submitted the proof of registration No.EPF No.& GST No.at the Time of tender application failure should not be issued tender forms.
4. Application without earnest money will not be entertained.
5. Executive engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

Executive Engineer,
Kasauli Division
HPPWD Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost:	489886.00
Earnest Money:	9800.00
Time:	Two Months

Name of Work :- R/R Damages on Sukhi Johari Kanda Katal Ka Bag road in km 0/00 to 15/500 (SH:- C/O R/Wall at RDs 14/213.50 to 14/235) under PDNA)

Sr. No	Description of work	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	22.58	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	6266.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	7.08	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine Paise Fourty Five Only	28599.00

Scanned with OKEN Scanner

3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	89.44	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	405807.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	33.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	10056.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	18.06	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	19990.00
6	Providing and laying plain./reinforced concrete i.e. P.C.C. grade M-15 (fifteen) nominal mix 1:2.5:5 (One cement isto two point five sand isto five graded stone) Mechanically mixed and vibrated in / under water and curing complete in open foundations including the cost of form work complete as per drawings and technical specifications clause 802, 803,1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thous two hundred three) curing complete as per MORD specifications including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads lifts and all incidental charges.	3.43	Per Cubic Meter	5588.20	Rupees Five Thousand Five Hundred & Eighty Eight Paise Twenty Only	19168.00
	Total:-					489886.00

Rupees Four Lakh Eighty Nine Thousand Eight Hundred & Eighty Six Only

T/S No. 536 for the year 2025-2026
Sr. No. 547 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost: -	468735.00
	Earnest Money: -	9400.00
	Time: -	Two Months

Name of Work :- R/R Damages on Chandi Ghyan road in km 0/00 to 5/600 (SH:- Repair of damaged portion by P/L 80mm thick Interlocking Tiles Pavement at various RDs) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	85.50	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	23726.00
2	Construction of Granular sub-base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site upto lead of 1000 m spreading in uniform layers with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 as per direction of Engineer in Charge including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	18.00	Per Cubic Metre	2113.35	Rupees Two Thousand One Hundred & Thirteen - Paise Thirty Five Only	38040.00
3	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406.	47.70	Per Cubic Meter	2433.40	Rupees Two Thousand Four Hundred & Thirty Three - Paise Fourty Only	116073.00

Scanned with OKEN Scanner

4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One),including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	198.00	Per Square Meter	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	246787.00
5	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	7.51	Per Cubic Meter	5873.40	Rupees Five Thousand Eight Hundred & Seventy Three - Paise Fourty Only	44109.00
						468735.00
	Total:-					
	Rupees Four Lakh Sixty Eight Thousand Seven Hundred & Thirty Five Only					

T/S No.537 for the year 2025-2026
Sr. No. 548 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD, Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost:	488568.00
		Earnest Money:	9800.00
		Time:	Two Months

Name of Work :- R/R Damages on Chandi Ghyan road in km 0/00 to 5/600 (SH:- ROFD at various reaches and P/L Hume Pipe Culvert at RDs 5/160) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. (one six zero three point one) and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erossions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited). All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge.The recovery of stone, wether useful or not for 19.46 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute	577.74	Per Cubic Metre	193.75	Rupees One Hundred & Ninety Three Paise Seventy Five Only	111937.00
2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.2 and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. All earth work in cutting / excavation ; including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material inspecified manner,trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge for smooth riding. The recovery of stone, wether useful or not for 57.09 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the	342.52	Per Cubic Metre	317.75	Rupees Three Hundred & Seventeen Paise Seventy Five Only	108836.00

3	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc, and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	47.64	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	13220.00
4	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	3.13	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine - Paise Fourty Five Only	12643.00
5	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 20mm (twenty milimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	14.54	Per Cubic Meter	5297.65	Rupees Five Thousand Two Hundred & Ninety Seven Paise Sixty Five Only	77028.00

6	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	27.60	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	125227.00
7	Providing and laying (to level or slope) reinforced cement concrete pipe NP2- 900 mm (nine hundred milimeter) diameter for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement isto two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets as per technical specification clause 1108(one thousand one hundred eight), or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	7.50	Rmt	3902.60	Rupees Three Thousand Nine Hundred & Two - Paise Sixty Only	29270.00
8	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	8.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	2438.00
9	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	7.20	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	7969.00
	Total:-					488568.00

Rupees Four Lakh Eighty Eight Thousand Five Hundred & Sixty Eight Only

T/S No. 535 for the year 2025-2026
Sr. No. 546 for the year 2025-2026

Executive Engineer
B&R Division, HP PWD, Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost:-	498713.00
Earnest Money:-	10000.00
Time:-	Two Months

Name of Work :- R/R Damages on Chandi Ghyan road in km 0/00 to 5/600 (SH:- C/O R/Wall at RDs 5/255 to 5/267) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	64.80	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	17982.00
2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 20mm (twenty milimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	48.24	Per Cubic Meter	5297.65	Rupees Five Thousand Two Hundred & Ninety Seven - Paise Sixty Five Only	255559.00

Scanned with OKEN Scanner

3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	44.10	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	200091.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	30.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	9142.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	14.40	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	15939.00
						498713.00
	Total:-	**Rupees Four Lakh Ninety Eight Thousand Seven Hundred & Thirteen Only**				

T/S No. 534 for the year 2025-2026
Sr. No. 545 for the year 2025-2026

Executive Engineer
B&R Division, HP PWD, Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No :-	Estimated Cost: -	498232.00
	Earnest Money: -	10000.00
	Time: -	Two Month

Name of Work :- R/R Damages on Himatpur Dabli Kheel (Basholu road) in km 0/00 to 6/135 (SH:- C/O R/Wall at RDs 2/200 to 2/235) under PDNA

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing; removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	65.10	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	18065.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand jsto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	5.43	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine - Paise Fourty Five Only	21934.00
3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	92.14	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	418058.00

Scanned with OKEN Scanner

4	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	17.85	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six Paise Eighty Five Only	19757.00
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) :20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	67.00	No	304.74	Rupees Three Hundred & Four Paise Seventy Four Only	20418.00
	Total:-					**498232.00**
	Rupees Four Lakh Ninety Eight Thousand Two Hundred & Thirty Two Only					

T/S No. 531 **for the year 2025-2026**
Sr. No. 540 **for the year 2025-2026**

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost:-	399911.00
	Earnest Money:-	8000.00
	Time:-	Two Months

Name of Work :- R/R Damages on Garkhal Shaktighat Shamaghat road in km 0/00 to 7/00 (SH:- C/O R/Wall in PCC at RDs 5/985 to 6/00) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	48.00	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	13320.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	3.00	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine - Paise Fourty Five Only	12118.00

Scanned with OKEN Scanner

3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	73.13	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	331805.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	39.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	11885.00
5	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	7.65	Per Cubic Meter	1441.35	Rupees One Thousand Four Hundred & Fourty One - Paise Thirty Five Only	11026.00
6	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	17.85	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	19757.00
						399911.00
	Total:-	**Rupees Three Lakh Ninety Nine Thousand Nine Hundred & Eleven Only**				

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

T/S No. for the year 2025-2026
Sr. No. 564 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No:	
Estimated Cost:	495296.00
Earnest Money:	9900.00
Time:	Two Months

Name of Work :- R/R Damages on Garkhal Gunai road in km 0/00 to 9/710 (SH:- C/O R/Wall in PGC at RDs 3/725 to 3/733) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	54.40	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	15096.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.36	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine Paise Fourty Five Only	5494.00

Scanned with OKEN Scanner

3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	91.36	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	414519.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transpersation in all leads lifts and all incidental charges.	42.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	12799.00
5	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 Including carriage of all labour equipment and materials to various location through all modes of transportsation in all leads lifts and all incidental charges.	6.00	Per Cubic Meter	1441.35	Rupees One Thousand Four Hundred & Fourty One - Paise Thirty Five Only	8648.00
6	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	35.00	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six Paise Eighty Five Only	38740.00
	Total:-				**Rupees Four Lakh Ninety Five Thousand Two Hundred & Ninety Six Only**	495296.00

T/S No. ---- for the year 2025-2026

Sr. No. 561 for the year 2025-2026

Executive Engineer
B&R Division, HP PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Estimated Cost: -	492565.00
Earnest Money: -	9900.00
Time: -	Two Months

Name of Work :- R/R Damages on Garkhal Gunai road in km 0/00 to 9/710 (SH:- C/O R/Wall in PCC at RDs 3/743 to 3/754) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	62.70	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	17399.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.87	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine Paise Fourty Five Only	7554.00

Executive Engineer
B&R Division, HP
Kasauli.

Scanned with OKEN Scanner

3	Providing and laying cement concrete for plain concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	91.82	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	416606.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	45.00	No	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	13713.00
5	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	7.92	Per Cubic Meter	1441.35	Rupees One Thousand Four Hundred & Fourty One - Paise Thirty Five Only	11415.00
6	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	23.38	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	25878.00
	Total:-				**Rupees Four Lakh Ninety Two Thousand Five Hundred & Sixty Five Only**	492565.00

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

T/S No. ..... for the year 2025-2026

Sr. No. 563 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD.Kasauli.

Scanned with OKEN Scanner