



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Telephone No:-01782-240075  
e-mail:-ee-kum-hp@nic.in

No. PW-KMS-AB-NIT/2025-26-

8265-58

Dated: - 04/02/26

To

✓ The Executive Engineer (IT Cell),  
HP, PWD, Nirman Bhawan,  
Nigam Vihar Shimla-2

**Subject: -**

**Publication of Tender Notice**


Enclosed please find herewith the tender of works as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 16.07.2021 as the works mentioned in the tender notice are urgent in nature and public interest.

**Encl: - Notice Inviting tender &  
Schedule of Quantity and certificate.**

  
Executive Engineer,  
Kumarsain Division,  
HPPWD Kumarsain

Copy to the Superintending Engineer, 11th Circle,  
HP.PWD., Rampur Bsr. for information please.

Copy to Drawing Branch in this office.

  
Executive Engineer,  
Kumarsain Division,  
HPPWD Kumarsain

## CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED VIDE THIS OFFICE LETTER NO. PW-KMS-AB-NIT/ 2025-26 8216-65 DATED 06/02/26 ARE URGENT NATURE AND PUBLIC INTEREST.

  
Executive Engineer,  
Kumarsain Division,  
HPPWD Kumarsain

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDER"**

Sealed item/percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD. Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before **12.02.2026** up to **10:30 AM** and will be opened on same day at **11:00 AM** in the presence of intending contractors or their authorized representatives who may wish to be present.

The application for issue of tender form shall be received on **11.02.2026** up to **1.00 PM**. The tender form can be had from his office against cash payment (Non-refundable) on **11.02.2026** upto **5.00 PM**.

The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

1. **Name of work:** Restoration of Rain damage on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-C/O PCC R/Wall at Rd.4/620 to 4/635). Estimated Cost:-4,35,408/- Earnest Money: 8750/- Time allowed: -One Month.
2. **Name of work:** Restoration of Rain damage on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-C/O PCC R/Wall at Rd.1/860 to 1/880). Estimated Cost:-4,63,514/- Earnest Money: 9300/- Time allowed: -One Month.
3. **Name of work:** Restoration of Rain damage on Kumarsain Sharambal Camp road Km.0/000 to 2/400 (SH:-C/O PCC R/Wall at Rd.0/820 to 0/838). Estimated Cost:-4,97,176/- Earnest Money:-9950/- Time allowed: -One Month.
4. **Name of work:** Restoration of Rain damage on Link road to Lower Jarol Km.0/000 to 2/400 (SH:-C/O PCC R/Wall at Rd.1/200 to 1/210). Estimated Cost:-4,26,508/- Earnest Money: 8550/- Time allowed: -One Month.
5. **Name of work:** Restoration of Rain damage on Lauga Shathla road Km.0/000 to 3/000 (SH:-C/O PCC R/Wall at Rd.0/420 to 0/429.60). Estimated Cost:-2,22,402/- Earnest Money: 4450/- Time allowed: -One Month.
6. **Name of work:** Restoration of Rain damage on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-C/O PCC B/Wall at Rd.4/560 to 4/580). Estimated Cost:-3,45,048/- Earnest Money: 6900/- Time allowed: -One Month.
7. **Name of work:** Restoration of Rain damage on Link road to Lower Jarol Km.0/000 to 2/400 (SH:-C/O PCC R/Wall at Rd.0/300 to 0/315). Estimated Cost:-4,35,408/- Earnest Money: 8750/- Time allowed: -One Month.
8. **Name of Work:** Restoration of Rain damage on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-C/O PCC B/Wall at Rd.4/050 to 4/075). Estimated Cost:-4,31,425/- Earnest Money: 8650/- Time allowed: -One Month.
9. **Name of Work:** Restoration of Rain damage on Link road to Lower Jarol Km.0/000 to 2/400 (SH:-C/O PCC R/Wall at Rd.1/700 to 1/720). Estimated Cost:-4,63,514/- Earnest Money: 9300/- Time allowed: -One Month.

10. **Name of work:** Restoration of Rain damage on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-C/O PCC R/Wall at Rd.4/588 to 4/608).Estimated Cost:-4,63,514/- Earnest Money: 9300/- Time allowed: -One Month.
11. **Name of work:** Restoration of Rain damage on Jogsha Kumarsain road Km.0/000 to 2/400 (SH:-C/O PCC R/Wall at Rd.1/842.50 to 1/850). Estimated Cost:-3,11,971/- Earnest Money: 6250/- Time allowed: -One Month.
12. **Name of Work:** Restoration of Rain damage on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-C/O PCC B/Wall at Rd.4/945 to 4/965).Estimated Cost:-3,45,048/- Earnest Money: 6900/- Time allowed: -One Month.

**Terms and conditions:-**

1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPF No./ PAN No. along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 75 days.
4. The amount should be within the 5% above.
5. The work should be started within fifteen days from the opening of tender.

Executive Engineer,  
Kumarsain Division  
HP.PWD, Kumarsain

No.PW-KMS-AB-N.I.T/2025-26-

8216-65

Dated:- 04/02/26

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.  
Copy to the Deputy Commissioner Shimla, District Shimla (H.P.)  
Copy to the Sub-Divisional Officer © Kumarsain, Distt. Shimla (H.P.)  
Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.  
Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)  
Copy to all Assistant Engineers under this Division for information & n.a.  
Copy to various contractors for information.  
Copy to Notice Board of this office.

Executive Engineer,  
Kumarsain Division,  
HP.PWD. Kumarsain

DRAFT SCHEDULE OF QUANTITY

216

Estimated cost:-Rs.435408/-

Earnest money:-8750/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Tikker Aldi Baza road Km. 0/000 to 5/090 (SH:-Construction of P.C.C. Retaining wall at RD.4/620 to 4/635). (P.D.N.A)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1.	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	10.35 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	1863.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	53.40 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	13350.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	85.65 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	402555.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	8.40 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	7980.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	42 Nos.	230.00	(Rupees two hundred thirty only).	Each.	9660.00
<b>Total:-</b>						<b>435408.00</b>

Draft schedule of quantity approved for  
Rs. 435408/- only

Executive Engineer,  
Kumarsain Division,  
H.P.W.D., Kumarsain.

219

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.463514/-


Earnest money:-9300/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Tikker Aldi Baza road Km. 0/000 to 5/090. (SH:-Construction of P.C.C. Retaining wall at RD.1/860 to 1/880). (PDMA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	12.80 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	2304.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	54.80 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	13700.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	90.00 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	423000.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	12.00 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	11400.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	57 Nos.	230.00	(Rupees two hundred thirty only).	Each.	13110.00
<b>Total:-</b>						<b>463514.00</b>

Draft schedule of quantity approved for  
Rs. 4,63,514/- only

  
Executive Engineer,  
Kumarsain Division,  
HP PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

223

Estimated cost:-Rs.497176/-

Earnest money:-9950/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Kumarsain Sharambal Camp road Km. 0/000 to 2/400 (SH:-Construction of P.C.C. Retaining wall at RD. 0/820 to 0/838). (PONA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate:		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	26.64 m <sup>3</sup>	180.00	(Rupees one hundred eighty only).	Per cubic metre.	4795.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	55.26 m <sup>3</sup>	250.00	(Rupees two hundred fifty only).	Per cubic metre.	13815.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	98.46 m <sup>3</sup>	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	462762.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	36 Nos.	230.00	(Rupees two hundred thirty only).	Each.	8280.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	7.92 m <sup>3</sup>	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	7524.00
<b>Total:-</b>						<b>497176.00</b>

Draft schedule of quantity approved for  
Rs. 497176/- only

Executive Engineer,  
Kumarsain Division,  
M.P.P.W.D., Kumarsain.

**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.426508/-

Earnest money:-8550/-

Time allowed:-One month.

217

Name of work:-Restoration of rain damages on link road to Lower Jarol Km. 0/000 to 2/400 (SH:-Construction of P.C.C. Retaining wall at RD. 1/200 to

1/210). (PDNA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	21.60 m <sup>3</sup>	180.00	(Rupees one hundred eighty only).	Per cubic metre.	3888.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	35.70 m <sup>3</sup>	250.00	(Rupees two hundred fifty only).	Per cubic metre.	8925.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	84.50 m <sup>3</sup>	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	397150.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	8.70 m <sup>3</sup>	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	8265.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	36 Nos.	230.00	(Rupees two hundred thirty only).	Each.	8280.00
<b>Total:-</b>						<b>426508.00</b>

Draft schedule of quantity approved for  
Rs. 4,26,508/- only

Executive Engineer,  
Kumarsain Division,  
H.P.P.W.D., Kumarsain.

218


DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.222402/-  
Earnest money:-~~4450~~/-  
Time allowed:-One month.

Name of work:-Restoration of rain damages on Luga Shathla road Km. 0/000 to 3/000 (SH:-Construction of P.C.C. Retaining wall at RD. 0/420 to 0/429.60). (PONA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in fill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	6.14 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	1105.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	26.30 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	6575.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	43.20 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	203040.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	5.76 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	5472.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	27 Nos.	230.00	(Rupees two hundred thirty only).	Each.	6210.00
<b>Total:-</b>						<b>222402.00</b>

Draft schedule of quantity approved for  
Rs. 222402/- only

  
Executive Engineer,  
Kumarsain Division,  
H.P.W.D., Kumarsain.

224

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.345048-  
 Earnest money:-6900/-  
 Time allowed:-One month.

Name of work:-Restoration of rain-damages on Tikker Aldi Baza road Km. 0/000 to 5/090 (SH:-Construction of P.C.C. Breast wall at RD.4/560 to 4/580).

(PDNA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	9.60 m <sup>3</sup>	180.00	(Rupees one hundred eighty only).	Per cubic metre.	1728.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	33.60 m <sup>3</sup>	250.00	(Rupees two hundred fifty only).	Per cubic metre.	8400.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	69.40 m <sup>3</sup>	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	326180.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	38 Nos.	230.00	(Rupees two hundred thirty only).	Each.	8740.00
<b>Total:-</b>						<b>345048.00</b>

Draft schedule of quantity approved for  
 Rs. 3,45,048/- only

  
 Executive Engineer,  
 Kumarsain Division,  
 H.P.W.D., Kumarsain.

220

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.435408/-

Earnest money:-8750/-

Time allowed:-One month.

Name of work:-~~Restoration of rain damages on link road to Lower Jarol Km. 0/000 to 2/400 (SH:-Construction of P.C.C. Retaining wall at RD. 0/300 to 0/315).~~ (PDNA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603:10 as per direction of the Engineer-in-charge.	10.35 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	1863.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	53.40 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	13350.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	85.65 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	402555.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	8.40 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	7980.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	42 Nos.	230.00	(Rupees two hundred thirty only).	Each.	9660.00
<b>Total:-</b>						<b>435408.00</b>

Draft schedule of quantity approved for  
Rs. 435408/-

Executive Engineer,  
Kumarsain Division,  
H.P.PWD., Kumarsain.

221

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.431425/-

Earnest money:-8650/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Tikker Aldi Baza road Km. 0/000 to 5/090 (SH:-Construction of P.C.C. Breast wall at RD.4/050 to 4/075).

C PDNA

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	12.00 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	2160.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	42.00 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	10500.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	86.75 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	407725.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	48 Nos.	230.00	(Rupees two hundred thirty only).	Each.	11040.00
<b>Total:-</b>						<b>431425.00</b>

Draft schedule of quantity approved for  
Rs. 431425/- only

Executive Engineer,  
Kumarsain Division,  
H.P.W.D., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

222

Estimated cost:-Rs.463514/-


Earnest money:-9300/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on link road to Lower Jarol Km. 0/000 to 2/400 (SH:-Construction of P.C.C. Retaining wall at RD. 1/700 to 1/720). **(CPDNA)**

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	12.80 m <sup>3</sup>	180.00	(Rupees one hundred eighty only).	Per cubic metre.	2304.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	54.80 m <sup>3</sup>	250.00	(Rupees two hundred fifty only).	Per cubic metre.	13700.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	90.00 m <sup>3</sup>	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	423000.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	12.00 m <sup>3</sup>	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	11400.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	57 Nos.	230.00	(Rupees two hundred thirty only).	Each.	13110.00
<b>Total:-</b>						<b>463514.00</b>

Draft schedule of quantity approved for  
Rs. 4,63,514/- only

  
Executive Engineer,  
Kumarsain Division,  
H.P.W.D., Kumarsain.

226


DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.463514/-  
Earnest money:-9300/-  
Time allowed:-One month.

Name of work:-Restoration of rain damages on Tikker Aldi Baza road Km. 0/000 to 5/090 (SH:-Construction of P.C.C. Retaining wall at RD.4/588 to 4/608). (PDNA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate:		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	12.80 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	2304.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	54.80 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	13700.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	90.00 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	423000.00
4	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	12.00 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	11400.00
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	57 Nos.	230.00	(Rupees two hundred thirty only).	Each.	13110.00
<b>Total:-</b>						<b>463514.00</b>

Draft schedule of quantity approved for  
Rs. 4,63,514/- only

  
Executive Engineer,  
Kumarsain Division,  
H.P.W.D., Kumarsain.

**DRAFT SCHEDULE OF QUANTITY**

225

Estimated cost:-Rs.311971/-


Earnest money:-6250/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Jogsha Kumarsain road Km. 0/000 to 2/400 (SH:-Construction of P.C.C. Retaining wall at RD.1/842.50 to

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	15.37 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	2767.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	32.93 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	8233.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	62.33 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	292951.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	20 Nos.	230.00	(Rupees two hundred thirty only).	Each.	4600.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	3.60 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	3420.00
<b>Total:-</b>						<b>311971.00</b>

Draft schedule of quantity approved for  
Rs. 3,11,971/- only

  
Executive Engineer,  
Kumarsain Division,  
HP PWD., Kumarsain.

228

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.345048/-  
Earnest money:-6900/-  
Time allowed:-One month.

Name of work:-Restoration of rain damages on Tikker Aldi Baza road Km. 0/000 to 5/090 (SH:-Construction of P.C.C. Breast wall at RD.4/945 to 4/965).  
(PDNA)

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	9.60 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	1728.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	33.60 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	8400.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	69.40 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	326180.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	38 Nos.	230.00	(Rupees two hundred thirty only).	Each.	8740.00
<b>Total:-</b>						<b>345048.00</b>

Draft schedule of quantity approved for  
Rs. 3,45,048/- only

Executive Engineer,  
Kumarsain Division,  
I.C. BWD., Kumarsain.