

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Dated:- 26-2-2026

No:-PW-NCD-E-Tender- Publication/2025-26- 10425-82

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: -

Publishing of tender Notice under PDNA.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest and Approved under PDNA-2023.


DA: - Notice Inviting Tender.
(24 Nos. Works)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Copy to Account Branch in this office.
Copy to Drawing Branch in this office.
Notice Board.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed **Percentage rate** tenders on form "688" are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **07.03.2026 upto 01.30 PM** and will be opened on the same day at **3.00 PM** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on that day tender will be opened on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 06.03.2026** and tender form will be issued on dated **07.03.2026 upto 11:30 AM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Restoration of rain damages on Ratti to Randhara road km 0/0 to 9/00. (SH:- Providing B/Wall at RD 5/970 to 5/980). Under PDNA-2023	293579	5900	350	Two Months	"D"
2	Restoration of rain damages on Bhangrotu Nouru Mandal Tikkari road km 0/0 to 4/400. (SH:- C/O R/wall at RD 2/900 to 2/916 and edge wall at RD 2/980 to 2/985) Under PDNA-2023.	496163	10000	350	Two Months	"D"
3	Restoration of rain damages on Dulag Luhardi Banoun Kothi road km 0/0 to 4/00. (Sub Head:- Construction of PCC B/wall with 1:5:10 at RD 2/750 to 2/762). Under PDNA-2023	381651.4	7700	350	Two Months	"D"
4	Restoration of rain damages on Reur Durgapur road km 0/0 to 4/00. (Sub Head:- Construction of PCC Retaining wall with 1:5:10 at RD 1/570 to 1/576). Under PDNA-2023.	170234	3500	350	Two Months	"D"
5	Restoration of rain damages on Rewalsar Pingla Thona Dharpur road km 0/0 to 10/00. (Sub Head:- Construction of wire crate retaining wall at RD 2/313 to 2/332.40). Under PDNA-2023.	499412	10000	350	Two Months	"D"
6	Restoration of rain damages on Bhangrotu Nauru andal Tikkari road KM 0/0 to 4/400 (SH: C/o R/wall at RD 4/380 to 4/390) under PDNA-2023.	323791	6500	350	Two Months	"D"
7	Restoration of damages on 56.00m span Kansa Bridge on road Shimla Mandi Tattapani at km 185/700. (SH:- Construction of approach wall at RD. 185/746 to 185/731.800) Under PDNA-2023	355999	7200	350	Two Months	"D"
8	Restoration of rain damages on Kothi Gehri to Gambharpul road KM 0/0 to 6/750 (SH: Construction of Retaining wall at RD 1/645 to 1/650) under PDNA-2023.	94028	2000	350	One Month	"D"

9	Restoration of damages Jhor to Brangaloo road KM 0/0 to 1/500 (SH: C/o wire crates R/wall at RD 0/855 to 0/866) under PDNA 2023 VR(SD-169).	312024	6300	350	Two Months	"D"
10	Restoration of rain damages on Bhangrotu Nouru Mandal Tikkari road km 0/0 to 4/400. (SH:- C/O R/wall in PCC 1:5:10 at RD 3/490 to 3/501.50) Under PDNA-2023.	494319	9900	350	Two Months	"D"
11	Restoration of rain damages on Rewalsar Dhiundhar road KM 0/0 to 6/0 (Sub Head: Construction of R/wall in PCC 1:5:10 at RD 3/045 to 3/060) under PDNA-2023.	470429	9500	350	One Month	D
12	Restoration of rain damages on Chakkar to Challah road KM 0/0 to 3/0 (SH: C/o PCC drain in 1:3:6 at RD 0/190 to 0/330) under PDNA-2023.	262646	5300	350	Two Months	"D"
13	Restoration of rain damages on Samloun Manjhyali Chalhar Saphru road km 0/0 to 9/945. (SH:- Construction of R/wall in PCC 1:5:10 at RD 2/110 to 2/117) Under PDNA-2023.	131127	2700	350	Two Months	"D"
14	Restoration of rain damages on Tawan Kummi Bhiura Kehar Sakroha Gagal road km 0/0 to 10/700. (SH:- C/O edge wall in PCC at RD 10/070 to 10/080, 10/100 to 10/120 & 10/170 to 10/190) Under PDNA-2023.	430620	8700	350	Two Months	"D"
15	Restoration of rain damages on Kalkhar Leda Sundernagar road km 0/00 to 13/600. (SH:- C/O PCC R/wall with 1:5:10 at RD 7/510 to 7/517). Under PDNA-2023.	292838	5900	350	Two Months	"D"
16	Restoration of rain damages on Bhangrotu Nauru Tikkari road KM 0/0 to 4/400 (SH: Providing B/wall at RD 1/462 to 1/473) under PDNA.	203377	4100	350	One Month	"D"
17	Restoration of rain damages on Mukamgaloo to Arankothi road km 0/0 to 2/500. (SH:- Construction of R/wall in PCC 1:5:10 at RD 1/330 to 1/336). Under PDNA-2023.	113803	2300	350	Two Months	"D"
18	Restoration of rain damages on Lunapani Gehra Sain road km 0/0 to 6/900. (SH:- C/O wire crate R/wall at RD 4/200 to 4/205). Under PDNA-2023.	133555	1900	350	Two Months	"D"
19	Restoration of rain damages on Halyater Gushali Trayambala road km 0/0 to 8/00. (SH:- Construction of PCC R/wall with in 1:5:10 at RD 1/690 to 1/700). Under PDNA-2023.	170120	3500	350	Two Months	"D"
20	RRD on Leda Ghangnoo road km 0/0 to 12/00. (SH:- C/O R/wall in PCC 1:5:10 at RD 0/885 to 0/895). Under PDNA-2023.	186463	3800	350	Two Months	"D"
21	Restoration of rain damages on Bhangrotu Nouru Mandal Tikkari road km 0/0 to 4/400. (SH:- P/L CC pavement in km 0/265 to 0/275 & 0/330 to 0/380 and fixing of parapets at various reaches) Under PDNA-2023.	392937	7900	350	Two Months	"D"

22	Restoration of rain damages on Tawan Kummi Bhiura Kehar Sakroha Galgal road km 0/0 to 10/700. (SH:- C/O B/wall at RD 9/095 to 9/105 & R/wall at RD 9/510 to 9/525) Under PDNA-2023.	484182	9700	350	Two Months	"D"
23	Restoration of rain damages on Paidi Dhadwahan road km 0/0 to 1/700. (SH:- Providing B/wall at RD 0/235 to 0/242.50). Under PDNA-2023	138752	2800	350	One Month	"D"
24	Restoration of rain damages on Bhangrotu Nauru Tikkari road KM 0/0 to 4/400 (SH: C/o R/wall in PCC 1:5:10 at RD 1/730 to 1/745) under PDNA.	418483	8400	350	Two Months	"D"

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. Only two tenders shall be issued to each contractor.
4. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
5. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
6. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Name of Work:- Restoration of rain damages on Ratti to Randhara road km. 0/0 to 9/000 (SH:- Providing B/wall at RD. 5/970 to 5/980) under PDNA-2023.

Draft Sr. No. (171) For the year 2025-26
 DRAFT SCHEDULE OF QUANTITY

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	3875.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	58.48	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	286260.00
3	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	3444.00
TOTAL:-						293579.00

Soft Schedule of quantity checked & approved for Rs. 2,93,579/- only (Rs. Two Lakh Ninety Three Thousand Five Hundred seventy Nine only)


 Executive Engineer
 Nerchowk Division
 HPPWD-Nerchowk

DRAFT SCHEDULE OF QUANTITY
 DWT Sr. No. 216 for the year 2025-26

Name of Work:- Restoration of rain damages on Bhangrotru Nouru Mandal Tikhari road km. 0/0 to 4/400 (SH:- C/O R/wall at RD. 2/900 to 2/916 and edge wall at RD. 2/980 to 2/985) under PDNA-2023.

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	39.62	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	11370.94
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	95.28	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	466395.60
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.00	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	13230.00
4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	5166.00
TOTAL:-						496163.00

Staff schedule of quantity checked & approved for Rs. 4,19,61,63/- only (Rs. Four Lakh Ninety Six Thousand One Hundred Sixty Three only).

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DRAFT Schedule of Quantity for the year 2025.26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dulag Luhardi banoun kothi road km. 0/0 to 4/00. (Sub)
 Head :- Construction of PCC B/wall with 1:5:10 at RD. 2/750 to 2/762) Under PDNA-2023
 Estimated Cost:- 381651.40
 Earnest Money :- 7700.00
 Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	17.40	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	2992.80
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	12.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3444.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	75.48	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	369474.60
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3,7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
Total						381651.40

Say Rs.3,81,651/- only

Draft Schedule of Quantity approved for ₹ 3,81,651/- only.
 (Rs. Three lakh eighty one thousand six hundred fifty one only.)

Executive Engineer,
 HPPWD Division,
 HPPWD-Maharajpur

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP, PWD, Nerchowk.
 Name of Work:- Restoration of Rain Damages on Raur Durgapur road Km 0/00 to 4/000 (Sub Head :- Construction of P.C.C. Retaining Wall with 1:5:10 at RD 1/570 to 1/576) Under PDNA-2023

Contract No: _____

Estimated Cost:- Rs.1,70,234/- only
 Earnest Money :- Rs.3,500/- only
 Time:- Two Months

Sr. No.	Name of the Bidder/Bidding Firm/Company	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic metre	287.00	3814.23	Rupees Three Thousand Eight Hundred Fourteen and Paise Twenty Three Only
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	31.74	Per cubic metre	4895.00	155367.30	Rupees One Lakh Fifty Five Thousand Three Hundred Sixty Seven and Paise Thirty Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	15.00	Each	287.00	4305.00	Rupees Four Thousand Three Hundred Five Only
	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.12	Cum	1102.50	6747.30	Rupees Six Thousand Seven Hundred Fourty Seven and Paise Thirty Only
	TOTAL:-				170233.83	Rupees One Lakh Seventy Thousand Two Hundred Thirty Three and Paise Eighty Three Only

Draft schedule of Quantity approved for ₹ 1,70,234/- only.
 (Rs. One Lakh Seventy Thousand Two Hundred Thirty Four only)

Executive Engineer
 Nerchowk Division
 HP PWD, Nerchowk

DNIT SRNO 155 FOR THE YEAR 2025-26

118

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP, PWD, Nerchowk.
 Name of Work:- Restoration of Rain Damages on Rewalsar Pingla Thouna Diarnpur road Km 0/00 to 10/000 (Sub Head :- Construction of Wire crate Retaining Wall at RD 2/313 to 2/332.40) Under PDNA-2023
 Contract No: _____

Estimated Cost:- Rs.4,99,412/- only
 Earnest Money :- Rs.10,000/- only
 Time:- Two Months

St. No.	Name of the Bidder/Bidding Firm/Company	Quantity	Units	Rate including GST in Rs. P.	Total amount including GST in Rs. P.	Total amount with all taxes including GST in words
1	1	3	4	5	6	7
1	Providing and Laying of boulder apron laid in wire crates with 4mm mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications Clause 1301 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	153.65	Cum	3100.00	476315.00	Rupees Four Lakh SeventySix Thousand Three Hundred Fifteen Only
2	Back filling behind abutment behind wing wall & return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.95	Cum	1102.50	23097.38	Rupees TwentyThree Thousand NineySeven and Paise ThirtyEight Only
TOTAL:-					499412.38	Rupees Four Lakh NinetyNine Thousand Four Hundred Twelve and Paise ThirtyEight Only

Say Rs. 4,99,412 /-

Draft Schedule of Quantity approved for ₹ 4,99,412/- only.
 (Rupees Four lakh ninety nine thousand Four Hundred Twelve only)

Executive Engineer
 Nerchowk Division
 HP PWD Nerchowk

D/117 Sr. No. (196) for the year 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhangrotu Nauru Mandal Tikkari road km. 0/0 to 4/400 (SH:- C/O R/wall at RD. 4/380 to 4/390) under PDNA-2023.

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	30.50	Per cubic metre	287.00	Rupees Two Hundred EightySeven Only	8754.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	60.75	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred NinetyFive Only	297371.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.90	Per cubic metre	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty Only	14222.00

Estimated Cost:- 323791.00

Earnest Money:- 6500.00

Time:- Two Months

Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.

TOTAL:-

12.00	Nos.	287.00	Rupees Two Hundred Eighty Seven Only	3444.00
				323791.00

Self Schedule of quantity checked & approved for Rs. 3,23,791/- only (Rs. Three Lakh Twenty Three Thousand Seven Hundred Ninety one only)

[Signature]
 Executive Engineer
 Nerchowk Division
 P.P.W.D. Nerchowk

DWT Sr. No. 900 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of damages on 56.00m span Kansa Bridge on road Shimla Mandi Tattapani at km. 185/700 (SH):- Construction of approach wall at RD. 185/746 to 185/731.800) under PDNA-2023.

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.44	Per cubic metre	287.00	Rupees Two Hundred EightySeven Only	1561.28
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement: 4 fine sand: 8 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	60.71	Per cubic metre	5000.00	Rupees Five Thousand Only	303550.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement: 3 fine sand: 6 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.49	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred FourtySeven Only	39300.03

Estimated Cost:- 355999.00

Earnest Money:- 7200.00

Time:- Two Months

4	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.51	Per cubic metre	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty Only	11587.28
TOTAL:-						355999.00

Doft schedule of quantity checked & approved for Rs. 3,55,999 only (Rs. Three Lakh Fifty Five Thousand Nine hundred Ninety Nine only)

[Signature]
 Executive Engineer
 Nerchowk Division
 RPPWD-Nerchowk

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kolthigehri to Gambharpu road km. 0/0 to 6/750.
 Head :- Construction of Retaining wall at RD. 1/645 to 1/650) Under PDNA-2023

(Sub) Estimated Cost:- Say Rs. 94028/-

Earnest Money :- 2000.00

Time :- One Months

Sr.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
0						
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.35	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3257.45
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	17.73	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	86788.35
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (One vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including Carriage of material and other incidentals as per the direction of the Engineer-in Charge .	6.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Nos	1722.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	2.05	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	2260.13
					Total	94027.93

Draft Schedule of Quantity approved for ₹ 94028/- only.

Rs. Ninety Four Thousand Twenty Eight only)


 Executive Engineer
 HPWD Division,
 PWD Narayana

DNIT SRNO 162 FOR THE YEAR 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of damages Jhor to Brangaloo road km. 0/0 to 1/500. (Sub Head:- C/o Wire Crates R/wall at RD 0/855 to 0/866) Under PDNA-2023 VR(SD.-169)

Estimated Cost:- 312204.26

Earnest Money :- 6300.00

Time :- Two Months

Sr.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
0						
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	42.24	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	12122.88
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	95.04	3100.00	Rupees Three thousand One hundred and paise zero only.	Per Cubic Metre	294624.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	4.95	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	5457.38
					Total	312204.26
						Say Rs.3,12,204 /-

Draft Schedule of Quantity approved for ₹ 3,12,204 /- only.
(Rs Three Lakh Twelve Thousand Two Hundred Four only)

Executive Engineer,
MPPWD Division,
MPPWD Nerchowki

DRAFT SCHEDULE OF QUANTITY

DMIT Sr. No. (213) for the year 2025-26

Name of Work:- Restoration of rain damages on Bhangrotu Nouru Mandal Tikhari road km. 0/0 to 4/400 (SH:- C/O R/wall
 in PCC 1:5:10 at RD. 3/490 to 3/501.50) under PDNA-2023.

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	33.70	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	9671.90
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	94.59	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	463018.05
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	13.11	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	14453.78
4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	25.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	7175.00
TOTAL:-						494319.00

Do not schedule of quantity checked & approved for Rs. 4,94,319/only
 (Rs. Four Lakh Ninety Four Thousand Three Hundred Ninety only)


 Executive Engineer
 Nerchowk-Division
 HPPWD-Nerchowk

DRAFT SRNO 165 FOR THE YEAR 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rewalsar Dhunidhar road km. 0/0 to 6/00.
(Sub Head :- Construction of R/wall in PCC 1:5:10 at RD, 3/045 to 3/060), Under PDNA-2023

Estimated Cost:- 470429.00
Earnest Money :- 9500.00
Time :- One Months

Sr.No	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305. Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres, dressing of sides and bottom and back filling in trenches with excavated suitable material. Ordinary soil upto 3.00 mtrs. depth including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	50.70	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	14551.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	88.14	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	431445.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical iso twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	35.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	10045.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	13.05	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	14388.00
Total						470429.00

**Draft Schedule of Quantity approved for ₹ 4,70,429/- only.
(Rs. Four Lakh Seventy Thousand Four Hundred Twenty nine only)**

Executive Engineer,
HPPWD Division,
HPPWD Nerchowak

DRAFT Sr. No. 205 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Chakkar to Challah road km. 0/0 to 3/000 (SH:- C/O PCC drain in 1:3:6 at RD. 0/190 to 0/330) under PDNA-2023.

Estimated cost:- 262646.00
 Earnest Money Cost:- 5300.00
 Time:- Two Months

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	83.30	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	23907.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement : three sand : six graded, crushed stone aggregate 20mm (Twenty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.50	Per cubic meter	5247.00	Rupees Four Thousand Eight Hundred Ninety Five only	238739.00
TOTAL:-						262646.00

Draft schedule of quantity checked & approved for R. 2, 62, 646 / only (Rs. Two Lakh sixty Two Thousand six hundred forty six only).


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Samloun Manjiryali Chahar Saphru Road Km 0/0 to 9/945 (Sub Head :-Construction of RWWall in P.C.C. 1:5:10 at RD 2/110 to 2/117) Under PDNA-2023

Estimated Cost:- 131127.00

Earnest Money :- 2700.00

Time :- One Months

Sr.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305. Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres, dressing of sides and bottom and back filling in trenches with excavated suitable material. Ordinary soil upto 3.00 mtrs. depth including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.61	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	4480.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clause 802, 803, 1202 and 1203. (Nominal mix 1:5:10) including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	24.64	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	120613.00
3	Providing weep holes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3,7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	10.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2870.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3,8, including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	2.87	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	3164.00
					Total	131127.00

*Draft schedule of Quantity approved for ₹ 1,31,127/- only.
(Rs. One Lakh Thirty One Thousand One Hundred Twenty Seven only)*


 Executive Engineer,
 HPPWD Division,
 HPPWD Narchowda

DWT Sr. No. (214) for the year 2028-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Tawan Kumni Bhura Kehar Sakroha Gagal road km. 0/0 to 10/700 (SH:- C/O edge wall in PCC at RD. 10/070 to 10/080, 10/100 to 10/120 & 10/170 to 10/190) under PDNA-2023.

Estimated cost:- 430620.00
 Earnest Money Cost:- 8700.00
 Time:- Two Months

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	47.30	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	13575.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	80.02	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	391698.00
3	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1 (V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	33.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	9471.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.40	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	15876.00
TOTAL:-						430620.00

Draft Schedule of quantity checked & approved for Rs. 4,30,620/- only (Rs. Four Lakhs Thirty thousand six hundred Twenty only).

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kalkhar Leda Sundernager road Km. 0/00 to 13/600, (SH:- C/o P.C.C R/wall with 1:5:10 at R.D. 7/510 to 7/517) Under PDNA-2023

Estimated Cost:- 292838.00
 Earnest Money :- 5900.00
 Time :- Two Months

Sr.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
1	Earthwork in excavation for foundation of structures up to as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work. Including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	24.99	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	7172.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clause 802, 803, 1202 and 1203. (Nominal mix 1:5:10) including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	55.72	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	272749.00
3	Providing weep holes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3, 7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	6.51	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	7177.00
Total						292838.00

Draft Schedule of Quantity approved for ₹ 2,92,838/- only)
 (Rs. Two Lakh Ninety Two Thousand Eight Hundred Thirty Eight only)


 Executive Engineer,
 HPERWD Division,
 HPERWD Nerchowke

Draft Sr. No. 289 for the year 2025-26

Name of Work:- Restoration of rain damages on Bhangrotu Nauru Mandal Tikhari road km. 0/0 to 4/400 (SH:- Providing B/wall at RD. 1/462 to 1/473) under PDNA-2023.

DRAFT SCHEDULE OF QUANTITY

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5m and a lead upto 20m as per technical specification clause 1603.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.32	Per cubic metre	172.00	Rupees One Hundred SeventyTwo Only	2119.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	40.47	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred NinetyFive Only	198101.00
3	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.00	Nos.	287.00	Rupees Two Hundred EightySeven Only	3157.00
TOTAL:-						203377.00

Draft schedule of quantity checked & approved for Rs. 2,03,377/- only (Rs. Two Laks Three Thousand Three Hundred Seventy seven only.)


 Executive Engineer
 Nerchowk Division
 P.P.W.D. Nerchowk

DRAFT SCHEDULE OF QUANTITY FOR THE YEAR 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Mukamgaloo to Arankohli road Km 0/0 to 2/500.(Sub Head :-Construction of R/Wall in P.C.C. 1:5:10 at RD 1/330 to 1/336) Under PDNA-2023

Estimated Cost:- 113803.00
 Earnest Money :- 2300.00
 Time :- One Months

Sr.No	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres, dressing of sides and bottom and back filling in trenches with excavated suitable material. Ordinary soil upto 3.00 mtrs. depth, including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.62	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3909.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	21.31	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	104312.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge	10.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2870.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	2.46	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	2712.00
					Total	113803.00

Draft Schedule of Quantity approved for ₹ 1,13,803/- only.
 (One Lakh Twenty Thousand Eight Hundred Three only)

Executive Engineer,
 HPPWD Division,
 HPPWD, Nellore

DNIT S.R.No. 210 for the year 2028-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Lunapani Gehra Sain road km. 0/0 to 6/900 (SH:- C/O Wire Crate R/wall at RD. 4/200 to 4/205) under PDNA-2023.

Sr. No.	Description of items	Quantity	Unit	Estimated cost:-		Amount
				Rate with all taxes including GST in Rs. P.	Estimated Money Cost:-	
				Time:- One Month		
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per Cum	287.00	Rupees Two Hundred Eighty Seven Only	3900.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia G1 wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	39.05	Per Cum	3100.00	Rupees Three Thousand One Hundred Only	121055.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.80	Per Cum	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty Only	8600.00
TOTAL:-						133555.00

Draft schedule of quantity checked & approved for Rs. 1,133,555/- only (Rs. one lakh thirty three thousand five hundred fifty five only).


 Executive Engineer
 Nerchowk Division
 BPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

DIT SRNO (169) FOR THE YEAR 2025-26

Name of work:- Restoration of Rain Damages on Halyater Gushal Trayamba road Km 0/0 to 8/000. (Sub Head:- Construction of P.C.C R/Wall with in 1:5:10 at RD 1/690 to 1/700) Under PDNA-2023

Estimated Cost:- 170120.00
 Earnest Money :- 3500.00
 Time :- One Months

Sr.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs	In word		
1	Earthwork in excavation for foundation of structures up to as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work, including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	11.10	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3185.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clause 802, 803, 1202 and 1203. (Nominal mix 1:5:10) including carriage of material and other incidentals as per the direction of the Engineer-in Charge	31.50	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	154193.00
3	Providing weep holes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	6.35	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	7001.00
					Total	170120.00

Draft Schedule of Quantity approved for 2,1,70,120/- only.
 (Rs. One Lakh Seventy Thousand and one Hundred Twenty only)


 Executive Engineer,
 HEPWD Division,
 HFRWD Nerchowak

DRAFT SRNO 168 FOR THE YEAR 2025-26

DRAFT SCHEDULE OF QUANTITY

Sr.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
1	Earthwork in excavation for foundation of structures up to as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work. including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	21.10	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	6056.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clause 802, 803, 1202 and 1203. (Nominal mix 1:5:10) including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	35.19	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	172255.00
3	Providing weep holes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	14.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	4018.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	3.75	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	4134.00
					Total	186463.00

*Draft Schedule of Quantity approved for ₹ 1,86,463/- only.
 (Rs. One Lakh Eighty Six Thousand Four Hundred Sixty Three only)*


 Executive Engineer,
 HPPWD Division,
 HPPWD Nerchowar

DWT Sr. No. 218 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhangrotu Nouru Mandal Tikhari road km. 0/0 to 4/400 (SIH:- P/L CC pavement in km. 0/265 to 0/275 & 0/330 to 0/380 and fixing of parapets at various reaches) under PDNA-2023.

Estimated cost:- 392937.00
 Earnest Money Cost:- 7900.00
 Time:- Two Months

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	2 Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement: 2 fine sand: 4 graded stone aggregate 20 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	4 Per cubic meter	5 5810.00	6 Rupees Five Thousand Eight Hundred Ten only	7 158613.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	47.87	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	234324.00
TOTAL:-						392937.00

Doat schedule of quantity checked & approved for Rs. 3,192,1937 only (Rs. Three Lacs Ninety Two Thousand Nine Hundred Thirty seven only)


 Executive Engineer
 Nerchowk Division
 HPPWD-Nerchowk

DRAFT Sr.No. 217 for the year 2028-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Tawan Kummi Bhiura Kehar Sakroha Gagal road km. 0/0 to 10/700 (SI:- C/O B/wall at RD. 9/095 to 9/105 & R/wall at RD. 9/510 to 9/525) under PDNA-2023.

Estimated cost:-	484182.00
Earnest Money Cost:-	9700.00
Time:- Two Months	

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in		Amount
				Rs. P.		
				In figure	In words	
				5	6	7
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 0.5m and a lead upto 20m as per technical specification clause 1603.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.80	Per cubic meter	172.00	Rupces One Hundred Seventy Two only	2202.00
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	52.05	Per cubic meter	287.00	Rupces Two Hundred Eighty Seven only	14938.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	91.45	Per cubic meter	4895.00	Rupces Four Thousand Eight Hundred Ninety Five only	447648.00
4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	33.00	Nos.	287.00	Rupces Two Hundred Eighty Seven only	9471.00

5	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.00	per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	9923.00
TOTAL:-						484182.00

Dept schedule of quantity checked & approved for Rs. 4,184,182/only (Rs. Four Lakh Eighty Four Thousand One Hundred Eighty Two only).


 Executive Engineer
 Narechowk Division
 HIREYD Narechowk


DRAFT Sr. No. (282) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Paidi Dhadwahan road km. 0/0 to 1/700 (SH:- Providing B/wall at RD. 0/235 to 0/242.50) under PDNA-2023.

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				Rate with all taxes including GST in Rs. P. In figure	In words	
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.40	Per cubic metre	172.00	Rupees One Hundred SeventyTwo Only	1445.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.64	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred NinetyFive Only	135298.00
3	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.00	Nos.	287.00	Rupees Two Hundred EightySeven Only	2009.00
TOTAL:-						138752.00

Draft schedule of quantity checked & approved for Rs. 1,38,752/- only (Rs. one lakh thirty eight thousand seven hundred fifty two only).


Executive Engineer
Nerchowk Division
PPWD Nerchowk

DWT Sr. No. (232) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhangrotu Nouru Mandal Tikhari road km. 0/0 to J/400 (SH:- C/O R/wall in PCC 1:5:10 at RD. 1/730 to 1/745) under PDNA-2023.

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	35.85	Per cubic metre	287.00	Rupees Two Hundred EightySeven Only	10289.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	77.12	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred NinetyFive Only	377502.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.55	Per cubic metre	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty Only	22656.00

Estimated Cost:-	418483.00
Earnest Money:-	8400.00
Time:- Two Months	

4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment. Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	28.00	Nos.	287.00	Rupees Two Hundred EightySeven Only	8036.00
TOTAL:-						418483.00

Draft schedule of quantity checked & approved for Rs. 4,18,483, (Rs. Four Lakh Eighteen Thousand Four Hundred Eighty Three

[Signature]
 Executive Engineer
 Nerchowk Division
 JPPWD Nerchowk