

Himachal Pradesh  
Public Works Department

No. PWP/Agr. Asstt./Tender/2025/ 18288 -93

Dated/ 9/02/26

To

The Executive Engineer (IT Cell),  
Nirman Bhawan Nigam Vihar Shimla-2  
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer  
Palampur Division  
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer  
Palampur Division  
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office  
NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 18288-93  
Dated 09-02-2026 are urgent in nature and in public interest.

Executive Engineer  
Palampur Division  
HPPWD Palampur

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **18.02.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 17.02.2026 up to 4.00 P.M and the application for issue of tender form shall be received 16.02.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	A/R & M/O Dharamshala Yol Dadh Palampur road Km 15/00 to 27/00 (SW:- P/F Dual Direction Reflective Speed breaker/ Rumble strips at various reaches between Km 15/00 to 20/500)	Rs. 99,600.00	Rs. 2,000.00	Two Months
2	A/R & M/O Dharamshala Yol Dadh Palampur road Km 20/600 to 23/00 and Parour Lahla Chachian road at Km 0/00 to 10/00 under Gopalpur sub-division (Lahla section) (SW:- P/F Dual Direction Reflective Speed breaker/ Rumble strips )	Rs. 98,400.00	Rs. 2,000.00	Two Months
3	RRD on link road from Kandi to Malenta Via Thalla Km 0/00 to 4/500 (SH:- C/o R/Wall at RD 3/484 to 3/490 (DC Deposit)	Rs. 99,552.00	Rs. 2,000.00	Two Months
4	RRD on link road from Kandi to Malenta Via Thalla Km 0/00 to 4/500 (SH:- C/o R/Wall at RD 3/475 to 3/481 (DC Deposit)	Rs. 99,552.00	Rs. 2,000.00	Two Months
5	A/R & M/O Bhagotla Dharer Rajnali road Km 0/00 to 4/500 (SW:- C/o R/Wall at RD 1/870 to 1/876)	Rs. 99,300.00	Rs. 2,000.00	Two Months
6	A/R & M/O Bhagotla Dharer Rajnali road Km 0/00 to 4/500 (SW:- C/o R/Wall at RD 1/878 to 1/884)	Rs. 99,300.00	Rs. 2,000.00	Two Month
7	Minor repair work of Treasury Office at Palampur Distt. Kangra (HP) (SW:- P/F Blackout Roller Blind, P/F Water Cooler & Painting work etc) (Deposit)	Rs. 69,996.00	Rs. 1,400.00	Two Month
8	Rain damages on Banuri to Main Bazar Odder Km 0/00 to 3/500 (SW:- P/L Paver Blocks at Km 0/900 to 0/921)	Rs. 98,877.00	Rs. 2,000.00	Two Month
9	Rain damages on Banuri to Main Bazar Odder Km 0/00 to 3/500 (SW:- P/L Paver Blocks at Km 0/922 to 0/943.20)	Rs. 99,759.00	Rs. 2,000.00	Two Month
10	R/D on link road from village Jugher to Kharti KM 0/00 to 2/00 (SW:- C/o R/Wall at RD 1/080 to 1/087)	Rs. 99,676.00	Rs. 2,000.00	Two Month
11	Rain damages on Banuri to Main Bazar Odder Km 0/00 to 3/500 (SW:- P/L Paver Blocks at Km 0/810 to 0/831.80)	Rs. 99,489.00	Rs. 2,000.00	Two Month
12	Rain damages on NH- 154 to SCVB Degree College to connect SC Basti Km 0/00 to 5/00 (SW:- P/L Paver Blocks at Km 0/610 to 0/631.90)	Rs. 99,949.00	Rs. 2,000.00	Two Month
13	Repair of Landslide Mitigation for Ayushman Arogya Mandir Health Sub- Centre at Arth Jhikhli Ward No. 3 Mohal (SW:- C/o R/Wall (Deposit)	Rs. 99,619.00	Rs. 2,000.00	Two Month

14	Repair of Landslide Mitigation for Ayushman Arogya Mandir Health Sub- Centre at Arth Jhikhli Ward No. 3 Mohal (SW:- C/o U-shape drain & R/Wall (Deposit))	Rs. 49,821.00	Rs. 1,000.00	Two Month
15	Restoration of rain damages on various roads under Palampur Sub-Division (Section Ghar) (SW:- Painting and writing letters in Kilometres stones and bridges etc)	Rs. 99,996.00	Rs. 2,000.00	Three Months
16	Repair of Landslide Mitigation for Ayushman Arogya Mandir Health Sub- Centre at Bagora Ward No. 1 Mohal (SW:- C/o R/Wall (Deposit))	Rs. 99,775.00	Rs. 2,000.00	Two Month
17	Retaining wall at Ambedkar Bhawan Ward No. 1 Lohna MC Palampur on Lohna Jersey Farm road at Km 0/050 to 0/061.50 (SW:- R/Wall at RD 0/000 to 0/011.50)	Rs. 99,578.00	Rs. 2,000.00	Three Month
18	C/o Path from main road towards Sh. Sher Singh House Ward No. 3 GP Chandropa (MLA Deposit)	Rs. 39,967.00	Rs. 800.00	Three Month
19	C/o path from house of late Sh. Chuni Lal to main road village Rathan GP Ghar (MLA Deposit)	Rs. 99,452.00	Rs. 2,000.00	Three Month
20	C/o Patti Badehar Pahra road Km 0/000 to 5/000 (SW:- Providing and fixing of Cat Eyes at RD 3/000 to 5/000)	Rs. 98,750.00	Rs. 2,000.00	Three Month
21	C/o link road Patti to Badehar Km 0/000 to 2/500 (SW:- Providing and fixing of Cat Eyes at various RD 0/000 to 2/500)	Rs. 99,540.00	Rs. 2,000.00	Three Month
22	Restoration of road damages from Dharamshala Yol Dadh Palampur Chadiyar Sandhole road (SW:- Providing laying PVC Pipe 315 MM dia at RD 29/410 Horizontal)	Rs. 99,590.00	Rs. 2,000.00	Three Month
23	C/o Office of Assistant Director Animal Husbandary Sperm Station Palampur (SW:- C/o Ramps to Bull Sheds (Deposit))	Rs. 99,852.00	Rs. 2,000.00	Two Month
24	C/o Assistant Director Animal Production Sperm Station Palampur (SW:- Cutting Work for Quarantine Shed No. 1 to 4)	Rs. 99,821.00	Rs. 2,000.00	Two Month
25	C/o Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/00 to 10/00 (SW:- Providing and laying G-III and C.C Pavement at RD 3/340 to 3/369.45)	Rs. 98,724.00	Rs. 2,000.00	Two Month
26	C/o Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/00 to 10/00 (SW:- Providing and laying G-III and C.C Pavement at RD 3/370 to 3/399.50)	Rs. 98,936.00	Rs. 2,000.00	Two Month
27	Rain damages on Rathan Ropa Ghar Kapoor Basti via Jagraina KM 0/00 to 7/120 (SW:- P/L G-III, CC Pavement & Grating at RD 0/300)	Rs. 92,802.00	Rs. 2,000.00	Two Month
28	Rain damages on Rathan Ropa Ghar Kapoor Basti via Jagraina KM 0/00 to 7/120 (SW:- C/o U-shape drain/abutment under granting at RD 0/300)	Rs. 97,772.00	Rs. 2,000.00	Two Month
29	C/o Jeepable road from Rachhiyada towards Katooe Ward No. 4 Tehsil Palampur Distt. Kangra (HP) (SW:- Cutting in Earth work from RD 0/250 to 0/600 (Deposit))	Rs. 96,864.00	Rs. 2,000.00	Two Month
30	Rain damages on Sungal to Matt road Km 0/00 to 1/500 (SW:- P/L G-II, G-III and CC Pavement at RD 0/105 to 0/128.50)	Rs. 99,459.00	Rs. 2,000.00	Two Month
31	Rain damages on various roads under Palampur Sub-Division (SW:- Painting and writing of sign boards etc)	Rs. 99,700.00	Rs. 2,000.00	Two Month
32	A/R of Rest House Dadh HP.PWD Palampur (SW:- Repair of Doors, Painting work, Aluminium work at Rest House Dadh)	Rs. 95,812.00	Rs. 2,000.00	Two Month
33	C/o Retaining wall to protect the land of Kamaljeet S/o Sh. Jaisi Ram Ward No.1 in GP Nain (SW:- C/o R/Wall (Deposit))	Rs. 69,615.00	Rs. 1,400.00	Three Month
34	Rain damages on link road from Nanahar to Katoohin to Upper Gount (SW:- C/o Edge wall at RD 1/200 to 1/221)	Rs. 99,497.00	Rs. 2,000.00	Three Month

35	C/o link road Dharaman Rajehar Gwaltikker via Kapain road (SW:- C/o CC Pavement Km at RD 0/00 to 0/025)	Rs. 99,900.00	Rs. 2,000.00	Two Month
36	C/o link road Dharaman Rajehar Gwaltikker via Kapain road (SW:- C/o CC Pavement at Km 0/025 to 0/054)	Rs. 98,716.00	Rs. 2,000.00	Two Month
37	Completion of Paver Pucca Path main road towards Joginder Kumar & Etc House GP Lahla (SW:- P/L Interlocking Tiles edge wall (Deposit)	Rs. 89,346.00	Rs. 2,000.00	Two Month

**Terms & Conditions-**

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer  
Palampur Division  
HPPWD Palampur

1

**SCHEDULE OF QUANTITY**

Name of work:- A/R & M/O Dharamshala Yol Dadh Palampur Road Km 15/00 to 27/00. (SH:- P/F Dual direction

reflective speed breaker/ Rumble strips at various reaches between Km 15/00 to 20/500).

Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Two Months Amount	
			In Figures	In Word			Earnest Money Rs.
1	Providing and Fixing dual directional reflective speed breaker rumble strips high impact plastic body of sizes 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having six glass large 12mm (twelve millimetre) diameter reflector lenses to one side 12 (twelve) number on both side provided with two steel zinc plated nails of 12mm. (twelve millimetre) and length of 120mm (one hundred twenty millimetre) for fixing to road by hammering make green greenlite ectetera as per drawing and specifications including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Matikana, Tol tax, GST or any other taxes imposed by the Government.	83.00			Each		
Total							

Executive Engineer  
Palampur Division  
HP.PWD Palampur

2

**SCHEDULE OF QUANTITY**

Name of work:- A/R & M/O Dharamshala Yol Dadh Palampur Road at Rd 20/600 to 23/00 and Parour Lahla Chachian road at Rd 0/00 to 10/00 under Gopalpur Sub Division (Lahla Section). (SH:- P/F Dual direction reflective speed breaker/Rumble strips).

Estimated cost Rs. 98400.00

Earnest Money Rs. 2000.00

Time Limits Two Months

Sr No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Fixing dual directional reflective speed breaker rumble strips high impact plastic body of sizes 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having six glass large 12mm (twelve millimetre) diameter reflector lenses to one side 12 (twelve) number on both side provided with two steel zinc plated nails of 12mm (twelve millimetre) and length of 120mm (one hundred twenty millimetre) for fixing to road by hammering make green greenlitie etcetera as per drawing and specifications including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana, Tol tax, GST or any other taxes imposed by the Government.	82.00			Each	
	Total					

*Executive Engineer,*  
Palampur Division  
HP.PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:-RRD on Link road from Kandi to Malenta via Thalla Km 0/00 to 4/500. (SH- C/o R/wall at Rd 3/484 to 3/490). DC Deposit 2.50 Laacs

Sr No.	Description of item.	Quantity	Rate		Unit	Amount
			Time Limits			
			In Figures	In Word		
			Estimated cost Rs.	99552.00		
			Earnest Money Rs.	2000.00		
				Two Months		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.10			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.42			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORD technical specification clauses 710.14 of IRC 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.32			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one-hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total						

Executive Engineer  
Palampur Division  
HP PWID Palampur

4

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Link road from Kandi to Malenta via Thalla Km 0/00 to 4/500, (SH- C/o R/wall at Rd 3/475 to 3/481). DC. Deposit 2.50 Laacs

Sr No	Description of Item	Quantity	Rate		Unit	Amount
			Time Limits			
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD (technical specification clause 3051 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.10			Per cubic metre	99552.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.42			Per cubic metre.	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4. of IRC- 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.32			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total						2000.00

Executive Engineer  
Palampur Division  
HP-PWD Palampur

5

**SCHEDULE OF QUANTITY**

Sr. No.		Description of Item	Quantity	Rate		Unit	Amount
				Estimated cost Rs.			
				In Figures	In Word		
Name of work:- A/R & M/O Bhagotia Dharer Rajnali road Km 0/00 to 4/500 . (SH:- C/o R/wall at Rd 1/870 to 1/876) .							
Earnest Money Rs.							99300.00
Time Limits							2000.00
							Two Months
1		Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MOR/D technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20			Per cubic metre	
2		Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.42			Per cubic metre.	
3		Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads: lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.F.F of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.32			Per cubic metre	
4		Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R/D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total							

Executive Engineer  
Palampur Division  
HP PWD Palampur

6

SCHEDULE OF QUANTITY						
Name of work:- A/R & M/O Bhagotla Dharer Rajnali road Km 0/00 to 4/500 - (SH:- C/o R/wall at Rd 1/878 to 1/884) .						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Word			
			In Figures			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20			Per cubic metre	99300.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.42			Per cubic metre.	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.32			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total						

Executive Engineer,  
Palampur Division  
HP, PWD Palampur

7

**SCHEDULE OF QUANTITY**

Sr No.		Description of Item	Quantity	Rate		Unit	Amount
				Time Limits			
				In Figures	In Word		
		Name of work:- Minor repair work of treasury office at Palampur Distt. Kangra (H.P.). (SH:- P/F Blackout Roller Blind, P/F Water collar & Painting work etc.). <b>Deposit balance 71634/-</b>	Estimated cost Rs.		69996.00		
			Earnest Money Rs.		1400.00		
			Time Limits		Two Months		
1		Renewing glass panes, with wooden fillets wherever necessary. Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm). The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.60		Per square metre		
2		Painting with synthetic enamel paint of approved brand and manufacture re of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	68.37		Per square metre		
3		Providing & Installation of Blackout roller blind with chain operated system utilizing by directional wrap spring clutch bearing ball mechanism made of zinc plated MS on existing windows of approved make with all fitting and fixing arrangement. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.34		Per square metre		
4		Providing and fixing 20 mm nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/e fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.00		Per Running Metre		
5		P/F water collar storage capacity 40 to 80 ltr With all leads lifts and other incidents as per direction of Engineer in charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00		Each		
6		Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms 15 mm (fifteen millimetre) nominal bore. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.00		Each		
7		Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	20.00		Per Kilogram		
Total							

Executive Engineer,  
Palampur Division  
HP PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- Rain Damages on Banuri to Main Bazar Odder Km 0/0 to 3/500, (SH:- P/L Paver Blocks at Km 0/900 to 0/921)		Estimated cost Rs.		98877.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred ) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.20			Per square metre	
3	Providing and laying concrete for plan/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.97			Per cubic metre.	
	<b>Total</b>					

Executive Engineer  
Palampur Division  
HP.PWD Palampur

9

**SCHEDULE OF QUANTITY**

Name of work:- Rain Damages on Banuri to Main Bazar Odder Km 0/0 to 3/500. (SH:- P/L Paver Blocks at Km 0/922 to 0/943.20)		Estimated cost Rs.		99759.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred ) K. N static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.84			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.98			Per cubic metre.	
Total						

Executive Engineer,  
Palampur Division  
HP, PWD Palampur

10

**SCHEDULE OF QUANTITY**

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Estimated cost Rs. Earnest Money Rs. Time Limits			
Name of work:- R/D on Link Road from Village Jughar to Kharti Km 0/00 to 2/00. (SH:- C/O R/wall at Rd 1/080 to 1/087)						
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.30			Per cubic metre	99676.00 2000.00 Two Months
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	22.05			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads: lifts: and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.26			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total						

Executive Engineer,  
Palampur Division  
HP. PWD Palampur

11

**SCHEDULE OF QUANTITY**

Name of work:- Rain Damages on Banuri to Main Bazar odder Km 0/0 to 3/500. (SH:- P/L Paver Blocks at Km 0/810 to 0/831.80)		Estimated cost Rs.		99489.00		
		Earned Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred ) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	67.58			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.99			Per cubic metre	
<b>Total</b>						

Executive Engineer,  
Palampur Division  
HP, PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- Rain Damages on NH-154 to SCVB Degree College to connect SC Basti Km 0/0 to 5/00. (SH:- P/L Paver Blocks at Km 0/610 to 0/631.90)		Estimated cost Rs.		99949.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred ) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.89			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.00			Per cubic metre.	
Total						

Executive Engineer,  
Palampur Division  
HP.PW/D Palampur

13

**SCHEDULE OF QUANTITY**

Name of work:- Repair of Landslide Mitigation for Ayushman Arogya Mandir Health Sub Centre at Arth Jhikli ward No.3 Mohal. (SH:- C/o R/wall ). Deposit 1.50 Lacs		Estimated cost Rs.		Unit	Amount
		Earnest Money Rs.			
Sr. No.	Description of Item	Quantity	Rate		Amount
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MOR/D technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	9.18		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government	22.03		Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P V C pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and MOR/D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00		Each	
Total					

Executive Engineer,  
Palampur Division  
HP.PWD Palampur

**SCHEDULE OF QUANTITY**

Sr No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Estimated cost Rs.			
Name of work:- Repair of Landslide Mitigation for Ayushman Arogya Mandir Health Sub Centre at Arth Jhikli ward No.3 Mohal. (SH:- C/o U-Shape drain & R/wall ). <b>Deposit 1.50 Lacs</b>						
Earnest Money Rs.						
Time Limits						
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culvert, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	8.51			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government	3.84			Per cubic metre.	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand :ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	6.70			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M O R D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	2.00			Each	
<b>Total</b>						

**Schedule of Quantity**

Name of Work :- Restoration of rain damages on various roads under Palampur Sub-Division (section Ghar)  
(S. W. :- Painting & Writing letters in Kilometres Stones and bridges etc.

Work No. 15

Estimated Cost : Rs. 99,996/-  
Earnest Money : 2000/-  
Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	32.00			Per Square metre	
2	Writing letters/figures on any surface with Japan paint (Stops, commas,hyphones and other like not to be measured and paid for seperately. Writing letters/figures on any surface with Japan paint (Stops, commas,hyphones and other The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	42500.00			Per letter,Per Cm. height	
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives.New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming cost of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	32.00			Per Square metre	
					Total :-	

**Executive Engineer  
Palampur Division  
HP.PWD Palampur**

**SCHEDULE OF QUANTITY**

Name of work:- Repair of Land slide Mitigation for Ayushman Arogya Mandir Health Sub Centre at Bagora Ward No. 1 Mohal. (SH:- C/o R/wall). Deposit 1.00 Lacs		Estimated cost Rs.		99775.00	
		Earnest Money Rs.		2000.00	
		Time Limits		Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.86			Per cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.78			Per cubic metre.
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	12.00			Each
Total					

Executive Engineer,  
Palampur Division  
HP.PWD Palampur

17

Work No.

Schedule of Quantity

Name of Work :- Retaining wall at Ambedkar Bhawan Ward No. 1 Lonna MC Palampur on Lonna Jersey Farm road at RDO/OSU to 0/011.50  
 S.W. :- R/Wall At RD 0/000 to 0/011.50  
 Estimated Cost :- Rs. 99,578/-  
 Earnest Money :- Rs. 2000/-  
 Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, Sale Tax or other taxes imposed by the Government.	8.97			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana,Toll tax, GST or any other taxes imposed by the Government.	21.39			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, Malkana,Toll tax, GST or any other taxes imposed by the Government.	9.00			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	3.91			Per Cubic metre	
					<b>Total :-</b>	

*[Signature]*  
 Executive Engineer  
 Palampur Division  
 HP.PWD Palampur

**Schedule of Quantity**

Name of Work :- C/O Path from main road towards Sh. Sher Singh house W.No. 3 GP Chandropa (MLA Deposit)

Work No. **118**

Estimated Cost :- Rs. 39,967/-

Earnest Money :- Rs. 800/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, Malkana, Tolltax, sale tax or other taxes imposed by the Government.	30.24			Per square metre	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, Tolltax, sale tax or other taxes imposed by the Government.	0.20			Per Cubic metre.	
					<b>Total :-</b>	

  
 Executive Engineer  
 Palampur Division  
 HP.PWD Palampur

Name of Work : - C/O Path from house of Late Sh. Chuni Lal to main road village Rathana Gp Ghar (MLA Deposit)

Schedule of Quantity

Work No/19

Estimated Cost :- Rs. 99,452/-  
Earnest Money :- Rs. 2000/-  
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1 with in all leads, lifts and other incidental.	267.00			Per Cubic metre	
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, Sale Tax or other taxes imposed by the Government.	13.05			Per Cubic metre	
3	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, Malkana, Tolltax, GST or other taxes imposed by the Government.	4.80			Per Cubic metre	
4	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (1 Cement : 2.5 sand : 5 crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Clause 802.804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, Malkana, Tolltax, GST or other taxes imposed by the Government.	0.97			Per cubic metre	
5	Providing and laying 900 mm.(Nine hundred millimetre) dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 .including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	5.00			Per Running metre	
6	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	9.00			Per Cubic metre	
					Total :-	

Executive Engineer  
Palampur Division  
HP.PWB Palampur

Schedule of Quantity

of Work :- C/O Patti Badehar Pahra road Km 0/000 to 5/000

Estimate Cost:- Rs. 98,750/-  
Earnest Money:- Rs. 2000/-

20

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
		In figure	In Words	In figure	In Words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M /Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ double shank Heavy duty without nails having 50 mm stem of ABS. The pavement marker shall be installed with suitable any ABS including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	250.00	Nos.			Each	
<b>Total :-</b>							

  
 Executive Engineer,  
 Palampur Division,  
 HPPWD Palampur

Schedule of Quantity


Work :- C/O link road Patti to Badehar Km 0/000 to 2/500

Estimate Cost:- Rs. 99,540/-  
Earnest Money:- Rs. 2000/-

21

Time Limit:- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
		In figure	Nos.	In Words	Each		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M /Every or equivalent plastic of size 100x90x20mm (One hunderd into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable any ABS including carriage.of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	252.00	Nos.			Each	
<b>Total :-</b>							


  
 Executive Engineer,  
 Palampur Division,  
 HPPWD Palampur



23

**SCHEDULE OF QUANTITY**

Name of work:- C/o office of Assistant Director Animal Husbandary sperm station Palampur. (SH:- C/o Ramps to Bull Sheds). Deposit		Estimated cost Rs.		99852.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying concrete for plain reinforced Cement concrete 1:2:4 (One Cement - Two Sand - four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 805, 1202 & 1203 including carriage of materials with in all roads, lifts and other incidental. The rate is including octroi, royalty, Matkama, toll tax, GST or other taxes imposed by the Government time to time.	15.90			Per cubic methe.	
	Total					

  
 Executive Engineer  
 Palampur Division  
 H.P. PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- C/o Assistant Director Animal Production sperm station Palampur. (SH:- Cutting work for Quarantine Sheds No. 1 to 4)

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	631.78			Per cubic metre.	99821.00
	Total					2000.00

Executive Engineer,  
Palampur Division  
HP.PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- C/O Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/00 to 10/00. (SH:- P/L G-III and C.C. Pavement at Rd 3/340 to 3/369.45).		Estimated cost Rs.		98724.00	
		Earnest Money Rs.		2000.00	
Sr. No.		Time Limits		Two Month	
		Description of Item		Amount	
		Quantity	Rate	Unit	Amount
		In Figures	In Word		
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm ( fifty three millimeter to twenty two point four millimeter) Grading-III 75mm (seventy five millimetre) thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2 mm (eleven point two millimetre) nominal size at the rate of 0.18 cyn (zero point eighteen cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 including carriage of materials within all leads, lifts and other incidentals or as per the directions of Engineer-In-Charge. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	6.63		Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	13.25		Per cubic metre	
Total					

Executive Engineer  
Palampur Division  
HP.PWD Palampur

26

**SCHEDULE OF QUANTITY**

Name of work:- C/o Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/00 to 10/00. (SH:- P/L G-III and C.C. Pavement at Rd 3/370 to 3/399.50).		Estimated cost Rs.		98936.00		
		Earnest Money Rs.			2000.00	
Sl. No.	Description of Item	Quantity	Rate			Unit
			In Figures	In Word	Time Limits	
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm ( fifty three millimeter to twenty two point four millimeter) Grading-III 75mm (seventy five millimeter) thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2 mm (eleven point two millimeter) nominal size at the rate of 0.18 cym (zero point eighteen cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 including carriage of materials within all leads, lifts and other incidentals or as per the directions of Engineer-In-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	6.64			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	13.28			Per cubic metre.	
Total						

Executive Engineer,  
Palampur Division  
HP.PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- Rain Damages on Rathan Ropa Char Kapoor Basti via Jagrena Km 0/00 to 7/120. (SHI:-P/L G-III, C.C. Pavement & Grating at Rd 0/300)		Estimated cost Rs.		92802.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	668.98			Per Kilogram	
2	Providing, laying, spreading and compacting stone aggregate size 55mm to 22.4mm ( fifty three millimeter to twenty two point four millimeter) Grading-III 75mm (seventy five millimetre) thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2 mm (eleven point two millimetre) nominal size at the rate of 0.18 cyn (zero point eighteen cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 including carriage of materials within all leads, lifts and other incidentals or as per the directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	1.63			Per cubic metre	
3	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14days using curing compound (where specified) and water finishing lines and grade as per drawing and Technical specification clause 1501. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.40			Per cubic metre	
<b>Total</b>						

Executive Engineer,  
Palampur Division  
HP.PWD Palampur

28

**SCHEDULE OF QUANTITY**

Name of work:- Rain Damages on Rathan Ropa Ghar Kapoor Basti via Jagrena Km 0/00 to 7/120, (SH:- C/o U-shape drain / abutment under grating at Rd 0/300)

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
						97772.00
						2000.00
						Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	30.17			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	14.68			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-15 ( M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.63			Per cubic metre	
	Total					

Executive Engineer,  
Palampur Division  
HP, PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- C/O Jeepable road from Rachhiyada towards Katooe ward No. 4 Tehsil Palampur Distt. Kangra H.P. (SH):-		Estimated cost Rs.		96864.00		
Cutting in earth work from Rd 0/250 to 0/600). Deposit 1.00 Lacs		Earnest Money Rs.		2000.00		
		Time Limits		Two Month		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	605.40			Per cubic metre.	
	Total					

Executive Engineer,  
Palampur Division  
HP PWD Palampur

30

**SCHEDULE OF QUANTITY**

Name of work:- Rain damages on Sungal to Matt road Km 0/00 to 1/500. SH:- P/L G-II, G-III & C.C. Pavement at Rd 0/105 to 0/128.50)		Estimated cost Rs.		99459.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Month		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 43mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred ) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.82			Per cubic metre	
2	Providing laying, spreading and compacting stone aggregate size 53mm to 22.4mm ( fifty three millimeter to twenty two point four millimeter) Grading-III 75mm (seventy five millimetre) thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2 mm (eleven point two millimetre) nominal size at the rate of 0.18 cum (zero point eighteen cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 including carriage of materials within all leads, lifts and other incidentals or as per the directions of Engineer-In-Charge. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	5.82			Per cubic metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	11.63			Per cubic metre.	
	Total					

Executive Engineer  
Palampur Division  
HP, PWD Palampur

31

**SCHEDULE OF QUANTITY**

Name of work:- Rain damages on various roads under Palampur Sub Division. (SH:- Painting and writing of sign boards etc.)

Sr. No.	Description of Item	Quantity	Rate		Unit	Two Months Amount
			In Figures	In Word		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	270.00			Per square metre	99700.00
	Painting two coats (excluding priming coat) on new concrete / masonry/plastered surfaces with enamel paint of approved brand and manufacture for use on floors to give an even shade, including cleaning of all dirt, dust and other foreign matter and sand papering as required. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	54.00			Per square metre	2000.00
2	Writing letters or figures on any surface with black japan paint (stops, commas, hyphens and the like not to be measured and paid separately) <b>Indian / English (letters/figures)</b> . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	32800.00			Per letter per cm. height	
	Total					

Executive Engineer,  
Palampur Division  
HP PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work:- A/R of Rest House Dadh HPPWD Palampur. (SH:- Repair of Doors, Painting work, Aluminium work at Rest House Dadh).		Estimated cost Rs.		95812.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.15			Per square metre	
2	Finishing walls with water proofing cement paint of required shade. New work (Two or more coats applied @ 3.84 kg/10 sqm). The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	144.00			Per Square Metre	
3	Supplying and fixing C.I. cover without frame for manholes :455x610 mm rectangular C.I. cover (light duty) the weight of the cover to be not less than 23 kg. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	4.00			Each	
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	314.16			Per Square Metre	
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and joined mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron). The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	70.00			Per Kilogram	
6	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.07			Per Square Metre	

132

7	Providing & fixing 4.0 mm thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.59			Per Square Metre
8	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc., complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.00			Each
9	Providing Sal wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately)Sal wood. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.13			Per cubic metre
	Total				

~~Executive Engineer~~  
Palampur Division  
HP, PWD Palampur

33

**SCHEDULE OF QUANTITY**

Name of work:- C/o Retaining wall to protect the land of Kamaljeet S/o Sh. Jaisi Ram Ward No. 1 in GP Nain (SH:- C/o R/wall )DEPOSIT Rs.70,000/-		Estimated cost Rs.		69615.00		
		Earnest Money Rs.		<del>20000.00</del> 14000.00		
		Time Limits		Three Month		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.75		Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement, five sand ten graded crushed stone aggregate, 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	15.75		Per cubic metre		
<b>Total</b>						

Executive Engineer,  
Palampur Division  
HP, PWD Palampur

34

**SCHEDULE OF QUANTITY**

Name of work:- Rain damages on c/o link road from Nanahar to katoohin to upper gount (SH :- C/o Edge wall at Rd 1/200 to 1/221).

Sl. No.	Description of item	Quantity	Rate		Unit	Three Months Amount
			In Word			
			In Figures			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and (MOR) technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.72			Per cubic metre	99497.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement, five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	22.05			Per cubic metre.	2000.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V) : 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00			Each	
Total						

Executive Engineer,  
Palampur Division  
HP, PWD Palampur

**SCHEDULE OF QUANTITY**

Name of work: C/O link road Dharman Rajchar Gawalikker via kapain road (sw.-C/O. C.C. Pavement KM at RD 0/000 (103/025)		Estimated cost Rs.	99990.00			
Time Limits		Earnest Money Rs.	2000.00			
Sr No	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm; sixty three millimetre to forty five millimetre) grading-II to water bound Macadam specification) including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred ) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 1) 2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.75			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	13.50			Per cubic metre	
	Total					

~~Executive Engineer,~~  
 Palampur Division  
 HP PWD Palampur

36

**SCHEDULE OF QUANTITY**

Name of work:- C/O link road Dharman Rajchar Gawaltikker via kapain road (sw:- C/O C.C. Pavement KM at RD 0/025 to 0/054)		Estimated cost Rs.	98716.00			
		Earnest Money Rs.	2000.00			
		Time Limits	Two Months			
Sr. No	Description of item	Quantity	Rate		Limit	Amount
			In Figures	In Word		
1	Providing laying, spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) (grading-II) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K N static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.67			Per cubic metre	
2	Providing and laying concrete for plain reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M:20 (M: twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	13.34			Per cubic metre	
Total						

Executive Engineer,  
Palampur Division  
HP.PWD Palampur

57

**DRAFT SCHEDULE OF QUANTITY**

Name of work:- Compl. Of Paver Pucca Path main road towards Joginder Kumar & Etc. House G.P Lahla.  
SW:- P/L Interlocking tiles edge wall (Deposit SDP)

Estimated cost Rs. 89346.00  
Earnest Money Rs. 2000.00  
Time Limits Two Months

Sr. No.	Description of Item.	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	33.60			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.70			Per cubic metre.	
3	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.70			Per cubic metre	
4	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	8.76			Per cubic metre.	
	<b>Total</b>					

Executive Engineer,  
Palampur Division  
HP.PWD Palampur.