

HIMACHAL PRADESH  
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

11920

Dated:- 25-2-2026

To,

The Executive Engineer  
IT Cell Nirman Bhawan Nigam Vihar  
HP PWD Shimla



Subject: \_

Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 09 Nos copy of Schedule of quantity.

Executive Engineer  
Tanda Division HP PWD  
at Nagrota Bagwan

  
Executive Engineer  
Tanda Division HP PWD  
 at Nagrota Bagwan

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 05.03.2026 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 03.03.2026 up to 4:00 P.M and the application for issue of tender form shall be received on 02.03.2026 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for

120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Repair of Robtic Surgery Area at Dr. R.P. Govt. Medical College Tanda Distt. Kangra HP Deposit work (SH: Providing and fixing Venyl Flooring in O T 2 <sup>nd</sup> Part-II)	65975.00	1350.00	One Months
2	Construction of Shed and Boundary wall near Dead House at Dr. R.P. Govt. Medical college Tanda in Distt. Kangra HP Deposit work (SH: Construction of Shed & Boundary wall part-II)	78742.00	1600.00	One Months
3	Repair of Guest House at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit work (SH: Providing and fixing pre-painted Sheet work etc. (part-II)	98348.00	2000.00	One Month
4	Construction of Shed and Boundary wall near Dead House at Dr. R.P. Govt. Medical college Tanda in Distt. Kangra HP Deposit work (SH: Construction of Shed & Boundary wall part-III)	78742.00	1600.00	One Months
5	Special Repair of Labour Room Adjuent area, Galley & Corridor etc at Dr. R.P. Govt. Medical College Tanda Distt. Kangra HP Deposit Work (SH: Providing and applying painting work etc ( Part- II)	85818.00	1750.00	One Months
6	Repair to Guest House Building at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Plaster work Painting work & Other Civil Work etc (Part-II)	66024.00	1350.00	One Months
7	Special Repair of Labour Room Adjuent area, Galley & Corridor etc at Dr. R.P. Govt. Medical College Tanda Distt. Kangra HP Deposit Work (SH: Providing and applying painting work etc ( Part-III)	85818.00	1750.00	One Months
8	Construction of Paraclinic Block at Dr. R.P. Govt Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Construction of Aluminium Partition at Dianonds Lab (Part-II)	83423.00	1300.00	One months
9	Construction of Sarai Bhawan at Dr. R.P. Govt, Medical College Tanda in Distt. Kangra HP Deposit work (SH: Balance work of lift Portion).	56002.00	1120.00	One months

**Terms & Conditions:-**

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

**HIMSUCHANA AVAM & JAN SAMPARK**

(On behalf of Governor of Himachal Pradesh)

No. PW/NBD/TA/Tender/NIT/2025-26- **11921-35** Dated/ **25-2-2026**

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan


**Schedule of Quantity**

ESTIMATED COST: - ₹ 65975.00  
 EARNEST MONEY :- ₹ 1350.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of Robotic Surgery Area at Dr. R.P. Govt. Medical College Tanda Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and fixing Venyl Flooring in O.T. 2<sup>nd</sup> (Part-II)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 2mm (Two millimetres) thick heavy duty homogeneous venyl Flooring (ROBUST) plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	22.75	Square metres		Per Square metre	
<b>Total:-</b>						


  
 Executive Engineer,  
 HP-PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 78742.00  
 EARNEST MONEY :- ₹ 1600.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Construction of Shed and Boundary Wall Near Dead House at Dr. R.P. Govt. Mdical College Tanda in Distt. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Construction of Shed & Boundary wall (Part-II)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m Ordinary rock complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.21			Per Cubic metre	
2	Providing and laying 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.21			Per Cubic metre	
3	Providing and laying 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.50			Per Cubic metre	
4	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/ m <sup>2</sup> complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	25.00			Per Square metre	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	200.00			Per Kilograms	
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	118.25			Per Kilograms	
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	16.45			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 98348.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair to Guest House Building at Dr. R.P. Govt. Mdical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Plaster work, Painting work & Other Civil work etc. (Part-II)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	1 Providing and fixing 0.60mm (Zero point Sixty millimeters) thick prepainted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimeters) dia metre with prepainted limpet and rubber washers complete with all accessories as required including carriage of materials within all leads, lifts and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	27.00	Square metres		Per Square metre	
2	2 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials within all leads, lifts and other incidentals	607.50	Kilogram		Per kilogram	
<b>Total:-</b>						



Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 78742.00  
 EARNEST MONEY :- ₹ 1600.00  
 TIME LIMIT : ONE MONTH

**Item of Work:-** Construction of Shed and Boundary Wall Near Dead House at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Item Head:-** Construction of Shed & Boundary wall (Part-II)

Sl. No.	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m. including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m Ordinary rock complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.21			Per Cubic metre	
2	Providing and laying 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.21			Per Cubic metre	
3	Providing and laying 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.50			Per Cubic metre	
4	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/ m <sup>2</sup> complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	25.00			Per Square metre	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	200.00			Per Kilograms	
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	118.25			Per Kilograms	
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	16.45			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 85818.00  
 EARNEST MONEY :- ₹ 1750.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Special Repair of Labour Room Adjacent area , Gallery & Corridor etc at Dr. R.P. Govt. Medical College Tanda Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and applying painting work etc. (Part-II)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	749.00	Square metres		Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm (One millimetres), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	298.00	Square metres		Per Square metre	
3	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	749.00	Square metres		Per Square metre	
<b>Total:-</b>						



Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 66024.00  
 EARNEST MONEY :- ₹ 1350.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair to Guest House Building at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Plaster work, Painting work & Other Civil work etc. (Part-II)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	15mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering above floor two level to floor three level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	15.56	Square metres		Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	207.00	Square metres		Per Square metre	
3	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	118.88	Square metres		Per Square metre	
4	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	324.92	Square metres		Per Square metre	
5	Painting One or more coats on old work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	121.54	Square metres		Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.


## Schedule of Quantity

ESTIMATED COST :- ₹ 85818.00  
 EARNEST MONEY :- ₹ 1750.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Special Repair of Labour Room Adjuent area , Gallery & Corridor etc at Dr. R.P. Govt. Medical College Tanda Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and applying painting work etc. (Part-III)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	749.00	Square metres		Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm (One millimetres), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	298.00	Square metres		Per Square metre	
3	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	749.00	Square metres		Per Square metre	
<b>Total:-</b>						


  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 83423.00  
 EARNEST MONEY :- ₹ 1700.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Construction of Paraclinic Block at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Construction of Aluminium Partition at Dianonds Lab (Part-II)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including oleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	123.20	Square metres		Per Square metre	
2	Providing and Fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer- in-charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	20.82	Square metres		Per Square metre	
3	Providing and fixing 300 x16 mm (Three hundred into sixteen millimetres) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers		Each	
4	Providing and fixing 200x10mm (Two hundred into ten millimetres) size aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4	Numbers		Each	
5	Providing and fixing 125 mm (One hundred twenty five millimetres) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4	Numbers		Each	
6	Providing and fixing 125x64x1.90mm (One hundred twenty five into sixty four into one point ninety millimetres) IS:12817 marked stainless steel butt hinges with stainless steel screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6	Numbers		Each	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 56002.00  
 EARNEST MONEY :- ₹ 1120.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Construction of Sarai Bhawan at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Balance work of Lift Portion.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.55	Cubic metres		Per Cubic metre	
2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms. vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels granite of any colour and shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.64	Square metres		Per Square metre	
3	Providing and Laying Stone soiling under floor complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.58	Cubic metres		Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	0.58	Cubic metres		Per Cubic metre	
5	Providing and laying water proofing of Reinforced cement concrete (RCC) slab with liquiteore 151 as Acrylic Polymade binding with cement, providing Fibre mesh and liquiteore RTU as Two components Acrylic base Modified cementation water proofing coat system complete and ornamental moulding in side of gutter complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	2.87	Square metres		Per Square metre	
6	Centering and shuttering including strutting, propping etc. and removal of form for :Suspended floors, roofs, landings, balconies and access platform complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.29	Square metres		Per Square metre	
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone	0.95	Cubic metres		Per Cubic metre	
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Cold twisted bars complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	113.40	Kilograms		Per Kilogram	
9	6 mm cement plaster of mix :1:3 (1 cement : 3 fine sand) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.29	Square metres		Per Square metre	
10	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	64.10	Square metres		Per Square metre	
11	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats on new work complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	64.10	Square metres		Per Square metre	

1911

1911

