

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:-
To,

20776-82

Dated:- 6/3/2026


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 16.03.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 17.03.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 18.03.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 18.03.2026 at 11.30 AM |


The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contract or
1.	A/R&M/O on Sunhara Khadlow Baroh Malhanta Nangal road Km. 0/0 to 8/500 Under SCDP (SH:- Removal of land slide slips, construction of embankment, maintenance of earthen shoulder/berms both, unlined drain in hill sides at various RD's between Km. 0/100 to 2/700)	Rs.97362 /-	Rs.2000/-	One month	350/-	Class D&C
2.	A/R&M/O on Sunhara Khadlow Baroh Malhanta Nangal road Km. 0/0 to 8/500 Under SCDP (SH:- Removal of land slide slips, construction of embankment, maintenance of earthen shoulder/berms both, unlined drain in hill sides at various RD's between Km. 3/500 to 5/800)	Rs.96903 /-	Rs.2000/-	One month	350/-	Class D&C
3.	A/R&M/O on Sunhara Khadlow Baroh Malhanta Nangal road Km. 0/0 to 8/500 Under SCDP (SH:- Removal of land slide slips, construction of embankment, maintenance of earthen shoulder/berms both, unlined drain in hill sides at various RD's between Km. 6/00 to 7/500)	Rs.96824 /-	Rs.2000/-	One month	350/-	Class D&C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Estimated Cost:- Rs.97362/- only

Name of Work:- A/R&M/O on Sunhara Khadlow Baroh Malhanta Nangal road Km. 0/0 to 8/500 Under SCDP (SH:- Removal of land slide


slips, construction of embankment, maintenance of earthen shoulder/berms both, unlined drain in hill sides at various RD's between Km. 0/100

to 2/700) Earnest Money:- Rs.2000/- only

Time limit:- One Month

Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In figures.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	118.13 cubic meter	135.40	Rupees One Hundred Thirty Five And Paise Forty Only	Per cubic meter	15995.00
2	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MOR technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	37.50 Cubic meter.	270.90	Rupees Two Hundred Seventy And Paise Ninety Only	Per cubic meter	10159.00
3	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1100.00 square meter	45.70	Rupees Forty Five And Paise Seventy Only	Per square meter	50270.00
4	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in ordinary roack to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Mechanical Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	380.00 Running meter	55.10	Rupees Fifty Five And Paise Ten Only	Per Running meter	20938.00
					Total:-	97362.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)


SCHEDULE OF QUANTITY

Name of Work:- A/R&M/O on Sunhara Khadlow Baroh Malhanta Nangal road Km. 0/0 to 8/500 Under SCDP (SH:- Removal of land slide slips, construction of embankment, maintenance of earthen shoulder/berms both, unlined drain in hill sides at various RD's between Km. 3/500 to 5/800)

Estimated Cost:- Rs.96903/- only
Earnest Money:- Rs.2000/- only
Time limit:- One Month

Sr. No.	Description of items	Quantity		Rate		Unit.	Amount.
		In figures.	In words	In figures.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	52.50		135.40	Rupees One Hundred Thirty Five And Paise Forty Only	Per cubic meter	7109.00
2	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MORD technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	37.50		270.90	Rupees Two Hundred Seventy And Paise Ninety Only	Per cubic meter	10159.00
3	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1200.00		45.70	Rupees Forty Five And Paise Seventy Only	Per square meter	54840.00
4	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in ordinary roack to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Mechanical Means as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	450.00		55.10	Rupees Fifty Five And Paise Ten Only	Per Running meter	24795.00
						Total:-	96903.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (P.R.)

SCHEDULE OF QUANTITY


Estimated Cost:- Rs.96824/- only
Earnest Money:- Rs.2000/- only

Name of Work:- A/R&M/O on Sunhara Khadlow Baroh Malhanta Nangal road Km. 0/0 to 8/500 Under SCDP (SH:- Removal of land slide slips, construction of embankment, maintenance of earthen shoulder/berms both, unlined drain in hill sides at various RD's between Km. 6/00 to 7/500)

Time limit:- One Month

Sr. No.	Description of items	Quantity		Rate		Unit.	Amount.
		In figures.	In words.	In figures.	In words.		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	262.50	Rupees One Hundred Thirty Five And Paise Forty Only	135.40	Rupees One Hundred Thirty Five And Paise Forty Only	Per cubic meter	35543.00
2	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MOR technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	14.06	Rupees Two Hundred Seventy And Paise Ninety Only	270.90	Rupees Two Hundred Seventy And Paise Ninety Only	Per cubic meter	3809.00
3	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	920.00	Rupees Forty Five And Paise Seventy Only	45.70	Rupees Forty Five And Paise Seventy Only	Per square meter	42044.00
4	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in ordinary roack to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) as per technical specification clause 307 Mechanical Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	280.00	Rupees Fifty Five And Paise Ten Only	55.10	Rupees Fifty Five And Paise Ten Only	Per Running meter	15428.00
						Total:-	96824.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)