



Office of the  
Executive Engineer  
Una Division, HP PWD Una  
Tel: +911975226036,  
E-mail: [ee-una-hp@nic.in](mailto:ee-una-hp@nic.in)

No.PWU/CB/TA/Tender/2025-26:-

11480-27

Dated :- 28

02  
2026

To

The Executive Engineer (IT) Cell,  
Nirman Bhawan, Nigam Vihar,  
Shimla-171002.


Subject: - Regarding publication of Tenders Notice.

Sir,

“JAI HIND”


Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.

  
Executive Engineer,  
Una, Division,  
HPPWD, Una

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15<sup>th</sup> Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.

  
Executive Engineer,  
Una, Division  
HPPWD, Una

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDERS**

Sealed percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Una Division HPPWD Una H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office or before 10.03.2026 upto 11.00 A.M. and will be opened on the same day at 11.30 A.M. in presence of the intending contractors or their authorized representatives who may like to be present. If it happened be holiday on the day of opening of tender the same will be opened on next working day at the same time. The application for obtaining the tender forms will be received latest by 07.03.2026 at 10.00 AM upto 10.30 AM against cash payment (non-refundable) and the tender form can be had from this office upto 09.03.2026 during the office hours.

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Una Division HPPWD Una, will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice. The offers of the tender (s) shall be kept open for 75 days from the date of opening the tender(s).

Sr. No.	Name of work	Estimated cost	Earnes t Money	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	Repair & maintenance of link road Dehlan to Behdala Km 0/0 to 2/0 (SH: P/L 80mm thick interlocking paver at Rd 1/545 to 1/560 both side and C/O edge wall at Rd 1/450 to 1/465 (Under BPCL deposit)	98,213/-	2,000/-	One Month	350/-	Class-C & D
2	Repair & maintenance of link road Dehlan to Behdala Km 0/0 to 2/0 (SH: P/L 80mm thick interlocking paver at Rd 1/525 to 1/540 both side and C/O edge wall at Rd 1/415 to 1/430 (Under BPCL deposit)	98,169/-	2,000/-	One Month	350/-	Class-C & D
3	A/R & M/O L/R Santoshgarh Mehatpur road Km 0/0 to 7/0 & Ajouli Santoshgarh road Km 0/0 to 3/600 (SH:- Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.	99,000/-	2000/-	One Month	350/-	Class-C & D
4	A/R & M/O L/R Ajouli to Sanoli upto Punjab Boundary Km 0/0 to 4/600 & Circular road Sanoli Km 0/0 to 0/800 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.	99,000/-	2000/-	One Month	350/-	Class-C & D
5	Repair & maintenance of HPPWD, residential building at Jalgran Tehsil & Distt. Una (SH:- P/L interlock pavers along residence )(Part-VI)	65,445/-	2,000/-	One Month	350/-	Class-C & D
6	Repair & maintenance of HPPWD, residential building at Jalgran Tehsil & Distt. Una (SH:- P/L interlock pavers along residence )(Part-V)	65,404/-	2,000/-	One Month	350/-	Class-C & D
7	A/R & M/O PWD Rest House at Una (SH:- Providing services out of sources basis for one number Gardner (Mali) (Period of 147 days)	99,901/-	2,000/-	147 Days	350/-	Class-C & D
8	A/R & M/O PWD Rest House at Una (SH: Providing and fixing plantation different type of plant, flower plant and ornamental plant and rose plant etc.	99,550/-	2,000/-	One Month	350/-	Class-C & D
9	Repair & damages on Charatgarh Khanpur road km. 0/0 to 2/200 (SH: C/O Edge wall in RD. 1/010 to 1/075 (Left side) Under BPCL Deposit.	98,509/-	2,000/-	One Month	350/-	Class-C & D
10	Repair & damages on Charatgarh Khanpur road km. 0/0 to 2/200 (SH: C/O Edge wall in RD. 1/075 to 1/140 (Left side) Under BPCL Deposit.	98,339/-	2,000/-	One Month	350/-	Class-C & D
11	Repair and maintenance of L/R Dehlan to Behdala km 0/00 to 2/00 (SH: C/O Paver blocks at RD. 1/505 to 1/520 both side and C/O edge wall at RD 1/395 to 1/410) Under BPCL	98,124/-	2,000/-	One Month	350/-	Class-C & D

	Deposit					
12	Repair and maintenance of L/R Dehlan to Behdala km 0/00 to 2/00 (SH: C/O Paver blocks at RD. 1/566 to 1/581 both side and C/O edge wall at RD 1/470 to 1/485) Under BPCL Deposit	98,258/-	2000/-	One Month	350/-	Class-C & D
13	Repair & maintenance of Behdala Jakhera road Km 0/0 to 5/500 (SH:- C/o Drain wall & bed along road side at RD 0/827.50 to 0/845) (Under BPCL deposit )	89,852/-	2,000/-	One Month	350/-	Class-C & D
14	Repair & maintenance of Behdala Jakhera road Km 0/0 to 5/500 (SH:- C/o Drain wall & bed along road side at RD 0/810 to 0/827.50) (Under BPCL deposit )	89,682/-	2,000/-	One Month	350/-	Class-C & D
15	Restoration of rain damages on Badehar Khuhi Pekhabela road at Rd 3/600 (SH: Channelization on RHS of Pekhabela bridge at RD 3/200)	99,000/-	2,000/-	One Month	350/-	Class-C & D
16	Restoration of rain damages on Badehar Khuhi Pekhabela road at Rd 3/600 (SH: Channelization on LHS of Pekhabela bridge at RD 3/200)	99,000/-	2,000/-	One Month	350/-	Class-C & D
17	Restoration of rain damages on various road under Una Sub-Divn. No. II HPPWD Mehatpur (SH:- Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.	99,000/-	2,000/-	One Month	350/-	Class-C & D
18	A/R & M/O link road from Bangarh to Nangran road km 0/000 to 8/200 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains from RD 3/0 to 4/500)	99,000/-	2,000/-	One Month	350/-	Class-C & D
19	Restoration of rain damages on link road Dyallan Mohalla Km 0/0 to 2/200 (SH: P/L 80mm thick interlocking paver in Rd 1/750 to 0/762.50) Under BPCL deposit	99,728/-	2,000/-	One Month	350/-	Class-C & D
20	Restoration of rain damages on Dehlan Badehar road Km 0/0 to 3/0 (SH:- C/O R/wall at RD 1/550 to 1/570) (Under BPCL deposit	99,970/-	2,000/-	One Month	350/-	Class-C & D
21	Restoration of rain damages on Dehlan Badehar road Km 0/0 to 3/0 (SH:- C/O R/wall at RD 1/570 to 1/590) (Under BPCL deposit	99,936/-	2,000/-	One Month	350/-	Class-C & D
22	Restoration of rain damages on link road Rakkar to Basoli road Km 0/0 to 2/400 (SH:- P/L of balance work interlocking pavers at Rd 1/812 to 1/823.70) (Under OFC deposit)	78,595/-	2,000/-	One Month	350/-	Class-C & D
23	Repair work of HPPWD 15 <sup>th</sup> Circle building Una (SH:- Repair of Ws & SI etc)	85,896/-	2,000/-	One Month	350/-	Class-C & D
24	Repair of HPPWD Rest House at Una Distt. Una HP (SH:- Providing and laying tile work and WI and SI work in set No. 6	99,752/-	2,000/-	One Month	350/-	Class-C & D
25	A/R & M/O residential building Una (SH: Repair of Plaster, panting and other maintenance for type-III qtr. No. 17 Dc colony Una (Part-5)	99,269/-	2,000/-	One Month	350/-	Class-C & D
26	A/R & M/O residential building for pooled accommodation in Type-III Qtr. No. 17 and outer paint Type-III Qtrs in DC Colony Una (SH: Providing and Fixing PVC paneling etc Bed room 1 and Dining (Part-4)	98,328/-	2,000/-	One Month	350/-	Class-C & D
27	A/R & M/O residential building Una (SH:- P/F wall tile and other maintenance for Type-III qtr. No. 17 DC Colony Una ) (Part-2)	99,123/-	2,000/-	One Month	350/-	Class-C & D
28	C/o link road to Harijan Basti Kuthar Khurd Tehsil & Distt. Una Km 0/0 to 1/500 (GP Kuthar khurd) (SH: Providing and laying gravel Soil aggregate at RD 0/180 to 0/335)	99,360/-	2,000/-	One Month	350/-	Class-C & D
29	A/R & M/O residential building for Distt. Attorney Type-IV Qtr. In DC Colony Una (SH: Providing and fixing 18mm thick (HDJMR board) and painting etc)	99,985/-	2,000/-	One Month	350/-	Class-C & D
30	Repair of HPPWD Rest House at Una Distt. Una (HP) (SH:- Refilling of various type Fire Executioner cylinder in HPPWD Rest House Una )	99,525/-	2,000/-	One Month	350/-	Class-C & D
31	Restoration of rain damages on Old Hoshiarpur road at RD 4/200 (SH: Channelization on D/S side of Lalsingi bridge at RD 3/600) (RHS)	99,000/-	2,000/-	One Month	350/-	Class-C & D
32	Restoration of rain damages on Old Hoshiarpur road at RD 4/200 (SH: Channelization on D/S side of Lalsingi bridge at RD 3/600) (LHS)	99,000/-	2,000/-	One Month	350/-	Class-C & D
33	Restoration of rain damages on link road to village Lower Amjala Km 0/0 to 1/0 (SH: P/F CC interlocking paver blocks	99,936/-	2,000/-	One Month	350/-	Class-C & D

	at RD 0/040 to 0/082 (Left side berms) (Under OFC deposit)					
34	A/R & M/O non residential building for DC Colony Una (SH: Providing and fixing convex mirror and other maintenance in Judges residence )	99,941/-	2,000/-	One Month	350/-	Class-C & D
35	Restoration of rain damage on 120 meter span bridge on Una Santoshgarh road at Rd 1/760 (SH: Channelization of Khad on Upstream side of Rampur bridge 1/760 LHS	99,537/-	2,000/-	One Month	350/-	Class-C & D
36	Restoration of rain damage on 120 meter span bridge on Una Santoshgarh road at Rd 1/760 (SH: Channelization of Khad on Upstream side of Rampur bridge 1/760 along the length of bridge	99,286/-	2,000/-	One Month	350/-	Class-C & D
37	A/R & M/O residential building of ADC residence at DC Colony Una (SH: Providing and fixing aluminum work and other repairs etc.	98,260/-	2,000/-	One Month	350/-	Class-C & D
38	A/R & M/O residential building of ADC residence at DC Colony Una (SH: P/L Painting and other	98,050/-	2,000/-	One Month	350/-	Class-C & D
39	A/R & M/O residential building of Una (SH: P/L Painting and floor tile etc for type -I qtr. No. 8 at DC Colony Una	98,684/-	2,000/-	One Month	350/-	Class-C & D
40	A/R & M/O residential building at Una (SH: Providing and fixing HDHMR cupboard at SDM residence in DC Colony Una )	99,875/-	2,000/-	One Month	350/-	Class-C & D
41	A/R & M/O residential building in DC Colony Una (SH: Providing and laying wall painting in HPPWD SE residence )	99,474/-	2,000/-	One Month	350/-	Class-C & D
42	A/R & M/O residential building in DC colony Una (SH: Providing and laying wall painting and other repair work in HPPWD SE residence )	99,982/-	2,000/-	One Month	350/-	Class-C & D
43	Repair maintenance on Behdala Jankour via Abada Barana road km 0/0 to 4/600 Tehsil & Distt. Una (SH;- C/o R/wall along road from RD 0/972.25 to 0/988.40)	99,956/-	2,000/-	One Month	350/-	Class-C & D
44	Repair maintenance on Behdala Jankour via Abada Barana road km 0/0 to 4/600 Tehsil & Distt. Una (SH;- C/o R/wall along road from RD 0/956.15 to 0/972.25	99,513/-	2,000/-	One Month	350/-	Class-C & D
45	A/R & M/O to link road from Jhalera bridge to Una via lower LalSingi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/397 to 4/009 (OFC Deposit)	93,492/-	2,000/-	One Month	350/-	Class-C & D
46	A/R & M/O to link road from Jhalera bridge to Una via lower LalSingi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/455 to 3/461 & 3/462 to 3/465 (RHS) (OFC Deposit)	93,150/-	2,000/-	One Month	350/-	Class-C & D
47	A/R & M/O to link road from Jhalera bridge to Una via lower LalSingi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/465 to 3/468 & 3/482 to 3/488 (RHS) (UNDER OFC DEPOSIT)	93,495/-	2,000/-	One Month	350/-	Class-C & D
48	A/R & M/O to link road from Jhalera bridge to Una via lower LalSingi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/494.70 to 3/501.80 (RHS) (UNDER OFC DEPOSIT)	93,150/-	2,000/-	One Month	350/-	Class-C & D
49	A/R & M/O to link road from Jhalera bridge to Una via lower LalSingi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/428 to 3/436) (RHS) (UNDER OFC DEPOSIT)	93,712/-	2,000/-	One Month	350/-	Class-C & D
50	A/R & M/O to link road from Jhalera bridge to Una via lower LalSingi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/421 to 3/425 (RHS) (UNDER OFC DEPOSIT)	93,657/-	2,000/-	One Month	350/-	Class-C & D
51	A/R & M/O to link road from Jhalera bridge to Una via lower Lal Singi Km 0/0 to 4/340 (SH: C/o Slab on U-shape drain at Rd 3/450 to 3/455 (RHS) (UNDER OFC DEPOSIT)	93,655/-	2,000/-	One Month	350/-	Class-C & D
52	Repair and maintenance of link road to Village Galua (SH: Providing and fixing grating on drain at Rd 0/117 to 0/135) (RHS) (UNDER OFC DEPOSIT)	97,958/-	2,000/-	One Month	350/-	Class-C & D
53	Repair and maintenance of link road to Village Galua (SH: Providing and fixing grating on drain at Rd 0/140 to 0/155 (RHS) (UNDER OFC DEPOSIT)	98,123/-	2,000/-	One Month	350/-	Class-C & D
54	Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at Rd 0/078 to 0/095) (RHS) (Under OFC Deposit )	98,179/-	2,000/-	One Month	350/-	Class-C & D
55	Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at Rd 0/097 to 0/115) (RHS) (Under OFC Deposit )	97,902/-	2,000/-	One Month	350/-	Class-C & D
56	A/R & M/O to link road from Jhalera to Una via lower lalsingi km 0/0 to 4/340 (SH: Providing and marking of rumble strip lines 100mm at Rd 0/800 to 1/605) (Under OFC Deposit )	93,380/-	2,000/-	One Month	350/-	Class-C & D

57	A/R & M/O to link road from Jhalera to Una via lower lalsingi km 0/0 to 4/340 (SH: Providing and marking of rumble strip lines 100mm at Rd 4/350 to 4/340) (Under OFC Deposit)	97,440/-	2,000/-	One Month	350/-	Class-C & D
58	A/R & M/O LIG 107 & 108 quarters Pooled accommodation at Rakkar colony Distt. Una (SH:- Providing and laying interlock paver etc (Phase-I)	99,868/-	2,000/-	One Month	350/-	Class-C & D
59	Restoration & repair on Una Santosgarh road km 0/0 to 14/0 (SH:- Removal of debries , silt sludge & aggregate from drain at various Rd,s)	98,919/-	2,000/-	One Month	350/-	Class-C & D
60	Restoration & repair on Una Santosgarh road km 0/0 to 14/0 (SH:- Maintenance earthen shoulder at Rd 8/0 to 9/350)	99,225/-	2,000/-	One Month	350/-	Class-C & D
61	A/R & M/O residential building at HPPWD, Electrical Sub – Division Una (SH:- P/F aluminum work and WS & SI etc	99,884/-	2,000/-	One Month	350/-	Class-C & D
62	Repair work of HPPWD 15 <sup>th</sup> Circle building Una (SH: Repair of Toilet block )	65,737/-	2,000/-	One Month	350/-	Class-C & D
63	A/R & M/O Various roads under Mehatpur Sub-Division at Rakkar section (SH:- Providing and fixing sign board and painting or bridge etc)	99,854/-	2,000/-	One Month	350/-	Class-C & D
64	A/R & M/O residential building for pooled accommodation in Type-III Qtr. No. 17 and outer paint Type-III Qtrs in DC Colony Una (SH: Providing and Fixing PVC paneling etc Bed room 2 and 3 (Part-3)	99,636/-	2,000/-	One Month	350/-	Class-C & D
65	A/R & M/O residential building Una (SH:- P/F Floor tile and other maintenance for Type-III qtr. No. 17 DC Colony Una ) (Part-I)	99,800/-	2,000/-	One Month	350/-	Class-C & D
66	A/R & M/o residential building Una (SH:- Repair of Plaster, painting and other maintenance for Type-III Qtr No. 15 DC Colony Una (Phase-I)	99,991/-	2,000/-	One Month	350/-	Class-C & D
67	A/R & M/O residential building Una (SH: Painting and WS work for Type-III Qtr No. 15 DC Colony Una (Phase-II)	99,495/-	2000/-	One Month	350/-	Class-C & D
68	Restoration of rain damage to Path from the house of Dr. Atri etc. to house of Shri Ram Murti in Ward No.1 in village Arniala upper MC Una (SH:- Providing and laying interlocking paver blocks Km 0/040 to 0/080) Under VKVNY (MLALAD)	99,700/-	2000/-	One Month	350/-	Class-C & D
69	Restoration of rain damage to Path from the house of Dr. Atri etc. to house of Shri Ram Murti in Ward No.1 in village Arniala upper MC Una (SH:- Providing and laying interlocking paver blocks Km 0/080 to 0/120) Under VKVNY (MLALAD)	99,746/-	2000/-	One Month	350/-	Class-C & D
70	Restoration of rain damages of link damages of link road to Harizan Basti Dehlan Km 0/0 to 0/800 (SH:- C/O U-Shape drain and P/L RCC NP-2 pipe with Chambers is Rd. 0/720 to 0/735 (GP Dehlan) Deposit	99,845/-	2000/-	One Month	350/-	Class-C & D
71	Construction of link road with retaining wall in HarizanBasti Ward No. 8 GP Behdala Block Una Tehsil & Distt. Una (HP) (Phase-I ) (Deposit work)	95,411/-	2000/-	One Month	350/-	Class-C & D
72	Construction of link road with retaining wall in HarizanBasti Ward No. 8 GP Behdala Block Una Tehsil & Distt. Una (HP) (Phase-II (Deposit work)	95,581/-	2000/-	One Month	350/-	Class-C & D
73	Construction of link road with retaining wall in HarizanBasti Ward No. 8 GP Behdala Block Una Tehsil & Distt. Una (HP) (Phase-III (Deposit work	95,751/-	2000/-	One Month	350/-	Class-C & D
74	A/R & M/O Type-III HPPWD Qtr. No.1 to 4 pooled accommodation at Rakkar colony Una (SH:- Repair of roof with water proofing compound etc)	99,984/-	2000/-	One Month	350/-	Class-C & D
75	A/R & M/O Type-III HPPWD Qtr. No.5 to 8 pooled accommodation at Rakkar colony Una (SH:- Repair of roof with water proofing compound etc)	99,991/-	2000/-	One Month	350/-	Class-C & D
76	A/R & M/O Qtr No. 6 Type-I Qtr Pooled Accommodation at Rakkar Colony Distt. Una (SH:- Repair of wood work, Distempering Painting etc	95,743/-	2000/-	One Month	350/-	Class-C & D
77	A/R & M/O Qtrs No.4 Type-I Quarters Pooled Accommodation at Rakkar Colony Distt. Una (HP) (SH:- Repair of wood work , Distempering Painting etc	99,982/-	2000/-	One Month	350/-	Class-C & D

78	A/R & M/O Qtrs No.5 Type-I Quarters Pooled Accommodation at Rakkar Colony Distt. Una (HP) (SH:- Repair of wood work , Distempering Painting etc	99,954/-	2000/-	One Month	350/-	Class-C & D
79	A/R & M/O link road from Bangarh to Nangran road km 0/000 to 8/200 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains from RD 3/0 to 4/500)	99,000/-	2,000/-	One Month	350/-	Class-C & D

**TERM & CONDITIONS: -**

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department.
2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
9. A sign Board "Men at work / work in progress " shall be placed " by Contr. At least 200-150 meters ahead or places / roads where road are under repair / construction.
10. For Job No.7 & 8 experienced in Horticulture.
11. The contractor should be personally present for submission of application from 10.00 AM to 10.30 AM for purchase of tender form. No application will be accepted after 10.30 AM.
12. Contactor cannot submit application for more than two works/ Jobs.

  
Executive Engineer

Una Division, HP: PWD, Una.  
On behalf of Governor of H.P.

No. PWU/CB/T-1/2025-26:-

11465<sup>th</sup>-79

Dated:- 28-02-2026

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. The Superintending Engineer, 15<sup>th</sup> Circle Una.
4. All the Assistant Engineers under this Division.
5. The Deputy Commissioner, Una.
6. The Sub Divisional Officer (C), Una.
7. The District Treasury Officer, Una.
8. The Block Development Officer, Una.
9. The Municipality, Una.
11. All the Head of the Branches in this office.
12. The Notice Board.

  
Executive Engineer,  
Una Division, HP:PWD,  
Una

## Certificate

Certified that the tenders called vide this office letter No.PWU/CB/T-I/2025-26:- 11465-79 dated- 28-02-2026 emergent nature and in Public interest.

  
Executive Engineer,  
Una Division, HP:RWD,  
Una

①

SCHEDULE OF QUANTITY						Estimated Cost	98213/-
Name of work Repair & maintenance of link road Dehlan to Behdala km.0/0 to 2/0 (SH: P/L 80mm thick interlocking paver at RD.1/545 to 1/560 both side and C/O edge wall at RD.1/450 to 1/465) (Under BPCL deposit)						Earnest Money	2000/-
						Time limit	One month
						RATE In	
Sl. No.	Description of work	Quantity	Unit	Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carmaga of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.13	Per cubic metre	170.00	Rupees One hundred seventy only	1722	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.89	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	46532	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horzontial) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Each	170.00	Rupees One hundred seventy only	2380	

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	21.10	Per square metre	890.00	Rupees Eight hundred ninety only	18779
5	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.00	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	28800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	98213
	2) The rates shall be including of all types of taxes including GST etctra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	<b>Percentage quoted Rate in Figures</b>					
	<b>Percentage quoted Rate in Words</b>					
	<b>Note: Rates quoted in figures &amp; words are mandatory</b>					
	<b>by the contractor otherwise the tender will be rejected.</b>					

  
 Executive Engineer,  
 Una Division, HRPWD  
 Una

SCHEDULE OF QUANTITY						
					Estimated Cost	98169/-
					Earnest Money	2000/-
					Time limit	One month
Name of work Repair & maintenance of link road Dehlan to Behdala km.0/0 to 2/0 (SH: P/L 80mm thick interlocking paver at RD.1/525 to 1/540 both side and C/O edge wall at RD.1/415 to 1/430) (Under BPCL deposit)						
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.13	Per cubic metre	170.00	Rupees One hundred seventy only	1722
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.89	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	46532
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horzontial) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Each	170.00	Rupees One hundred seventy only	2380

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	21.05	Per square metre	890.00	Rupees Eight hundred ninety only	18735
5	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.00	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	28800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	98169
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	<b>Percentage quoted Rate in Figures</b>					
	<b>Percentage quoted Rate in Words</b>					
	<b>Note: Rates quoted in figures &amp; words are mandatory</b>					
	<b>by the contractor otherwise the tender will be rejected.</b>					

  
 Executive Engineer,  
 Una Division, HPPWD  
 Una

SCHEDULE OF QUANTITY							
						Estimated Cost	99000/-
						Earnest Money	2000/-
Name of work : A/R & M/O L/R Santoshgarh Mehatpur road km.0/0 to 7/0 & Ajouli Santoshgarh road km.0/0 to 3/600 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.)						Time limit	One Month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	99.00	Per Hour	1000.00	Rupees One thousand only	99000	
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	99000	
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
	4) The bidder should have his own machinery.						
	5) The bidder must have provide machinery immediately as an when required.						
	Percentage quoted Rate in Figures						
	Percentage quoted Rate in Words						
	Note: Rates quoted in figures & words are mandatory						
	by the contractor otherwise the tender will be rejected.						

  
 Executive Engineer  
 Una Divn.HP.PWD.,  
 Una

13

SCHEDULE OF QUANTITY						
					Estimated Cost	99000/-
Name of work : A/R & M/O L/R Ajouli to Sanoli upto Punjab Boundary km.0/0 to 4/600 & Circular road Sanoli km.0/0 to 0/800 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	99.00	Per Hour	1000.00	Rupees One thousand only	99000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99000
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	4) The bidder should have his own machinery.					
	5) The bidder must have provide machinery immediately as an when required.					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD.,  
 Una


(5)

SCHEDULE OF QUANTITY						
					Estimated Cost	65445/-
	Name of work : Repair & maintenance of HP.PWD., residential building at Jaigran Tehsil & Distt.Una (SH: P/L interlock pavers along residence)(Part -VI)				Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	80.30	Per square metre	815.00	Rupees Eight hundred fifteen only	65445
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	65445
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

*Keshab*  
Executive Engineer  
Una Divn HP PWD  
Una

6

SCHEDULE OF QUANTITY						
					Estimated Cost	65404/-
Name of work : Repair & maintenance of HP.PWD., residential building at Jalgran Tehsil & Distt.Una (SH: P/L interlock pavers along residence)(Part -V)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	80.25	Per square metre	815.00	Rupees Eight hundred fifteen only	65404
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					Total:	65404
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						


  
 Executive Engineer  
 Una Divn.HP:PWD  
 Una

7

SCHEDULE OF QUANTITY						
					Estimated Cost	99901/-
Name of work :A/R & M/O PWD Rest House at Una (SH: Providing services out of sources basis for one number Gardner( Mall) (period of 147 days )					Earnest Money	2000/-
					Time limit	147 days
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing Services on temporary basis of one number Gardner(Mali) for maintenance , plantation & beautification of Rest House complex.	147.00	Per day	679.60	Rupees Six hundred seventy nine and paise sixty only	99901
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					Total:	99901
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

*Hemankumar*  
 Executive Engineer  
 Una Divn.HP.PW  
 Una.

SCHEDULE OF QUANTITY							
					Estimated Cost	99550/-	
Name of work :A/R & M/O PWD Rest House at Una (SH: Providing and fixing plantation different type of plant, flower plant and ornamental plant and roser plant etc)					Earnest Money	2000/-	
					Time limit	<del>10/11/2021</del>	
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and fixing different type of ornamental plant & rose plant.	110.00	each	330.00	Rupees Three hundred thirty only	36300	
2	Providing and fixing different type of flower plant	575.00	each	110.00	Rupees One hundred ten only	63250	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018						Total:	99550
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una.

81

9

SCHEDULE OF QUANTITY							
						Estimated Cost	98509/-
Name of work :Repair & damages on Charatgarh Khanpur road km.0/0 to 2/200 (SH: C/O edge wall in RD. 1/010 to 1/075(Left side) <i>(Under BPC L deposit)</i>						Earnest Money	2000/-
						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	13.16	Per cubic metre	170.00	Rupees One hundred seventy only	2237	
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	24.38	Per cubic metre	3900.00	Rupees Three thousand nine hundred only	95082	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 Including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.00	Each	170.00	Rupees One hundred seventy only	1190	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	98509
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate In Figures							
Percentage quoted Rate In Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

*K. Singh*  
 Executive Engineer,  
 Una Division, HPPWD.,  
 Una

82

16

Estimated cost 98339/-

SCHEDULE OF QUANTITY					Estimated cost 98339/-	
Name of work :Repair & damages on Charatgarh Khanpur road km.0/0 to 2/200 (SH: C/O edge wall in RD. 1/075 to 1/140(Left side) (Under BPLC deposit)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	13.16	Per cubic metre	170.00	Rupees One hundred seventy only	2237
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.38	Per cubic metre	3900.00	Rupees Three thousand nine hundred only	95082
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Each	170.00	Rupees One hundred seventy only	1020
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	98339
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

*Ravinder*  
 Executive Engineer,  
 Una Division, HPPWA  
 Una

SCHEDULE OF QUANTITY

Estimated Cost 98124/-

Earnest Money 2000/-

Time limit One month

Name of work Repair & maintenance of link road Dehlan to Behdala km.0/0 to 2/0 (SH: P/L 80mm thick intrerlocking paver at RD.1/505 to 1/520 both side and C/O edge wall at RD.1/395 to 1/410) (Under BPCL deposit)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.13	Per cubic metre	170.00	Rupees One hundred seventy only	1722
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.89	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	46532
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horzontial) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Each	170.00	Rupees One hundred seventy only	2380

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	21.00	Per square metre	890.00	Rupees Eight hundred ninety only	18690
5	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.00	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	28800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	98124
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer,  
 Una Division, HPFIWD

Una

SCHEDULE OF QUANTITY							Estimated Cost	98258/-
Name of work Repair & maintenance of link road Dehlan to Behdala km.0/0 to 2/0 (SH: P/L 80mm thick interlocking paver at RD.1/566 to 1/581 both side and C/O edge wall at RD.1/470 to 1/485) (Under BPCL deposit)							Earnest Money	2000/-
							Time limit	One month
							Sl. No.	Description of work
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.13	Per cubic metre	170.00	Rupees One hundred seventy only	1722		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.89	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	46532		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Each	170.00	Rupees One hundred seventy only	2380		

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	21.15	Per square metre	890.00	Rupees Eight hundred ninety only	18824
5	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.00	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	28800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	98258
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


  
 Executive Engineer  
 Una Division, HPPWD  
 Una

13

SCHEDULE OF QUANTITY						
Name of work :Repair & maintenance of Behdala Jakhera road km.0/0 to 5/500 (SH: C/O Drain wall & bed along road side at RD.0/827.50 to 0/845) (Under BPCL deposit)					Estimated Cost	89852/-
					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.61	Per cubic metre	170.00	Rupees One hundred seventy only	1974
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.28	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	67938
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horzontial) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Each	170.00	Rupees One hundred seventy only	1020

6

4	Providing and laying in position cement concrete 1.3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.73	Per cubic metre	4000.00	Rupees Four thousand only	18920
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:	89852
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PW.,  
 Una

SCHEDULE OF QUANTITY						
					Estimated Cost	89682/-
					Earnest Money	2000/-
					Time limit	One month
Name of work :Repair & maintenance of Behdala Jakhera road km.0/0 to 5/500 (SH: C/O Drain wall & bed along road side at RD.0/810 to 0/827.50) (Under BPCL deposit)						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.61	Per cubic metre	170.00	Rupees One hundred seventy only	1974
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.28	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	67938
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horzontial) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana toll tax,GST,labour cess or other taxes imposed by the Government.	5.00	Each	170.00	Rupees One hundred seventy only	850

6

4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toil tax,GST,labour cess or other taxes imposed by the Government..	4.73	Per cubic metre	4000.00	Rupees Four thousand only	18920
	NOTE. 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8 2018				Total:	89682
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

SCHEDULE OF QUANTITY							Estimated Cost	99000/-
Name of work :Restoration of rain damages on Badehar Khuhi Pekhubela road at RD.3/600 (SH: Channelization on RHS of Pekhubela bridge at RD.3/200)							Earnest Money	2000/-
							Time limit	07/07/2021
							RATE In	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	99.00	Per Hour	1000.00	Rupees One thousand only	99000		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018						Total:	99000	
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
4) The bidder should have his own machinery.								
5) The bidder must have provide machinery immediately as an when required.								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor, otherwise the tender will be rejected.								

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	99000/-
Name of work :Restoration of rain damages on Badehar Khuhi Pekhubela road at RD.3/600 (SH: Channelization on LHS of Pekhubela bridge at RD.3/200)						Earnest Money	2000/-
						Time limit	One Month
						RATE in	
S. No.	Description of work	Quantity	Unit	Figures	Words		
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	99.00	Per Hour	1000.00	Rupees One thousand only	99000	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018						Total:	99000
2) The rates shall be including of all types of taxes including GST etcetra)							
3) The bidder are requested to submit their bid as per notification Issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
4) The bidder should have his own machinery.							
5) The bidder must have provide machinery immediately as an when required.							

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	99000/-
Name of work :Restoration of rain damages on various road under Una Sub-Divn.No.II HP.PWD.,Mehatpur (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.)						Earnest Money	2000/-
						Time limit	one Month
						RATE In	
S. No.	Description of work	Quantity	Unit	Figures	Words		
				1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	99.00	Per Hour
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018						Total:	99000
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
4) The bidder should have his own machinery.							
5) The bidder must have provide machinery immediately as an when required.							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

SCHEDULE OF QUANTITY							
						Estimated Cost	99000/-
Name of work : A/R & M/O link road from Bangarh to Nangran road km. 0/000 to 8/200 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains from RD.3/0 to 4/500)						Earnest Money	2000/-
						Time limit	<del>15 days</del> One Month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	99.00	Per Hour	1000.00	Rupees One thousand only	99000	
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99000	
	2) The rates shall be including of all types of taxes including GST etcetra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
	4) The bidder should have his own machinery.						
	5) The bidder must have provide machinery immediately as an when required.						
	Percentage quoted Rate in Figures						
	Percentage quoted Rate In Words						
	Note: Rates quoted in figures & words are mandatory						
	by the contractor otherwise the tender will be rejected.						

*K. K. K.*  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	99728/-
Name of work : Restoration of rain damages on link road Dyallan Mohalla km.0/0 to 2/200 (SH: P/L 80mm thick interlocking paver in RD.1/750 to 0/762.50)(Under BPCL deposit)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	16.99	Per cubic metre	170.00	Rupees One hundred seventy only	2888	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed / stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.000	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	20100	
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other Incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	68.75	Per square metre	890.00	Rupees Eight hundred ninety only	61188	

4	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentais .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.24	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	15552
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99728
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
[Redacted text block containing various administrative details and contact information]						

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

2b

SCHEDULE OF QUANTITY						
					Estimated Cost	99970/-
					Earnest Money	2000/-
					Time limit	One month
Name of work :Restoration of rain damages on Dehlan Badehar road km.0/0 to 3/0 (SH: C/O R/wall at RD.1/550 to 1/570)(Under BPCL deposit)						
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.60	Per cubic metre	170.00	Rupees One hundred seventy only	1802
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.45	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	91958
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.00	Each	170.00	Rupees One hundred seventy only	1700

4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.20	Per cubic metre	550.00	Rupees Five hundred fifty only	4510
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:	99970
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
<p>1. The rates shall be including of all types of taxes including GST ectra)</p> <p>2. The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 &amp; Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021</p>						

  
 K. Mahalingam  
 Executive Engineer  
 Una Divn. HP. PWD., Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99936/-
					Earnest Money	2000/-
					Time limit	One month
Name of work :Restoration of rain damages on Dehian Badehar road km.0/0 to 3/0 (SH: C/O R/wall at RD.1/570 to 1/590)(Under BPCL deposit)						
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.60	Per cubic metre	170.00	Rupees One hundred seventy only	1802
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.44	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	91924
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.00	Each	170.00	Rupees One hundred seventy only	1700

4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.20	Per cubic metre	550.00	Rupees Five hundred fifty only	4510
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99936
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					
<p>ਮੁੱਲ ਦਾ ਅੰਤਿਮ ਹਿਸਾਬ ਪੇਸ਼ ਕਰਨਾ</p> <p>ਮੁੱਲ ਦਾ ਅੰਤਿਮ ਹਿਸਾਬ ਪੇਸ਼ ਕਰਨਾ</p> <p>ਮੁੱਲ ਦਾ ਅੰਤਿਮ ਹਿਸਾਬ ਪੇਸ਼ ਕਰਨਾ</p> <p>ਮੁੱਲ ਦਾ ਅੰਤਿਮ ਹਿਸਾਬ ਪੇਸ਼ ਕਰਨਾ</p>						

  
 Executive Engineer  
 Una Divn. HP. PWD., Una

166

22

SCHEDULE OF QUANTITY						
					Estimated Cost	78595/-
Name of work :Restorationn of rain damages on link road Rakkar to Basoli road km.0/0 to 2/400(SH: P/L of balance work interlocking pavers at RD.1/812 to 1/823.70) (Under OFCdeposit)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or balling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.32	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	21172
2	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentais .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.79	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	3792

*[Handwritten signature]*


3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	60.26	Per square metre	890.00	Rupees Eight hundred ninety only	53631
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	78595
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor, otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD.,  
 Una

SCHEDULE OF QUANTITY						
Name of work : Repair work of HP.PWD., 15th Circle building Una (SH: Repair of WS & SI etc)					Estimated Cost	85896/-
					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	2500.00	Rupees Two thousand five hundred only	10000
2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistem, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	4500.00	Rupees Four thousand five hundred only	9000
3	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931: 15 mm nominal bore.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.00	Each	450.00	Rupees Four hundred fifty only	4500
4	Providing and fixing G.I./ PE-AL-PE/ PP-R pipes. 15 mm dia nominal bore.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	40.00	Mtr	300.00	Rupees Three hundred only	12000
5	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	Each	550.00	Rupees Five hundred fifty only	8250
6	Providing and fixing kitchen sink with C.I. Or M.S brackets, painted white including cutting holes in walls and making good the same but including fittings 450mm x 350 x 150 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2800.00	Rupees Two thousand eight hundred only	2800
7	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete Semi rigid pipe including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.00	Each	90.00	Rupees Ninety only	900

8	Providing and fixing uplasticised PVC connection pipe with brass unions 15 mm nominal bore including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	Each	75.00	Rupees Seventy five only	1125
9	Providing and fixing 110mm high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.00	Mtr	250.00	Rupees Two hundred fifty only	1250
10	Providing and fixing 75 mm high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.00	Mtr	195.00	Rupees One hundred ninety five only	1950
11	Providing and fixing 110mm PVC Plain bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	140.00	Rupees One hundred fofty only	280
12	Providing and fixing 75mm PVC Plain bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	100.00	Rupees One hundred only	200
13	Providing and fixing 110 x 75mm (one hundred ten into seventy five millimeter) PVC floor trap make of Finolex self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etcetera complete upto all floor level/height including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	790.00	Rupees Seven hundred ninety only	3160
14	Providing and fixing PVC plastic seat cover.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	550.00	Rupees Five hundred fifty only	2200
15	Providing and fixing PTMT jet spray make of Viking, Prayag of approved quality and colour with one metre tube including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	260.00	Rupees Two hundred sixty only	1040
16	Providing and fixing white vitreous china squatting plate with integral longitudinal flush pipe including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	2600.00	Rupees Two thousand six hundred only	10400

17	Providing and fixing Division Plate for Urinals 600mm x 300. Vitreous China including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	2100.00	Rupees Two thousand one hundred only	8400
18	Providing and fixing PTMT urinal waste coupling of approved quality and colour.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	100.00	Rupees One hundred only	400
19	Providing and fixing PTMT coloured/white high density polyethylene / poly propylene 10 litres capacity ( full flush) European standard control low level flushing cistem with fittings with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with inlet, outlet and over flow pipe, 40mm dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistem and closet (overflow pipe to be measured and paid for separately) .including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	1500.00	Rupees One thousand five hundred only	6000
20	Polishing on wood work with ready made wax polish of approved brand and manufacture :Old work including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	45.36	Sqm	45	Rupees Forty five only	2041
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	85896
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99752/-
Name of work :Repair of HPPWD Rest House at Una Distt. Una HP(SH: - Providing and laying tile work and WI and SI work in set No 6					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres lead (wooden / concrete joists to be measured and paid for separately) 20210100 For thickness of tiles upto 25mm including carriage of material with in all lead and lifts	22.56	Sqm	40.00	Rupees Forty only	902
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete ing with bricks of class designation Description 11.41.2 Size of Tile 1200x600 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.50	Sqm	1100.00	Rupees One thousand one hundred only	4950
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).Size of Tile 1200x600 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	18.06		1150.00	Rupees One thousand one hundred fifty only	20769


*b*

4	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2200.00	Rupees Two thousand two hundred only	2200
5	P/F automatic flushing cistern with a pair of C.I. Or M.S. brackets complete with fittings including C.I. Syphonic apparatus, mosquito proof lid, C.P. Brass unions and coupling for connections with inlet, outlet and overflow pipes including cutting holes and making good the same (overflow pipe to be measured and paid for separately) :-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1500.00	Rupees One thousand five hundred only	1500
6	Providing and fixing PVC plastic seat cover.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1000.00	Rupees One thousand only	1000
7	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings:-630mmx450mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2200.00	Rupees Two thousand two hundred only	2200
8	Providing and fixing vitreous China pedestal for wash basin complete recessed at the back for the reception of pipes and fittings .including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1000.00	Rupees One thousand only	1000
9	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	192.00	Rupees One hundred ninety two only	192

10	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (light grade) tube fitting and clamps including making good the wall, ceiling and floor:- 15mm nominal bore including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	18.00	Rmt	325.00	Rupees Three hundred twenty five only	5850
11	P/F 450x600mm bevelled edge mirror-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	850.00	Rupees Eight hundred fifty only	850
12	Providing and fixing CP waste including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	150.00	Rupees One hundred fifty only	300
13	P/F PVC connection for wash basin/sink-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Each	100.00	Rupees One hundred only	600
14	P/F 15 mm bib tap with long nose.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.00	Each	650.00	Rupees Six hundred fifty only	3250
15	Chromium plated brass bib taps with cap stain heads. i) 15 mm dia. Weight 400 gms including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	550.00	Rupees Five hundred fifty only	2200
16	P/F CP brass soap dish- including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	250.00	Rupees Two hundred fifty only	500
17	P/F 750x12mm towel rail-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	350.00	Rupees Three hundred fifty only	700

18	P/F brass angle valve 15 mm without nuts and pipes including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Each	650.00	Rupees Six hundred fifty only	3900
19	P/F hydraulic door closer duly I.S marked including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1000.00	Rupees One thousand only	1000
20	C.P. Shelf with plate glass 600 X 120 mm with guard rail of standard size and bracket. including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	350	Rupees Three hundred fifty only	350
21	Providing and fixing C.P. Brass shower rose with 15mm or 20mm inlet ) 150mm dia (Jaguar) including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	500.00	Rupees Five hundred only	500
22	PTMT grating round 150 mm. including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	50.00	Rupees Fifty only	100
23	Providing and fixing sink 15mm mixer for kitchen sink with casted swinging spout tap of make cera or equiv.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	4500.00	Rupees Four thousand five hundred only	4500
24	P/F CP brass heavy duty make ISI marked No. 8931 & 8934 toilet paper holders including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	250.00	Rupees Two hundred fifty only	250
25	Providing and fixing 110mm dia dia pipe 2.7mm thick PVC pipe including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Rmt.	370.00	Rupees Three hundred seventy only	2220

26	Providing and fixing Wall paper on wall including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.50	Sqm	650.00	Rupees Six hundred fifty only	4225
27	Providing and fixing 25mm diameter curtain rods with brackets, plugs etc. where ever required. First class indian teak wood. including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.40	Rmt	250.00	Rupees Two hundred fifty only	6600
28	Providing and fixing 40mm(forty millimeter) thick 2 <sup>nd</sup> class deodar wood wire gauge <sup>va</sup> shutters using galvanized MS wire gauge of IS gauge designation 85-G(eighty five) with wire of dia 0.56mm(zero point fifty six millimeter) for doors windows clerestory windows including bright finished /black enameled iron butt hinges with necessary screws including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.56	Sqm	2800.00	Rupees Two thousand eight hundred only	9968
29	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm thick 2nd class deodar wood.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.52	sqm	3800.00	Rupees Three thousand eight only	17176
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					G.Total	99752
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected.						


  
 Executive Engineer  
 Una Divn HP PWD. Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99269/-
Name of work :A/R & M/O residential building Una (SH: Repair of plaster, painting and other maintenance for Type-III qtr. No.17 DC colonyt Una (Part-5)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Demolition above G.L. upto floor two level including disposal of unserviceable materials within 20 metres lead and including cutting the necessary reinforcement and separating out from R.C.C. /R.B. works: R.C.C. work. includng carriage of material with in all lead and lifts	0.44	Cum	550.00	Rupees Five hundred fifty only	242
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: S sand)including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	12.96	Sq.Mtr	160.00	Rupees One hundred sixty only	2074
3	Providing and laying cement concrete 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 20mm (twenty millimetres) nominal size) and curing complete, excluding cost of form work and reinforcement for reinforced concrete work in; (Cement concrete to be machine mixed and mechanically vibrated) including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.44	Cum	4800.00	Rupees Four thousand eight hundred only	2112
4	Providing mild steel/tor steel reinforcement for R.C.C. work including bending, binding and placing in position complete up to all floor level / all height. TOR STEELincluding carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	53.06	kg	90.00	Rupees Ninety only	4775
5	Applying 8mm white wall care putty over plaster/other surface after thoroughly brushing the surface free from oil and drops dirt, loose materials and other foreign matter sand papere d smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	86.49	Sq.Mtr	50.00	Rupees Fifty only	4325

6	Applying one coat of Acrylic Washable emulsion Spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat i/c necessary putty to give smooth even surface, sand papered smooth complete.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	86.49	Sq.Mtr	65.00	Rupees Sixty five only	5622
7	Providing and fixing 25mm diameter curtain rods with brackets, plugs etc. where ever required. First class indian teak wood. as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	14.40	Rmt	250.00	Rupees Two thundred fifty only	3600
8	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately). Sal wood. including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.174	Cum	80000.00	Rupees Eighty thousand only	13920
9	Providing and fixing 40mm(forty millimeter) thick 2 <sup>nd</sup> class deodar wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85-G(eighty five) with wire of dia 0.56mm(zero point fifty six millimeter) for doors windows clerestory windows including bright finished /black enameled iron butt hinges with necessary screws including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.25	Sqm	2800.00	Rupees Two thousand eight hundred only	11900
10	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws and 2mm thick 2nd class deodar wood including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mall,hana toll tax,GST,labour cess or other taxes imposed by the Government..	4.25	sqm	3800.00	Rupees Three thousand eight hundred only	16150

11	P/F brass angle valve 15 mm without nuts and pipes including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	3.00	Each	800.00	Rupees Eight hundred only	2400
12	P/F hydraulic door closer duly I.S marked including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	1000.00	Rupees One thousand only	1000
13	P/F 450x600mm bevelled edge mirror-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	650.00	Rupees Six hundred fifty only	650
14	P/F 750x12mm towel rail-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	450.00	Rupees Four hundred fifty only	450
15	C.P. Shelf with plate glass 600 X 120 mm with guard rail of standard size and bracket.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	Each	150.00	Rupees One hundred fifty only	150
16	P/F CP brass soap dish- including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	Each	250.00	Rupees Two hundred fifty only	500
17	Providing and fixing 32mm dia lead waste pipes for wash basin or sink including brass check nut including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	Each	150.00	Rupees One hundred fifty only	300
18	Providing and fixing CP waste including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	Each	150.00	Rupees One hundred fifty only	300
19	P/F PVC connection for wash basin/sink- including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	4.00	Each	120.00	Rupees One hundred twenty only	480
20	P/F CP brass pillar tap 15mm dia including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	Each	650.00	Rupees Six hundred fifty only	650

21	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :610x460 mm bowl depth 200 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2500.00	Rupees Two thousand five hundred only	2500
22	Providing and fixing sink 15mm mixer for kitchen sink with casted swinging spout tap of make cera or equiv.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2800.00	Rupees Two thousand eight hundred only	2800
23	Providing and fixing C.P. Brass shower rose with 15mm or 20mm inlet ) 150mm dia including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	500.00	Rupees Five hundred only	500
24	Finishing wall with weather proof exterior grade emulsion of approved design( Apex ultima/heritage ) or its equivalent on undecorated wall surface(two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt,dust, and other foreign matter etc. including sand paper smooth complete.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	291.60	Sqm	75.00	Rupees Seventy five only	21870
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					G.Total	99269
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Notes: Rates quoted in figures, words, and in figures by the contractor, other wise the tender will be rejected.						

  
 Executive Engineer  
 Una Divn.HP.PWD. U.P.

26

SCHEDULE OF QUANTITY							Estimated Cost	98328/-
Name of work :A/R & M/O residential building for pooled accomodation in Type III Qtr No. 17 and outer paint Type III Qtrs in D C colony Una (SH: Providing and Fixing PVC panelling etc Bed room 1 and Dining (Part-4)							Earnest Money	2000/-
							Time limit	One month
							Sl. No.	
				Figures	Words			
1	Providing and Fixing PVC panelling tiles wall lining includng carriage of material with in all lead and lifts as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.		81.94	Sqm	1200.00	Rupees One thousand two hundred only	98328	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/0212 dated 7.8.2018							G.Total	98328
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								


*Kudgkins*  
Executive Engineer  
Una Divn.HP.PWD.,  
Una

(27)

SCHEDULE OF QUANTITY							Estimated Cost	99123/-
Name of work :A/R & M/O residential building Una (SH: P/F wall tile and other maintenance for Type-III qtr. No.17 DC colony Una)(Part-2)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).Size of Tile 1200x600 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	48.92	Sqm	1150.00	Rupees One thousand one hundred fifty only	56258		
2	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts. (125mm)	20.00	each	80.00	Rupees eighty only	1600		
3	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc.200 x 10mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.00	each	120.00	Rupees One hundred twenty only	2400		
4	Providing and laying granite stone in flooring 20mm(average)thickness base of cement mortar 1:3(1cement: 3 sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone i/c rubbing and polishing complete. 20mm.thick. including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.05	Sqm	3500.00	Rupees Three thousand five hundred only	10675		

2

5	Painting two coat(excluding priming coat)on wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	51.08	sqm	65.00	Rupees Sixty five only	3320
6	Finishing wall with weather proof exterior grade emulsion of approved design( Apex ultima/heritage ) or its equivalent on undecorated wall surface(two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt,dust, and other foreign matter etc. including sand paper smooth complete.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	291.60	Sqm	75.00	Rupees Seventy five only	21870
7	P/F hydraulic door closer duly I.S marked as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.00	each	1000.00	Rupees One thousand only	3000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	99123
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn HP:PWD  
 Una

(28)

SCHEDULE OF QUANTITY				Estimated cost	99360/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: C/O link road to Harijan Basti Kuthar Khurd Tehsil & Distt. Una km.0/0 to 1/600(GP Kuthar Khurd) (SH: Providing and laying gravel soil aggregate at RD.0/180 to 0/335)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	86.40	Per Cubic metre	1150.00	Rupees One thousand one hundred fifty only	99360
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99360
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

*K. K. K.*  
 Executive Engineer  
 Una Divn. HP. PW  
 Una

SCHEDULE OF QUANTITY				Estimated cost	99985/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & M/O residential building for Distt. Attorney Type-IV Qtr. In DC colony Una (SH: Providing and fixing 18mm thick(HDHMR board) and painting etc)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition RCC/RB work above GL upto floor two level including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.90	Per cubic metre	650.00	Rupees Six hundred fifty only	1235
2	Providing and fixing 18mm(eighteen millimetre) (HDHMR BOTH SIDE prelamated) thick water proof termite resistant(Box type) including shelves and back side of wall and shutters with edge bending with adhesivle in front of shutter fixing 1mm thick sunmica approved shade brand action tessa etertra including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	12.30	Per square metre	7500.00	Rupees Seven thousand five hundred only	92250
3	Finishing with Deluxe multi surface paint, system for interiors and exteriors using primer as per manufacture specifications Two or more coat applied on walls @1.25 ltr/10 sqm over and including one coat of @0.75 ltr/10 sqm including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	100.00	Per square metre	65.00	Rupees Sixty five only	6500
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					G.Total	99985
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

*[Signature]*  
 Executive Engineer  
 Una Divn.HP.PW  
 Una

**SCHEDULE OF QUANTITY**

Estimated cost 99525/-  
 Earnest money 2000/-  
 Time limit One month

Name of Work: Repair of HP.PWD., Rest House at Una Dist. Una (HP) (SH: Refilling of various type Fire Executioner cyliner in HP.PWD., Rest House Una)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Refilling of Fire Executioner cyliner having capacity charge Co2 type 9.00kg capacity used to control small fires often in emergencies including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	15	Each	4450	Rs. Four thousand four hundred fifty only	66750
2	Refilling of Fire Executioner cyliner having capacity charge DCP type 5.00kg capacity used to control small fires often in emergencies including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	3	each	1875	Rs. One thousand eight hundred seventy five only	5625
3	Refilling of Fire Executioner cyliner having capacity charge DCP type 10.00kg capacity used to control small fires often in emergencies including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	4	each	3050	Rs. Three thousand fifty only	12200
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinable priming coat with cement primer including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	230.00	Per square metre	65.00	Rupees Sixty five only	14950
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total		99525
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected						

*[Signature]*  
 Executive Engineer  
 Una Divn. HP.PWD.  
 Una

SCHEDULE OF QUANTITY							
						Estimated Cost	99000/-
Name of work :Restoration of rain damages on Old Hoshiarpur road at RD.4/200 (SH: Channelization on D/S side of Lalsingi bridge at RD.3/600) (RHS) -						Earnest Money	2000/-
						Time limit	One Month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	99.00	Per Hour	1000.00	Ruppes One thousand only	99000	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018						Total:	99000
2) The rates shall be including of all types of taxes including GST etetra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
4) The bidder should have his own machinery.							
5) The bidder must have provide machinery immediately as an when required.							
<p>Prepared by: _____</p> <p>Checked by: _____</p> <p>Approved by: _____</p> <p>_____</p>							

  
 Executive Engineer  
 Una Divn.HP.PWB  
 Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99000/-
Name of work :Restoration of rain damages on Old Hoshiarpur road at RD.4/200 (SH: Channelization on U/S side of Laisingi bridge at RD.3/600) (LHS)					Earnest Money	2000/-
					Time limit	One Month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toli tax,GST,labour cess or other taxes imposed by the Government..	99.00	Per Hour	1000.00	Rupees One thousand only	99000
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					Total:	99000
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
4) The bidder should have his own machinery.						
5) The bidder must have provide machinery immediately as an when required.						
Bidding process is open for all interested parties to submit their bids in sealed envelopes to the undersigned at the address mentioned below.						

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99936/-
Name of work :Restorationn of rain damages on link road to village Lower Amriala km.0/0 to 1/0(SH: P/F CC interlocking paver blocks at RD.0/040 to 0/082( left side berms)(Under OFC deposit)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE in		AMOUNT
				Figures	Words	
1	Demolition above G.L upto floor two level including disposal of unserviceable materials within 20 metres lead and including cutting the necessary reinforcement and separating out from R.C.C. /R.B. works: R.C.C. work including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	9.36	Per cubic metre	650	Rupees Six hundred fifty only	6084
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.16	Per cubic metre	170.00	Rupees One hundred seventy only	877
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidentia.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.36	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	21306
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 25mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	59.30	Per square metre	850.00	Rupees Eight hundred fifty only	50405

5	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.43	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	21264
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99936
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
<p>             1) The rates shall be including of all types of taxes including GST ectra)              2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 &amp; Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021           </p>						

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	99941/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & W/O non residential building for DC Colony Una (SH: Providing and fixing convex mirror and other maintenance in Judges residence)

S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Repair to plaster in patches of 2.50sqm and under 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20mtr. with Cement mortar 1:4 (1cement:4sand)including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.57	Per square metre	150.00	Rupees One hundred fifty only	4586
2	Applying Birla white wall care putty over plaster/other surface after thoroughly brushing the surface free from mortar drops dirt loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.57	Per square metre	60.00	Rupees Sixty only	1834
3	Finishing with Deluxe multi surface paint, system for interiors and exteriors using primer as per manufacture specifications Two or more coat applied on walls @1.25 ltr/10 sqm over and including one coat of @0.75 ltr/10 sqm including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	163.35	Per square metre	65.00	Rupees Sixty five only	10618
4	Providing and fixing PVC panelling tiles in ceiling lining including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	51.60	Per square metre	1200.00	Rupees One thousand two hundred only	61920
5	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinable priming coat with cement primer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	48.30	Per square metre	65.00	Rupees Sixty five only	3140
6	Painting wood work with deluxe multi surface paint of required shade: Two or more coat applied @ 0.90ltr/10sqm. over an under coat of primer applied @ 0.75ltr/10sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	59.13	Per square metre	65.00	Rupees Sixty five only	3843

*le*

7	Providing and fixing of road safety convex( size 80 cm) made of polycarbonate and ABS body suitable for indoor/ outdoor with hood complete with mounting hardware including post as per drawing and technical specifications including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2	each	7000.00	Rupees Seven thousand only	14000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)G(17)2/0212 dated 7.8.2018				G.Total	99941
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
<p>         Bidding and purchase of road safety convex          Bidding and purchase of road safety convex          Bidding and purchase of road safety convex          Bidding and purchase of road safety convex       </p>						

  
 Executive Engineer  
 Una Divn.HP.PWD,  
 Una

124

35

SCHEDULE OF QUANTITY							
						Estimated Cost	99537/-
						Earnest Money	2000/-
Name of work : Restoration of rain damage on 120metre span bridge on Una Santoshgarh road at RD.1/760 (SH: Channellization of Khad on Upstream side of Rampur bridge 1/760 LHS)						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90cum. bucket capacity including cutting and loading in tippers and disposal within any leads and lifts. The rates are inclusive octrol, royalty, malkana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	951.60	Per cubic metre	104.60	Rupees One hundred four and paise sixty only	99537	
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99537	
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
	Percentage quoted Rate In Figures						
	Percentage quoted Rate In Words						
	Note: Rates quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected.						

*Kamala*  
 Executive Engineer  
 Una Divn.HP.PW  
 Una

25

36

SCHEDULE OF QUANTITY							
						Estimated Cost	99286/-
Name of work : Restoration of rain damage on 120metre span bridge on Una Santoshgarh road at RD.1/760 (SH: Channelization of Khad on Upstream side of Rampur bridge 1/760 along the length of bridge)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90cum. bucket capacity including cutting and loading in tippers and disposal within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	949.20	Per cubic metre	104.60	Rupees One hundred four and paise sixty only	99286	
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99286	
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification Issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
	Percentage quoted Rate In Figures						
	Percentage quoted Rate In Words						
	Note: Rates quoted in figures & words are mandatory						
	by the contractor, otherwise the tender will be rejected.						

*Bhaskar*  
 Executive Engineer  
 Una Divn.HP.PW  
 Una

96

37

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	98260/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: ~~XXXXXX~~ residential building of ADC residence at DC colony Una (SH: - Providing and fixing aluminium work and other repairs etc.


S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and fixing 18mm(eighteen millimetre) (HDHMR BOTH SIDE prelaminated) thick water proof termite resistant(Box type) including shelves and back side of wall and shutters with edge bending with adhesivle in front of shutter fixing 1mm thick sunmica approved shade brand action tessa etertra including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	6.84	Per square metre	8500.00	Rupees Eight thousand five hundred only	58140
2	Providing and fixing aluminium work(Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately) :including entire carriage of material within all leads and lifts and other Incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.					

6

(b)	For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	49.68	Per kilogramme	550.00	Rupees Five hundred fifty only	27324
3	Providing and fixing glazing with glass panes of 5.50mm thickness (weight not less than 13.75 kg/ sqm in aluminium door, window, ventilator shutters make it Hindal Co., Jindal Indian aluminum Co. and partition etcetera with PVC/neoprens gasket etcetera complete upto any floor level/height as per the architectural drawings including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	3.38	Per square metre	850.00	Rupees Eight hundred fifty only	2873
4	Providing and fixing fly proof galvanised MS wire gauge designation 140 G (one hundred forty G) with wire of dia 0.56mm to windows and clerstory windows including 60 x 20mm ( beading upto any floor level/height including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	3.38	Per square metre	850.00	Rupees Eight hundred fifty only	2873
5	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc.200 x 10mm including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	15.00	Each	80.00	Rupees Eighty only	1200

6

6	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts. (125mm)including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	15.00	each	90.00	Rupees Ninety only	1350
7	Providing and fixing 25mm diameter curtain rods with brackets, plugs etc. where ever required. First class indian teak wood. including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	18.00	Per running metre	250.00	Rupees Two hundred fifty only	4500
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	98260
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


  
 Executive Engineer ,  
 Una Divn.HP.PW,  
 Una

38

SCHEDULE OF QUANTITY						
					Estimated Cost	98050/-
Name of work <del>XXXXXXXXXX</del> residential building of ADC residence at DC colony Una (SH: - P/L Painting and other repairs etc.					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry oil bound distemper by washing and scrapping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	461.05	Per square metre	7.00	Rupees Seven only	3227
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.12	Per square metre	160.00	Rupees One hundred sixty only	2419
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface to give smooth even surface, sand papered smooth complete. including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	461.05	Per square metre	45.00	Rupees Forty five only	20747
4	Applying Birla white wall care putty over plaster/other surface after thoroughly brushing the surface free from mortar drops durt loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	461.05	Per square metre	60.00	Rupees Sixty only	27663
5	Applying one coat of AcrylicWashable emulsion Spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat to give smooth even surface, sand papered smooth complete. i/c carriage of material within all leads and lifts.	461.05	Per square metre	65.00	Rupees Sixty five only	29968

*Handwritten signature*

6	Painting two coat on steel and other metal surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.24	Per square metre	65.00	Rupees Sixty five only	796
7	Providing and fixing 10 mm thick pre-laminated particle board (decorative lamination on both sides) grade - 1, medium density flat pressed, three layer particle board FPT- I or graded wood particle board FPT- I, conforming to IS : 3087, bonded with BWP type synthetic resin adhesive as per IS : 848 and pre- laminated conforming to IS : 12823, Grade 1, Type - II marked including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.85	Per square metre	1800.00	Rupees One thousand eight hundred only	3330
8	Providing and fixing 1000 litres net capacity tank three layers technology water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting up to all heights above ground level in all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1000.00	Per litre	9.90	Rupees Nine and paise ninety only	9900
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	98050
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor. otherwise the tender will be rejected.					

  
 Executive Engineer,  
 Una Divn.HP.PWD  
 Una

92

39

Estimated cost:- Rs. :-

98684

Earnest money:- Rs. :-

2000

Time limit :-

one  
MonthSCHEDULE OF QUANTITY

Name of work:-A/R &amp; M/O residential building at Una

SH: - P/L Painting and floor tile etc for Type 1 Qtr No 8 at DC Colony Una

Sr No	Description of item	Quantity	Unit	Rate	Rate in Words	Amount
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)	8.64	Sqm	150.00	Rupees one hundred fifty only	1296
2	Applying Birla white wall care putty over plaster/other surface after thoroughly brushing the surface free from mortar drops dirt loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete i/c carriage of material within all leads and lifts.	50.00	Sqm	50.00	Rupees fifty only	2500
3	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surface to give an even shade after thoroughly brushing the surface clean of all grease, dirt, loose pieces of scales and also i/c preparing the surface even and sand papering smooth.	138.22	Sqm	65.00	Rupees Sixtiffive only	8984
4	Finishing wall with weather proof exterior grade emulsion of approved design( Apex ultima/heritage ) or its equivalent on undecorated wall surface(two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt,dust. and other foreign matter etc. including sand paper smooth complete.	274.30	Sqm	75.00	Rupees Seventiffive only	20573
5	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	34.91	sqm	65.00	Rupees Sixtiffive only	2269
6	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accesoriees as required as per the direction of Engineer-in-charge.	3.92	sqm	1050.00	Rupees one thousand fifty only	4116

7.	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. IN GRATING, FRAMED GUARD, BARS LADDERS RAILING BRACKETS AND SIMILAR WORKS including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.78	qtl	9500.00	Rupees nine thousand five hundred only	7410
8	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc, and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/ 450N/ 5cm. Tear strength in longitudinal and transverse direction as 300/ 250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane : 3 mm	47.88	sqm	500.00	Rupees five hundred only	23940
9	Providing and fixing 10mm thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete.	4.72	Sqm	1150.00	Rupees one thousand one hundred fifty only	5428
10	Providing and fixing 40mm (forty millimeter) thick Kiln seasoned and chemically treated hollock wood wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85-G (eighty five) with wire of dia 0.56mm (zero point fifty six millimeter) for doors windows clerestory windows including bright finished /black enameled iron butt hinges with necessary screws	1.84	sqm	3800.00	Rupees three thousand eight hundred only	6992
11	glazing with glass panes of 4mm thickness (weight not less than 10.00 kg/sqm. i/c carriage of material within all leads and lifts. as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.47	Sqm	800.00	Rupees eight hundred only	1176
12	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts. (125mm). including carriage of materials in all leads and lifts.	10.00	each	95.00	Rupees ninty five only	950
13	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc. 200 x 10mm .including carriage of materials in all leads and lifts.	10.00	each	90.00	Rupees ninty only	900
14	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 sand) (Seat and over to be measured and paid for separately	1.00	Each	2500.00	Rupees two thousand five hundred only	2500

15	Providing and fixing PVC plastic seat cover including carriage of material within all leads and lifts The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1000.00	Rupees One thousand only	1000
16	Providing and fixing PTMT Jet spray of approved quality and colour with one metre tube Including carriage of material within all leads and lifts The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	350.00	Rupees Three hundred fifty only	350
17	Providing and fixing vitreous china wash basin with single hole for pillar tap with C.I. or MS brackets painted white Including cutting holes and making good the same but excluding fittings:630mmx460mm as per direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2200.00	Rupees two thousand two hundred only	2200
18	Providing and fixing automatic flushing cistern with a pair or C/I. or MS brackets complete with fittings including C.I. syphonic apparatus, mosquito proof lid, C.P. brass unions and coupling for connections with inlet, outlet and overflow pipes including cutting holes and making good the same(overflow pipe to be measured and paid for separately) including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1800.00	Rupees One thousand eight hundred only	1800
19	Providing and fixing to wall ceiling and floor galvanised mild steel tubes(light grade) tube fitting and clamps including making good the wall, ceiling and floor. 15mm nominal bore as per the direction by the Engineer-in-charge..The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Rmt	325.00	Rupees Three hundred twenty five only	2600
19	Providing and fixing 15mm bib tap long nose as per the direction by the Engineer-in-charge.he rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	850.00	Rupees eighth hundred fifty only	1700
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	98684
	2) The rates shall be including of all types of taxes including GST etc(tra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

143

40


SCHEDULE OF QUANTITY							
						Estimated Cost	99875/-
						Earnest Money	2000/-
						Time limit	One month
Name of work :A/R & M/O residential building at Una (SH: Providing and fixing HDHMR cupboard at SDM residence in DC colony Una)						RATE IN AMOUNT	
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT	
				Figures	Words		
7	Providing and fixing 18mm(eighteen millimetre) (HDHMR BOTH SIDE prelaminate) thick water proof termite resistant(Box type) including shelves and back side of wall and shutters with edge bending with adhesive in front of shutter fixing 1mm thick sunmica approved shade brand action tessa etertra including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	11.75	Per square metre	8500.00	Rupees Eight thousand five hundred only	99875	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018							99875
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							

*K. Singh*  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

(119)

(41)

SCHEDULE OF QUANTITY						
					Estimated Cost	99474/-
	Name of work :A/R & M/O residential building in DC colony Una (SH: Providing and laying wall painting in HP.PWD., SE residence)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs scratches complete including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	993.45	Per square metre	8.00	Rupees eight only	7948
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts. The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	993.45	Per square metre	60.00	Rupees Fifty only	59607
3	Distemping with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade after thoroughly brushing the surface clean of all grease dirt,loose,pieces of scales and also including preparing the surface even and sand papered smooth including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	491.06	Per square metre	65.00	Rupees Fifty only	31919
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				Total:	99474
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD.,  
 Una


118

42

SCHEDULE OF QUANTITY						
					Estimated Cost	99982/-
					Earnest Money	2000/-
					Time limit	One month
Name of work :AR & M/O residential building in DC colony Una (SH: Providing and laying wall painting and other repair work in HP.PWD., SE residence)						
S. No.	Description of work	Quantity	Unit	RATE in		AMOUNT
				Figures	Words	
1	Demolition above GL upto floor two level RCC/RB works Including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.22	Per cubic metre	1000.00	Rupees One thousand only	220
2	Providing and fixing 0.60mm thick prepainted steel sheet in roofing over steel members/ trusses ,prepainted steel hot dipped metallic zinc coated sheet with top coat of regular modified polyster (R.N.P.) organic coating of 20(twenty) microns over 5(five) microns primer coating to back coat of polyster of five micron over 5 (five ) microns primer coating including fixing with prepainted iron J or L hooks bolts and nuts 6mm diametre with prepainted limpet and rubber washers complete including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.97	Per Square metre	1100.00	Rupees One thousand one hundred only	3267
3	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	0.45	Per Quintal	10000.00	Rupees Ten thousand only	4500
4	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentials and aa per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	43.20	Per square metre	170.00	Rupees One hundred sixty only	7344
5	Finishing walls with apex exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	502.39	Per square metre	85.00	Rupees Eighty five only	42703

6

6	Painting one coats(excluding priming coat) on previously wood and wood based surfaces with readymixed paint, brushing to give an even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	70.14	Per square metre	60.00	Rupees Sixty only	4208
7	Providing and fixing 18mm(eighteen millimetre) (HDHMR BOTH SIDE prelamated) thick water proof termite resistant(Box type) including shelves and back side of wall and shutters with edge bending with adhesivle in front of shutter fixing 1mm thick sunmica approved shade brand action tessa etertra including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-In-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	4.44	Per square metre	8500.00	Rupees Eight thousand five hundred only	37740
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					99982
	2) The rates shall be including of all types of taxes (including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted, In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

113

SCHEDULE OF QUANTITY				Estimated cost	99956/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: ~~Repair & maintenance~~ <sup>on</sup> Behdala Jankour via Abada Barana road km.0/0 to 4/800 Tehsil & Distt.Una (SH: C/O R/wall along road from RD.0/972.25 to 0/988.40)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.09	Per cubic metre	170.00	Rupees One hundred seventy only	1715
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.26	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	94671
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)d/ia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 814,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	21.00	Each	170.00	Rupees One hundred seventy only	3570
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				G.Total	99956
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bld as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


  
 Executive Engineer  
 Una Divn.HP.PWD,Una

44

SCHEDULE OF QUANTITY				Estimated cost	99513/-
				Earnest money	2000/-
				Time limit	One month


Name of Work: Repair & maintenance Behdala Jankour via Abada Barana road km.0/0 to 4/600 Tehsil & Distt.Una (SH: C/O R/wall along road from RD.0/956.15 to 0/972.25)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octrol, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.06	Per cubic metre	170.00	Rupees One hundred seventy only	1710
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ dapths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as par the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.18	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	94403
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.00	Each	170.00	Rupees One hundred seventy only	3400
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				<b>G.Total</b>		<b>99513</b>
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govl. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted In figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

  
 Executive Engineer  
 Una Divn.HP.PWD,Una

45

SCHEDULE OF QUANTITY						Estimated Cost	93492/-						
Name of work :A/R & M/O to link road from Jhatera bridge to Una via lower Lal singi km.0/0 to 4/340(SH: C/O slab on U-shape drain at RD.3/397 to 4/009) (RHS) (Under OFC deposit)						Earnest Money	2000/-						
												Time limit	One month
						Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words								
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	24.00	Per square metre	250.00	Rupees Two hundred fifty only	6000							
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.52	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30360							
3	Steel reinforcement (Sail/RiNU/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	634.80	Per Kilogramme	90.00	Rupees Ninety only	57132							
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	93492						
2) The rates shall be including of all types of taxes including GST ectra)													
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021													
Percentage quoted Rate in Figures													
Percentage quoted Rate in Words													
Note: Rates quoted in figures & words are mandatory													
by the contractor otherwise the tender will be rejected.													

  
 Executive Engineer,  
 Una Division, HPPWD.

45

SCHEDULE OF QUANTITY						
					Estimated Cost	93150/-
Name of work :A/R & M/O to link road from Jhalera bridge to Una via lower Lal singi km.0/0 to 4/340(SH: C/O slab on U-shape drain at RD.3/455 to 3/461 & 3/462 to 3/465 (RHS) (Under OFC deposit)					Earnest Money	2000/-
					Time limit	One month
					RATE In	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	23.90	Per square metre	250.00	Rupees Two hundred fifty only	5975
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.50	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30250
3	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	632.50	Per Kilogramme	90.00	Rupees Ninety only	56925
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	93150
2) The rates shall be including of all types of taxes including GST etctra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

*Kishore*  
Executive Engineer,  
Una Division, HPPWD, Una

47

SCHEDULE OF QUANTITY							Estimated Cost	93495/-
Name of work :A/R & M/O to link road from Jhalera bridge to Una via lower Lal singi km.0/0 to 4/340(SH. C/O slab on U-shape drain at RD.3/465 to 3/468 & 3/482 to 3/488 (RHS) (Under OFC deposit)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	24 01	Per square metre	250.00	Rupees Two hundred fifty only	6003		
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.52	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30360		
3	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	634.80	Per Kilogramme	90.00	Rupees Ninety only	57132		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018							Total:	93495
2) The rates shall be including of all types of taxes including GST etetra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate In Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

*Kulabun*  
 Executive Engineer ,  
 Una Division, HPPWD. Dna


(48)

SCHEDULE OF QUANTITY							Estimated Cost	93150/-							
Name of work :A/R & M/O to link road from Jhalera bridge to Una via lower Lal singi km.0/0 to 4/340(SH: C/O slab on U-shape drain at RD.3/494.70 to 3/501.80 (RHS) (Under OFC deposit)							Earnest Money	2000/-							
														Time limit	One month
							Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
Figures	Words														
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	23.90	Per square metre	250.00	Rupees Two hundred fifty only	5975									
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.50	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30250									
3	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	632.50	Per Kilogramme	90.00	Rupees Ninety only	56925									
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018							Total:	93150							
2) The rates shall be including of all types of taxes including GST ectra)															
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021															
Percentage quoted Rate in Figures															
Percentage quoted Rate in Words															
Note: Rates quoted in figures & words are mandatory															
by the contractor otherwise the tender will be rejected.															

*Kumales*  
 Executive Engineer,  
 Una Division, HPPWD., Una

49

SCHEDULE OF QUANTITY						Estimated Cost	93712/-						
Name of work :A/R & M/O to link road from Jhalera bridge to Una via lower Lal singi km.0/0 to 4/340(SH: C/O slab on U-shape drain at RD.3/428 to 3/436(RHS) (Under OFC deposit)						Earnest Money	2000/-						
												Time limit	One month
						Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words								
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	24.00	Per square metre	250.00	Rupees Two hundred fifty only	6000							
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.56	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30580							
3	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	634.80	Per Kilogramme	90.00	Rupees Ninety only	57132							
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	93712						
2) The rates shall be including of all types of taxes including GST ectra)													
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021													
<b>Percentage quoted Rate in Figures</b>													
<b>Percentage quoted Rate in Words</b>													
<b>Note: Rates quoted in figures &amp; words are mandatory</b>													
<b>by the contractor otherwise the tender will be rejected.</b>													

  
 Executive Engineer,  
 Una Divn, HPPWD., Una


50

SCHEDULE OF QUANTITY						Estimated Cost	93657/-
Name of work :A/R & M/O to link road from Jhalera bridge to Una via lower Lal singi km.0/0 to 4/340(SH: C/O slab on U-shape drain at RD.3/421 to 3/425(RHS) (Under OFC deposit)						Earnest Money	2000/-
						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	24.00	Per square metre	250.00	Rupees Two hundred fifty only	6000	
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.55	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30525	
3	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	634.80	Per Kilogramme	90.00	Rupees Ninety only	57132	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	93657
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

*Kishan*  
Executive Engineer,  
Una Divn. HPPWD., Un

51

SCHEDULE OF QUANTITY						
					<b>Estimated Cost</b>	93655/-
Name of work :A/R & M/O to link road from Jhalera bridge to Una via lower Lal singi km.0/0 to 4/340(SH: C/O slab on U-shape drain at RD.3/450 to 3/455(RHS) (Under OFC deposit)					<b>Earnest Money</b>	2000/-
					<b>Time limit</b>	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	24 00	Per square metre	250.00	Rupees Two hundred fifty only	6000
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.55	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30525
3	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	634.78	Per Kilogramme	90.00	Rupees Ninety only	57130
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018					Total:	93655
2) The rates shall be including of all types of taxes including GST etcetra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						


  
 Executive Engineer ,  
 Una Divn. HPPWD.,Una

113

52

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	97958/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/117 to 0/135)(RHS) (Under OFC deposit)						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.505	Per cubic metre	550.00	Rupees Five hundred fifty only	828
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.000	Per square metre	170.00	Rupees One hundred seventy only	170
3	Providing and laying in position specified grade of reinforced cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.450	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	2160
4	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in posltion and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	9.48	Per quantial	10000.00	Rupees Ten thousand only	94800
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018					G.Total	97958
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Prncipal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						


  
 Executive Engineer  
 Una Divn.HP.PWD.,Una

115

53

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	98123/-
				Earnest money	2000/-
				Time limit	One month

<b>Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/140 to 0/155)(RHS) (Under OFC deposit)</b>						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentials. The rate includes sale tax octroi, royally,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.50	Per cublc metre	550.00	Rupees Five hundred fifty only	825
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)Including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royality,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.994	Per square metre	170.00	Rupees One hundred seventy only	169
3	Providing and laying in position specified grade of reinforced cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-In-charge .The rates are inclusive octroi, royality,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.506	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	2429
4	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other Incidentials as per the direction by the Engineer-in-charge .The rates are Inclusive octroi, royality,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	9.47	Per quantial	10000.00	Rupees Ten thousand only	94700
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	98123
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn. HP. PWD., Una


116

54

SCHEDULE OF QUANTITY				Estimated cost	98179/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/078 to 0/095) (RHS) (Under OFC deposit)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.50	Per cubic metre	550.00	Rupees Five hundred fifty only	825
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.988	Per square metre	170.00	Rupees One hundred seventy only	168
3	Providing and laying in position specified grade of reinforced cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.497	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	2386
4	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	9.48	Per quantial	10000.00	Rupees Ten thousand only	94800
				G.Total		98179
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						
2) The rates shall be including of all types of taxes including GST etc(tra)						
3) The bidder are requested to submit their bid as per notification Issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

  
 Executive Engineer  
 Una Divn.HP.PWD.,Una


117

SS

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	97902/-
				Earnest money	2000/-
				Time limit	One month

**Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/097 to 0/115)(RHS) (Under OFC deposit)**

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.50	Per cubic metre	550.00	Rupees Five hundred fifty only	825
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand) including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.994	Per square metre	170.00	Rupees One hundred seventy only	169
3	Providing and laying in position specified grade of reinforced cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.460	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	2208
4	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.47	Per quantial	10000.00	Rupees Ten thousand only	94700
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018 2) The rates shall be including of all types of taxes including GST etcra)				G.Total	97902
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words,					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn. HP. PWD. U.P.

128

58

SCHEDULE OF QUANTITY						
					Estimated Cost	93380/-
					Earnest Money	2000/-
					Time limit	One month
<b>Name of work : A/R &amp; M/O to link road from Jhalera to Una via lower lalsingl km.0/0 to 4/340(SH: Providing and marking of rumble strip lines 100mm at RD.0/800 to 1/605) (UnderOFC deposit)</b>						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and applying 2.5mm thick road marking strips(retro-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt, seals, oil grease and foreign material etc. complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	161.00	Per square metre	580.00	Rupees Five hundred eighty only	93380
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					Total:	93380
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

*Kewal*  
 Executive Engineer  
 Una Divn. HP. PW  
 Una

130

57


SCHEDULE OF QUANTITY						
					Estimated Cost	97440/-
Name of work : A/R & M/O to link road from Jhalera to Una via lower lalsingl km.0/0 to 4/340(SH: Providing and marking of rumble strip lines 100mm at RD.4/350 to 4/340) (UnderOFC deposit)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing amnd applying 2.5mm thick road marking strips(retroi-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic tyhermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt , seals , oil grease and foreign material etc. complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Governmmnt	168.00	Per square metre	580.00	Rupees Five hundred eighty only	97440
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)6(17)2/0212 dated 7.8.2018					Total:	97440
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor, otherwise the tender will be rejected.						

*[Signature]*  
 Executive Engineer  
 Una Divn.HP.PW  
 Una

58

SCHEDULE OF QUANTITY						Estimated Cost	99868/-
Name of work :A/R & M/O LIG 107 & 108 quarters Pooled accommdation at Rakkar colony Distt.Una (SH: Providing and laying interlock paver etc)(Phase-I)						Earnest Money	2000/-
						Time limit	One month
						RATE In	
Sl. No.	Description of work	Unit	RATE In		AMOUNT		
			Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.90	Per cubic metre	170.00	Rupees One hundred seventy only	663	
2	Providing and laying cement concrete 1:5:10(one cement:five sand: ten graded stone aggregate 40mm(forty millimetre) nominal size plain/reinforced concrete in open foundations and curing complete including cost of form work on ground or under water including pumping and bailing out water,dewatering, removal of sluch as required at site which may arrise at the time of laying under water complete in all heights/depths in Retaining wall and parapets etc.complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per drawing and HP.PWD., technical specification including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.30	Per cubic metre	2850.00	Rupees Two thousand eight hundred fifty only	23655	
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of requiredstrength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	75.50	Per square metre	850.00	Rupees Eight hundred fifty only	64175	

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	3.50	Per cubic metre	3250.00	Rupees Three thousand two hundred fifty only	11375
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99868
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una.

59

SCHEDULE OF QUANTITY						Estimated Cost	98919/-
Name of work : Restoration & Repair on Una Santoshgarh road km.0/0 to 14/0(SH: Removal of debries , silt, sludge & aggregate from drain at various RD,s)						Earnest Money	2000/-
						Time limit	One month
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Removal of debries, silt/ sludge & aggregate etc. upto a depth of 3.00 below ground level and disposed the silt upto dumping site eatly dressed the surface in all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	306.25	Per cubic metre	323.00	Rupees Three hundred twenty three only	98919	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	98919
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

  
 Executive Engineer  
 Una Divn.HP.PWD,  
 Una

60

SCHEDULE OF QUANTITY					Estimated Cost	99225/-
Name of work : Restoration & repair on Una Santoshgarh road km.0/0 to 14/0(SH: Maintenance of earthen shoulder at RD.8/0 to 9/350)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUNT
				Figures	Words	
1	Maintenance of earthen shoulder(stripping of excess soil) stripping excess soilk from the shoulder surface to achieve the approved level and compacting wityh plate compactor at OMC as per draweings and technical specification clause 1903 including entire cariage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	4725.00	Per square metre	21.00	Rupees Twenty one only	99225
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@(17)2/0212 dated 7.8.2018					Total:	99225
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected.						

*K. Singh*  
 Executive Engineer  
 Una Divn.HP.PW,  
 Una

61

SCHEDULE OF QUANTITY							
						Estimated Cost	99884/-
						Earnest Money	2000/-
Name of work :A/R & M/O residential building at HP.PWD., Electrical Sub-Division Una (SH:P/F aluminium work and WS & SI etc)						Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT		
			Figures	Words			
1 i)	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, aluminium snap beading for glazing/ paneling, C.P.brass/stainless steel screws , all complete as per architectural drawings and the directions of Engineer-in-charge(Glazing paneling and dash fasteners to be paid for separately For fixed portion powder coated aluminium(minimum thickness of powder coating 50 micron) including entire carriage of material within all leads and lifts and other incidentials as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	27.90	Kg	550.00	Rupees Five hundred fifty only	15345	
ii)	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the the directions of Engineer-in-charge(cost of aluminium snap beading shall be paid in basic item) with float glass panes of 5mm thickness(weight not less than 12.5kg/sqm) including entire carriage of material within all leads and lifts and other incidentials as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	24.33	Kg	550.00	Rupees Five hundred fifty only	13382	
2	Providing and fixing 12mm thick pre-laminated water proof particle board(decorative lamination on both sides) grade-I medium density flat pressed , three layer board FPT-1 or graded wood particle board FPT-1 conforming to IS: 3087, bonded with BWP type synthetic resin adhesive as per IS: 848 and pre-laminated conforming to IS: 12823, Grade_I, Type-UU marjed including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Sqm	1550.00	Rupees One thousand five hundred fifty only	3100	

*Handwritten mark*

3	Providing and fixing glazing with glass panes of 5.50mm(five point fifty millimetre) thickness(weight not less than 13.75kilogramme square metre in aluminium door, window , ventilator shutters make it Hindcol Co.Jindal Indian aluminium Co. and partition etcetra with PVC/neoprens gasket etcetra complete upto floor all level/height as per the architectural drawings including entire carnage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	2.00	Sqm	650.00	Rupees Six hundred fifty only	1300
4	Providing and fixing Non woven carpet flooring including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.22	Sqm	640.00	Rupees Six hundred forty only	12301
5	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately including carriage of materials within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	2.00	Each	3500.00	Rupees Three thousand five hundred only	7000
6	Providing and fixing PVC plastic seat cover including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.00	each	750.00	Rupees Seven hundred fifty only	2250
7	Providing and fixing vitreous china wash basin with single hole for pillar tap with CI or MS brackets painted white including cutting holes and making good the same but excluding fittings 630x450mm . including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.000	each	2200.00	Rupees Two thousand two hundred only	4400
8	Providing and fixing vitreous china pedestal for wash basin complete recessed at the back for the reception of pipes and fittings including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	1000.00	Rupees One thousand only	2000

*[Handwritten signature]*


9	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (light grade) tube fittings and clamps including making good the wall ceiling and floor 15mm nominal size including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.00	Rmt	300.00	Rupees Three hundred only	7500
10	Chormoulm plates brass bib taps with cap stain head 15mm dia weight 400gms including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	each	550.00	Rupees Five hundred fifty only	2200
11	P/F CP brass soad dish including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	250.00	Rupees Two hundred fifty only	500
12	P/F 750x12mm towel rail-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	350.00	Rupees Three hundred fifty only	700
13	P/F brass angle valve 15mm without nuts and pipes -including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.00	each	650.00	Rupees Six hundred fifty only	3250
14	P/F hydraulic door closer duly IS marked .including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	each	800.00	Rupees Eight hundred only	800
15	Providing and fixing PVC water storage tank ISI marked of approved brand and make (Sintex or equivalent) with 40mm (forty milimetre) nominal bore galvanised mild steel scour tube with fitting, 25mm(twenty five nominal bore galvanised mild steel over flow tube with fittings and mosquito proof coupling of approved municipal design 15mm (fifteen milimetre) nominal bore ball valve and cover with locking arrangement providing pads of required sizes for inlet and outlet etc. complete including hoisting at roof level height 1000ltres.net capacity tank including carriage of material within all leads and lifts	1.00	each	9500.00	Rupees Nine thousand five hundred only	9500
16	Providing and fixing 60 interlocking paver blocks from footpath/central verge including removal of rubbish etc disposal of unserviceable material to the dumping ground for which payment shall be made separately and stacking of serviceable material wityhin 50metre lead including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	49.50	sqm	55.00	Rupees Fifty five only	2723

17	Laying of Old cement concrete interlocking paver blocks of anyt design, fshape laid in required line, level , curvature, colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete (old CC paver blocks shall be supplied by the departament free of cost) including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	49.50	sqm	235.00	Rupees Two hundred thirty five only	11633
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Secy.to the Govt. of HP vide letter No.PBW(B)0(17)2/0212 dated 7.8.2018				G.Total	99884
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected.					

n  
P.

  
Executive Engineer  
Una Divn.HP.PWD  
Una.

SCHEDULE OF QUANTITY							
						Estimated Cost	65737/-
Name of work : Repair work of HP.PWD., 15th Circle building Una (SH: Repair of toilet block)						Earnest Money	2000/-
						Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT		
			Figures	Words			
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	56.28	P/sqm.	45	Rupees Forty five	2533	
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqmincluding grouting the joints with white cement and matching pigments etc., complete of joints . Size of Tile 600x600 mm.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.36	P/sqm.	1100.00	Rupees One thousand one hundred only	33396	
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm. including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.92	P/sqm.	1150.00	Rupees One thousand one hundred fifty only	29808	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						G.Total	65737
2) The rates shall be including of all types of taxes including GST ectra)							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

63

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	99854/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & M/O various roads under Mehatpur Sub-Division at Rakkar section(SH: Providing and fixing sign board and painting or bridges etc)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs scratches complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	312.2	Per square metre	6.00	Rupees Six only	1873
2	Providing ,applying & finishing with apex paint( two or more coats) at all locvations prepared and applied as per manufactures specification including appropriate priming coat, preparation of surface etc. complete and direction of E-in-charge including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	312.20	Per square metre	132.15	Rupees One hundred thirty two and paise fifteen only	41257
3	Supplying and fixing of direction and place identification sign boards as per IRC: 67 made of 1.5mm thick MS sheeting vide clause 1701.23 with area exceeding 0.90sqm. supported on 40mm dia pipe , painted with red lead primer as approved drawing and technical specifications clause 1701(1200mmx900mm) size boards including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	each	5350.00	Rupees Five thousand three hundred fifty only	32100
4	Writing letter of figures on anty surface with black japan paint(stop comes hyphen and the like not to be measured and paid for separately including carriage of materials within all leads and lifts	24624	P/letter P/cm.heig ht	1.00	Rs.One only	24624
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					G.Total	99854
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected.						

*K. S. S. S.*  
 Executive Engineer  
 Una Divn. HP. PWD  
 Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99636/-
					Earnest Money	2000/-
					Time limit	One month
	Name of work :A/R & M/O residential building for pooled accomodation in Type III Qtr No. 17 and outer paint Type III Qtrs in D C colony Una (SH: Providing and Fixing PVC panelling etc Bed room 2 and 3(Part-3)					
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Providing and Fixing PVC panelling tiles wall lining including carriage of material with in all lead and lifts as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	83.03	Sqm	1200.00	Rupees One thousand two hundred only	99636
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	99636
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


*Koushik*  
 Executive Engineer  
 Una Divn.HP.PWD.,  
 Una.

65

SCHEDULE OF QUANTITY						
					Estimated Cost	99800/-
Name of work :A/R & M/O residential building Una (SH: P/F floor tile and other maintenance for Type-III qtr. No.17 DC colony Una)(Part-I)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., completing with bricks of class designation Description 11.41.2 Size of Tile 1200x600 mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	43.92	Sqm	1100.00	Rupees One thousand one hundred only	48312
2	Providing and fixing 19mm thick HDHMR board covered with lamination on both side including cutting of board as per required size and tapes, fevicol, nails and all other necessary arrangements to fix the boards on wall for panneling and for ward robe etcetra as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Sqm	1780.00	Rupees One thousand seven hundred eighty only	28302
3	Glazing with glass panes of 4mm thickness (weight not less than 10.00 kg/sqm. as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.36	Sqm	850.00	Rupees Eight hundred fifty only	2856

4	Providing and fixing fly proof galvanised MS wire gauge designation 140 G (one hundred forty G) with wire of dia 0.56mm to windows and clerstory windows including 60 x 20mm ( beading upto any floor level/height as per the direction by the Engineer in charge.including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.60	Sqm	800.00	Rupees Eight hundred only	2880
5	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	2200.00	Rupees Two thousand two hundred only	2200
6	P/F automatic flushing cistern with a pair of C.I. Or M.S. brackets complete with fittings including C.I. Syphonic apparatus, mosquito proof lid, C.P. Brass unions and coupling for connections with inlet, outlet and overflow pipes including cutting holes and making good the same (overflow pipe to be measured and paid for separately) :-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1500.00	Rupees One thousand five hundred only	1500
7	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings:-630mmx450mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1,800.00	Rupees One thousand eight hundred only	1800
8	Providing and fixing vitreous China pedestal for wash basin complete recessed at the back for the reception of pipes and fittings .including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1000.00	Rupees One thousand only	1000
9	Providing and fixing to wall ceiling and floor galvanised mild-steel tubes (Medium grade) tube fitting and clamps including making good the wall, ceiling and floor. 15mm nominal bore-including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Roof	225	Rupees Two hundred twenty five only	3150

10	ii) Providing and fixing to wall ceiling and floor galvanised mild steel tubes (Medium grade) tube fitting and clamps including making good the wall, ceiling and floor:-20mm nominal bore including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	12.00	Rmt	250	Rupees Two hundred fifty only	3000
11	Chromium plated brass bib taps with cap stain heads. i) 15 mm dia. Weight 400 gms including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Each	800.00	Rupees Eight hundred only	4800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99800
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD.,  
 Una

105

66


<b>SCHEDULE OF QUANTITY</b>				Estimated cost	99991/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & M/O residential building Una SH: Repair of Plaster, painting and other maintenance for Type - III Qtr No. 15 DC colony Una (Phase-I)

S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres lead (wooden / concrete joists to be measured and paid for separately) 20210100 For thickness of tiles upto 25mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	13.50	Per square metre	40.00	Rupees Forty only	540
2	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.96	Per square metre	150.00	Rupees One hundred fifty only	1944
3	Applying Birla white wall care putty over plaster/other surface after thoroughly brushing the surface free from mortar drops durt loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	23.30	Per square metre	55.00	Rupees Fifty five only	1282
4	Applying one coat of AcrylicWashable emulsion Spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat i/c necessary putty to give smooth even surface, sand papered smooth completeincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	131.48	Per square metre	65.00	Rupees Sixty five only	8546
5	Providing and fixing 25mm diameter curtain rods with brackets, plugs etc. where ever required. First class indian teak wood. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.60	Per Running metre	200.00	Rupees Two hundred only	2520

6	Providing and fixing 40mm(forty millimeter) thick 2 <sup>nd</sup> class deodar wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85-G(eighty five) with wire of dia 0.56mm(zero point fifty six millimeter) for doors windows clerestory windows including bright finished /black enameled iron butt hinges with necessary screws including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.18	Per square metre	2800.00	Rupees Two thousand eight hundred only	6104
7	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm thick 2nd class deodar wood.including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.18	Per square metre	3800.00	Rupees Three thousand eight hundred only	8284
8	Providing and fixing 10mm(ten millimetre) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nitco /Kajaria (600x600x10mm)(six hundred into six hundred into ten millimetre)manufactured of approved shade and colour in flooring treads of steps and landing laid on a bed of 12mm(twelve millimetre) thick cement mortar 1:3( one cement: three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment to match the shade of tiles as required complete including carriage of materials within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	8.42	Per Square Metre	1100.00	Rupees One thousand one hundred only	9262
9	Providing and laying Duro stone vetrified tiles Kajaria,Nitco,Somany quality orient ,Rak by the Engineer-in-charge (600x600mmx8mm)(three hundred into three hundred into eight millimetre) in grey/coloured of required shade in skirting risers of steps and dado on 12mm thick cement mortar 1:3(1cement:3sand)laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.03	Per square metre	1150.00	Rupees One thousand one hundred fifty only	12685
10	Providing and fixing aluminum handles anodized transparent or dyed to required colour and shade with necessary screws etc complete including carriage of materials with all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. (a)125mm(one hundred twenty five millimetre)	10.00	Each	80.00	Rupees Eighty only	800
11	Providing and fixing aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etc.complete including carriage of materials with all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. . (a) 200x10mm (two hundred into ten millimetre)	10.00	Each	100.00	Rupees One hundred only	1000

17	Providing and laying granite stone in flooring 20mm(twenty millimetre) (average) thickness base of cement mortar 1:3(one cement:three sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone including rubbing and polishing complete 20mm(twenty millimetre) thick Including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.05	Per square metre	3000.00	Rupees Three thousand only	9150
18	Providing and fixing 19mm thick HDHMR board covered with lamination on both side including cutting of board as per required size and tapes, fevicol, nails and all other necessary arrangements to fix the boards on wall for paneling and for ward robe etcetra as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	18.75	Per square metre	1780.00	Rupees One thousand seven hundred eighty only	33375
19	Providing and fixing vitreous china pedestal type water closet (European type WC pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 ( 1cement : 1 sand )( Seat and over to be measured and paid for separately ) (ii) Anglo Indian WC (Universal ) No.2090 of Cera or its equivalent closet including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	each	4500.00	Rupees Four thousand five hundred only	4500
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99991
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

106

67


<b>SCHEDULE OF QUANTITY</b>				Estimated cost	99495/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & M/O residential building Una SH: Painting and WS work for Type - III Qtr No. 15 DC colony Una (Phase-II)

S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Painting two coat(excluding priming coat)on wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	51.08	Per square metre	65.00	Rupees Sixty five only	3320
2	Providing and fixing PVC wall panelling and roof panelling including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	58.20	Per square metre	1200.00	Rupees One thousand two hundred only	69840
3	Providing and fixing glazing with glass panes of 4mm thickness (weight not less than 10kg/sqm.)including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.10	Per square metre	650.00	Rupees Six hundred fifty only	1365
4	Providing and fixing fly proof galvanized MS wire gauge designation 140 G (one hundred forty G) with wire of dia 0.56mm to windows and clerstory windows including 60 x 20mm ( beading upto any floor level/height as per the direction by the Engineer in charge including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.80	Per square metre	600.00	Rupees Six hundred only	6480
5	Providing and fixing to wall ceiling and floor galvanized mild steel tubes (Medium grade) make of B.S.T.Jindal(Hissar) Tata steel tubes Ltd. prakash surya tube fittings and clamps Including making good the wall ceiling and floor 15mm(fifteen millimetre) nominal bore ncluding carriage of material within all leads and lifts and other incidentalsThe rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Per Running metre	325.00	Rupees Three hundred twenty five only	1950
6	Providing and fixing to wall ceiling and floor galvanized mild steel tubes (Medium grade) make of B.S.T.Jindal(Hissar) Tata steel tubes Ltd. prakash surya tube fittings and clamps including making good the wall ceiling and floor 20mm(twenty millimetre) nominal bore ncluding carriage of material within all leads and lifts and other incidentalsThe rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.00	Per Running metre	350.00	Rupees Three hundred fifty only	2100

7	Providing and fixing Chromium plated brass bib taps with cap stain heads. i) 15 mm dia. Weight 400 gms including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.00	Each	800.00	Rupees Eight hundred only	2400
8	Providing and fixing brass angle valve 15 mm without nuts and pipes including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.00	Each	800.00	Rupees Eight hundred only	2400
9	Providing and fixing hydraulic door closer duly I.S marked including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	1000.00	Rupees One thousand only	1000
10	Providing and fixing 450x600mm bevelled edge mirror including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	650.00	Rupees Six hundred fifty only	650
11	Providing and fixing 750x12mm towel rail including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	450.00	Rupees Four hundred fifty only	450
12	Providing and fixing C.P. Shelf with plate glass 600 X 120 mm with guard rail of standard size and bracket including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	160.00	Rupees One hundred sixty only	160
13	Providing and fixing CP brass soap dish including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	250.00	Rupees Two hundred fifty only	500
14	Providing and fixing 32mm dia lead waste pipes for wash basin or sink including brass check nut including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.00	Each	150.00	Rupees One hundred fifty only	300
15	Providing and fixing CP waste including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	Each	150.00	Rupees One hundred fifty only	300
16	Providing and fixing PVC connection for wash basin/sink including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Each	120.00	Rupees One hundred twenty only	480
17	Providing and fixing stainless steel A ISI 304 ( 18/8) kitchen sink of approved make of AMC, Unik, Diamond, Neelkanth sink 610x460mm(six hundred ten into four hundred sixty millimetre) with bowl depth 200mm(two hundred millimetre) with CP waste with CI or MS brackets painted white including cutting holes and making good the same but excluding fitting including carriage of material with in all leads and lifts and other incidentials .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	each	2500.00	Rupees Two thousand five hundred only	2500

18	Providing and fixing 15mm(fifteen millimetre) Mixer for Kitchen sink with casted swinging spout at top Kingston, Gem, Parko Techno, JAL, ESS, JAGUAR, Seiko including carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	2800.00	Rupees Two thousand eight hundred only	2800
19	Providing and fixing C.P. Brass shower rose with 15mm or 20mm inlet ) 150mm dia including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	Each	500.00	Rupees Five hundred only	500
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99495
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted ,In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn.HP.PWD,  
 Una

SCHEDULE OF QUANTITY							Estimated Cost	99700/-
Name of work : Restoration of rain damage to Path from the house of Dr. Attri etc. to house of Shri Ram Nutri in ward No.1 in village Arniala upper MC Una(SH: Providing and laying interlocking paver blocks km.0/040 to 0/080 )(Under VKVNY/MLALAD)							Earnest Money	2000/-
							Time limit	One month
							RATE In	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	116.00	Per square metre	800.00	Rupees Eight hundred only	92800		
2	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.50	Per cubic metre	4600.00	Rupees Four thousand six hundred only	6900		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	99700	
2) The rates shall be including of all types of taxes including GST etetra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate In Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

*Kundan*  
 Executive Engineer  
 Una Divn.HP, PWD,  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	99746/-
Name of work : Restoration of rain damage to Path from the house of Dr. Attri etc. to house of Shri Ram Mutri in ward No.1 in village Arniala upper MC Una(SH: Providing and laying interlocking paver blocks km.0/080 to 0/120 )(Under VKVNY(MLALAD)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	116.00	Per square metre	800.00	Rupees Eight hundred only	92800	
2	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.51	Per cubic metre	4600.00	Rupees Four thousand six hundred only	6946	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						Total:	99746
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7. 10.2021							
Percentage quoted Rate In Figures							
Percentage quoted Rate In Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

*Kingdon*  
 Executive Engineer  
 Una Divn.HP.PWD,  
 Una

70 ✓

SCHEDULE OF QUANTITY						
					Estimated Cost	99845/-
Name of work :Restoration of rain damages of link road to Harizan Basti Dehlan km.0/0 to 0/800(SH: C/O U-shape drain and P/L RCC NP-2 pipe with chambers in RD.0/720 to 0/735(GP Dehlan) Deposit work					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.15	Per cubic metre	170.00	Rupees One hundred seventy only	2066
2	Demolishing cement concrete manually by mechanical means including disposal of material within any leads and lifts in cement concrete 1:3:6 .The rates are inclusive octroi, royalty, malkhana, toll tax sale tax or other taxes imposed by the Govt.	4.05	Per cubic metre	550.00	Rupees Five hundred fifty only	2228
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.	2.03	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	6801
4	Providing and laying non-pressure NP-2 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : two fine sand) including testing of joints etc. complete 450mm dia RCC pipe including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	Per Running metre.	1800.00	Rupees One thousand eight hundred only	27000
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.50	Per cubic metre	6000.00	Rupees Six thousand only	45000


6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	192.00	Per kilogramme	98.00	Rupees Ninety eight only	18816
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99845
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn. HP. P.W.D.  
 Una

PS

71


SCHEDULE OF QUANTITY						
					Estimated Cost	95411/-
	Name of work :Construction of link road with Retaining wall in Harizan Basti Ward No.8 GP Behdala Block Una Tehsil & Distt.Una (HP)				Earnest Money	2000/-
	(Phase-I)(Deposit work)				Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.24	Per cubic metre	170.00	Rupees One hundred seventy only	2081
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.	27.20	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	91120
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.00	Each	170.00	Rupees One hundred seventy only	2210
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	95411
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer,  
 Una Divn.HP.PWD.,Una

87

73

SCHEDULE OF QUANTITY						
					Estimated Cost	95751/-
Name of work :Construction of link road with Retaining wall in Harizan Basti Ward No.8 GP Behdala Block Una Tehsil & Distt.Una (HP) (Phase-III)(Deposit work)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.24	Per cubic metre	170.00	Rupees One hundred seventy only	2081
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.	27.20	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	91120
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentials .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	Each	170.00	Rupees One hundred seventy only	2550
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	95751
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

  
 Executive Engineer ,  
 Una Divn.HP.PWD.,Una

74

SCHEDULE OF QUANTITY					Estimated Cost	99984/-
Name of work : A/R & M/O Type-III HP.PWD., Qtr. No.1 to 4 pooled accommodation at Rakkar colony					Earnest Money	2000/-
Una (SH: Repair of roof with water proofing compound etc)					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.00	Per square metre	160.00	Rupees One hundred sixty only	480
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.50	Per running metre	250.00	Rupees Two hundred fifty only	625
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall beupto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	148.69	Pe square metre	665.00	Rs.Six hundred sixty five only	98879
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	99984
2) The rates shall be including of all types of taxes including GST etctra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. ef HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate-in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

Executive Engineer  
Una Divn.HP.PWD.,Una



SCHEDULE OF QUANTITY						
					Estimated Cost	99991/-
	Name of work : A/R & M/O Type-III HP.PWD., Qtr. No.5 to 8 pooled accommodation at Rakkar colony				Earnest Money	2000/-
	Una (SH: Repair of roof with water proofing compound etc)				Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.00	Per square metre	160.00	Rupees One hundred sixty only	480
2	Providing and fixing on wall face unplastiscised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.50	Per running metre	250.00	Rupees Two hundred fifty only	625
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscocty 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	148.70	Pe square metre	665.00	Rs.Six hundred sixty five only	98886
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99991
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
Executive Engineer  
Una Divn.HP.PWD.,Una


<b>SCHEDULE OF QUANTITY</b>				Estimated cost	95743/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & M/O Qtr No.6 Type-I quarter Pooled accommodation at Rakkar colony Distt.Una (SH:Repair of wood work, distempering , painting etc)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought, framed and fixed in position 2nd class deodar wood including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.041	Per cubic metre	70000.00	Rupees Seventy thousand only	2870
2	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws 40 mm(forty millimetre ) thick 2nd class deodar wood including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	4.95	Per Square metre	3800.00	Rupees Three thousand eight hundred only	18810
3	Providing and fixing 40mm thick (forty millimetre ) second class deodar wood frame fly wire mesh shutters using galvanized MS wiregauge of I.S.gauge designation 85G(eighty five )with wire of dia 0.56mm(zero point five six millimetre)for doors windows and clerestory windows including bright finished black enameled iron hinges with necessary screws including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	3.65	Per Square metre	2800.00	Rupees Two thousand eight hundred only	10220
4	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning of all dirt dust and other foreign matter sand papering and stopping with enamel paint other than white.including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	33.74	Per square metre	55.00	Rupees Fifty five only	1856
5	Removiding dry oil bound by washing and scraping and sand papering the wall surface smooth including n necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	130.87	Per square metre	7.00	Rupees Seven only	916
6	Applying Birla white wall care putty over plaster/other surface after thoroughly brushing the surface free from mortar drops durt loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	130.87	Per square metre	50.00	Rupees Fifty only	6544

*(Handwritten signature)*

7	Distemperring(two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade after thoroughly brushing the surface clean of all grease dirt, loose, pieces of scales and also including preparing the surface even and sand papered smooth including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	130.87	Per square metre	50.00	Rupees Fifty only	6544
8	Providing and laying Duro stone vetrified tiles Nitco/orient/kajaria equivalent (600x600x10mm)(six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring treads of steps and landing laid on a bed of 12mm(twelve millimetre) thick cement mortar 1:3( one cement: three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment to match the shade of tiles as required complete including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government...	23.53	Per Square Metre	1150.00	Rupees One thousand one hundred fifty only	27060
9	White glazed tiles 6mm thick in skirting risers of steps and dado 12mm thick cement mortar 1:3(1cement:3sand) jointed with cement slurry including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	9.21	Per square metre	800.00	Rupees Eight hundred only	7368
10	Providing and fixing brass bib tap(superior or heavy type) 15mm dia including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.00	each	600.00	Rupees Six hundred only	1800
11	Providing and fixing CP brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	550.00	Rupees Five hundred fifty only	550
12	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (Medium grade) make of B.S.T. Jindal(Hissar) Tata steel tubes l.t.d. prakash surya tube fittings and clamps including making good the wall ceiling and floor 15mm(fifteen millimetre) nominal bore including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	7.50	Per Running metre	300.00	Rupees Three hundred only	2250
13	Repair to plaster in patches of 2.50sqm and under 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20mtr. with Cement mortar 1:4 (1cement:4sand) including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	14.72	Per square metre	160.00	Rupees One hundred sixty only	2355
14	Providing and fixing PTMT coloured/white PVC low level dual flushing cistern with a pair of PVC/CI/MS bracket complete with fittings including PVC syphonic apparatus such as load valve, less syphon, 15mm(fifteen millimetre) nominal size PVC ball valve with polythene float, PVC handle, union and coupling for connection with inlet, outlet and overflow pipes 40mm(forty millimetre) dia PVC flush bend with cistern and closet over flow pipe to be measured and paid for separately) including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	1600.00	Rupees One thousand six hundred only.	1600



15	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government...	1.00	Each	2500.00	Rupees Two thousand five hundred only	2500
16	Providing and fixing vitreous china wash basin with single hole for pillar tap with CI or MS brackets painted white including cutting holes and making good the same but excluding fittings flat back 550mmx400mm (five hundred fifty into four hundred millimetre) No. 1001 of hindware or its equivalent in white shade Including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	2500.00	(Rupees Two thousand five hundred only.	2500
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	95743
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn. HP. PWB.  
 Una

<b>SCHEDULE OF QUANTITY</b>				Estimated cost	99982/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: A/R & M/O Qtr No.4 Type-I quarter Pooled accommodation at Rakkar colony Distt.Una (SH:Repair of wood work, distempering , painting etc)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.038	Per cubic metre	70000.00	Rupees Seventy thousand only	2660
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary serews, including panelling , all complete as per direction of Engineer-incharge Kiln seasoned and chemically treated sheesham wood 30 mm thick shutter including entire carriage of material within all leads and lifts and	5.53	Per Square metre	3800.00	Rupees Three thousand eight hundred only	21014
3	P/F wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge of average width of aperture 1.4mm both side direction with wire of dia 0.63 mm for doors, windows and celerestory windows i/e bright finished black enamelled iron hinges with necessary screws. Hollock woods 30 mm thick	3.17	Per Square metre	2800.00	Rupees Two thousand eight hundred only	8876
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work. including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	33.74	Per square metre	65.00	Rupees Sixty five only	2193
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	130.87	Per square metre	7.00	Rupees Seven only	916
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand andmanufacturer, over the plastered wall surface to prepare the surface even and smooth completeincluding entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	85.00	Per square metre	60.00	Rupees Sixty only	5100

*(Handwritten signature)*

7	Distemping with oil bound washable distemper of 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer.including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other	130.87	Per square metre	55.00	Rupees Fifty five only	7198
8	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqmincluding grouting the joints with white cement and matching pigments etc., complete of joints . Size of Tile 600x600 mm. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	16.26	Per Square Metre	1100.00	Rupees One thousand one hundred only	17886
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqmincluding grouting the joints with white cement and matching pigments etc., complete of joints . Size of Tile 300x300 mm. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.45	Per square metre	850.00	Rupees Eight hundred fifty only	13133
10	Providing and fixing brass bib tap ( superior or heavy type)15mm dia i/c carriage of material within all lead & lifts.	5.00	each	550.00	Rupees Five hundred fifty only	2750
11	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.00	each	550.00	Rupees Five hundred fifty only	1100
12	Providing and fixing G.I./ PE-AL-PE/ PP-R pipes. 15 mm dia nominal bore15 mm nominal bore. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.00	Per Running metre	300.00	Rupees Three hundred only	3000

6

13	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	24.00	Per square metre	160.00	Rupees One hundred sixty only	3840
----	---	-------	------------------	--------	-------------------------------	------

6

14	Renewing glass panes, with wooden fillets wherever necessary Float glass panes of nominal thickness 4 mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.41	Per square metre	550.00	(Rupees Five hundred fifty only	226
15	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	1.00	Each	4000.00	Rupees Four thousand only	4000
16	Providing and fixing kitchen sink with C.I. Or M.S brackets, painted white including cutting holes in walls and making good the same but including fittings 450mm x 350 x 150 mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	each	2500.00	(Rupees Two thousand five hundred only.	2500
17	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 450x300 mm with a pair of 15 mm C.P. brass pillar taps. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	each	1800.00	(Rupees One thousand eight hundred only	1800
18	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including Bend, jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.20	each	250.00	(Rupees Two hundred fifty only	1550

6

19	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 110 mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.00	each	120 00	(Rupees One hundred twenty only)	240
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018				G.Total	99982
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	By the contractor otherwise the tender will be rejected.					

  
 Executive Engineer  
 Una Divn. HP. PWD.,  
 Una

78

SCHEDULE OF QUANTITY						Estimated cost	99954/-
						Earnest money	2000/-
						Time limit	One month
Name of Work: A/R & M/O Qtr No.5 Type-I quarter Pooled accommodation at Rakkar colony Distt.Una (SH:Repair of wood work, distempering , painting etc)							
S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)	
				Figures	Words		
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.023	Per cubic metre	70000.00	Rupees Seventy thousand only	1610	
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, including panelling , all complete as per direction of Engineer-incharge Kiln seasoned and chemically treated sheesham wood 30 mm thick shutter including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.97	Per Square metre	3800.00	Rupees Three thousand eight hundred only	15086	
3	P/F wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge of average width of aperture 1.4mm both side direction with wire of dia 0.63 mm for doors, windows and clerestory windows i/c bright finished black enamelled iron hinges with necessary screws. Hollock woods 30 mm thick	2.70	Per Square metre	2800.00	Rupees Two thousand eight hundred only	7560	
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work. including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	33.74	Per square metre	65.00	Rupees Sixty five only	2193	
5	Removing dry or oil bound distemper, water proofing cement paint and the like by serapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	130.87	Per square metre	7.00	Rupees Seven only	916	

6

6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	130.87	Per square metre	60.00	Rupees Sixty only	7852
7	Distempering with oil bound washable distemper of 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	130.87	Per square metre	55.00	Rupees Fifty five only	7198
8	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete of joints. Size of Tile 600x600 mm. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	23.53	Per Square Metre	1100.00	Rupees One thousand one hundred only	25883
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete of joints. Size of Tile 300x300 mm. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	16.20	Per square metre	850.00	Rupees Eight hundred fifty only	13770
10	Providing and fixing brass bib tap ( superior or heavy type) 15mm dia i/c carriage of material within all lead & lifts.	5.00	each	550.00	Rupees Five hundred fifty only	2750
11	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.00	each	550.00	Rupees Five hundred fifty only	1100

12	Providing and fixing G.I./ PE-AL-PE/ PP-R pipes. 15 mm dia nominal bore 15 mm nominal bore. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.00	Per Running metre	300.00	Rupees Three hundred only	1800
13	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.00	Per square metre	160.00	Rupees One hundred sixty only	1920
14	Renewing glass panes, with wooden fillets wherever necessary Float glass panes of nominal thickness 4 mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.41	Per square metre	550.00	(Rupees Five hundred fifty only	226
15	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	1.00	Each	4000.00	Rupees Four thousand only	4000
16	Providing and fixing kitchen sink with C.I. Or M.S brackets, painted white including cutting holes in walls and making good the same but including fittings 450mm x 350 x 150 mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	each	2500.00	(Rupees Two thousand five hundred only.	2500
17	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 450x300 mm with a pair of 15 mm C.P. brass pillar taps. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	each	1800.00	(Rupees One thousand eight hundred only	1800

18	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including Bend, jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or <u>other taxes imposed by the Government.</u>	6.20	each	250.00	(Rupees Two hundred fifty only	1550
19	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised RigidPVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382,leaving 10 mm gap for thermal expansion. 110 mm including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.00	each	120.00	(Rupees One hundred twenty only	240
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7 8.2018				G.Total	99954
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


  
Executive Engineer

Una Divn.HP.PWD.,

Una

79

SCHEDULE OF QUANTITY						
					Estimated Cost	99000/-
Name of work : A/R & M/O link road from Bangarh to Nangran road km. 0/000 to 8/200 (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains from RD.4/500 to 6/0)					Earnest Money	2000/-
					Time limit	<del>One Month</del>
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock( where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	99.00	Per Hour	1000.00	Rupees One thousand only	99000
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018					Total	99000
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
4) The bidder should have his own machinery.						
5) The bidder must have provide machinery immediately as an when required.						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una