

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **20/03/2026** up to 10.30 A.M. and will be opened on the same day at **11.00 A.M.** in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **16/03/2026** up to 5.00 PM and the tender form can be had from this office on **18/03/2026** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I., HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	Repair and restoration of rain damages on Harlog Kuh Trifalghat roads Km. 0/00 to 20/00. (SH:- Re-construction of R/wall at RD's 7/330 to 7/351) (Under PDNA-2023).	4,91,692/-	10000/-	350	One month
2	Repair and Restoration of rain damages on Harlog Kuh Trifalghat road Km. 0/00 to 20/00. (SH:- Re-Construction of R/wall at RD's 3/900 to 3/921)(Under PDNA2023).	4,86,762/-	10000/-	350	One month
3	Repair and restoration of rain damages on Harlog Kuh Trifalghat roads Km. 0/00 to 20/00. (SH:- Re-construction of R/wall at RD's 7/315 to 7/323) (Under PDNA-2023).	4,92,854/-	10000/-	350	One month
4.	Repair and restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Re-construction of R/wall at RD's 3/870 to 3/873.45) (Under PDNA-2023).	99,423/-	2000/-	350	One month
5	Repair and maintenance of Police building (Old Sadar Police Station building) at Bilaspur (H.P.) (SH:- Removing, painting, distemping and repair of plaster etc.).	74,047/-	1600/-	350	One month
6	Repair and restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Re-construction of R/wall at RD's 3/860 to 3/863.45). (Under PDNA-2023).	99,106/-	2000/-	350	One month
7	Repair and restoration of rain damages on link road from Lower Sungal to Planighat Km. 0/00 to 4/885. (SH:- Re-construction of B/wall at RD's 4/600 to 4/640). (Under PDNA2023).	4,86,991/-	10000/-	350	One month
8	Repair and restoration of rain damages on Chandigarh Mandi Manali road Km. 140/0 to 146/0, (SH:- Re-construction of B/wall at RD.143/280 to 143/310) (UNDER PDNA2023).	4,99,894/-	10000/-	350	One month
9	Repair and restroation of rain damages on link road from Lower Sungal to Planighat Km. 0/00 to 4/885. (SH :-Re-construction of R/wall at RD 4/840 to 4/860). Under PDNA 2023	4,82,364/-	10000/-	350	One month
10	Repair and restroation of rain damages om Panoh Harlog Samaila road Km.0/00 to 10/00. (SH:-Re-construction of B/wall at RD 5/870 to 5/878) Under PDNA 2023.	99,483/-	2000/-	350	One month

11	Repair and restoration of rain damages on various road under Beri Sub Division. (SH:-Hiring of Excavator-cum-loader/Hydraulic Excavator).	97,900/-	2000/-	350	One month
12	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km.0/00 to 10/00.(SH:-Re-construction of B/wall at RD 5/860 to 5/868). Under PDNA 2023.	99,800/-	2000/-	350	One month
13	Repair and restoration of rain damages on Chandigarh Mandi Manali road Km.146/00 to 156/750. (SH:- Re-construction of crash barrier Km . 155/090 to 155/135 & 155/350 to 155/425). Under PDNA 2023.	4,82,452/-	10000/-	350	One month
14	Repair and Restoration of rain damages on Chandigarh Mandi Manali road km.140/00 to 146/00. (SH:- Re-construction of R/wall at RD 144/890 to 144/915).Under PDNA 2023.	4,79,338/-	10000/-	350	One month
15	A/R & M/O various road under Sub Division No.II HP.PWD Bilaspur. (SH;-Repair of 6 Nos. Rain shelter painting, distempering and emulsion paint etc.)	97,522/-	2000/-	350	One month
16	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of R/wall at RD's 6/455 to 6/466.30) Under PDNA 2023.	4,98,971/-	10000/-	350	One month
17	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/0 to 10/0 .(SH:- Re-construction of R/wall at RDs 5/650 to 5/658.10).Under PDNA 2023.	4,98,580/-	10000/-	350	One month
18	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at RD's 15/880 to 15/610).	4,89,512/-	10000/-	350	One month
19	Repair and Restoration of rain damages on Harlog Kuh Trifalghat road Km. 0/00 to 20/00. (SH:- Formation cutting at RD. 2/360 to 2/426). (UNDER PDNA 2023).	98,728/-	2000/-	350	One month
20	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at RD's 5/600 to 5/630) Under PDNA 2023).	4,90,146/-	10000/-	350	One month
21	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at RD's 3/180 to 3/186) Under PDNA 2023).	99,891/-	2000/-	350	One month
22	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at RD's 5/700 to 5/578) (Under PDNA 2023).	4,86,871/-	10000/-	350	One month
23	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at RD's 5/580 to 5/588.20) (Under PDNA 2023).	4,96,121/-	10000/-	350	One month
24	Repair and Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at RD's 9/700 to 5/708) (Under PDNA 2023).	99,929/-	2000/-	350	One month
25	Construction of link road Ropa to Ghatu Km.0/00 to 0/600.(SH:-Construction of R/wall with toe wall at RD 0/140 to 0/153).	4,90,737/-	10000/-	350	One month
26	Construction of link road Ropa to Ghatu Km.0/00 to 0/600.(SH:-Construction of B/wall at RD 0/160 to 0/180).	3,89,304/-	8000/-	350	One month
27	Construction of over head Bridge for direct entry of D.C. office Bilaspur (H.P.). (SH:- C/o gate in D.C. office Bilaspur (H.P.)).	4,99,685/-	10000/-	350	One month
28	Restoration of damages due to laying of sewerage line on various road under Sub Division No.II(SH:-Construction of unlined drain ,dressing of berms,Hiring of Excavator-cum-loader/Hydraulic Excavator at various roads).	99,297/-	2000/-	350	One month

29	A/R & M/O of various roads under Division No.1 HP.PWD Bilaspur (SH:-Providing and fixing bamboo tree guards).	98,600/-	2000/-	350	One month
30	A/R & M/O Rest House Dholra at Bilaspur. (SH:- Supply of refrigerator, Dinner set & tea set etc.).	99,937/-	2000/-	350	One month

1. Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.

TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/GST/EPF/Registration should be attached with the application otherwise tender form will not be issued.

Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 10/03/2026

NO.PW-BLP-I-CB-EA-I-Tender/ 2025- 20911-30

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur .
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portai.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.

Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.

DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,91,692/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit = One Month

Name of work:- Repair & Restoration of rain damages on Harlog Kuh Trifalghat roas Km. 0/00 to 20/00. (SH:- Re-construction of R/wall at Rd's 7/330 to 7/351). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.57	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	10481.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.15	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	434343.00
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.00	Each	317.00	Rupees Three Hundred Seventeen Only	14265.00
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.83	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyThree Only	32603.00
		TOTAL				491692.00

Rates,quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 4,86,762/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

DRAFT SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Harlog Kuh Trifalghat road Km. 0/00 to 20/00. (SH:- Re-construction of R/wall at Rd's 3/900 to 3/921). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.90	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	9177.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.15	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	434343.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204 3 8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octori, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.24	Per Cubic metre	1262.25	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyFive Only	38170.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octori, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Each	317.00	Rupees Three Hundred Seventeen Only	5072.00
TOTAL						486762.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

3

DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,92,854/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on Harlog Kuh Trifaighat roas Km. 0/00 to 20/00. (SH:- Re-construction of R/wall at Rd's 7/315 to 7/323). Under PDNA 2023.

Sr No	Description of items.	Qty.			Rates		Amount
		3	4	5	In words	In Figure	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.92	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	11022.00	
2	Providing and laying in position cement concrete of specified grade, excluding the cost of centering and shuttering - All work up to plinth level . 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.44	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	445756.00	
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7. including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.00	Each	317.00	Rupees Three Hundred Seventeen Only	14265.00	
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204 3.8 of MORD Specification 1200 including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.28	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred SixtyTwo Paase TwentyThree Only	21811.00	
TOTAL							492854.00


Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

4

Sr No		Description of items.	Qty.		Rates		Amount
			3	4	In Figure	In words	
<p align="center">DRAFT SCHEDULE OF QUANTITY.</p> <p align="center">Estimated cost Rs. = 99,423/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month</p>							
<p>Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Re-construction of R/wall at Rd's 3/870 to 3/873.45). Under PDNA 2023.</p>							
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.73	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	1778.00
2	2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.25	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred Eighty Three Paise Eighty Five Only	90955.00
3	3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octori, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.04	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred Sixty Two Paise Twenty Three Only	3837.00
4	4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octori, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00	Each	317.00	Rupees Three Hundred Seventeen Only	2853.00
			TOTAL				99423.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

5

Draft Schedule of quantity

		Estimated cost Rs. 74,047/-only		Earnest Money Rs. 1600/- only.		Time Limit. = One month	
Name of work:- Repair and maintenance of Police building (Old Sadar Police Station Building) at Bilaspur (H.P). (SH:- Removing, painting, distemping and repair of plaster etc.)							
Sr No	Description of items.	Qty.	Rates		Unit	Amount	
			In Figure	In Word			
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	4	5	6	7	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	587.6	9.50	Rupees Nine Paise Fifty Only	Per Square Meter	5582.00	
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	344.61	95.90	Rupees NinetyFive Paise Ninety Only	Per Square Metre	33048.00	
3	Finishing wall with weather proof exterior grade emulsion of approved design (Apex ultima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	236.55	95.00	Rupees NinetyFive Only	Per Square Meter	22472.00	
4	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, sand papering and stopping with white enamel paint. as per HP.PWD Specification clause 16, including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.10	95.00	Rupees NinetyFive Only	Per Square Metre	6945.00	

5	<p>Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	20.00	300.00	Rupees Three Hundred Only	Per Square Meter	60000.00
Rates quoted by contractor in percentage Above/Below						74047.00



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

6


Estimated cost Rs. = 99,106/-only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

DRAFT SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Re-construction of R/wall at Rd's 3/860 to 3/863.45). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.73	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	1778.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.25	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	90955.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORR Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.04	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyThree Only	3837.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each	317.00	Rupees Three Hundred Seventeen Only	2536.00
TOTAL						99106.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.P.W.D., Bilaspur

7


DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,86,991/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on link road from Lower Sungal to Planighat Km. 0/00 to 4/885. (SH:- Re-construction of B/wall at Rd's 4/600 to 4/640). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	68.40	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	15732.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.55	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	451288.00
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00	Each	317.00	Rupees Three Hundred Seventeen Only	19971.00
TOTAL						486991.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

8

DRAFT SCHEDULE OF QUANTITY.							Estimated cost Rs. = 4,99,894/-only	
							Earnest Money Rs. = 10000/- only.	
							Time Limit. = One Month	
Name of work:- Repair & Restoration of rain damages on Chandigarh Mandi Manali road Km. 140/00 to 146/00 (SH):- Re-construction of B/wall at Rd's 143/280 to 143/310). Under PDNA 2023.								
Sr No	Description of items.	Qty.		Rates		Amount		
		3	4	In Figure	In words		5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax. Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.60	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	15318.00		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (Forty millimetre) nominal size), including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	88.16	Per Cubic metre	5284.40	Rupees Five Thousand Two Hundred EightyFour Paise Forty Only	465873.00		
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	59.00	Each	317.00	Rupees Three Hundred Seventeen Only	18703.00		
		TOTAL				499894.00		

Rates quoted by contractor in percentage Above/Below

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

9

Sr No		Description of items.	Qty.		Rates		Amount
			3	4	In Figure	In words	
<p align="center">DRAFT SCHEDULE OF QUANTITY.</p> <p align="center">Estimated cost Rs. = 4,82,364/-only Earnest Money Rs. = 10000/- only. Time Limit. = One Month</p>							
<p>Name of work:- Repair & Restoration of rain damages on link road from Lower Sungal to Planihat Km. 0/00 to 4/885. (SH:- Re-construction of R/wall at Rd's 4/840 to 4/860). Under PDNA 2023.</p>							
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.68	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	8 10046.00
2	2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.10	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	434093.00
3	3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.00	Each	317.00	Rupees Three Hundred Seventeen Only	14899.00
4	4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.48	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyThree Only	23326.00
TOTAL							482364.00

Rates quoted by contractor in percentage Above/Below



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur


DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 99,483/-only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Re-construction of B/wall at Rd's 5/870 to 5/878). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.40	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	2852.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.88	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	94095.00
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhanna , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each	317.00	Rupees Three Hundred Seventeen Only	2536.00
TOTAL						99483.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer.
 Bilaspur Division No.1
 HP.PWD., Bilaspur

11

Draft Schedule of Quantity

Estimated cost Rs. = 97,900/-only.
Earnest Money Rs. = 2000/- only.
Time Limit. = One Month

Name of work :- A/R & M/O on various road under Beri Sub Division. (SH:- Hiring of Excavator-cum-loader/Hydraulic Excavator).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leades and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	89.00	Hours	1100.00	Rupees One Thousand One Hundred Only	97900.00

Rates quoted by contractor in percentage Above/Below


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

12

Sr No		Description of items.	Qty.		Rates		Amount
			3	4	In Figure	In words	
<p align="center">DRAFT SCHEDULE OF QUANTITY.</p> <p>Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH):- Re-construction of B/wall at Rd's 5/860 to 5/868). Under PDNA 2023.</p>							
			12.40	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	2852.00
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.88	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	94095.00
3	3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	9.00	Each	317.00	Rupees Three Hundred Seventeen Only	2853.00
			TOTAL				99800.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

13

DRAFT SCHEDULE OF QUANTITY.						
Estimated cost Rs. = 4,82,452/-only						
Earnest Money Rs. = 10000/- only.						
Time Limit. = One Month						
Name of work:- Repair & Restoration of rain damages on Chandigarh Mandi Manali road Km. 146/00 to 156/750 (SH:- Re-construction of crash barrier Km. 155/090 to 155/135 & 155/350 to 155/425). Under PDNA 2023.						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure 5	In words 6	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.58	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	3353.00
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.58	Per Cubic metre	5,747.50	Rupees Five Thousand Seven Hundred FourtySeven Paise Fifty Only	83799.00
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (Three millimetre) thick corrugated sheet metal beam rail, 70 Cm (Seventy centimetre)above road/ ground level, fixed on ISMC series channel vertical post, 150 x75 x5 mm (One hundred fifty into seventy five into five millimetre) spaced 2 m (Two meter) centre-to-centre, 1.8 m (One point eight meter) high, 1.1 m (One point one meter) below ground / road level , all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS : 1367 (One thousand three hundred sixty seven) and IS : 1364 (One thousand three hundred sixty four) metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm (One hundred fifty into seventy five into five millimetre, three hundred thirty millimetre) long complete as per clause 810 item including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, royalty, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	118.00	Per Running Metre	3350.00	Rupees Three Thousand Three Hundred Fifty Only	395300.00
TOTAL						482452.00

Rates quoted by contractor in percentage Above/Below

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

14

DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,79,338/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on Chandigarh Mandi Manali road Km. 140/00 to 146/00 (SH):- Re-construction of R/wall at Rd's 144/890 to 144/915). Under PDNA 2023.

Sl No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.45	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	11374.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (Forty millimetre) nominal size), including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	82.61	Per Cubic metre	5284.40	Rupees Five Thousand Two Hundred EightyFour Paise Fourty Only	436544.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.34	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyThree Only	16838.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.00	Each	317.00	Rupees Three Hundred Seventeen Only	14582.00
TOTAL						479338.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD, Bilaspur

15

Draft Schedule of quantity

Estimated cost Rs. 97,522/-only
Earnest Money Rs. 2000/- only.
Time Limit. = One month

Name of work:- A/R & M/O various roads under Sub Division No. II HP.PWD Bilaspur (H.P.). (SH:- Repair of 6 Nos. rain shelter Painting, distemping and emulsion paint etc.)

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) ASIAN company manufacturing content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	662.40	90.00	Rupees Ninety Only	Per Square Meter	59616.00
2	Finishing walls with Acrylic Smooth exterior paint of required shade of ASIAN APEX ULTIMA weather proof company manufacturing: Old work (Two or more coat applied @ 1.67 litr/ 10 sqm) (One point six seven Litre / ten Per Square Metre) on existing cement paint surface, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	197.82	95.00	Rupees NinetyFive Only	Per Square Metre	18793.00
3	Painting two coats(excluding priming coat) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surface of all dirt dust and other foreign matters, enamel paint as approved in standard design, as per HP.PWD Specification clause 16, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	224.86	85.00	Rupees EightyFive Only	Per Square Meter	19113.00
						97522.00

Rates quoted by contractor in percentage Above/Below

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

		DRAFT SCHEDULE OF QUANTITY.		Estimated cost Rs. = 4,98,971/-only Earnest Money Rs. = 10000/- only. Time Limit. = One Month		
Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of R/wall at Rd's 6/455 to 6/466.30). Under PDNA 2023.						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.96	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	10111.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.83	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	447699.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.81	Per Cubic metre	1262.25	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyFive Only	27530.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.00	Each	317.00	Rupees Three Hundred Seventeen Only	13631.00
		TOTAL				498971.00

Rates quoted by contractor in percentage Above/Below


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

17

DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,98,580/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Re-construction of R/wall at Rd's 5/650 to 5/658.10). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metree) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.28	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	11104.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.56	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	451337.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.33	Per Cubic metre	1262.23	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyThree Only	21874.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.00	Each	317.00	Rupees Three Hundred Seventeen Only	14265.00
TOTAL						498580.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

18

DRAFT SCHEDULE OF QUANTITY.						
Estimated cost Rs. = 4,89,512/-only						
Earnest Money Rs. = 10000/- only.						
Time Limit. = One Month						
Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at Rd's 15/580 to 15/910). Under PDNA 2023.						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.52	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	10930.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	94.50	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	470974.00
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malikhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Each	317.00	Rupees Three Hundred Seventeen Only	7608.00
		TOTAL				489512.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

19

		Qty.		Rates		Amount
				In Figure	In words	
DRAFT SCHEDULE OF QUANTITY. Estimated cost Rs. = 98,728/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month						
Name of work:- Repair & Restoration of rain damages on Harlog Kuh Trifalghat road Km. 0/00 to 20/00. (SH:- Formation cutting at RD. 2/360 to 2/426). Under PDNA 2023.						
Sr No	Description of items.	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	334.67	Per Cubic metre	295.00	Rupees Two Hundred NinetyFive Only	98728.00
TOTAL						98728.00

Rates quoted by contractor in percentage Above/Below


(Signature)

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

20

DRAFT SCHEDULE OF QUANTITY.		Estimated cost Rs. = 4,90,146/-only				
		Earnest Money Rs. = 10000/- only.				
		Time Limit. = One Month				
Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at Rd's 5/600 to 5/630). Under PDNA 2023.						
Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 47.52	4 Per Cubic metre	5 230.00	6 Rupees Two Hundred Thirty Only	8 10930.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	94.50	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	470974.00
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malikhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00	Each	317.00	Rupees Three Hundred Seventeen Only	8242.00
		TOTAL.				490146.00

Rates quoted by contractor in percentage Above/Below


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur


DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 99,891/-only
 Earnest Money Rs. = 2000/- only,
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of B/wall at Rd's 3/180 to 3/186). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	12.36	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	2843.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	18.90	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred Eighty Three Paise Eighty Five Only	94195.00
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00	Each	317.00	Rupees Three Hundred Seventeen Only	2853.00
TOTAL						99891.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,86,871/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-construction of R/wall at Rd's 5/570 to 5/578), Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.16	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	9697.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.06	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	448846.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.68	Per Cubic metre	1262.25	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyFive Only	24841.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.00	Each	317.00	Rupees Three Hundred Seventeen Only	3487.00
TOTAL						486871.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

23

Estimated cost Rs. = 4,96,121/-only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

DRAFT SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/6/15. (SH):- Re-construction of R/wall at Rd's 5/580 to 5/588.20). Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.21	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	9938.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	91.68	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred Eighty Three Paise Eighty Five Only	456919.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.17	Per Cubic metre	1262.25	Rupees One Thousand Two Hundred Sixty Two Paise Twenty Five Only	25460.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Each	317.00	Rupees Three Hundred Seventeen Only	3804.00
TOTAL.						496121.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

24

Sr No		Description of items.	Qty.		Rates		Amount
			3	4	5	6	
<p align="center">DRAFT SCHEDULE OF QUANTITY.</p> <p>Estimated cost Rs. = 99,929/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month</p> <p>Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Rb-construction of B/wall at Rd's 9/700 to 9/708). Under PDNA 2023.</p>							
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 0.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.96	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	2981.00
2	2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement - Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.88	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	94095.00
3	3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00	Each	317.00	Rupees Three Hundred Seventeen Only	2853.00
TOTAL			TOTAL				99929.00

Rates quoted by contractor in percentage Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

25

Name of work:- Construction of link road Ropa to Ghattu Km. 0/00 to 0/600. (SH:- Construction of R/wall with toe wall at Rd's 0/140 to 0/153).		Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.30	Per Cubic metre	230.00	Rupees Two Hundred Thirty Only	6279.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	92.95	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	463249.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.04	Per Cubic metre	1262.25	Rupees One Thousand Two Hundred SixtyTwo Paise TwentyFive Only	17722.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.00	Each	317.00	Rupees Three Hundred Seventeen Only	3487.00
TOTAL						490737.00

Rates quoted by contractor in percentage Above/Below

Executive Engineer,
Bilaspur Division No.1
HP.P.W.D., Bilaspur

26

Sr No		Description of items.	Qty.		Rates		Amount
			3	4	In Figure	In words	
<p align="center">DRAFT SCHEDULE OF QUANTITY.</p> <p align="center">Estimated cost Rs. = 3,89,604/-only Earnest Money Rs. = 7800/- only. Time Limit. = One Month</p>							
<p>Name of work:- Construction of link road Ropa to Ghattu Km. 0/00 to 0/600. (SH:- Construction of B/wall at Rd's 0/160 to 0/180).</p>							
1	1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	250.00	Per Cubic metre	250.00	Rupees Two Hundred Thirty Only	57500.00
2	2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.00	Per Cubic metre	4983.85	Rupees Four Thousand Nine Hundred EightyThree Paise EightyFive Only	328934.00
3	3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Each	317.00	Rupees Three Hundred Seventeen Only	3170.00
			TOTAL				389604.00

Rates quoted by contractor in percentage Above/Below

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

27

Draft Schedule of Quantity

		Estimated cost Rs. 4,99,685/-only		Earnest Money Rs. 10000/- only.		Time Limit. = One month	
Name of work:- Construction of over head Bridge for direct entry of D.C office Bilaspur (H.P.), (SH:- C/O Gate in D.C office Bilaspur (H.P.).							
Sr No	Description of items.	Qty.	Rates		Unit	Amount	
			In Figure	In Word			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 Per Square Meter (Ten Per Square Metre) on plan), including dressing of sides and running of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.55	295.00	Rupees Two Hundred NinetyFive Only	Per Cubic Metre	4587.00	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.35	5284.40	Rupees Five Thousand Two Hundred EightyFour Paise Fourty Only	Per Cubic Meter	65262.00	
3	Providing Tor steel Fe-500D SAIL TISCO reinforcement for Reinforced Cement Concrete work including bending, binding and placing in position complete in all heights including cost of binding wires completed and other incidentals due for its completion for all floors level.as per HP.PWD Specification clause 2.28.2, including carriage of materials , tools machinery within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	164.78	105.00	Rupees One Hundred Five Only	Per Kilogramme	17302.00	
4	Centering and shuttering including strutting, propping etc. and removal of form for all heights :					0.00	
4.1	Foundations, footings, bases of columns, etc. for mass concrete	12.15	330.00	Rupees Three Hundred Thirty Only	Per Square Meter	4010.00	

4.2	Lintels, beams, plinth beams, girders, brussesumers and cantilevers	2.22	470.00	Rupees Four Hundred Seventy Only	Per Square Metre	1043.00
4.30	Vertical surfaces such as walls (any thickness) partitions and the like including attached pilasters buttresses, plinth and string courses and the like.	24.00	411.15	Rupees Four Hundred Eleven Paise Fifteen Only	Per Square Metre	9868.00
5	Steel work welded in built up sections/ framed work, hollow section including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. including wheel as required, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2220.21	135.00	Rupees One Hundred ThirtyFive Only	Per Kilogramme Metre	299728.00
6	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (One cement : One point five coarse sand): three graded stone aggregate 20 mm (twenty millimetre) Each (minimal size). The including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.99	7800.00	Rupees Seven Thousand Eight Hundred Only	Per Cubic Metre	31122.00
7	Providing and laying high graded metal single including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.38	1415.00	Rupees One Thousand Four Hundred Fifteen Only	Per Square Metre	23178.00
8	Providing ridges or hips of width 60 cm (Sixty centimetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.80 mm (Zero point eighty millimetre) thick with zinc coating not less than 275 gm/m ² (Two hundred seventy five grammes / Per Square Metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.80	580.00	Rupees Five Hundred Eighty Only	Per Running Metre	1044.00

9	Stone work ashlar / chiseler punched (ordinary work) in superstructure upto floor two level in cement mortar 1:6 (1 cement:6 sand) including pointing with cement mortar 1:2(1 cement : 2 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.19	35748.80	Rupees ThirtyFive Thousand Seven Hundred FourtyEight Paise Eighty Only	Per Cubic Metre	42541.00
---	---	------	----------	---	-----------------	----------

Rates quoted by contractor in percentage

Above/Below

499685.00


Executive Engineer,
Bilaspur Division No.1
HP.P.W.D., Bilaspur

28

Draft Schedule of Quantity


Estimated cost Rs. = 99,297/- only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One month.

Name of work :- Restoration of damages due to laying of Sewerage line on various road under Sub Division No. II (NBT Section). (SH:- C/O unlined drain, dressing of berms, Hiring of Excavator-cum-loader/Hydraulic Excavator at various road's).

Sr No.	Description of items.	Qty.	Unit	In Figure	Rate		Amount
					In words	Amount	
1	Surface dressing of the ground including dressing vegetation and in-squalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	825.00	Square Meter	20.30	Rupees Twenty Paise Thirty Only	16748.00	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	665.00	Per Running Meter	64.75	Rupees SixtyFour Paise Seventyfive Only	43059.00	
3	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leads and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	35.90	Hours	1100.00	Rupees One Thousand One Hundred Only	39490.00	
	TOTAL						99297.00

Rates quoted by contractor in percentage

Above/Below


 Executive Engineer,
 Bilaspur Division No.1
 H.P.P.W.D., Bilaspur

29

Draft Schedule of quantity						
Name of work:- A/R & M/O of various roads under Division No. 1 HP.PWD Bilaspur. (SH:- Providing and fixing bamboo tree guards).						
Estimated cost Rs. 98,600/-only						
Earnest Money Rs. 2000/- only.						
Time Limit. = One month						
Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2 Providing and fixing Bambo tree guards of 1.80 metre height with 30cm diametre with 4 Nos vertical strips (Length 1.80 metre height, breadth 30mm, thickness 5mm) further weaving with different smaller size of vertical and circular strips. The weaved portion should be 125 cm having 3 rings at the top, bottom and middle portion. The first ring should be 55 cm above the 4 thick vertical strips including strengthening with barbed wire complete in all respect as per the standard specification and direction of Engineer-in-charge. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	340.00	290.00	Rupees Two Hundred Ninety Only	Each	98600.00
Rates quoted by contractor in percentage						98600.00
Above/Below						

(Signature)
Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

20

Estimated cost Rs. 99,937/-only
Earnest Money Rs. 2000/- only.
Time Limit. = One month

Draft Schedule of Quantity

Name of work:- A/R & M/O Rest House Dholra at Bilaspur. (SH:- Supply of refrigerator, Dinner set & tea set etc).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	Supply of LG 653 Litre convertible 5 in 1 side by side refrigerated RS76CG800S9, product net width 91.20 cm, Number of shelf 4 EA, number of door pocket 5 EA, interior LED ligh, tempered glass, Door alarm, vacation mode, refrigerator R600a, compressor Digital inverter, Door handle recess, noise level 37 dBA & climate class SN, N.S.T., net weight 100 kg, cooling type twin cooling plus, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	77990.00	Rupees Seventy Seven Thousand Nine Hundred Ninety Only	Each	77990.00
2	Supply of Bone China Dinnerware: 20 PC set, Service for 4, Double Gold Rim, White, Microwave safe Product ID 528909431 & item model number BC29730, material type lead free, 20 number of pieces and product safe from dishwasher and microwave uses, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	16,797.00	Rupees Sixteen Thousand Seven Hundred Ninety Seven Only	Each	16797.00
3	Supply of Bone China Tea Set with 6 Cups & Saucer, Tea Kettle Pot, Milk Pot, Sugar Pot White with Gold Line (Set of 15pcs) model No. B08438B2R2 and product safe from dishwasher including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Each	3650.00
4	Supply of Stainless steel water mug 2 litre capacity in best quality and product safe from dishwasher as per clause 304 SS grade Milton, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	750.00	Rupees Seven Hundred Fifty Only	Each	1500.00
			TOTAL			99937.00

Rates quoted by contractor in percentage Above/Below


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur