

— 2 —

OFFICE OF

EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA  
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA  
Phone No. 01899-222229 Email ee-cha-hp@nic.in

NOTING INVITING TENDER

Sealed item rate tender on form 6&8 are hereby invited by the undersigned for the works on behalf of the Governor of Himachal Pradesh from the approved and eligible contractors enlisted in HPPWD. So as to reach in his office on or before **18-03-2026 to 11:00 AM** and will be opened on the same day at **11:30 AM**, in the presence of the intending Contractor or their authorized representatives if any. The tender application will be received in this office on **16-03-2026 upto 10.00 AM to 12.30 PM** and tender form can be had from this office on **17-03-2026 from 3.00 PM to 5.00 PM**. The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Chamba Division HPPWD Chamba must be accompanied with each tender. The tender form will be issued to contractor who giving proof of enlistment, GST, Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No.	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of tender form (Rs.)	Class	Completion period
1	2	3	4	5	6	7
1	A/R & M/O Various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD,s)	97650/-	1960/-	350	D	One Month
2	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of crawler excavator for removal of slips at various RD,s)	97650/-	2000/-	350	D	One Month

— 2 —

3	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of crawler excavator for removal of slips at various RD,s)	97650/-	2000/-	350	D	One Month
4	Rest of rain damages on various roads under Bhadram section Chamba Sub Division No I HPPWD Chamba (SH:- Hiring of Tipper for removal of slips at various Rd,s)	99540/-	2000/-	350	D	One Month
5	A/R & M/O Various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD,s)	97650/-	1960/-	350	D	One Month
6	A/R & M/O Various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD,s)	97650/-	1960/-	350	D	One Month
7	A/R & M/O Various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD,s)	97650/-	1960/-	350	D	One Month
8	A/R & M/O Various roads under Bhadram section (SH:- Hiring og excavator cum pocklane for removal of slips at various RD,s)	97650/-	1960/-	350	D	One Month
9	A/R & M/O Various roads under Sahoo/Maredi section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD,s)	97650/-	1960/-	350	D	One Month
10	A/R & M/O Various roads under Sahoo section Chamba Sub Division No I (SH:- Hiring of Tipper for removal of slips at various Rd,s)	99540/-	2000/-	350	D	One Month
11	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of Tipper)	99540/-	2000/-	350	D	One Month

12	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of Tipper)	99540/-	2000/-	350	D	One Month
13	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of crawler excavator for removal of slips at various RD,s)	97650/-	2000/-	350	D	One Month
14	Rest of rain damages on Chamba Khajjiar road Km. 0/0 to 19/0 SH:- Removal of slip & boulders from portion Gate to Sultanpur Chowk)	98959/-	2000/-	350	D	One Month
15	Rest of rain damages on Chamba Khajjiar road Km. 0/0 to 19/0 SH:- Removal of slip & boulders from portion Gate to Sultanpur Chowk)	98959/-	2000/-	350	D	One Month
16	Rest of rain damages on Chamba Khajjiar road Km. 0/0 to 19/0 SH:- Removal of slip & boulders from portion Gate to Sultanpur Chowk)	98959/-	2000/-	350	D	One Month
17	Rest of rain damages on Chamba Khajjiar road Km. 0/0 to 19/0 SH:- Removal of slip & boulders from portion Gate to Sultanpur Chowk)	98959/-	2000/-	350	D	One Month
18	A/R & M/O on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of Tipper for removal of slips at various Rd,s)	99540/-	2000/-	350	D	One Month
19	A/R & M/O on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of Tipper for removal of slips at various Rd,s)	99540/-	2000/-	350	D	One Month
20	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of excavator cum Loder for removal of slips at various RD,s)	99000/-	2000/-	350	D	One Month

21	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of excavator cum loder for removal of slips at various RD,s)	99000/-	2000/-	350	D	One Month
22	Rest of rain damages on Jeepable road Bhalian to Gadiyara Km. 0/0 to 1/500 G.P Rinda (SH:- Hiring of excavator cum loder for removal of slips at various RD,s)	99000/-	2000/-	350	D	One Month
23	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 3/999.32 to 4/00) (Additional work)	97014/-	1940/-	350	D	One Month
24	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 4/002 to 4/003) (Additional work)	97014/-	1940/-	350	D	One Month
25	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 4/000 to 4/002) (Additional work)	97014/-	1940/-	350	D	One Month
26	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 4/003 to 4/005) (Additional work)	97014/-	1940/-	350	D	One Month
27	Rest of rain damages on various roads under Kiri Section Sub Division No I (SH:- Herring of Tipper for Shifting of muck / Slips)	99540/-	2000/-	350	D	One Month
28	Rest of rain damages on various roads under Kiri Section Sub Division No I (SH:- Herring of Tipper for Shifting of muck / Silps)	99540/-	2000/-	350	D	One Month




29	Rest of rain damages on various roads under Kiri Section Sub Division No I (SH:- Herring of Tipper for Shifting of muck / Silps)	99540/-	2000/-	350	D	One Month
30	Rest of rain damages on various roads under Kiri Section Sub Division No I (SH:- Herring of Tipper for Shifting of muck / Silps)	99540/-	2000/-	350	D	One Month
31	Rest of rain damages on Chamba Banikhet via above Parel road Km. 0/0 to 14/0 (SH:- Hiring of excavator cum loder for removal of slips at various RD,s)	99000/-	2000/-	350	D	One Month
32	Rest of rain damages on Chamba Banikhet via above Parel road Km. 0/0 to 14/0 (SH:- Hiring of excavator cum loder for removal of slips at various RD,s)	99000/-	2000/-	350	D	One Month
33	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 3/989.66 to 3/991.04) (Additional work)	97014/-	1940/-	350	D	One Month
34	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 3/988.28 to 3/989.66) (Additional work)	97014/-	1940/-	350	D	One Month
35	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 3/991.04 to 3/992.42) (Additional work)	97014/-	1940/-	350	D	One Month
36	Rest of rain damages on various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Hiring of crawler excavator with breaker for removal of slips at various RD,s)	97650/-	2000/-	350	D	One Month
37	Rest of rain damages on various roads under Chamba Sub Division No II (SH:- Hiring of Tipper)	99540/-	2000/-	350	D	One Month

38	Rest of rain damages on various roads under Kiri Section Sub Division No I (SH:- Hiring of JCB/excavator cum loader for removal of slips at various RD,s)	99000/-	1980/-	350	D	One Month
39	Rest of rain damages on various roads under Kiri Section Sub Division No I (SH:- Hiring of JCB/excavator cum loader for removal of slips at various RD,s)	99000/-	1980/-	350	D	One Month
40	Repair and maintenance of PWD residential qtr Type-II Type III in HPPWD Chamba (SH:- Brick work, sanitary installation and PVC ceiling in Type -III qtr)	49365/-	1000/-	350	D	One Month
41	Repair and maintenance of PWD residential qtr Type-II Type III in HPPWD Chamba (SH:- Brick work, sanitary installation)	66777/-	1400/-	350	D	One Month
42	A/R & M/O various roads under Chamba Sub Division No II HPPWD Chamba (SH:- Supplying and stacking of Rumble Strips)	98865/-	2000/-	350	D	One Month
43	Rest of rain damages on Bhanera Kolka road Km. 0/0 to 5/370 SH:- C/o PCC B/wall at Rd. 4/284.10 to 4/288.65)	99919/-	1998/-	350	D	One Month
44	Rest of rain damages on Bhanera Kolka road Km. 0/0 to 5/370 SH:- C/o PCC B/wall at Rd. 4/279.55. to 4/284.10)	99919/-	1998/-	350	D	One Month
45	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 3/995.18 to 3/996.56) (Additional work)	97014/-	1940/-	350	D	One Month
46	Rest of rain damages on link road Sahoo to Kiri Km. 0/0 to 5/00 (SH:- C/o PCC R/wall at Rd. 3/993.80 to 3/995.18) (Additional work)	97014/-	1940/-	350	D	One Month

## TERMS AND CONDITIONS:-

1. The contractor should produce a copy of enlistment /renewal at time of application
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have his registration and GST No. ,the copy of same be attached with the application
4. The earnest Money shall be deposited duly pledged in favour of executive Engineer, Chamba Division HPPWD Chamba and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected .
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.


The tender shall not be issued to those contractor who have more than two works in hand.

  
Executive Engineer,  
Chamba Division  
HPPWD Chamba

No. PWC-WA-II/Contract/2025-26-56076-125 Dated:- 9-3-26

Copy forwarded to:-


1. The F.C-cum-Principal Secretary (PW) to the govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD., Shimla
3. The Chief Engineer (KZ) HPPWD Dharamshala
- 4 The Superintending Engineer, 7<sup>th</sup> Circle HPPWD Dalhousie .
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
- 6 All the Assistant Engineers under Chamba Division
7. All the Contractor working under this division
- 8 H.D.M./Supdt./Acctt. of this office.
9. Notice Board..

  
Executive Engineer,  
Chamba Division  
HPPWD Chamba

OFFICE OF  
EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA  
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA  
Phone No 01899-222229 Email [ee-cha\\_hp@nic.in](mailto:ee-cha_hp@nic.in)

### CERTIFICATE

Certified that tender of works, as called vide this office  
letter No PWC-WA-II/Contract/2025-26-56076-125 Dated 4-3-26  
are emergent nature in exigency of public interest

  
Executive Engineer,  
Chamba Division  
Division, HPPWD,



1

Draft Schedule of Quantity

Name Of Work:- A/R & M/O various roads under Bhadrans section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD's)	Estimated Cost	97650/-
	Earnest Money	1960/-
	Time Limit	One month

Sr. No	Description of item	Qty.	Rate	unit	Amount
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equivalent for removal of slip debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all heights and depths as per direction and entire satisfaction of Engineer-In-Charge. the excavator should work minimum 8,001 hours from 9 AM to 5.00PM daily and excavated at least 200 cum quantity fo snow slips per hour. Any loss of public/private property or any accident etc. happening during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-In-Charge.	31.000	3150.00	Per hour	97650
<b>Total:-</b>					<b>97650</b>

*Draft submitted Rs Rs 97650/-*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

**Draft schedule of quantity**

Name of work :- Restoration of rain damages on various roads under Chamtha Sub Division No-II HPPWD Chamtha (SH :  
 Hiring of Crawler excavator for removal of slips at various RDs).  
 Estimated cost : Rs. 97,650/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S.No	Descriptions of item.	Qty.	Rate		Unit	Amount	
			In fig	In words			
1	Hiring of Crawler Excavator cum POKELANE or JS 210 or equivalent for removal of slips, debris, and boulders clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all leads as per directions and entire satisfaction of Engineer-in-Charge. The Excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow/slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	31.00	Hour	3150.00	Rupees three thousand one hundred fifty only.	Per hour	97650.00
<b>Total :</b>							97650.00

*DRAFT APPROVED FOR RS 97650/- only*

  
**Executive Engineer**  
 Chamtha Division  
 H.P.P.W.D., Chamtha

*JS*

**Draft schedule of quantity**

Name of work :- Restoration of rain damages on various roads under Chamba Sub Division No-II HPPWD Chamba (SH :  
Hiring of Crawler excavator for removal of slips at various RDs).

Estimated cost : Rs.97,650/-  
Earnest money : Rs. 2000/-  
Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount	
			In fig	In words			
1	Hiring of Crawler Excavator cum Pokelane or JS 210 or equivalent for removal of slips, debris, and boulders clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all leads as per directions and entire satisfaction of Engineer-in-Charge. The Excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow/slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	31.00	Hour	3150.00	Rupees three thousand one hundred fifty only.	Per hour	97650.00
Total :							97650.00

  
**Executive Engineer**  
**Chamba Division**  
**H.P.P.W.D., Chamba**

*DNIT Approval for Rs 97650/- only*

*JB*

2

DNIT

Name of work :- Restoration of rain damages on various roads under Bhadram Section Chamba Sub Divn no. 1, HPPWD  
Chamba (SH : Hiring of Tipper for removal of slips at various RDs).

Estimated cost : Rs. 99540/-  
Earnest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Tipper 10 cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge.	126.00	790.00	Rupees hundred only	Seven ninety Per hour	99540.00
<b>Total :</b>						<b>99540.00</b>

*[Handwritten signature]*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

*DNIT approved Rs 99540/-*

5

Draft Schedule of Quantity

Estimated Cost	97650/-
Earnest Money	1960/-
Time Limit	One month

Name Of Work:- A/R & M/O various roads under Bhadram section (Sh:- Hiring of excavator cum pocklane for removal of slips at various RD's )

Sr. No	Description of item	Qty.	Rate	unit	Amount
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equivalent for removal of slip debries abd boulders clear from the roads surface upto all hights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all hights and depths as per direction and entire satisfaction of Engineer-in-Charge. the excavator should work minimum 8,001 hours from 9 AM to 5,00PM daily and excavated at least 200 cum quantity to snow slips per hour. Any loss of public/private property or any accident etc. happening during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-In-Charge.	31.000	3150.00	Per hour	97650
<b>Total:-</b>					<b>97650</b>

*[Handwritten Signature]*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

*DN 17 approved R-R/S 9/9/2018*

6

Draft Schedule of Quantity

Estimated Cost	97650/-
Earnest Money	1960/-
Time Limit	One month

Name Of Work:- A/R & M/O various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RDI's )

Sr. No	Description of item	Qty.	Rate	unit	Amount
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equivalent for removal of slip debnes abd boulders clear from the roads surface upto all hights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all hights and depths as per direction and entire satisfaction of Engineer-in-Charge. the excavator should work minimum 8.00l hours from 9 AM to 5.00PM daily and excavated at least 200 cum quantity fo snow slips per hour. Any loss of public/private property or any accident etc. happening during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-In-Charge.	31.000	3150.00	Per hour	97650
Total:-					97650

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

*02/11/2016*

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

1

Draft Schedule of Quantity

Estimated Cost	97650/-
Earnest Money	19665/-
Time limit	One month

Name of Work: AR & MO various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD's )

Sr. No	Description of item	Qty.	Rate	unit	Amount
1					
2					
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equivalent for removal of slip debris abd boulders clear from the roads surface upto all hights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all hights and depths as per direction and entire satisfaction of Engineer-in-Charge. the excavator should work minimum 8,001 hours from 9 AM to 5,00PM daily and excavated at least 200 cum quantity fo snow slips per hour. Any loss of public/private property or any accident etc. happening during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-In-Charge.	31.000	3150.00	Per hour	97650
Total:-					97650

*DNITC/AMR/AR 97650*

*Singh*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

9

Draft Schedule of Quantity

Estimated Cost	97650/-
Earnest Money	1960/-
Time Limit	One month

Name Of Work:- A/R & M/O various roads under Bhadram section (SH:- Hiring of excavator cum pocklane for removal of slips at various RD's )

Sr. No	Description of Item	Qty.	Rate	unit	Amount
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equivalent for removal of slip debries abd boulders clear from the roads surface upto all hights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all hights and depths as per direction and entire satisfaction of Engineer-in-Charge: the excavaror should work minimum 8.00l hours from 9 AM to 5.00PM daily and excavated at least 200 cum quantity fo snow slips per hour. Any loss of public/private property or any accident etc. happening during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-In-Charge.	31.000	3150.00	Per hour	97650
<b>Total:-</b>					<b>97650</b>

*Dr. J. K. Prasad*

*Shirga*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba


9

Draft schedule of quantity

Name of Work:- A/R & M/O various road on various roads under Sahoo / Maredi section RD (SH:- Hiring of excavator cum Pocklane for removal of slips at various RDs )

Estimated Cost	97650/-
Earnest Money	2000/-
Time Limit	One month

Sr. No	Description of item	Qty.	Rate	unit	Amount
1		3	4	5	6
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equivalent for removal of slip debnes abd boulders clear from the roads surface upto all hights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all hights and depths as per direction and entire satisfaction of Engineer-in-Charge. the excavator should work minimum 8,00l hours from 9 AM to 5 00PM daily and excavated at least 200 cum quantity to snow slips per hour. Any loss of public/private property or any accident etc. happening during the course of hiring penod/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-in-Charge.	31.000	3150.00	Per hour	97650
Total:-					97650

  
 Assistant Engineer  
 Chamba Sub- Division No-1  
 HPPWD Chamba

  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

*Draft approved & Rs 97650/- only*

Name of Work - A/R & M/O on various road under Sahoo Section Chamba Sub Division No-1 (SH:- Hiring of Tipper for removal of slips at various RD's )

Estimated Cost	99540/-
Earnest Money	2000/-
Time Limit	One month

Sl. No	Description of item	Qty.	Rate	unit	Amount
1	Hiring of Tipper having 5.5 cum per trip capacity for shifting of construction material or earth upto all leads and lifts as per direction and entire satisfaction of Engineer-in-Charge and loss of public/private property or any accident etc. happened during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner of his own cost and repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-In-Charge.	3	790.00	Per Hour	99540
<b>Total:-</b>					<b>99540</b>

*SK*

Assistant Engineer  
Sub. Division No.1  
H.P. P.W.D. Chamba (H.P.)

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

*DRIT approved Rs 99540/-*

(11)

**Draft schedule of quantity**

Name of work : Restoration of rain damages on various roads under Chamba Sub Division No-II  
HPPWD Chamba (SIH : Hiring of Tipper).

Estimated cost : Rs. 99540 /  
Earnest money : Rs. 2000 /  
Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Tipper 10cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner. at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including actual royalty/Mahana,toll tax sale tax, GST or other taxes imposed by the Government.	126.00 Hour	790.00	Rupees seven hundred ninety only	Per hour	99540.00
Total:						99540.00

*Do not approve for Rs 99540.00*

Executive Engineer  
Chamba Division  
HPPWD, Chamba

12

**Draft schedule of quantity**

Name of work : Restoration of rain damages on various roads under Chamba Sub Division No-II

Estimated cost : Rs. 99540/-

HPPWD Chamba (SH : Hiring of Tipper )

Earrest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Rs.	In words		
1	Hiring of Tipper 15cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Mahakavali tax sale tax, GST or other taxes imposed by the Government.	126.00 Hour	790.00	Rupees seven hundred ninety only	Per hour	99540.00
Total :						99540.00

*DNIT approved for Rs. 99540/-*

Executive Engineer  
Chamba Div. No. II  
HPPWD, Chamba

Draft schedule of quantity

Name of work : Restoration of rain damages on various roads under Chandra Sub Division No-11 (HPPWD) Chandra (SIL) : Estimated cost : Rs. 97,650/-  
 Hiring of Crawler excavator for removal of slips at various RDS) Largest money : Rs. 2000/-  
 Time : One month

S.No.	Description of Item.	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Crawler Excavator cum Pakehane or JS 210 or equivalent for removal of slips, debris, and boulders clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all loads as per directions and entire satisfaction of Engineer-in-Charge. The excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/evacuation shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and want of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including cost, royalty, Mahanagar tax sale tax, GST or other taxes imposed by the Government.	1.000	1150.00	Rspees (three thousand one hundred fifty only.	per hour	97650.00
Total :						97650.00

*0 no. amount for Rs 97650/-*



Executive Engineer  
 Chandra Div No-11  
 HPPWD, Chandra

*J's*

19

Draft schedule of quantity

Name of work :- Restoration of rain damages on various roads under Chamba Sub Division No-II HPPWD Chamba (SH : Hiring of Crawler excavator for removal of slips at various RDs).

Estimated cost : Rs. 97,650/-  
Earnest money : Rs. 2000/-  
Time : One month

S.No.	Descriptions of item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Crawler Excavator cum Pokelane or JS 210 or equivalent for removal of slips, debris, and boulders clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all leads as per directions and entire satisfaction of Engineer-in-Charge. The Excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow/slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	31.00 Hour	3150.00	Rupees three thousand one hundred fifty only.	Per hour	97650.00
Total :						97650.00

*DIT approved for Rs 97650/-*

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chambs

14

Draft Schedule of quantities

Name of work :- Restoration of rain damages on Chamba Khajjiar road Km. 0/0 to 19/0  
(Sl. Removal of slip & boulders from portion (gate to Sulampur chowk )  
Estimated cost = Rs. 98959/-  
Earnest Money = Rs. 2000/-  
Time - one month

S.No.	Descriptions of item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Removal of truck/boulder/trees, breaking of boulder up to specified sizes by mechanical means including loading & un-loading up to all leads till as per entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malakona, toll tax, GST or other taxes imposed by the government	122.00	234.50	Rupees two hundred thirty four & paise five zero only	Per cubic metre	98959.00
<b>Total</b>						<b>98959.00</b>

*QAH*

*QAH*  
Assistant Engineer  
Chamba Sub Division No.-II  
(H.P. Baramulla, Chamba, J&K)

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

*DNT approved Rs. 98959/-*

115

Draft Schedule of quantities

Name of work :- Restoration of rain damages on Chamba Kihajjar road Km. 0/0 to 19/0  
(SH:-Removal of slip & boulders from portion Gate to Sultanpur chowk )

Estimated cost= Rs. 98959/-  
Earnest Money =Rs. 2000/-  
Time = one month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Removal of muck/boulder/rocks; breaking of boulder up to specified sizes by mechanical means including loading & un-loading up to all leads; lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidents. The rate is including petrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	422.00	234.50	Rupces two hundred thirty four & paise five zero only	Per cubic metre	98959.00
<b>Total</b>						<b>98959.00</b>

**Assistant Engineer**  
Chamba Sub Division No. 11  
H.P.P.W.D. Chamba (H.P.)

**Executive Engineer**  
Chamba Division  
H.P.P.W.D., Chamba

*DAIT Abstract Rs 98959/-*

Draft Schedule of quantities

Name of work :- Restoration of rain damages on Chamba Khajjar road Km. 0/0 to 19/0  
 (SH:-Removal of slip & boulders from portion Gate to Sultampur chowk )

Estimated cost= Rs. 98959/-  
 Earnest Money =Rs. 2000/-  
 Time = one month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Removal of track/boulder/rocks, breaking of boulder up to specified sizes by mechanical means including loading & un-loading up to all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	422.00	234.50	Rupees two hundred thirty four & paise five zero only	Per cubic metre	98959.00
<b>Total</b>						<b>98959.00</b>

*[Handwritten Signature]*

*[Handwritten Signature]*  
 Assistant Engineer  
 Chamba Sub Division No-II  
 H.P.P.W.D., Chamba (H.P.)

*[Handwritten Signature]*  
 Draft approved Rs. 98959/-  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

Draft Schedule of quantities

Name of work :- Restoration of rain damages on Chamba Khajjiar road Km. 0/0 to 19/0  
 (Sl:-Removal of slip & boulders from portion Gate to Sultampur chowk )

Estimated cost= Rs. 98959/-  
 Earnest Money =Rs. 2000/-  
 Time = one month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Removal of muck/boulder/rocks, breaking of boulder up to specified sizes by mechanical means including loading & un-loading up to all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	422.00	234.50	Ruppes two hundred thirty four & paise five zero only	Per cubic metre	98959.00
<b>Total</b>						<b>98959.00</b>

*(Signature)*  
 Assistant Engineer  
 Chamba Sub Division No. II  
 H.P.P.W.D., Chamba

*(Handwritten in red)*  
 Draft approved Rs. 98959/-  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

DNIT

Name of work :- A/R & M/O on various roads under Chamba Sub Division No. II H.P.P.W.D. Chamba (SI) : Hiring tipper for removal of slaps at various RDS)

Estimated cost : Rs. 99540/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S.No.	Descriptions of items.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Taper 10cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property on any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for mach we will be provided by the owner at his own cost and repair & spare parts and wear of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Market, toll tax, sales tax, G.T or any other taxes imposed by the Government.	126.00	790.00	RupeseSeven hundred ninety and paise zero only.	Per hour	99540.00
<b>Total :</b>						<b>99540.00</b>

Assistant Engineer  
 Chamba Sub Division No. II  
 H.P.P.W.D. Chamba

DNIT approved for  
 Rs 99540 only  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D. CHAMBA

19

DNIT

Name of work :- A/R & M/O on various roads under Chamba Sub Division No. 11 H.P.P.W.D Chamba (SH : Hiring tipper for removal of slips at various RDS).

Estimated cost : Rs. 99540/-  
Earnest money : Rs. 2000/-  
Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Tipper 10cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	126.00	790.00	Rupees Seven hundred ninety and paise zero only.	Per hour	99540.00
<b>Total :</b>						<b>99540.00</b>

*[Handwritten Signature]*

Assistant Engineer  
Chamba Sub Division No. 11  
H.P.P.W.D. Chambe (H.P.)

Executive Engineer  
Chamba Division  
H.P.P.W.D CHAMBA

*DNIT approved for Rs. 99540/-*

20

**DNIT**

Restoration of rain damages on various roads under Chamba Sub Division No-II HPPWD Chamba (SH : Hiring of Excavator cum Loader for removal of slips at various RDS).

Estimated cost : Rs. 99000/-

Earnest money : Rs. 9900/-

Time : One month

S No	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for cutting/ widening of road and removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge.	90.00	1100.00	Rupees one thousand one hundred fifty & paise zero only	Per hour	99000.00
<b>Total :</b>						<b>99000.00</b>

Assistant Engineer  
Chamba Sub Division No-II  
H.P.P.W.D. Chamba (H.P.)

Executive Engineer  
Chamba Division  
H.P.P.W.D.. Chamba

DNIT Chamba Rs. 99k

DNIT

Restoration of rain damages on various roads under Chamba Sub Division No-II HPPWD Chamba (SH : Hiring of Excavator cum Loader for removal of slips at various RDs)

Estimated cost : Rs. 99000/-  
 Earnest money : Rs. 9900/-  
 Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for cutting/ widening of road and removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge.	90.00	1100.00	Rupees one thousand one hundred fifty & paise zero only	Per hour	99000.00
<b>Total :</b>						<b>99000.00</b>



Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

*DNIT approved for Rs 99000/only*

22

Draft schedule of quantity

Name of work : Restoration of rain damages on Jeppable road Ethulam to Chadyara Km 0.0 to 1/500 . GIP  
Kinda (SI) : Hiring of Excavator cum Loader for removal of slips.

Estimated cost : Rs. 99000/-  
Earnest money : Rs. 2000/-  
Time : One month

S No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public private property or any accident etc. happened during the course of hiring period execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including extra, royalty, Malkana:oll tax sale tax, GST or other taxes imposed by the Government.	90.00 Hour	1100.00	Rupees one thousand one hundred only.	Per hour	99000.00
Total :						99000.00

*DNH approval Rs.99000/-*

Executive Engineer  
Chandrayana Division  
H.P.P.W.D., Chennai

(83)

(15)

12.11.17

Estimated Cost 97014/-  
Earnest Money 1940/-  
TIME LIMIT 1 MONTH

NAME OF WORK :- Resto of R/W on LINK ROAD SAHOO TO KIRAI KM 0/0 TO 5/00 (Additional work)

B HEAD :- G.O P.C.C SURFACE AT RD 3/999 TO 4/000

NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
A	B	C	D	E	F
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1204 including setting out construction of shoring and bracing removal of slumps and other detemour material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octrio royalty malikna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD technical specification clause 802,803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octrio royalty malikna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clauses 1204.3.8 The Rate including octrio royalty malikna toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing weed hole in brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full width the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614,709,1204,3.7 The Rate including octrio royalty malikna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
TOTAL					97,014.00

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D., Chamba

0417 approved for RS 97014/10/17

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

24

DN 11

17

Estimated Cost 97014/-  
Earnest Money 1940/-  
TIME LIMIT 1 MONTH

NAME OF WORK :- Part of HPD on Link Road SAHO To KIRI KM 0/0 To 5/00 (Amenity work)

B HEAD Qo P.C.C. 4/1002 To 4/1003

NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
A	B	C	D	E	F
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of stumps and other heterogeneous material and disposal upto all leads including dressing of slides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals. The Rate including octroi royalty Malkna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD technical specification clause 802, 803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octroi royalty Malkna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clause 1204, 3.8 The Rate including octroi royalty Malkna toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm. (One Hundred millimeter) Diameter PVC pipe extending through the full width of the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614, 709, 1204, 3.7 The Rate including octroi royalty Malkna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
TOTAL					97,014.00

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

SE

0417 Approved by Asst. Engineer  
Chamba Division  
H.P.P.W.D., Chamba

25

D.M.I.T

(ATC)

Estimated Cost 97014/-  
Earnest Money 1340/-

TIME LIMIT 1 MONTH

(Additional work)

NAME OF WORK :- Repair of RIP on LINK ROAD SAHOO TO KIRAI KM 0/0 TO 3/00

IB HEAD :- G.O.P.C.C. NUMBER AT RD 4/000 TO 9/002

NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work in excavation in all kind of soil for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	---	350.00	Per Cubic mtr.	---
2	Providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD technical specification clause 802, 803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clauses 1204.3.8 The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	---	950.00	Per Cubic mtr.	---
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the toll within the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 514, 709, 1204.3.7 The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
	TOTAL				97014.00

*[Signature]*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

D.M.I.T approved for Rs 97014/-

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

26

DMIT

(18)

Estimated Cost 97014/-  
Earnest Money 1940/-  
TIME LIMIT 1 MONTH

NAME OF WORK :- Road of P.P.W.D. LINK ROAD SAHOO TO KIRI KM 0/0 TO 5/00 (Additional work)

SUB HEAD :- 40 Pcc Material AT RD 4/003 TO 4/005

S NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
A	B	C	D	E	F
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1.134 including setting out construction of shoring and bracing removal of slumps and other detritious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals. The Rate including octrio royalka toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and H.P.P.W.D technical specification clause 802.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octrio royalka toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clauses 1204.3.8 The Rate including octrio royalka toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full width of the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and H.P.P.W.D Technical Specifications Clause 614.709,1204.3.7 The Rate including octrio royalka toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
TOTAL					97014.00

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

Assistant Engineer  
Chamba Division  
H.P.P.W.D., Chamba

DMIT approval No 97014/0

(41)

Work : Restoration of rain damage on various under km Section sub Division No-1 (SIT)- Hiring of hiring of  
of Hiring Of truck Slips/1

**DNIT**

Descriptions of Item	Qty.	In fig	Estimated Cost:-		Unit	Amount
			Earnest Money	One month		
			Rate	In words		
ing of Tipper having 1 <sup>st</sup> cum per trip capacity for shifting of construction material or earth upto all ds and lifts as per direction and entire satisfaction of Engineer-in-Charge and loss of public/private property or any accident etc happened during the course of hiring period/excavation shall be the source responsibility of the Excavator owner The daily log book will be mentioned at site which at be duly verified by the Engineer-in-Charge	126.00	790.00			Per Hour	99540.00
<b>Total</b>						<b>99540.00</b>

*[Handwritten Signature]*

Assistant Engineer  
Chamba Sub Division No-1  
H.P.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chamba

*DNIT approved Rs. 99540.00*

Work : Restoration of rain damage on various under kirt Section sub Division No.1 (SHE - Hiring of hiring of  
 for shifting of muck (MPSH)

**DNIT**

Descriptions of Item	Qty	In fig	Estimated Cost		Unit	Amount
			Estimated Money Time Limit	In words		
Hiring of Tipper having 11 cum per trip capacity for shifting of construction material of earth upto all roads and lifts as per direction and entire satisfaction of Engineer-in-Charge and loss of public/private property or any accident etc. happened during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-in-Charge	126.00	790.00			Per Hour	99540.00
<b>Total</b>						<b>99540.00</b>

*Not approved for Rs: 99540/-*

*[Signature]*  
 Assistant Engineer  
 Chamba Sub Division No.-1  
 H.P.P.W.D. Chamba

*[Signature]*  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

*[Signature]*  
 STE

69

**DNIT**

Age of work - Restoration of earth damage on various under kind Section sub Division No-1 (S.H. Hiring of Hiring of  
 type of shifting of truck Slaps)

Sl. No.	Descriptions of Item.	Qty.	Estimated Cost:		Per Hour	Amount
			In fig.	In words		
			Estimated Cost:	Rs. 1991/-		
			Earnest Money:	One month		
			Time Limit	Rate	Unit	Amount
				In words		
01	Hiring of Tractor having 11 cum per trip capacity for shifting of construction material or earth upto all leads and the direction and entire satisfaction of Engineer-in-Charge and loss of public/private property or any accident etc happened during the course of hiring period/excavation shall be the absolute responsibility of the excavator owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-in-Charge	126.00	790.00			
<b>Total</b>						99540.00

*DNIT approved for Rs 1 99540/-*

Assistant Engineer  
 Chamba Sub Division No.-1  
 H.P.P.W.D. Chamba

Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

STF

Report of work of Restoration of all rain damage on various under KRII Section sub Division No.1 (SH) Hiring of Lining of  
 type for Shifting Of m/c. Slips A

**DNTT**

Sl. No.	Descriptions of Item.	Qty.	Estimated Costs:-		Per Hour	Amount
			In fig	In words		
	Hiring of Tipper having 11 cum per trip capacity for shifting of construction material or earth upto all leads and lifts as per direction and entire satisfaction of Engineer-in-Charge and loss of public/private property or any accident etc. happened during the course of hiring period/excavation shall be the absolute responsibility of the Excavator owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-in-Charge	126.00	790.00			
<b>Total</b>						<b>99540.00</b>

*DNTT approved for Rs. 99540/-*

*[Signature]*  
 Assistant Engineer  
 Chamba Sub Division No.-1  
 H.P.P.W.D. Chamba

*[Signature]*  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

**DNT**

Name of work :- Restoration of rain damages on Chamba Banikhet via above Parcel road Km. 0/0 to 14/0  
 Hiring of Excavator cum Loader for removal of slips at 0/0 to 4/0). (SH : )

Estimated cost : Rs. 99000/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand one hundred only.	Per hour	99000.00
<b>Total :</b>						<b>99000.00</b>

*[Signature]*

*[Signature]*  
 Assistant Engineer  
 Chamba Sub Division No.-II  
 H.P.P.W.D. Chamba (H.P.)

*[Signature]*  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

*DNT approved Rs. 99000/-*

**DNIT**

Name of work :- Restoration of rain damages on Chambe Banihset via above Parcel road Km. 0/0 to 14/0  
 Hiring of Excavator cum loader for removal of slips at 0/0 to 4/0.

Estimated cost : Rs. 99000/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S.No	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for removal of slips in all kinds of soft and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair . watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	90.00	1100.00	Rupces one thousand one hundred only.	Per hour	99000.00
<b>Total :</b>						<b>99000.00</b>

**Assistant Engineer**  
 Chambe Sub Division No-II  
 H.P.P.W.D. Chambe (H.P.)

**Executive Engineer**  
 Chambe Division  
 H.P.P.W.D. Chambe

*DNIT approved Rs.99000/-*

D.H.1.T

(8)

Estimated Cost 97014/-  
Earnest Money 1940/-

TIME LIMIT 1 MONTH

NAME OF WORK :- Restoof R.P.P.W.D. ROAD SAHOO TO KIRI KM 0/0 TO 5/00 (Additional work)  
SUB HEAD :- GPO P.C.C. ROAD AT RD 3 1989.66 To 3/991.04

S NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octroi royalty malikna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	Providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and H.P.P.W.D. technical specification clause 802.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octroi royalty malikna toll tax sale tax of other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Revetting with granular material behind abutment wing wall return walls complete as per drawing and H.P.P.W.D. technical specification clauses 1204.3.8 The Rate including octroi royalty malikna toll tax sale tax of other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing sweep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall. return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full width of the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and H.P.P.W.D. Technical Specifications Clause 614.709, 1204.3.7 The Rate including octroi royalty malikna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
	TOTAL				97014.00

Assistant Engineer  
Chamba Sub Division No.1  
H.P.P.W.D. Chamba

*[Signature]*

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

D.H.1.T approved by RS 97014/- only

D.M.I.T

(7)

Estimated Cost 97014/-  
 Earnest Money 1940/-  
 TIME LIMIT 1 MONTH

(Additional work)

NAME OF WORK :- Repts of R/D of LINK ROAD SAHOO TO KIRAI KM 0.0 TO 5.00

SUB HEAD :- 90 P.C.C. R/W. AT RD 3/1988.28 To

S NO. DESCRIPTION OF ITEM

A	B	C	D	E	F
S NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	Providing and laying plain cement concrete 1:3:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD Technical specification clause 802,803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clauses 1204.3.8 The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall. return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full within the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614,709,1204.3.7 The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
TOTAL					97014.00

Assistant Engineer  
 Chamba Sub Division No.  
 H.P.P.W.D. Chamba

ST

D.M.I.T approved by Rs 97014/-

Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

D.M.I.T

(9)

NAME OF WORK :- Resto of R/D on SAHOO ROAD SAHOO TO KIRI KM 0/0 TO 5/00  
 SUB HEAD :- 40 P.C.C  
 S NO. RD 3/99104 TO 3/99242

Estimated Cost 97014/-  
 Earnest Money 1940/-  
 TIME LIMIT 1 MONTH  
 (Additional work)

A	B	C	D	E	F
S NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	For this work in excavation in all kind of soils for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octroi royalty malna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	Providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD technical specification clause 802.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octroi royalty malna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and HPPWD technical specification clauses 1204.3.8 The Rate including octroi royalty malna toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall. return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full width of the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 514,709,1204.3.7 The Rate including octroi royalty malna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
	TOTAL				97014.00

Assistant Engineer  
 Chamba Sub Division No. 4  
 H.P.P.W.D. Chamba

Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

*(Signature)*

*D.M.I.T Approved for Rs 97014 only*

DNIT

Restoration of road damages on various roads under Chamba Sub Division No-II HPPWD Chamba.  
 Hiring of Crawler excavator with breaker for removal of slips at various RDSs.

Estimated cost : Rs. 97650/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Crawler Excavator cum Pokelane with breaker or JS 210 or equivalent for removal of slips, debris, and boulders and cutting work in hard rocks clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all leads as per directions and entire satisfaction of Engineer-in-Charge. The Excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow/slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge.	31.00	3150.00	Rupees three thousand one hundred fifty only	Per hour	97650.00
Total :						97650.00

*[Signature]*

Assistant Engineer  
 Chamba Sub Division No.-II  
 H.P.P.W.D. Chamba (H.P.)

Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

DNIT approval Rs. 97650/-

Name of work: Restoration of rain damages on Various roads under Chamba Sub Division No-2  
 H.P.W.D Chamba (SH : Hiring of Tipper).

Draft schedule of quantity

Estimated cost : Rs. 99540/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S.No.	Descriptions of item	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Tipper 10cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkanatali tax sale tax GST or other taxes imposed by the Government	126.00 Hour	790.00	Rupees seven hundred ninety only	Per hour	99540.00
Total :						99540.00

*Handwritten signature*

Assistant Engineer  
 Chamba Sub Division No-1  
 H.P.W.D. Chamba (H.P.)

Engineer  
 Chamba Sub Division  
 H.P.W.D. Chamba

*DNIT approval Rs 99540/-*

Part B - Restoration of Rain damage on Various R.D. K.M. Section under sub no 1 (N.E. Hiring of L.B. Excavator for removal of slips at various R.D.)

**DNT**

Descriptions of Item.	Qty.	In fig	In words	Estimated Cost	
				Unit	Amount
Hiring of excavator cum loader for cutting/watering of road and removal of slips in all kinds soil and disposing of all excavated earth of un-servicable material from the road surface upto all leads and lifts and upto all heights and depths as per direction and entire satisfaction of Engineer-in-Charge and loss of public private property or any accident etc. happens during the course of hiring period excavation shall be the absolute responsibility of the Excavator owner, which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor owner. The daily log book will be mentioned at site which shall be duly verified by the Engineer-in-Charge.	99.00	1100.00	Rupess One thousand one hundred only.	Per Hour	99000.00
	Total				

Estimated Cost  
 Rupees One thousand one hundred only.  
 One month

*DNT approved Rs 99000/-*

Assistant Engineer  
 Sub. Division No.1  
 H.P. P.W.D. Chamba (H.P.)

Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

*E.J.e*

(39)

**DNTT**

Contract No. 100/2017-18 (M&A) (H.P.) (H.P. Div. Chambe)

Description of Item	Qty.	To By	Rate		Total	Amount
			In words	In figures		
<p>There shall be a tender for supply, maintenance of road and removal of slips of all sorts, soil and stones, all excavated earth of un-suitable material to level the road surface upto all road lines and open all drains and depths as per direction and written instructions of Engineer in Charge and also on P.W.D. private property or any accident etc. Ingress during the course of bringing of material shall be the absolute responsibility of the Contractor. The staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge.</p>	20000	1000/00	Rs. 20000000	20000000	20000000	20000000
<b>Total</b>					<b>990000.00</b>	

*DNTT approved RSH 990000/-*

Assistant Engineer  
Sub. Division No. 1  
H.P. P.W.D. Chambe (H.P.)

Executive Engineer  
Chamba Division  
H.P.P.W.D. Chambe

*ks*

**DNT**  
 Repair and maintenance of PWD residential qtr. Type-I and Type-II in HPPWD Gamba, Brick Work, sanitary installation and PVC ceiling in Type-III QTR.)

S.No. Description of Work / Item (S) 49365/-  
1000/-  
One Month

S.No	Description of Work / Item (S)	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and fixing 150 mm dia (one hundred fifty millimeter) P.V.C single equal branch with oval access door of Finolex / Relpipe (Relience) / Vectus insertion rubber washer 3mm (three millimeter) thick bolts and nuts ISI marked including finishing with approved adhesive including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	10	490	Rupees Four Hundred & Ninety Only	Each	4900.00
2	Providing and fixing 150mm (one hundred fifty millimeter) nominal bore/diameters P.V.C plain bend of Finolex / Relpipe (Relience) / Vectus Confirming to IS No.-14735-99 including filling the joints with approved adhesive etcetra complete carriage of material with in all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes imposed by the Government.	8	380	Rupees Three Hundred & Eighty Only	Each	3040.00
3	Providing and fixing 150x 100 mm (one hundred fifty into one hundred millimeter) nominal bore/diameters P.V.C Reducer of Finolex / Relpipe (Relience) / Vectus Confirming to IS No.-14735-99 including filling the joints with approved adhesive etcetra complete carriage of material with in all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	8	260	Rupees Three Hundred & Sixty Only	Each	2880.00
4	Providing and fixing 90 mm dia (ninety millimeter) P.V.C single equal branch with oval access door, of Finolex / Relpipe (Relience) / Vectus insertion rubber washer 3mm (three millimeter) thick bolts and nuts ISI marked including finishing with approved adhesive including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	12	250	Rupees Two Hundred & Fifty Only	Each	3000.00
5	Providing and fixing 110mm (one hundred ten millimeter) nominal bore/diameters P.V.C (plain bend of Finolex / Relpipe (Relience) / Vectus Confirming to IS No.-14735-99 including filling the joints with approved adhesive etcetra complete carriage of material with in all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	14	240	Rupees Two Hundred & Fourty Only	Each	3360.00
6	Excavating trenches of required width for pipes, cables, etc. including excavation for sockets, dressing of sides, ramming of bottom, depth upto 1.5f. one point five) metre including getting out the excavated soil and then returning the soil as required in layers not exceeding 20cm (twenty centimetre) in depth including consolidating each deposited layer by ramming, watering etcetra and disposing of surplus excavated soil as directed within a lead of 50 (fifty) metres. Pipes and cables exceeding 80mm (eighty millimetre) dia but not exceeding 300mm (three hundred millimetre) diameter or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	40.00	369.00	Rupees Three Hundred & Nine Only	Per running metre	12360.00
7	Providing and fixing (kulti) way pipe connector with Manhole Inspection Chamber of UNSTD size 500x 400x300 mm including filling the joints with approved adhesive etcetra complete carriage of material with in all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.00	3600.00	Rupees Three Thousand Six Hundred Only	Each	3600.00
8	Providing and laying cement concrete 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work in Foundation and plinth carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.21	6500.00	Rupees Six Thousand Five Hundred Only	Per cubic metre	7865.00
9	Providing and fixing Pvc Ceiling Panel Thickness: 6 to 7 mm (six to seven millimetre thick) with GI frame complete carriage of material with in all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	7.60	1100.00	Rupees One Thousand One Hundred Only	Per square metre	8360.00

DNT approved for Rs 99365 from 99365.00

Exposing Engineer  
 Circle Division  
 H.P.P.W.D. Gamba

21

**DNIT**

Nature of Work:- Repair and maintenance of PWD residential qtr. Type-II and Type-III in HPPWD Chamba ( Brick Work sanitary installation )

SrNo	Description of Work / Item (S)	Qty.	In fig.	In words	Unit	Amount	Estimated Cost: Rs.
							66,777/-
							Earnest Money :- Rs.
							1,400/-
							Time Limit :-
							One Months
							Rate
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 ( one cement isto six coarse sand) complete including all taxes and carriage of material, as directed by the Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	3.01	9500.00	Rupees Nine Thousand Five Hundred Only	Per cubic metre	28595.00	
2	Providing 20mm (twenty millimetre) thick cement plasters in single coat on rough side of brick/concrete/stone walls for exterior plastering including making groove or drip course, arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:5 (One cement isto five sand) upto floor all levels complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	22.80	315.00	Rupees Three Hundred & Fifteen Only	Per square metre	7182.00	
3	Providing and fixing 150 mm (One hundred fifty millimetre) diameter on wall face single socketed conforming to IS : 13592 Type A ISI marked of Finolex/Supreme working pressure not less than 6 kg/cm <sup>2</sup> (Six Kilogram per centimetre square), including jointing with seal ring conforming to IS : S382 including jointing with seal ring leaving 10mm (Ten millimetre) gap for thermal expansion including filling the joints with approved adhesive complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, GST and any other taxes imposed by the Government.	40	800.00	Rupees Eight Hundred Only	Per running metre	32000.00	
<b>Total</b>						<b>67777.00</b>	

MS 074

DNIT approved for Rs 67777/- Jay

Executive Engineer  
Chamba Division  
H.P.P.W.D CHAMBA


42

Name of work :- A/R & M/O various roads under Chamba Sub Division No-II HPPWD  
 Chamba. (SH:- Supplying and stacking of Rumble strips) DNIT  
 Estimated cost: Rs.98865/-  
 Earnest money : Rs. 2000/-  
 Time : One month

S. No.	Description of item	Quantity	Rate		Unit	Amount
			in Fig	in words		
1	Supplying & stacking of dual directional rumble strips made of ABS (Acrylonitrile Butadiene styrene )materials of size 250mmx 150 mm x32mm duly reflectronised with highly reflective Nos. imported glass panels or both side (6x2) six into two and to be filled with two nos, steel pins and suitable epoxy A&B and as per Engineer-in-Charge complete in all respect. The rate including octroi, royalty, Malkana, toll tax GST or other taxes imposed by the Government.	117.00	845.00	Rupees eight hundred forty five	Each	98865.00
<b>Total</b>						<b>98865.00</b>

DNIT approved for Rs 98865/- only

  
 Executive Engineer  
 Chamba Division  
 H.P.P.W.D CHAMBA

  
 Assistant Engineer  
 Chamba Sub Division No.-II  
 H.P.P.W.D. Chamba (H.P.)

(43)

D.N.I.T

Estimated Cost 99,919/-  
Earnest Money 19,981/-  
Time Limit 1 Month

Name of Work :- Restoration of Rain damages on Bhanera Kolka Road KM 0/0 To 5/370  
(SH :- C/O Pcc B/Wall at RD 4/284.10 TO 4/288.65

	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cutting in earth work in hilly area by mechanical means including trimming of side slope and disposing of excavation earth with a lift upto 1.50 m ( one and half meter ) and a lead upto 20m (twenty metre) as per drawing and technical Specifications Clause 1603.1	22.79	175.00	Per Cubic mtr.	3988
2	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto all leads of 50 mtr. including dressing of sides and bottom and backfilling in trenches with excavation suitable material	3.45	350.00	Per Cubic mtr.	1208
3	providing and laying plain cement concrete 1:5:10 (One cement : Five sand : Ten graded stone aggregate 25 millimeter nominal size) in open foundation complete as per drawing and HPPWD Technical specification clause 802,803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	18.97	4900.00	Per Cubic mtr.	92953
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full width of the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614,709,1204,3.7 The Rate including octroi royalty Malkna toll tax sale tax or other taxes imposed by the Government	6	295.00	Per Cubic mtr.	1770
	<b>Total :-</b>				<b>99919</b>

*D.N.I.T approved for Rs 99919/-mtr*

Assistant Engineer  
Chamba Sub-Division No-1  
H.P.P.W.D. Chamba (H.P)

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

54

D.N.I.T

Estimated Cost 99919/-  
Earnest Money 1998/-  
Time Limit 1 Month

Name of Work :- Restoration of Rain damages on Bhanera Kolka Road KM 0/0 To 5/370  
(SH :- C/O Pcc B/Wall at RD 4/279-55 TO 4/284.10

	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cutting in earth work in hilly area by mechanical means including trimming of side slope and disposing of excavation earth with a lift upto 1.50 m ( one and half meter ) and a lead upto 20m (twenty metre) as per drawing and technical Specifications Clause 1603.1	22.79	175.00	Per Cubic mtr.	3988
2	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto all leads of 50 mtr. including dressing of sides and bottom and backfilling in trenches with excavation suitable material	3.45	350.00	Per Cubic mtr.	1208
3	providing and laying plain cement concrete 1:5:10 (One cement : Five sand : Ten graded stone aggregate 25 millimeter nominal size) in open foundation complete as per drawing and HPPWD Technical specification clause 802,803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	18.97	4900.00	Per Cubic mtr.	92953
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full width of the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614,709,1204,3.7 The Rate including octroi royalty malikna toll tax sale tax or other taxes imposed by the Government	6	295.00	Per Cubic mtr.	1770
	<b>Total :-</b>				<b>99919</b>

Assistant Engineer  
Chamba Sub Division North  
H.P.P.W.D. Chamba (H.P.)

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

*D.N.I.T approved for Rs 99919/-*

43

D.N.17

Estimated Cost 97014/-  
 Earnest Money 1940/-  
 TIME LIMIT 1 MONTH

NAME OF WORK :- Rate of Riprap Link Road SAHOO TO KIARI KM 0/0 TO 5/00 (Additional work)

SUB HEAD :- GPO P.C.C. AT RD 3/995/18 To 3/996.56

S NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of slumps and other heterogeneous material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD technical specification clause 802.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clauses 1204.3.8 The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing weep hole in Brick masonry/Stone masonry/Plain reinforced concrete abutment wing wall, return wall with 100 mm (One Hundred millimeter) Diameter PVC pipe extending through the full within the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614.709, 1204.3.7 The Rate including octrio royalty Malkna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
TOTAL					97014.00

Assistant Engineer  
 Chamba Sub Division No.-1  
 H.P.P.W.D. Chamba

*D.N.17 approved for Rs 97014/-*

Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

46

D.N.I.T

(11)

Estimated Cost 97,014/-  
Earnest Money 1940/-

TIME LIMIT 1 MONTH

NAME OF WORK :- Resfo of R/P on LINK ROAD SAHOO TO KIRAI KM 0/0 TO 5/00 (Additional work)

SUB HEAD :- P.C.C. ROAD 3/993.80 To 3/995.18

S NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work in excavation in all kind of soils for structure as per drawing and technical specification clause 1104 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavation suitable material within all leads and lifts as per the direction of the Engineer in Charge and other incidentals. The Rate including octrio royalty malna toll tax sale tax or other taxes imposed by the Government	—	350.00	Per Cubic mtr.	—
2	Providing and laying plain cement concrete 1:5:10 (One cement : five sand : 10 graded stone aggregate forty millimeter nominal size) in open foundation complete as per drawing and HPPWD technical specification clause 302.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals. The Rate including octrio royalty malna toll tax sale tax or other taxes imposed by the Government	18.66	5120.00	Per Cubic mtr.	95539.00
3	Backfilling with granular material behind abutment wing wall return walls complete as per drawing and MORD technical specification clauses 1204.3.8 The Rate including octrio royalty malna toll tax sale tax or other taxes imposed by the Government	—	950.00	Per Cubic mtr.	—
4	Providing weep hole in Brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 300 mm (One hundred millimeter) Diameter PVC pipe extending through the full within the structure with slope of 1(V):20 (H) towards Drawing face complete as per drawing and HPPWD Technical Specifications Clause 614.709.1204.3.7 The Rate including octrio royalty malna toll tax sale tax or other taxes imposed by the Government	5	295.00	each	1475.00
	TOTAL				97,014.00

*[Signature]*

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.P.W.D. Chamba

*D.N.I.T approved for Rs 97014/-*

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba