

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26 15027-35

Dated:- 28/03/2026


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:- Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER


Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **07.04.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **06.04.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **06.04.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please note no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/o Ambulance road from NH-205 to (Harizen basti) Kayarad km. 0/0 to 0/940(SH:- Formation cutting at RD's 0/00 to 0/420.) DMFT Deposit.	4,00,006/-	8,100/-	1 Month	350/-
2.	C/o link road from Karoda to village Nouni km. 0/00 to 1/500 (SH:- Formation Bed cutting in km. 0/900 to 0/960)(DMFT Deposit	48,035/-	1,000/-	1 Month	350/-
3	R/R damages on Talab (Rau Khad) Behli road km. 0/00 to 2/170 (SH:- Construction of Toe wall and Slab for 3.00 meter span RCC slab culvert at RD 1/480) PDNA	4,98,863/-	10,000	1 Month	350/-
4	R/R damages on Talab (Rau Khad) Behli road km. 0/00 to 2/170 (SH:- Construction of Abutments for 3.00 meter span RCC slab culvert at RD 1/480) PDNA	4,98,694/-	10,000/-	1 Month	350/-
5	R/R damages on Gang Hut building at HP,PWD., Section Jainagar under HPPWD Kunihar Sub Division (SH:- Providing and fixing Water Supply and Sanitary installation fitting along with floor tiles work and prepainted steel sheets for Gang Hut building at Jainagar.)	98,681/-	2,000	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.



Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

Dated:-

No: PW-AD-EA-I-Tender-2025-26-


Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for
4(Four) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY

Name of Work:- C/o Ambulance Road from NH-205 to (Harijan Basti) Kayard Km 0/00 to 0/940. (SH:- Formation Cutting at Rd,s 0/00 to 0/420.)DMFT Deposit

Estimated Cost: -Rs 4,00,006/- only


Earnest Money :-Rs8,100/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 193.90 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1817.88	Per. Cum.	220.04	Rupees two hundred twenty and paise four only .	400006
					Total	400006

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
B&R Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road from Karoda to village Nouni Km 0/00 to 1/500). (SH:- Formation Bed Cutting in Km 0/900 to 0/960.)DMFT Deposit

Estimated Cost: -Rs 48,035/- only

Earnest Money :-Rs1,000/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charge, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, dressing, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 12.06 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	120.60	Per. Cum.	398.30	Rupees three hundred ninety eight and paise thirty only .	48035
					Total	48035

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Talb (Rau Khad) behli Road km 0/00 to 2/170.(Sh :Construction-of Toe wall and Slab for 3.00 meter span Rcc slab culvert at Rd 1/480) PDNA

Estimated Cost :- Rs 4,98,863.00

Earnest money :- Rs 10,000.00

Time: One months

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	2	3		4	5	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	17.93	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	3073.00
2.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	0.50	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	2647.00
3.00	Providing and laying Plain Cement Concrete Mechanically mixed and vibrated Plain cement concrete 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 20mm (twenty milimetre) nominal size for plain /reinforced conceret in open foundations and plinths or similar works and curing complete as per drawings and technical specifications for RURAL ROAD AUGUST 2004 AND CLAUSES 802,803,1202 & 1203 and curing complete including the cost of form work including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	15.50	cum	5954.35	Rupees Five Thousand nine Hundred fifty four and thirty Five paise Only	Per cubic metre	92292.00
4.00	Providing and laying Reinforced Cement Concrete Mechanically mixed and vibrated RCC M-20 (M- twenty) upto 5.00 meters height in super structure and curing complete as per drawings and technical specifications clauses 800,1205.4 and 1205.50 and curing complete including the cost of form work and including carriage of materials in all leads and lifts and as per entire stisfaction of Engineer-in -Charge.	3.79	cum	6891.20	Rupees six Thousand eight Hundred ninety one and and paise twenty Only	Per cubic metre	26118.00
5.00	Providing and laying Reinforced Cement Concrete Mechanically mixed and vibrated RCC M-25 (M- twenty five) upto 5.00 meters height in super structure and curing complete as per drawings and technical specifications clauses 800,1205.4 and 1205.50 and curing complete including the cost of form work and including carriage of materials in all leads and lifts and as per entire stisfaction of Engineer-in -Charge.	8.55	cum	7366.30	Rupees Seven Thousand three Hundred sixty six and and paise thirty Only	Per cubic metre	62982.00

6.00	Supplying ,fitting and placing HYSD bar reinforcement (fe 415) in sub structure complete as per drawing and technical specification Clauses 1002, 1005,1010 & 1202. as per drawings and technical specifications including carriage of metreioals with in all leads and lifts as per the entire satisfaction and direction of Engineer-In-Charge.	1450.03	Kg	96.50	Rupees Ninety six and and paise fifty Only	Per Kilogra mme	139928.00
7.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	36.34	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	159554.00
8.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	22.36	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	6132.00
9.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.10	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6137.00
						Total	498863.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HPJ PWD. Arki.

SCHEDULE OF QUANTITY


Name of Work:-Restoration of rain Damages on Talb (Rau Khad) behli Road km 0/00 to 2/170.(Sh :Construction-of Abutments for 3.00 meter span Rcc slab culvert at Rd 1/480) P D N A		Estimated Cost :- Rs 4,98,694.00					
		Earnest money :- Rs 10,000.00					
		Time: One months					
Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	87.79	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	15047.00
2.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	7.08	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	37488.00
3.00	Providing and laying Plain Cement Concrete Mechanically mixed and vibrated Plain cement concrete 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 20mm (twenty milimetre) nominal size for plain /reinforced conceret in open foundations and plinths or similar works and curing complete as per drawings and technical specifications for RURAL ROAD AUGUEST 2004 AND CLAUSES 802,803,1202 & 1203 and curing complete including the cost of form work including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	74.93	cum	5954.35	Rupees Five Thousand nine Hundred fifty four and thirty Five paise Only	Per cubic metre	446159.00
						Total	498694.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of rain damages to Gang hutt building at HP,PWD Section Jainagar under HPPWD Kunihar Sub Division.(Sh; Providing and fixing Water Supply and Sanitary Installation fittings along with floor tiles work and prepainted steel sheets for Gang hutt building at Jainagar)							Estimated Cost :- Rs 98,681.00
							Earnest money :- Rs 2,000.00
							Time: One months
Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Providing and fixing C.P. brass angle valve for basin mixer and geyser point of approved quality etc. including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge. 15mm dia	7.00	Nos.	532.00	Rupees Five Hundred thirty Two and paise zero only	Each	3724.00
2.00	Providing and fixing C.P. Brass bib cock of approved quality confirming to IS:8931 :15 mm nominal bore etc. including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge. 15mm dia.	1.00	No.	418.95	Rupees Four Hundred eighteen and paise ninety five only	Each	419.00
3.00	Providing and fixing C.P. brass long nose bib cock of approved quality confirming to IS standards and weighing not less than 810 gms.and 15 mm nominal bore complete.including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge. 15mm dia	1.00	No.	640.25	Rupees Six Hundrede forty and paise twenty fiv only	Each	640.00
4.00	Providing and fixing Chalorinated Polyvinyle chloride (CPVC) pipes, having thermal stability for hot and cold water supply,including all CPVC plain and brass threaded fittings, including fixing the pipes with clamp at 1.00 meter spacing.this includes jointing of pipes and fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per the direction of Engineer-in-Charge. concealed work, including cutting chases and making good the walls etc. 20 mm nominal outer dia pipe etc. including carriage of materials upto all leads and lifts and as per the direction of the Engineer-in-Charge	15.00	Rmt	362.30	Rupees Three Hundred sixty two and thirty paise only	Per running meter	5435.00
5.00	Providing and fixing Chalorinated Polyvinyle chloride (CPVC) pipes, having thermal stability for hot and cold water supply,including all CPVC plain and brass threaded fittings,.this includes jointing of pipes and fittings with one step CPVC solvent cement trenching,refilling and testing of Joints complete as per the direction of Engineer-in-Charge. concealed work, including cutting chases and making good the walls etc. 25 mm nominal outer dia pipe external work etc. including carriage of materials upto all leads and lifts and as per the direction of the Engineer-in-Charge	5.00	Rmt	272.60	Rupees Two Hundred seventy two and sixty paise only	Per running meter	1363.00

6.00	Providing and fixing white vitreous China pedestal type wash down, water closet (European type. W.C. pan) with seat and lid, 10.00 litre (ten litres) low level white PVC Flushing cistern, including flush pipe, with manually controlled device (hand lever) conforming to IS :7231 with all fittings and fixture complete. including carriage of materials upto all leads and lifts as per the direction of the Engineer-in-Charge	1.00	No	5363.05	Rupees Five thousand three hundred sixty three and five paise only	Each	5363.00
7.00	Providing and fixing 8 mm (eight milimeter) dia CP/SS jet with flexible tube upto 1.00 (one meter with SS triangular plate to European type WC of approved quality and make as approved by engineer in charge complete as per PWD specification of 1990 Volume-I. including carriage of materials upto all leads and lifts as per the direction of the Engineer-in-Charge	1.00	No	307.85	Rupees three hundred seven and eighty five paise only	Each	308.00
8.00	Providing and fixing vitreous china wash basin with single hole for pillar tap with C.I or M.S. brackets including cutting hole and making good the same but excluding fittings :as per PWD specification of 1990 Volume-I- Cera no 550 mm x 400 mm with CP brass pillar trap (Cat No1025 of including carriage of materials upto all leads and lifts as per the direction of the Engineer-in-Charge	2.00	Nos.	2926.15	Rupees Two Thousand Nine Hundred Twenty six and Fifteen paise only	Each	5852.00
9.00	Providing and fixing CP brass bottle trap (heavy duty) ISI marked IS: 8931 and 8934 for wash basin or sink. 32 mm (thirty two milimeter) dia. complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Nos	913.60	Rupees Nine hundred thirteen and paise sixty only.	Each	1827.00
10.00	Providing & fixing 100 mm dia sand cast iron grating for gully / floor trap complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge	2.00	Nos	47.40	Rupees Forty seven paise forty only.	Each	95.00
11.00	Providing and fixing 600mm x 450mm (six hundred milimetre into for hundred fifty milimetre) bevelled edge mirror of superior glass (of approved quality) complete with 6mm (six milimeter) thick hard board ground fixed to wooden cleats with C.P.brass screws and washers complete as per HP.PWD., specification Volume-I (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1.00	No	1200.35	Rupees One thousand two hundred and paise thirty five only.	Each	1200.00
12.00	Providing and fixing GI pipes complete with GI fittings including trenching and refilling etc. for external work ,complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge. 25mm (twenty five milimeter) diameter nominal bore	10.00	Rmt	243.65	Rupees Two hundred forty three and paise sixty five only.	Per running metre	2437.00

13.00	Making connection of GI distribution branch with GI main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete. 25mm to 40mm (twenty five into forty milimeter) nominal bore complete and including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	521.60	Rupees Five hundred twenty one and paise sixty only.	Each	522.00
14.00	Providing and fixing white vitreous china laboratory sink size of 510x1040x225 mm (five hundred ten into one thousand zero hundred forty into two hundred twenty five) with C.I. Bracket C.P brass chain with rubber plug, 40 mm (forty milimeter) complete including painting of fittings and brackets cutting making good the wall wherever required. complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	5304.05	Rupees five thousand three hundred four and paise five only.	Each	5304.00
15.00	Providing and fixing PTMT CP brass towel rail (heavy duty) ISI marked IS 8931 and 8934 complete with brackets fixed to wooden cleats with C.P. brass screws with concealed fittings arrangements of approved quality and colour complete (i) 600 mm (six hundred long) towel rail with total length of 645 mm (six hundred forty five milimeter) width 78 mm (seventy eight milimeter) and effective height of 88 mm (eighty eight milimeter) weighing not less than 190 (one hundred ninety) grams complete as per HP, PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	550.85	Rupees Five hundred fifty and paise eighty five only.	Each	551.00
16.00	Providing and fixing 600mm x 120 mm x 5mm (six hundred into one hundred twenty into five milimeter) glass shelf with EDGES ROUD OFF, SUPPORTED ON ANIDISED ALUMINIUM ANGLE FRAME with C.P. Brass bracket and guard rail complete, fixed to 40 mm (forty milimeter) long screws. rawl plugs etc complete. as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	786.85	Rupees Seven hundred eighty six and paise eighty five only.	Each.	787.00
17.00	Providing and fixing PVC waste and ventilating pipes including filling the joints with approved adhesive .complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge. (i) 75 mm diameter pipe	12.00	Rmt	478.25	Rupees Four hundred seventy eight and paise twenty five only.	per running meter	5739.00
18.00	Providing and fixing PVC fittings and accessories ISI marked complete and as per HP. PWD. Specifications of 1990 vplume-I including carriage of materials, labour, tool and plant through all modes of transportation						


	PVC door bends of required degree (any radius) with oval access door insertion rubber washer 3 mm (three millimeter) thick, bolts and nuts complete supreme fittings and accessories complete						
18.10	110 mm (One hundred ten millimeter) diameter	4.00	Nos	293.45	Rupees Two hundred ninety three and paise forty five only.	Each	1174.00
19.00	Providing and laying double charged vetrified floor tiles of size 60x60 CM (Sixty into sixty centimeter) (thickness to be specified by the manufacturer) with water absorption less than 0.08% and confirming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick (twenty millimeter) cement mortar 1:4 (one cement is to four sand) jointed with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. complete and as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	30.58	Sqm	1518.10	Rupees one thousand five hundred eighteen and paisa ten only	Per Square metre	46423.00
20.00	Providing and fixing 0.60mm thick prepainted steel sheet of TATA Durashine in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6 mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	6.48	Sqm.	1468.90	Rupees One thousand four hundred sixty eight and paisa ninety only	Per square metre	9518.00
						Total	98681.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil

Supply Depot if available

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP/PWD. Arki.