



Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:-[ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

NO: PWD/BN/TA/NIT/2025-26/- 20880-85 Dated:-03.03.2026  
To

✓  
The Executive Engineer, (IT Cell),  
Nirman Bhawan Nigam Vihar,  
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender  
& Schedule of Quantity.

Yours faithfully,

Executive Engineer  
Baijnath Division  
H.P.P.W.D. Baijnath

**Copy forwarded for information to:-**

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer  
Baijnath Division  
H.P.P.W.D. Baijnath



**"NOTICE INVITING TENDER"**

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 17.03.2026 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 16.03.2026 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 13.03.2026 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Restoration of Baijnath Chobin Balander Road km 0/00 to 14/000 (Under OFC) (SH: Providing and laying thermoplastic strip)	98,732/-	2,000/-	Rs.350/-	One Month
2	Balance work C/O Bhadhar Ghar at Kathog Baijnath Distt. Kangra (HP) (SH: Providing and fixing M S BP Sheet in Facia & interlocking paver block 40mm thick and structural steel work) (Deposit work VKV/2023/1653)	68,565/-	1,400/-	Rs.350/-	One Month
3	C/O Pandit Sant Ram Govt. Degree College Tehsil Baijnath Distt. Kangra (HP) (SH: Dismantling Brick work, Plastering, P/L Kota stone and aluminium work for creating passage b/w two rooms) (Deposit work)	44,282/-	900/-	Rs.350/-	One Month
4	C/O R/wall nearby House of Sh. Doli Ram (Deol) (SH: C/O R/wall at RD 0/00 to 0/005.50) (Deposit work SDF/2024/1651) (Lead 500 mtr)	99,991/-	2,000/-	Rs.350/-	One Month
5	A/R & M/O Office cum Residence at HPPWD Office Bir (SH: Construction of Boundary wall)	96,008/-	2,000/-	Rs.350/-	Two Months

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an undertaking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.

Executive Engineer  
Baijnath Division  
H.P.PWD, Baijnath  
For & On behalf of the Governor of H.P.

# SCHEDULE OF QUANTITY

①

Name of Work :- ~~Reconstruction~~ Restoration of Bajjnath Chobin Balandar Road km 0/00 to 14/000 ( under OFC.)  
(Sh:-Providing and laying Thermoplastic strip )

Estimate Cost: 98,732.00  
Earnest Money: 2,000.00  
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Road marking with hot applied thermoplastic compound with reflectorising glass baord on bitumenous surface. Profviding and laying of hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @ 250 gms/sqm area thickness of 2.5mm is exelusive of surface applied glass beads as per IRC:35. The finished surface to be uniform and free from streaks and holes.complete in all respects as per the direction and entire satisfaction of Engineer-In Charge."The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST; octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	124.63	Per Square meter	792.20	Rupees Seven Hundred Ninety Two And Paise Twenty Only	98,732.00
<b>Quoted Percentage</b>						<b>98,732.00</b>

  
 Executive Engineer  
 Bajjnath Division  
 HPPWD Bajjnath

2

**SCHEDULE OF QUANTITY**

Name of work : Balance work C/O Bhadhar Ghar at Kathog Bajinath Distt. Kangra (H.P.)  
 (S.H. : Providing and fixing M S BP sheet in Facia & interlocking Paver block 40mm thick and structural steel work ) ( Deposit work VKV/2023/1653 )  
 Estimate Cost: 68,565.00  
 Earnest Money: 1,400.00  
 Time Limit : One Month

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing plaining M.S. B.P. sheet 1.66mm (one decimal sixty six millimetre) thick to 2.00mm in eves board/ Facia / Soffit / Ceiling including cutting jointing with gass/electric welding to steel roofs members and applying a coat of red lead primer complete as per PWD specification (frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	11.21	Per square metre	2,600.00	Rupees Two Thousand Six Hundred Only	29,146.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 40 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	16.70	Per Square metre	1,250.00	Rupees One Thousand Two Hundred & Fifty Only	20,875.00
3	Providing and laying mechanically mixed and vibrated reinforced concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	0.13	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	904.00
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	168.00	Per Kilogram	105.00	Rupees One Hundred & Five Only	17,640.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						68,565.00

Executive Engineer  
 Bajinath Division  
 HPPWD Bajinath

3

**SCHEDULE OF QUANTITY**

Name of work : C/O Pandit Sant Ram Govt Degree College Tehsil Bajinath Distt. Kangra (H.P.)  
(S.H. : Dismantling Brick work, Plastering, P/L kota stone and aluminium work for creating Passage b/w two rooms ) ( Deposit work. )

Estimate Cost: 44,282.00  
Earnest Money: 900.00  
Time Limit : One Month

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Demolition above G.L. up to floor two level including disposal of unserviceable material within 20 m (Twenty metres) lead and including cutting the necessary reinforcement and separating out from brick masonry work "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time." "Credit for usable material recovered (e.g. bricks) shall be given to the contractor at the prevailing market rate not exceeding the amount paid for them, after deducting all approved deductions. For example, 1.00 cum of useable brick = 475 bricks x ₹5.00 per brick = ₹2,375 (Rupees Two Thousand Three Hundred Seventy-Five Only) credit shall be taken. The recovery/credit shall be made in accordance with HPPWD conditions for return of materials and prevailing market rates as directed by the Engineer-in-Charge.	1.49	Per Cubic metre	1020.00	Rupees One Thousand & Twenty Only	1,520.00
2	20mm (Twenty millimeter) thick cement plaster in single coat on the fair side of brick/concrete/stone walls for interior plastering upto any floor level including arries, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeters) in girth, in rough side with cement mortar 1:6 (one cement iso six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.59	Per square metre	310.00	Rupees Three Hundred & Ten Only	493.00
3	6mm (six millimeter) cement plaster 1:4 (one cement iso four sand) in ceiling complete including curing complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.10	Per square metre	235.00	Rupees Two Hundred & Thirty Five Only	259.00
4	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.69	Per square metre	125.00	Rupees One Hundred & Twenty Five Only	336.00
5	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papped smooth to give final matter finish to the surface complete "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.69	Per square metre	99.00	Rupees Ninety Nine Only	266.00
6	Providing and laying of Kota stone slab flooring 20mm (average) thick base of cement mortar 1:4 laid over slurry mixed with pigment match the shade of slab 20 mm. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	0.61	Per square metre	2250.00	Rupees Two Thousand Two Hundred & Fifty Only	1,373.00
7	Providing and fixing aluminium work for doors, windows ventilators and partitions with extended built up tubular section / appropriate. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	43.93	Per Kilo gram	650.00	Rupees Six Hundred & Fifty Only	28,555.00
8	Providing and fixing glazing with glass panes of 5 mm thickness (weight not less than 10.00 kg/sqm. in aluminium door, window, ventilator shutters and partition etc with PVC/ncoprens gasket etc. complete as per the architectural drawings and the directions of Engineer-in charge (cost of aluminium snap heading shall be paid in basic item). "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	6.50	Per Square metre	920.00	Rupees Nine Hundred & Twenty Only	5,980.00
9	Removing and re-fixing of old aluminium panel ( in library ) etc. complete as per the architectural drawings and the directions of Engineer-in charge (cost of aluminium snap heading shall be paid in basic item). "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	5,500.00	Rupees Five Thousand Five Hundred Only	5,500.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						44,282.00

Executive Engineer  
Bajinath Division  
HPPWD Bajinath

4

**SCHEDULE OF QUANTITY**

Name of work: C/O R/wall near by House of Sh. Doli Ram ( Deol )  
 ( Sh:- C/O R/wall at RD 0/00 to 0/005.50 ). ( Deposit work SDF/2024/1651 ) ( Lead 500 mtr )

Estimate Cost: 99,991,00/-  
 Earnest Money: 2,000,00/-  
 Time Limit :One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In-Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	6.71	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,946.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 &1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	16.85	Per cubic metre	5500.00	Rupees Five Thousand Five Hundred Only	92,675.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.96	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	3,920.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.00	Each	290.00	Rupees Two Hundred & Ninety Only	1,450.00
<b>Total</b>						<b>99,991.00</b>
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

Executive Engineer  
 Bajinath Division  
 HPPWD Bajinath

5

**SCHEDULE OF QUANTITY**

**Name of work :- A/R & M/O office cum Residence at HPPWD office Bir .  
(SH:- Construction of Boundary wall )**

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	7.20	Per Cum	290.00	Rupees Two Hundred & Ninety Only	2,088.00
2	Providing and laying cement concrete 1:6:12 (One cement isto six sand isto twelve aggregate) graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.58	Per cubic metre	4,200.00	Rupees Four Thousand Two Hundred Only	6,636.00
3	Providing and laying cement concrete 1:3:6 (one cement:three sand:six graded stone aggregate 40mm (forty millimeter) nominal size) and curing complete excluding cost of form work in Foundation and plinth ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.38	Cum.	5,600.00	Rupees Five Thousand Six Hundred Only	18,928.00
4	Providing and Laying precast cement concrete hollow block masonry in wall with cement concrete blocks of size 40 cm x 19 cm x 20 cm including quon blocks jamb blocks and closers etc made of cement concrete 1:4:8 (One cement isto four sand isto eight aggregate) laid with mortar 1:6 ( one :six ) and curing complete ( Clause 4.8.1 "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	7.32	cum	6,750.00	Rupees Six Thousand Seven Hundred & Fifty Only	49,410.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) in foundation Footings and Basis of columns "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	0.092	Per cubic metre	7,000.00	Rupees Seven Thousand Only	644.00
6	12mm (Twelve millimeter) cement plaster 1:4 (One : four ) in ceiling as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	58.10	Sq.m	205.00	Rupees Two Hundred & Five Only	11,911.00
7	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equvalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	58.10	Sqm	110.00	Rupees One Hundred & Ten Only	6,391.00
Quoted rates Percentage in figures						96,008.00
Quoted rates Percentage in words						

Executive Engineer  
Bajnath Division  
HPPWD Bajnath