

**OFFICE OF THE EXECUTIVE ENGINEER
BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA**

No:- PW-BGN-CB/T-1/2025-26-
To

15639-48

Dated:- 31-03-26


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.
cc-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.**


Executive Engineer
Bangana Division
HPPWD Bangana

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.



Executive Engineer
Bangana Division
HPPWD Bangana.



**OFFICE OF THE EXECUTIVE ENGINEER
BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA**

CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2025-26-15639-48 dated 31-03-2026.


Executive Engineer
Bangana Division
HPPWD Bangana




**OFFICE OF THE EXECUTIVE ENGINEER
BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA**

NOTICE INVITING TENDER.

Scaled percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **08.08.2026 up to 10.30 A.M** and same will be opened on the same day at **11.00 AM** in presence of the interested contractors or their authorized representative. The application will be received in this office on at **04.04.2026 upto 03.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **06.04.2026** during office Hours **up to 4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/049 to 0/052.50) Under RRD Head.	98223.00	2000.00	One Month	C&D
2	Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: Formation cutting from Rd 0/250 to 0/295) Under RRD Head.	96204.00	2000.00	One Month	C&D
3	Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/053 to 0/058.50) Under RRD Head.	97294.00	2000.00	One Month	C&D
4	Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: Formation cutting from Rd 0/120 to 0/235) Under RRD Head.	97503.00	2000.00	One Month	C&D
5	Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/059 to 0/062.50) Under RRD Head.	97577.00	2000.00	One Month	C&D
6	Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/063 to 0/066.50) Under RRD Head.	98190.00	2000.00	One Month	C&D

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
Bangana Division
HPPWD Bangana.

On behalf of Governor of Himachal Pradesh.

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana


Name of work:- Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/049 to 0/052.50)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	98223.00
Earnest Money Rs	2000.00
Time Limit:	One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	4.73	Per cubic metre	280.00	1324.00	Rupees One Thousand Three Hundred & Twenty Four Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetrr) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.760	Per Cubic metre	3150.00	8694.00	Rupees Eight Thousand Six Hundred & Ninety Four Only
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	22.970	Per Cubic metre.	3840.00	88205.00	Rupees Eighty Eight Thousand Two Hundred & Five Only
Total in Figures					98223.00	Rupees Ninety Eight Thousand Two Hundred & Twenty Three Only
Qouted Rate in Figures				Excess (+)		
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Thattoon to Bandu Brahmna Km 0/000 to 0/540 (SH: Formation cutting from Rd 0/250 to 0/295)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	96204.00
Earnest Money Rs	2000.00
Time Limit:	One Month

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603.1 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of a useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or /labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	202.05	Per Cubic metre	220.00	44451.00	Rupees Forty Four Thousand Four Hundred & Fifty One Only
2.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603.1 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of an useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or /labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts. A recovery of 13.27cum (thirteen point two seven only) stone to be obtained from excavation cutting at the rate of Rs. 300/-(Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item (10%). including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	132.700	Per Cubic metre	390.00	51753.00	Rupees Fifty One Thousand Seven Hundred & Fifty Three Only
Total in Figures					96204.00	Rupees Ninety Six Thousand Two Hundred & Four Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	

A. J. Kumar
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Thatthoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/053 to 0/058.50)

Name of Bidder/ Bidding Firm/ Company :-


Estimated Cost
Rs 97294.00

Earnest Money
Rs 2000.00

Time Limit:
One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.91	Per cubic metre	280.00	1655.00	Rupees One Thousand Six Hundred & Fifty Five Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetrrre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.360	Per Cubic metre	3150.00	7434.00	Rupees Seven Thousand Four Hundred & Thirty Four Only
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	22.970	Per Cubic metre.	3840.00	88205.00	Rupees Eighty Eight Thousand Two Hundred & Five Only
Total in Figures					97294.00	Rupees Ninety Seven Thousand Two Hundred & Ninety Four Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

4

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: Formation cutting from Rd 0/120 to 0/235)


Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	97503.00
Earnest Money Rs	2000.00
Time Limit:	One Month

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603. Land sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or /labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	203.13	Per Cubic metre	220.00	44689.00	Rupees Forty Four Thousand Six Hundred & Eighty Nine Only
2.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603. Land sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or /labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts. A recovery of 13.27cum (thirteen point two seven only) stone to be obtained from excavation cutting at the rate of Rs. 300/-(Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item (10%), including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	135.42	Per Cubic metre	390.00	52814.00	Rupees Fifty Two Thousand Eight Hundred & Fourteen Only
Total in Figures					97503.00	Rupees Ninety Seven Thousand Five Hundred & Three Only
Quoted Rate in Figures					Excess (+)	
Quoted Rate in Figures					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

(5)

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/059 to 0/062.50)

Estimated Cost Rs **97577.00**

Earnest Money Rs **2000.00**

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: **One Month**

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.12	Per cubic metre	280.00	1434.00	Rupees One Thousand Four Hundred & Thirty Four Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetrre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.520	Per Cubic metre	3150.00	7938.00	Rupees Seven Thousand Nine Hundred & Thirty Eight Only
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	22.970	Per Cubic metre.	3840.00	88205.00	Rupees Eighty Eight Thousand Two Hundred & Five Only
Total in Figures					97577.00	Rupees Ninety Seven Thousand Five Hundred & Seventy Seven Only
Quoted Rate in Figures					Excess (+)	
Less (-)						

Awllan
**Executive Engineer
Bangana Division
HP.PWD. Bangana**

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Thathoon to Bandu Brahmna Km 0/000 to 0/540 (SH: C/o Wire crate from Rd 0/063 to 0/066.50)

Estimated Cost Rs **98190.00**

Earnest Money Rs **2000.00**


Name of Bidder/ Bidding Firm/ Company :-

Time Limit: **One Month**

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.51	Per cubic metre	280.00	1543.00	Rupees One Thousand Five Hundred & Forty Three Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.680	Per Cubic metre	3150.00	8442.00	Rupees Eight Thousand Four Hundred & Forty Two Only
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22.970	Per Cubic metre.	3840.00	88205.00	Rupees Eighty Eight Thousand Two Hundred & Five Only
Total in Figures					98190.00	Rupees Ninety Eight Thousand One Hundred & Ninety Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana