



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
Office of the  
Executive Engineer  
Barsar Division HPPWD Barsar**

**Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in). Email:- [ee-bsr-hp@nic.in](mailto:ee-bsr-hp@nic.in)**

**Phone No:- 01972-288041**

**Fax No. 01972-288041**

No:-PW-BSR-E-105/2025-26-  
To

16177-207

Dated:-

13.3.26


The Executive Engineer (IT Cell),  
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16<sup>th</sup> July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity  
And "A" Certificate

  
Executive Engineer  
Barsar Division  
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, 8<sup>th</sup> Circle, HPPWD, Hamirpur.
2. The Assistant Engineer, Sub Division, HPPWD Barsar and Bijhari.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt. of C Branch in this office.
6. Notice Board.

  
Executive Engineer  
Barsar Division  
HPPWD Barsar.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**  
Office of the Executive Engineer Barsar Division HPPWD Barsar  
Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in) Email:- [ee-bar-hp@nic.in](mailto:ee-bar-hp@nic.in) Phone No:- 01972-288041  
Fax No. 01972-288041.

**NOTICE INVITING TENDER.**

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **19.03.2026 up to 10.30 A.M.** and same will be opened on the same day at **11.00 A.M.** in presence of the interested contractors or their authorized representative. The application must be reached in this office on dated **17.03.2026 upto 2.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **18.03.2026** during office hours till **4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from, earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions.. The contractor should be registered as dealer under GST Act, Valid copy of Registration as required along with latest returns, Copy of PAN Card, EPF along with latest returns failing which no tender form will be issued to him. All the required documents must be attached with the application.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender form	Time limit	Eligible Class
1.	Restoration of rain Damages on Barsar Shahtalai road , Maslana Bhutlar road, Mehre Jabble Kherian road (SH:- bush cutting )	93,660/-	1900/-	350/-	One Month	C & D
2.	Restoration of rain Damages on Armand Mandir Loharwin road , Jeoli Devi Saheli Bhebar road , Dandroo Nuel road (SH:-Maintenance of earthen shoulder & unlined surface drain )	92,946/-	1900/-	350/-	One Month	C & D
3.	Restoration of rain damages on Chakmoh Nalwar Bhatar road Km 0/00 to 5/500 (SH:- Removal of slips, Surface dressing and C/O unlined surface drain at various Rds )	94,241/-	1900/-	350/-	One Month	C & D
4.	Restoration of rain damages on Raily Jajri Ghorii Dhabiri road Km 0/00 to 4/600 (SH:- Removal of slips, Surface dressing and C/O unlined surface drain at various Rds)	94,468/-	1900/-	350/-	One Month	C & D
5.	SDP/2024/124 C/O Government High School at Kudhar Tehsil Barsar District Hamirpur (SH:- Balance work of 3 Nos Toilet block (Girls) (DC Deposit)	78,649/-	1600/-	350/-	Two Month	C&D

**Certified that the tenders for Job No. 1 to 5 are of urgent nature and in public interest.**

**HIM SUCHANA AVAM JAN SAMPARK.**



Executive Engineer  
Barsar Division HPPWD Barsar.

On behalf of Governor of  
Himachal Pradesh.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**Office of the Executive Engineer Barsar Division HPPWD Barsar**

**Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in). Email:- [ee-bar-hp@nic.in](mailto:ee-bar-hp@nic.in)**


**Phone No:- 01972-288041**

**Fax No. 01972-288041.**

**CERTIFICATE**

Certified that the works are of urgent in nature and for larger public interest so there is exigency/emergency in calling these tenders without press vide this office letter No:-PW-BSR-E-105/2025-26- 16177207 Dated 13/08/26



Executive Engineer  
Barsar Division, HPPWD  
Barsar. 

279

**Draft Schedule of Quantity**

Name of work:- Restoration of rain Damages on Barsar Shahtalai road , Maslana Bhutlar road, Mehre Jabble Kherian road (SH:- bush cutting )

JobNo |  
Estimated Cost Rs:-93,660.00  
Earnest Money Rs:- 1900.00  
Time Limit :- One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c		Unit	Amount
			Figure	G.S.T words		
1	Clearing jungle including up rooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm (thirty centi meter) measured at a height of 1m (meter) above ground level and removal of rubbish up to a distance of 50m (fifty meter) outside the periphery of the area cleared including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	8400.00	11.15	Rupees Eleven And Paise Fifteen Only	Per square Metre	93660.00
Total:-						93660.00

*Draft Schedule of Quantity approved.  
for Rs, 93,660/only. (Rupees ninety Three  
Thousand, Six hundred, sixty only.)*

Executive Engineer  
Barsar Division  
HPPWD Barsar

280

**Draft Schedule of Quantity**

Job No **2**  
 Estimated Cost Rs:- 92,946.00  
 Earnest Money Rs:- 1900.00  
 Time Limit :- One Month

Name of work:- Restoration of rain Damages on Armand Mandir Loharwin road , Jeoli Devi Saheli Bhebar road ,  
 Dandroo Nuel road (SH:-Maintenance of earthen shoulder & unlined surface drain )

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Maintenance of earthen shoulder (filling with fresh selected soil making up less of material / irregularities on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000 mtrs (one thousand meter) as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1248.00	Square metre	52.00	Rupees Fifty Two Only	Per square Metre	64896.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m (three meter) and lead of 50 m (fifty meter) (average lead 25 m) (average lead twenty five meter) as per Technical Specification Clause 307 as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	850.00	metre	33.00	Rupees Thirty Three Only	Per Running Metre	28050.00
Total:-							92946.00

*Draft Schedule of Quantity approved for  
 Rs. 92,946/- only (Rupees ninety two thousand,  
 nine hundred and forty six only.)*

*[Signature]*  
 Executive Engineer  
 Barsar Division  
 HPPWD Barsar

274


**Draft Schedule of Quantity**

Name of Work:-Restoration of rain damages on Chakmoh Nalwar Bhatner road Km 0/00 to 5/500 (SH:- Removal of slips, Surface dressing and C/O unlined surface drain at various Rds )

Job No- 3  
Estimated Cost Rs:-94,241.00

Sr. No	Description of Item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m (one point five meter) and lead upto 1000m (one thousand meter) as per technical specification 302.3.5 and 1611 including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	195.00	cubic metre	165.00	Rupees One Hundred Sixty Five Only	Per Cubic Metre	32175.00
2	Maintenance of earthen shoulder (filling with fresh slected soil making up less of material / irregularations on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000 mtrs (one thousand meter) as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government .	1003.20	Square metre	52.00	Rupees Fifty Two Only	Per square Metre	52166.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero point fourty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (fifty meter) (average lead 25 m (twenty five meter) as per Technical Specification Clause 307 as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	300.00	metre	33.00	Rupees Thirty Three Only	Per Running Metre	9900.00
						Total:-	94241.00

*Draft Schedule of Quantity approved for Rs, 94,241/only (Rupees Ninety four Thousand. Two hundred forty one only.*

  
Executive Engineer  
Barsar Division  
HPPWD Barsar

**Draft Schedule of Quantity**

Name of Work:- Restoration of rain damages on Raily Jajri Ghori, Dhabiri road Km 0/00 to 4/600 (SH):- Removal of slips, Surface dressing and C/O unlined surface drain at various Rds)

Job No- 4

Estimated Cost Rs:-94,468.00

Earnest Money Rs:-1900.00

Time Limit :- One month

Sr. No	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m (one point five meter) and lead upto 1000m (one thousand meter) as per technical specification 302.3.5 and 1611 including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government .	156.00	165.00	Rupees One Hundred Sixty Five Only	Per Cubic Metre	25740.00
2	Maintenance of earthen shoulder (filling with fresh slected soil making up less of material / irregutations on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000 mtrs (one thousand meter) as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	1144.00	52.00	Rupees Fifty Two Only	Per square Metre	59488.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero point fourty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (fifty meter) (average lead 25 m (twenty five meter) as per Technical Specification Clause 307 as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government	280.00	33.00	Rupees Thirty Three Only	Per Running Metre	9240.00
					Total:-	94468.00

*Draft Schedule of Quantity approved for Rs 94,468/only (Rupees hinty four Thousand, four hundred Sixty eight only.)*

285

Job-5

**Draft Schedule of Quantity**

Name of Work:- SDP/2024/124 C/O Government High School at Kudhar Tehsil Barsar District Hamirpur (SH:-  
Balance work of 3 Nos Toilet block (Girls) (DC Deposit)

Estimated Cost Rs:- 78,649.00

Earned Money Rs:-1600.00

Time Limit :- Two month

Sr. No	Description of Item	Quantity		Rate inclusive all taxes i/c		Unit	Amount
				Figure	G.S.T words		
1	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete. including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	0.66	Cubic metre	2000.00	Rupees Two Thousand Only	Per cubic metre	1320.00
2	Providing and laying mechanically Mixed cement concrete 1:6:12 (one cement : six sand : twelve graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) and curing complete excluding centring shuttering in foundation and plinth including carriage of materials in all lead and lift as per direction of Engineer-in- Charge.The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	0.49	cubic meter	4200.00	Rupees Four Thousand Two Hundred Only	Per cubic meter	2058.00
3	Providing and laying 6 mm (six millimetre) cement mortar 1:3 (one cement : three fine sand) including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	6.56	Square metre	209.70	Rupees Two Hundred Nine And Paise Seventy Only	Per square metre	1376.00
4	Providing and laying 15mm (fifteen millimetre) cement plaster in Cement Mortar 1:6 (one cement: six sand) in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	18.08	Square metre	261.65	Rupees Two Hundred Sixty One And Paise Sixty Five Only	Per square metre	4731.00
5	Providing and applying birla white wall care putty over plaster surface after thoroughly brushing the surface free form mortar frops dust loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	6.56	Square metre	99.85	Rupees Ninety Nine And Paise Eighty Five Only	Per square metre	655.00

6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	6.56	Square metre	80.25	Rupees Eighty And Paise Twenty Five Only	Per square metre	526.00
7	Providing and laying Duro stone vitrified tiles Kajaria , NITCO (300x300mmx10mm) (three hundred into three hundred millimeter into ten millimeter) in grey/coloured of required shade in flooring, treads of steps and landing laid on a bed of 12mm (twelve millimetre ) thick cement mortar 1:3 (one cement : three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete. including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	6.56	square metre	1432.65	Rupees One Thousand Four Hundred Thirty Two And Paise Sixty Five Only	per square metre	9398.00
8	Providing and laying kajaria/Nitco make white glazed tiles 6 mm (six millimeter) thick size 30x45cm (thirty into forty centimetre) in skirting risers of steps and dado 12 mm(twelve millimeter ) thick cement mortar 1:3 (one cement : three sand) and jointed with cement slurry, finishing with flush pointing in white cement including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	10.08	Square metre	1253.35	Rupees One Thousand Two Hundred Fifty Three And Paise Thirty Five Only	per square metre	12634.00
9	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately). Second class teak wood including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	0.085	cubic metre	109629.10	Rupees One Lakh(s) Nine Thousand Six Hundred Twenty Nine And Paise Ten Only	Per Cubic metre	9318.00
10	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws 40mm (Fourty millimetre) thick as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	2.85	square metre	2779.10	Rupees Two Thousand Seven Hundred Seventy Nine And Paise Ten Only	per square metre	7920.00

11	Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil greas dirt and other foreign matter Sand papering and knotting ready mixed paint brushing wood primer pink including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	9.04	Square metre	42.00	Rupees Forty Two Only	Per square metre	380.00
12	Painting two coat (excluding priming coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt dust and other foreign matter sand papering & stoping. With enamel paint other then white.including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	9.04	Square metre	97.10	Rupees Ninety Seven And Paise Ten Only	Per square metre	878.00
13	Providing and fixing 600x120x5 mm (six hundred into one hundred twenty into five) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P.(chromium plated) brass brackets and guard rail complete fixed with 40 mm (forty millimeter) long screws, rawl plugs etc., complete upto floor all level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government .	1.00	Numbers	796.95	Rupees Seven Hundred Ninety Six And Paise Ninety Five Only	Each	797.00
14	Steel work welded in built up sections/ framed work, (TATA/SAIL/Apollo/ JSW Make ) including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	47.70	Kilogramme	115.00	Rupees One Hundred Fifteen Only	per kilogramme	5486.00
15	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40 mm (forty millimetre ) thick with 20 mm(twenty millimetre) nominal size stone aggregate upto all floors level. including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	22.28	Square metre	457.40	Rupees Four Hundred Fifty Seven And Paise Forty Only	Per square metre	10191.00

16	Constructing brick masonry manhole in cement mortar 1:4 (one cement : four coarse sand) with R.C.C. top slab with 1:1.5:3 mix (one cement : One & Half coarse sand (zone- III) : 3 graded stone aggregate 20 mm (twenty millimetre) nominal size), foundation concrete 1:4:8 mix (one cement : four coarse sand (zone- III) : Eight graded stone aggregate 40 mm (forty millimetre) nominal size), inside plastering 12 mm (twelve millimetre) thick with cement mortar 1:3 (one cement : three coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (one cement : Two coarse sand : four graded stone aggregate 20 mm (twenty millimetre) nominal size) finished with a floating coat of neat cement complete as per standard design Inside size 90x80 cm (ninety into eighty centimetre) and 45cm (forty five centimetre) deep including C.I. cover with frame (light duty) 455x610 mm (four hundred fifty five into six hundred ten millimetre) internal diameter, total weight of cover and frame to be not less than 38kg (thirty eight kilogram (weight of cover 23 kg (twenty three kilogram) and weight of frame 15 kg)	1.00	Numbers	10981.25	Rupees Ten Thousand Nine Hundred Eighty One And Paise Twenty Five Only	Each	10981.00
					<b>Total:-</b>		<b>78649.00</b>

*Draft schedule of quantity approved  
for Rs 78,649 only (Rupees Seventy  
Eight Thousand. Six Hundred forty nine only)*

  
Executive Engineer  
Barsar Division  
HPPWD Barsar