



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"

Scaled percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **11-03-2026** up to 11.00 AM, and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 10-03-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 10-03-2026 up to **1.00 PM.**

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O Office cum Residential Building of AE HPPWD Sub Division Dheera Distt. Kangra (SW:- Providing and fixing Kitchen Cabinet & Water supply & Snitary Installation work)	94,021/-	2000/-	Three Month	350/-
2	A/R & M/O Office cum Residential Building of AE HPPWD Sub Division Dheera Distt. Kangra (SW:- Providing and fixing Curtain rod, Painting work, SITC LED Solar light and other repair work)	99,296/-	2000/-	Three Month	350/-
3	A/R & M/O Office cum Residential Building of AE HPPWD Sub Division Dheera Distt. Kangra (SW:- Providing and Laying Tile Flooring & other repair work)	95,660/-	2000/-	Three Month	350/-
4	A/R & M/O to AE Residenc cum office at Bhawarna under Sub Division Bhawarna (SH:- Painting & WSSI work)	99,998/-	2000/-	Three Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh
Dated:- 02-03-2026

No. PWD/BWD/TA/NIT/2025-26/

15387-96

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala,
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur,
3. All the Assistant Engineers under this Division,
4. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office,
6. Notice Board.

Executive Engineer,
Bhawarna Division,
HPPWD, Bhawarna.



Ministerial Resident
Public Works Department
4th Floor, 2nd Stage, Shivajinagar, 5th Cross, Bangalore (K.A.) 560003
Telephone 547777, e-mail: resident@pwr.kva.gov.in

CERTIFICATE

I certify that works are being called of an
emergency nature and of large public interest as there is exigencies/ emergency in calling
these works without prior call this office letter No. PWD/BWD/TA/NET/2025-26-
15282-96 dated 03-03-2026.


Executive Engineer,
Shivajinagar Division,
PWD, Bangalore

Schedule of Quantity

Name of work :- A/R & M/O Office Cum ~~Non~~-Residential Building of AE HPPWD Sub Division Dheera ,Distt- Kangra (HP) (SH :- Providing and Fixing Kitchen Cabinet & Water Supply & Sanitary Installtion work in Office Cum ~~Non~~-Residential Building.

Estimated Cost :- Rs. 94,021/-
Earnest Money :- Rs. 1900/-
Time Limit :- Three Months


S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing high density high moisture resistance (HDHMR) Board of cabinet work made of 18 mm thick high density high moisture resistance board which involves vertical partitions , shelves ,top and bottom rail of cabinet/cupboard including both sides 18 mm board finished of approved shade including blum cabinet hinges & cubboard lock complete as per desin/ Architectural drawings and as per HPPWD specifaions or as directed by th Enginner -in - charge. including carriage of material with in all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.68	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	Per Square metre	26620.00
2	Providing and fixing high density high moisture resistance (HDHMR) Board of cabinet/cupboard shutter work made of 18 mm thick high density high moisture resistance board including both sides 18 mm board finished of approved coloured shade including blum cabinet hinges & cubboard lock complete as per desin/ Architectural drawings and as per HPPWD specifaions or as directed by th Enginner -in - charge, including carriage of material with in all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.60	2800.00	Rupees Two Thousand Eight Hundred Only	Per Square metre	10080.00
3	Providing and fixing Megnatic door catcher for cup board and cabnit work as per direction of Engineer-In -Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	10.00	39.05	Rupees Thirty Nine And Paise Five Only	Each	391.00
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, w/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge Concealed work, including cutting chases and making good the walls etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	18.00	350.00	Rupees Three Hundred Fifty Only	Per running metre	6300.00
4.1	20 mm dia	24.00	280.00	Rupees Two Hundred Eighty Only	Per running metre	6720.00
4.2	15 mm dia					

5	Providing and fixing 75 mm (Seventy five millimetre) diametre high pressure P.V.C spigot and socket soil, waste and ventilating pipe of Supreme/Finolex/Prince working pressure 4.6 kg/cm ² (Four decimal Six kilogram per square centimetre) I.S.I Marked including fixing with approved adhesive etcetra complete including carriage of material within all leads, lifts and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	10.00	150.00	Rupees One Hundred Fifty Only	Per running metre	1500.00
6	Providing and fixing 110 mm (One hundred ten millimetre) diametre high pressure P.V.C spigot and socket soil, waste and ventilating pipe of Supreme/Finolex/Prince working pressure 4.6 kg/cm ² (Four decimal Six kilogram per square centimetre) I.S.I Marked including fixing with approved adhesive etcetra complete including carriage of material within all leads, lifts and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	12.00	250.00	Rupees Two Hundred Fifty Only	Per running metre	3000.00
7	Providing and fixing vitreous china European type W.C of star sr. No 20087 (S-50) of size 57x35x39 cm (fifty seven into thirty five into thirty nine centimeter) wash down water closet hindware/jaguar/cera of star white/ snow white including jet pressure integral P or S trap including jointing the trap with soil pipe in fixture (seat cover/ jet pressure to be paid separtely) including entire carriage of materials within all leads and lifts as per direction of Engineer-in-charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	4330.20	Rupees Four Thousand Three Hundred Thirty And Paise Twenty Only	Each	8660.00
8	Providing and fixing 10.00 (Ten) litres capacity P.V.C low level dual flushing cistern (Sleek plus) of Cera/Hindware/Jaquir with a pair of G.I.or mild steel brackets and fittings such as PVC syphonic appratus, mosquito proof lid of PVC union and coupling for connection with intet, outlet and over flow pipe including cutting holes and making good the same and connection the flush board with cistern and closet (over flow pipe to be measured and paid for separately) including entire carriage of materials within all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.00	1050.00	Rupees One Thousand Fifty Only	Each	2100.00
9	Providing and fixing vitreous china wash basin Delta No 10010 and size 55x40 cm (fifty five into forty centimeters) Hindware/Cera/Jaguar with double hole for pillar trap with C.I or M.S. brackets including hole in walls and making good the same (under counter basin) including all fitting complete in all respect including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	1800.00	Rupees One Thousand Eight Hundred Only	Each	3600.00

10	Providing and fixing heavy quality stainless steel kitchen sink of approved standard ISI marked with drain board and C.P. waste pipe C.I. or M.S. brackets painted white i/c cutting holes and making good the same including fitting 600x450x250 mm (six hundred into four hundred fifty into two hundred fifty millimetre) with bowl depth 20 mm (twenty millimetre) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	1.00	2800.00	Rupees Two Thousand Eight Hundred Only	Each	2800.00
11	Providing and fixing PVC waste pipe for wash basin or sink including necessary fitting and carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	3.00	90.00	Rupees Ninety Only	Each	270.00
12	Providing and fixing 40 mm dia (Forty millimetre) rubber plug for wash basin and fittings including testing of joints with approved adhesive etcetera including carriage of materials within all leads and lifts complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	3	75.10	Rupees Seventy Five And Paise Ten Only	Each	225.00
13	Providing and fixing 15 mm nominal bore unplasticised PVC connection pipe with brass unions 45 cm length and fittings including testing of joints with approved adhesive etcetera including carriage of materials within all leads and lifts complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5	83.00	Rupees Eighty Three Only	Each	415.00
14	Providing and fixing 15 mm bath Hand shower with angular and rest holder including necessary fitting and carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2	980.00	Rupees Nine Hundred Eighty Only	Each	1960.00
15	Providing and fixing 600mmx450mm (six hundred millimetre into four hundred fifty millimetre) beveled edge mirror of superior glass mounted on 6mm (six millimetre) thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. screws and washers of Atul/Modi Guard/ Golden fish including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	3	650.00	Rupees Six Hundred Fifty Only	Each	1950.00
16	Providing and fixing C.P. brass towel rail size 750x20mm (Seven hundred fifty into twenty millimetre) of continental series of Jaguar/Classic of Hindware/Cera complete with C.P. brass brackets fixed to wooden plugs with C.P. brass socket including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2	550.00	Rupees Five Hundred Fifty Only	Each	1100.00

17	Providing and fixing stainless steel Towel ring of continental including complete fitting entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2	400.00	Rupees Four Hundred Only	Each	800.00
18	Providing and fixing stainless steel soap dish of ESS with brackets fixed with cleats with screws, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3	220.00	Rupees Two Hundred Twenty Only	Each	660.00
19	Providing and fixing 15mm (Fifteen milimetre) diameters C.P. brass bib tap of continental series of Jaquar/ Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal/ Vintage series of Kerovite as per specifications including carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00	850.00	Rupees Eight Hundred Fifty Only	Each	5100.00
20	Providing and fixing C.P. brass pillar tap of Continental/Classic/ Floral series of Jaquar/Hindware/Cera 15mm (fifteen millimetre) diametre with capstan head (Heavy duty makes ISI marked No. 8931 & 8934) as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.00	1050.00	Rupees One Thousand Fifty Only	Each	3150.00
21	Providing and fixing PVC Floor Trap size 110x75 mm (one hundred ten into seventy five millimeters) ISI marked self cleaning design including fixing with approved adhesive cost of cutting and making good the wall and floor complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	6.00	250.00	Rupees Two Hundred Fifty Only	Each	1500.00
22	Providing and fixing 100mm (One hundred milimetres) nominal size diameters CP grating of ESS or nahni trap of approved brand complete, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	6.00	180.00	Rupees One Hundred Eighty Only	Each	1080.00
23	Providing and fixing casealed C P brass stop cock Continental/Classic sreies /floral series of Jaguare/Hindware/Cera 15mm (fifteen millimetre) dia (Heavey duty makes ISI marked) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00

24	Providing and fixing 15mm (fifteen millimetre) C.P. Brass Angle valve of Continental Series of Jaguar contess plus series /Hindware / Ocean series of Nintage series of Kerovite/ hindon series of Jal/ Cera/ Jal as per specifications with nuts & bolts including carriage of material within all leads, lifts, and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	4.00	450.00	Rupees Four Hundred Fifty Only	Each	1800.00
25	Providing and fixing CP Brass extension nipples ncluding carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	8.00	61.25	Rupees Sixty One And Paise Twenty Five Only	Each	490.00
				Total :-		94021.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- A/R & M/O office Cum Residential Building of AE HPPWD Sub-Division Dheera, Distt. Kangra (HP). (SW:- Providing and Fixing Curtain rod, Painting work, SITC LED Solar light and other Repair work in office Cum Residential Building).


Estimated Cost :- 99,296/-
Earnest Money :- 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing cement partical board 12mm (millimetre) ceiling of approved quality with butt jointing and nail (frame work and cover fillets to be paid for separately as per H.P.P.W.D. specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads lifts and other incidental. The rate is inclusive of octroi, royalty, malkana, sales tax, toll tax, GST or all type of other taxes imposed by the Government	24.80	850.00	Rupees Eight Hundred Fifty Only	Per Square metre	21080.00
2	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows i/c black enamelled in but hinges with necessary screws 35mm (Thirty five millimetre) thick Second class deodar wood .The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, The rate is inclusive of octroi, royalty, malkana, sales tax, toll tax, GST or all type of other taxes imposed by the Government.	3.78	1507.80	Rupees One Thousand Five Hundred Seven And Paise Eighty Only	Per Square metre	5699.00
3	Providing and fixing 20mm (Twenty millimetre) diameter chromium plated brass curtain rod and brackets plugs etc. complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.60	373.15	Rupees Three Hundred Seventy Three And Paise Fifteen Only	Per Running metre	1343.00
4	Providing and Fixing of Curtains in Doors & windows with all leads, lift and other incidents (Curtains Doors & Window's) complete including cost and carriage of material with in all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-in-Charge Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	22.00	350.00	Rupees Three Hundred Fifty Only	Each	7700.00
5	Providing and fixing 150x10mm (One hundred fifty into ten millimetre) matt finished aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.00	80.00	Rupees Eighty Only	Each	320.00

6	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metling the surface The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	282.18	95.00	Rupees Ninety Five Only	Per Square metre	26807.00
7	Painting two coats (excluding priming coat)on new wood and wood based surfacs with angel paint brushing to give an even shade including cleaning the surfaces of all dirt dust and other design sand papering and knotting with angle paint other than white including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive cost and carnage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge Rate inclusive toll tax, GST and any other taxes imposed by the government.	38.54	65.00	Rupees Sixty Five Only	Per Square metre	2505.00
8	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	23.22	75.00	Rupees Seventy Five Only	Per Square metre	1742.00
	Supplying, Installation, Testing and Commissioning of all in one integrated LED solar light consists of solar photovoltaic module, battery, battery management system, control electronics, LED driver, PIR sensor, inter-connecting cables and pole mounting piece integrated into the luminaire as a single unit Solar street light with IP65 ingress protection having a 2000 lumen output, 28Wp high efficiency polycrystalline solar panel, highly efficient MPPT based charge controller and 06 Mtr GI Tubular/round Pole, 2 section with base plate & J bolt, Top dia: 48-60mm and complete within all respect complete as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.00	11800.00	Rupees Eleven Thousand Eight Hundred Only	Each	23600.00

10	<p>Supplying, Installation, Testing and Commissioning of Wall Mounted Electric Water Heater (Geyser) with inbuilt 15 litres water storage stainless steel body tank, 02 kW rated copper heating element, 08 bar max. operating pressure, 05 star BEE rating, fully automatic, thermostat, indicators etc. This also includes all accessories required during installation like safety valves, NRV, connection pipes (hot & cold), suitable capacity electric plug top, electric cable etc. and suitable for 01 phase, 230 V, 50 Hz, AC electric supply as per standard practice and directions of Engineer In Charge Make- /Bajaj/ Crompton/ Havells / Jaquar / Usha or equivalent. complete as per the direction of Engineer-in-Charge including carnage of materials with in all leads, lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax , sales tax or other taxes imposed by the government.</p>	1.00	8500.00	Rupees Eight Thousand Five Hundred Only	Each	8500.00	
Quoted rates percentage in figures						Total	99296.00
Quoted rates percentage in words							


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity


Name of work :- A/R & M/O Office Cum ~~Non~~-Residential Building of AE HPPWD Sub Division Dheera ,Distt- Kangra (HP) (SH :-
Sub Wqrk :-Providing and Laying Tile Flooring & Other Repair work of Office Cum ~~Non~~-Residential Building)

Estimated Cost :- Rs. 95,660/-
Earnest Money :- Rs. 1900/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Dismantling W.C. Pan of all sizes including disposal of dismantled materials including malba all complete as per directions of Engineer-in- Charge including carriage of material with in all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	2.00	56.35	Rupees Fifty Six And Paise Thirty Five Only	Per Square metre	113.00
2	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within all lead as directed by th Enginner -in - charge, including carriage of material with in all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	3.00	421.85	Rupees Four Hundred Twenty One And Paise Eighty Five Only	Per Square metre	1266.00
3	Dismantling tile work in floors and roofs etc. laid in cement mortar including stacking material within all lead as directed by th Enginner -in - charge, including carriage of material with in all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	49.82	31.20	Rupees Thirty One And Paise Twenty Only	Each	1554.00
4	Demolishing cement concrete work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres as per direction of Engineer - in- charge as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.22	1004.45	Rupees One Thousand Four And Paise Forty Five Only	Per Cubic metre	3234.00
5	Second class half brick work using common burnt clay building bricks in cement mortar 1:4 (one cement isto four sand) in super structure up to all floor level as per PWD specification, drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.10	950.00	Rupees Nine Hundred Fifty Only	Per Square metre	1995.00

6	15mm (fifteen millimetre) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	2.10	180.00	Rupees One Hundred Eighty Only	Per Square metre	378.00
7	Providing and laying 300x300x10 mm (three hundred into three hundred into ten millimeters) thick antiskid ceramic tiles of premum quality of Nitco/ Kajaria/ Somany/ Well/ Johnson as per approved shade and manufacture in flooring over 12 mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per approved specification, drawing and design including entire . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.76	980.00	Rupees Nine Hundred Eighty Only	Per Square metre	10545.00
8	Providing and laying 300x450 (three hundred into four hundred fifty millimeter) acid resistance vetrified tiles of Restile/ Nitco/ Rak/ Simpolo/ Kajaria/ Johnson as per approved shade and design as per drawing and specification in flooring, skirting and dado laid over 12 mm (twelve millimeters) thick cement mortar 1:3 (one cement: three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as reured complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In- Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	39.06	995.00	Rupees Nine Hundred Ninety Five Only	Per Square metre	38865.00
9	Providing and laying 600x600 mm (Six hundred into six hundred millimetre) vitrified floor tiles (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percent) and conforming to IS 15622, of approved make, in all colours and shades, laid on 20mm (Twenty millimetre) thick cement mortar 1:4 (One cement isto four coarse sand), jointing with grey cement slurry at the rate 3.3 kg/ sqm (Three decimal three kilogram per square metre) including grouting the joints with white cement and matching pigments etcetra, complete as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	23.40	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square Metre	33930.00

10	Providing and fixing 5mm (Four millimetre) thick Float Glass panes with putty and nails including removal of broken glass panes complete in steel doors, windows, clerestory windows, all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government..	5.04	750.00	Rupees Seven Hundred Fifty Only	Each	3780.00
				Total :-		95660.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work:- A/R & M/O to AE Residence cum office at Bhawarna under Sub Division Bhawarna. (SH:- Painting & WS SI Work etc)

Estimated Cost :- Rs.99,998/-
 Earnest Money :- Rs.2000/-
 Time Limit :- Three Months


S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Painting two coats(excluding priming coat)on new steel and other metal surfaces with aluminium paint,brushing to give an even shade including cleaning the surface of the dirt,dust and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	422.60	65.00	Rupees Sixty Five Only	Per Square metre	27469.00
2	Providing and fixing 32mm (Thirty two millimetre) diametre to C.P. brass waste and plug for glazed ware sinks, basins, etc with long screwed shank and fly nut and fixed to steel pipe including vulcanite plug, brass chain and stud including for carriage of materials within all leads, lifts and other incidentals. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5.00	1000.00	Rupees One Thousand Only	Each	5000.00
3	Providing and fixing 600mmx450mm (six hundred millimeter into four hundred fifty millimeter) beveled edge mirror of superior glass mounted on 6mm (six millimeter) thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. screws and washers of Atul/Modi Guard/ Golden fish including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	900.00	Rupees Nine Hundred Only	Each	900.00
4	Providing and fixing C.P. brass towel rail size 600x20mm (Six hundred into twenty millimetre) of continental series of Jaguar/Classic of Hindware/Cera/ floral series of Hindustan series of Jal with C.P. brass brackets fixed to wooden plugs with C.P. brass screws including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing as per as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government	1.00	650.00	Rupees Six Hundred Fifty Only	Each	650.00
5	Providing and fixing CP brass soap dish holder of CERA make complete including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	1.00	450.00	Rupees Four Hundred Fifty Only	Each	450.00
6	Providing and fixing C.P. brass towel ring of continental series of Jaguar/Classic of Hindware/Cera complete with C.P. brass brackets fixed to wooden plugs with C.P. brass socket including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	350.00	Rupees Three Hundred Fifty Only	Per Square metre	350.00

7	Providing and fixing 600x120mm (Six hundred into one hundred twenty millimetres) glass shelf with C.P. brass brackets and guard rail complete fixed to wooden plugs with C.P. brass screws, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	350.00	Rupees Three Hundred Fifty Only	Each	350.00
8	Providing and fixing chromium plated brass soap dish of ESS with C.P. brass brackets fixed with cleats with C.P. brass screws, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
9	Providing and fixing 15mm (Fifteen millimetres) diameters C.P. brass bib tap of continental/ Hindware/Classic Series within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
10	Providing and fixing cased C.P. brass stop cock Continental/Classic series /floral series of Jaguar/Hindware/Cera 15mm (Fifteen millimetre) dia (Heavy duty makes ISI marked) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	6.00	250.00	Rupees Two Hundred Fifty Only	Each	1500.00
11	Providing and fixing CP brass one hole basin mixing faucet 15mm (Fifteen millimeters) dia of era/Jal made including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	1.00	1800.00	Rupees One Thousand Eight Hundred Only	Each	1800.00
12	Providing and fixing CP brass wall mixing faucet for shower and bath hand shower 15mm (Fifteen millimeters) dia of era/Jal made including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	1.00	2500.00	Rupees Two Thousand Five Hundred Only	Each	2500.00
13	Providing and fixing toilet paper holder CP brass with flap of CERA make complete including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	1.00	400.00	Rupees Four Hundred Only	Each	400.00
14	Providing and fixing PTMT/PVC jet spray of continental series/clasic series/floral series of jaguar/ hindware/ cera for European seat of approved brand and manufacture, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	550.00	Rupees Five Hundred Fifty Only	Each	550.00
15	Providing and fixing 100 mm dia chromium plated grating of superior quality for floor, gully or nahani trap	4.00	250.00	Rupees Two Hundred Fifty Only	Each	1000.00

6	Providing and fixing 32mm (Thirty two millimetre) diameter PVC Waste pipe for wash basin or sink including brass check net with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	150.00	Rupees One Hundred Fifty Only	Each	150.00
17	Providing and fixing PVC connection pipe brass union 450 mm (Four hundred millimetre) length 15mm (Fifteen millimetre) dia ISI marked of including fitting within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	6.00	150.00	Rupees One Hundred Fifty Only	Each	900.00
18	Providing and fixing C.P. brass full way valve with wheel of continental series/ classic series/ floral series of Hindware/Jaguar/Cera within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	350.00	Rupees Three Hundred Fifty Only	Each	350.00
19	Providing and fixing PVC Floor Trap size 110x75 mm (one hundred ten into seventy five millimeters) ISI marked self cleaning design including fixing with approved adhesive cost of cutting and making good the wall and floor complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00	250.00	Rupees Two Hundred Fifty Only	Each	750.00
20	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked including fixing with approved adhesive etc. Complete of Finolex/Vectus/red pipe within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge Rate inclusive toll tax, GST and any other taxes imposed by the government.					
20.1	75 mm (Seventy five millimeters)	9.00	150.00	Rupees One Hundred Fifty Only	Per Rmt	1350.00
20.2	110 mm (One hundred ten millimeters)	6.00	130.00	Rupees One Hundred Thirty Only	Per Rmt	780.00

	materials within all leads and lifts complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.					
21.1	100mm (one hundred millimetre) diameter.	3.00	120.00	Rupees One Hundred Twenty Only	Each	360.00
21.2	75mm (seventy five millimetre) diameter.	3.00	100.00	Rupees One Hundred Only	Each	300.00
22	Providing and fixing PVC Plain Bend ISI Marked including fixing with approved adhesive etc. Complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.					
22.1	75 mm (Seventy five millimeters)	2.00	150.00	Rupees One Hundred Fifty Only	Each	300.00
23	Providing and fixing anodised aluminium work for door, window, ventilator and partition frames of Jindal/ Hindolco with extruded built up standard tubular and other sections of approved make confirming to IS:733 and IS:1285 anodised transparent or dyed to require shade accordingly to IS:1868 (minimum anodic coating of grade AC15) fixed with raw plugs and screws or with fixing clips or with expansion holdfastners including necessary filling up of gaps and junctions at top, bottom and sides with required with PVC / neoprene felt etc. Aluminium section shall be smooth rust free, straight, mitred and jointed mechanically wherever required including cleast angle, aluminium, snap beeding for glazing/ panelling C.P. brass / stainless steel screws. All complete as per Architectural Drawings design and approved specifications and the direction of the Engineer -in Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	68.25	550.00	Rupees Five Hundred Fifty Only	Per Kilogram	37538.00
24	Providing and fixing 4mm thick ACP (Aluminum Composite Panel) per ISI and of approved shade for infill panels of aluminium door as per PWD specification, drawing and design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.42	900.00	Rupees Nine Hundred Only	Per Square metre	2178.00

	Providing and fixing 5mm (five millimetre) thick glazing with glass pane of Modiguard/ Saint gobin in aluminium, for window, ventilator and Dorner, shutters with PVC / neoprens gaskets complete weight not less than 12.50 Kg/Sqm (Twelve decimal five zero Kilogramme per square metre) as per the Architectural Drawings approved specification, (Cost of aluminium snap beeding shall be paid in basic item) including cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.42	650.00	Rupees Six Hundred Fifty Only	Per Square metre	1573.00
26	Repair of plaster from an old irregular walls average with including cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	50.00	180.00	Rupees One Hundred Eighty Only	Per Square metre	9000.00
Total:-						99998.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna