



"NOTICE INVITING TENDERS"


Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **18-03-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 17-03-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 17-03-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O EE Office Building at HPPWD Bhawarna (SH:- Construction of Edge wall alongwith U-shape drain at back side of the building)	77,670/-	1600/-	One Month	350/-
2	A/R & M/O EE Office Building at HPPWD Bhawarna (SH:- P/F AC (Air Conditioner) & wire Mesh for water cooler)	70,000/-	1400/-	One Month	350/-
3	A/R & M/O EE Office Building at HPPWD Bhawarna (SH:- Providing and fixing Railing)	49,950/-	1000/-	One Month	350/-
4	C/O 6 Nos. Type -III quarter at Bhawarna (SH:- P/F Collapsible Steel shutters, Brick work in Basement)	97,123/-	2000/-	One Month	350/-
5	C/O 6 Nos. Type -III quarter at Bhawarna (SH:- P/F Grill work etc)	99,978/-	2000/-	One Month	350/-
6	Restoration of rain damages on Patbag to Sapru via Lingan road (SH:- C/O R/Wall at RD 0/190 to 0/198)	99,606/-	2000/-	Three Month	350/-
7	Restoration of rain damages on Bhoda Gadiara Bye pass road (SH:- C/O R/Wall at RD 0/600 to 0/604 & 1/720 to 1/724)	99,856/-	2000/-	Three Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.



Executive Engineer
Bhawarna Division
HPPWD Bhawarna
On behalf of Governor of Himachal Pradesh
Dated:- **11-03-2026**

No. PWD/BWD/TA/NIT/2025-26/

15929-38

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26- 15929-38 dated 11-02 -2026.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Name of Work :- A/R & M/O EE Office Building at HPPWD Bhawarna. (SH):- Construction of Edge wall alongwith U-shape drain at back side of the building).

Estimated Cost :- Rs. 77,670/-
Earnest Money :- Rs. 1600/-
Time Limit :- 3 Months

S. No	Description of Item	Quantity	In figure	Rate		Unit	Amount Rs.
				In Words	Rs.		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseeling (wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.60	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	2400.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MOR D technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.60	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	72270.00	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12	250.00	Rupees Two Hundred Fifty Only	Each	3000.00	
Total :-							77670.00
Quoted rates percentage in figures							
Quoted rates percentage in words							


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work:- A/R & M/O EE Office Building at HPPWD Bhawarna . (SH:- P/F AC (Air Conditioner) & Wire Mesh for Water Cooler).

Estimated Cost :-Rs. 70,000/-
 Earnest Money :-Rs. 1400/-
 Time Limit :- ~~Three~~ ^{Six} Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing AC (Air Conditioner) having capacity of 1.5 (One decimal five) tonne make of IFB or equivalent complete as per direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	50000.00	Rupees Fifty Thousand Only	Each	50000.00
2	GST or other taxes imposed by the Government. Providing and fixing Wire Mesh with connecting plates or angles including 0.60 mm thick prepainted sheet on top complete as per Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	20000.00	Rupees Twenty Thousand Only	Per Job	20000.00
Total :-						70000.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work:- A/R & M/O EE Office Building at HPPWD Bhawarna. (SH:- Providing and fixing Railing).

Estimated Cost :-Rs. 49,950/-
 Earnest Money :-Rs. 1000/-
 Time Limit :- ~~Three~~ ^{Two} Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Steel work welded in built up sections of Tata/Sail/Jindal composed in grating, Framed guards, bars, ladders railings, brackets & similar works with connecting plates or angles, cleats as in trusses and trussed purlins, main and cross beams, hips, jack rafters, purlins connect to common rafter and like work including cutting hoisting fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	450.00	105.00	Rupees One Hundred Five Only	Per Kilogram	47250.00
2	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	30.00	90.00	Rupees Ninety Only	Per Square metre	2700.00
Total :-						49950.00
Quoted rates percentage in figures						
Quoted rates percentage in words						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of 6 Nos. Type-III Quarters at Bhawarna Division. (SH:- Providing and Fixing Collapsible steel shutters, Brick work in Basement)

Estimated Cost :- Rs. 97,123/-
 Earnest Money :- Rs. 2000/-
 Time Limit :- ~~Three~~ ^{Six} Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing in position collapsible steel shutters with vertical channels 20 mm X10 mmX2mm and braced with flat iron diagonals 20 mm X5 mm size with top and bottom rails of T.iron 40 mm X40 mm X6 mm with 38 mm dia steel pulley complete with bolts and nuts locking arrangements, toppers, handles, including applying a priming coat of red lead paint complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	14.25	4000.00	Rupees Four Thousand Only	Per Square metre	57000.00
2	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure upto all floor levels as per PWD specification drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.50	8500.00	Rupees Eight Thousand Five Hundred Only	Per Cubic metre	38250.00
3	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	20.81	90.00	Rupees Ninety Only	Per Square metre	1873.00
Total :-						97123
Quoted rates percentage in figures						
Quoted rates percentage in words						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna


Schedule of Quantity

Name of Work :- Construction of 6 Nos. Type-III Quarters at Bhawarna Division. (SH:- Providing and Fixing Grill work etc.)

Estimated Cost :- Rs. 99,978/-
 Earnest Money :- Rs. 2000/-
 Time Limit :- ~~Three~~ ^{Two} Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in beams joints, channels angles tees flats with connections plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	573.21	105.00	Rupees One Hundred Five Only	Per Kilogram	60187.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	52.12	90.00	Rupees Ninety Only	Per Square metre	4691.00
3	Providing and placing water tank of make PVC (Poly vinyl Chloride) Sintex having capacity 500 (five hundred) litres each with necessary fitting including over flow pipes scour pipe and bull valve and with cover locking arrangement of good quality including providing pads of sizes as required for inlet and outlet and inside painting of good quality all complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2000.00	8.50	Rupees Eight And Paise Fifty Only	Per litre	17000.00
4	Providing & Fixing water lifting pump (Tolu pump) of Havells / Usha / Crompton / Kirloskar 1.00 H.P centrifugal head range 6 - 25 (Six to Twenty) meter 20mm (Twenty millimetre) nominal bore making necessary connection, and fittings and accessories as required including carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	6000.00	Rupees Six Thousand Only	Each	6000.00
5	Providing and fixing 20mm (Twenty millimetre) diametre G.I. pipes ISI marked including fixing with approved adhesive etcetera complete upto all heights including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	40.00	250.00	Rupees Two Hundred Fifty Only	Per Running metre	10000.00

6	Providing and fixing 3-face G.I. wire mesh of 25 mm size including cutting, placing in position, fixing with nails, binding wire etc. complete in all respects as per direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	21.00	100.00	Rupees One Hundred Only	Per Running metre	2100.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					
Total :-						99978.00


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity


Name of Work :- Restoration of rain damages on Patbag to Sapruil via Lingan road (SH:- C/O R/wall at Rd 0/190 to 0/198).

Estimated Cost :-Rs.99,606/-
Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	11.44	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	2860.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead and lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	20.96	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	90128.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C pipe weep holes in brick masonry/ stone masonry plain/reinforced concrete abutment wing wall return wall and retaining/breast walls through the full width of the structures with slope of 1(V) 20 (H) (one vertical twenty horizontal) towards draining face complete as per drawing and M.O.R.D technical specifications clause 709 and 1206 6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax GST or other taxes imposed by the Government	9	250.00	Rupees Two Hundred Fity Only	Each	2250.00

4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.24	700.00	Rupees Seven Hundred Only	Per Cubic metre	4368.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					
Total :-						99606.00


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna


Schedule of Quantity

Name of Work :- Restoration of rain damage on Bhoda Gadiara Bye Pass road (Sh. C/O R/Wall at Rd 0/600 to 0/604 & 1/720 to 1/724).

Estimated Cost :- Rs.99,856/-
Earnest Money :- Rs.2000/-

Time Limit :- Three Months

S. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	11.44	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	2860.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement, four sand, eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	20.96	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	90128.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	10	250.00	Rupees Two Hundred Fifty Only	Each	2500.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and M.O.R.D technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	6.24	700.00	Rupees Seven Hundred Only	Per Cubic metre	4368.00
Total:-						99856.00
Quoted rates percentage in figures						
Quoted rates percentage in words						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna