



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

ccpwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2025-26-

142124270

Dated:-

16/03/2026

To

The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

*(Signature)*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

*(Signature)*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

Certificate

14212-14270  
/2025-26.....dated..16/3/26 is emergent nature and in public interest.

(N. J.)  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons: -

- 1 Date of issued/sale of tender form against **23.03.2026**
- 2 Cash payment (nonrefundable). **24.03.2026**


The tender shall be received upto **11.00 AM on 24.03.2026** and will be opened on the day of **24.03.2025 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **23.03.2026**. The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons: -

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on link Road to village Ganiyar km. 0.0 to 1/425(SH-C/O R/wall at RD 1/395 to 1/410)	463807.00	9300.00	Rs. 350/-	One Month	Class-D & C
2	Restoration of rain damage on Various Road Under Chowari Sub Division (Sub Head- Removal of slips in various road).	429162.00	8600.00	Rs. 350/-	One Month	Class-D & C
3	Restoration of rain damage on link Road to village Dangari Km. 0/00 to 3/575 (SH-Removal of slips in Km 0/0 to 3/500).	493500.00	10000.00	Rs. 350/-	One Month	Class-D & C
4	Restoration of rain damage on Prachhore to Naddal Road Km. 0/00 to 3/500 (SH Removal of slips in in Km. 0/00 to 3/500)	488250.00	10000.00	Rs. 350/-	One Month	Class-D & C
5	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in in Km. 25/500 to 40/00)	488250.00	10000.00	Rs. 350/-	One Month	Class-D & C
6	Restoration of rain damage on Chowari to Mandhiar Baloh Fagot Road Km. 0:00 to 13/330 (SH Removal of slips in in Km. 0/00 to 6:00)	486000.00	10000.00	Rs. 350/-	One Month	Class-D & C
7	Restoration of rain damage on Chowari to Mandhiar Baloh Fagot Road Km. 0/00 to 13/330 (SH Hiring of excavator cum loader for removal of slips & Tipper for Shifting of Muck/ Debris in km. 6/500 to 13/300).	485700.00	10000.00	Rs. 350/-	One Month	Class-D & C

8	Restoration of rain damage on Patka to Dalhousie Road Km. 14/00 to 32/00 (SH: Hiring of excavator cum loader for removal of slips & Tipper for Shifting of Muck/Debris in km. 15/00 to 25/00)	484500.00	10000.00	Rs. 350/-	One Month	Class-D & C
9	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH Removal of slips in in Km. 25/00 to 32/00)	483000.00	10000.00	Rs. 350/-	One Month	Class-D & C
10	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in in Km. 37/500 to 42/00)	460983.00	10000.00	Rs. 350/-	One Month	Class-D & C
11	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in in Km. 42/200 to 47/00)	480901.00	10000.00	Rs. 350/-	One Month	Class-D & C
12	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-Hiring of excavator cum loader for removal of slips in in Km. 8/500 to 16/00)	464129.00	10000.00	Rs. 350/-	One Month	Class-D & C
13	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-Hiring of excavator cum loader for removal of slips in in Km. 16/500 to 3/00).	488250.00	10000.00	Rs. 350/-	One Month	Class-D & C
14	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH: Hiring of Tipper and for Shifting of Muck Debris in Km. 25/500 to 40/00)	499500.00	10000.00	Rs. 350/-	One Month	Class-D & C
15	Restoration of rain Damage on Ghatasani Pull to Bhalog Road Km. 0/00 to 7/360 (SH-C/O R/wall at Rd. 4910 to 4/922)	286640.00	6000.00	Rs. 350/-	One Month	Class-D & C
16	Restoration of rain damage on Kamladi to Bakloh Ghatasani Road Km. 0/00 to 5/00 (SH-C/O R/Wall in PCC at Rd. 3/650 to 3/659)	455101.00	9300.00	Rs. 350/-	One Month	Class-D & C
17	Restoration of rain damage on Dhurasappar to Purkhda Road Km. 0/00 to 4/00 (SHC/O R/wall in PCC at Rd 3/730 to 3/735 & 3/742 to 3/750)	391697.00	7900.00	Rs. 350/-	One Month	Class-D & C
18	Restoration of rain damage on various Road Under Dhundiara Section (SH Removal of slips on various Road Under Dhundiara Section)	478601.00	10000.00	Rs. 350/-	One Month	Class-D & C
19	Restoration of rain damage on Nanikhed to Samlue Road Km. 0/00 to 30/585 (SH - Removal of slips in in Km. 0/00 to 30/585)	475266.00	10000.00	Rs. 350/-	One Month	Class-D & C
20	Repair of DMC Lab at Civil Hospital Chowari (SH-Dismantling of Door Window, Aluminum Work. painting work & miscellaneous work)	99664.00	2000.00	Rs. 350/-	One Month	Class-D & C
21	C/O Balance Work Mortuary at CHC Chowari (SH-Repair of Plaster & Painting Work)	200555.00	4000.00	Rs. 350/-	One Month	Class-D & C

22	Restoration of rain damage on Chowari To Jot Road Km. 0/00 to 23/00 (SH-C/O B/wall at Rd. 0/600 to 0/605)	97019.00	2000.00	Rs. 350/-	One Month	Class-D & C
23	Restoration of Rain Damage on Various Road section Chowari Under Chowari Sub Division (SH- Removal of slips at various roads)	235750.00	4100.00	Rs. 350/-	One Month	Class-D & C
24	Restoration of rain damage on Various Road Under Kakira Sub Division (SH Hiring of Breaker, Excavator Cum Loader for Removal of Slips & Tipper for Shifting of Muck/Debris in Kakira Section)	368630.00	7500.00	Rs. 350/-	One Month	Class-D & C
25	Restoration of rain damage on Various Road in Section Dhundiara-1 Under Sub Division Kakira (SH:- Removal of slips on various roads)	495495.00	10000.00	Rs. 350/-	One Month	Class-D & C
26	Restoration of rain damage on Various Road in Section Kakira Under Sub Division Kakira (SH- Removal of slips on various roads)	496282.00	10000.00	Rs. 350/-	One Month	Class-D & C
27	Restoration of rain damage on Various Road in Section Kakira Under Sub Division Kakira (SH:- Removal of slips on various roads)	494709.00	10000.00	Rs. 350/-	One Month	Class-D & C
28	A/R & M/O HPPWD Rest House at Sihunta (SH-C/O Septic Tank & Toilet Sanitary Work)	168179.00	4000.00	Rs. 350/-	One Month	Class-D & C
29	Restoration of Rain Damage on Motla to Sukhiyar Road Km. 0/00 to 9/00 (SH-C/O wire Crate Work for Protection of Existing R/wall at Rd. 0/450 to 0/475)	195894.00	4000.00	Rs. 350/-	One Month	Class-D & C
30	Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunnhatti Road Km. 25/00 to 40/00 (SH- C/O Edge Wall in Wire Crate at Rd. 35/765 to 35/785 along with Wing Wall at Rd. 35/735 to 35/825)	480829.00	10000.00	Rs. 350/-	One Month	Class-D & C
31	A/R & M/O NR Building Under Chowari Sub Division (SH:- C/o Protection wall & Joinery work, steel work & Flooring work)	277795.00	5600.00	Rs. 350/-	One Month	Class-D & C
32.	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-C/O B/wall at Rd. 0/720 to 0/745)	477113.00	10000.00	Rs. 350/-	One Month	Class-D & C
33	Restoration of rain damage on SSC Road Km. 47/00 to 52/00 (SH: C/O R/wall at Rd. 50/060 to 50/068 & U-shape PCC Drain in between RD 48/00 to 48/250)	427148.00	8600.00	Rs. 350/-	One Month	Class-D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

  
 Executive Engineer,  
 Chowari Division,  
 HPPWD, Chowari.



Tel.01899-299219.

cepwd-Chowari@hp.gov.in

No. PWD-CHW/Tender/2024-25-

To

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

6916-22

Dated:- 29-10-2025

M/s Chamunda Enterprises,  
Government Contractor,  
Ward No 1 College road Chowari,  
Tehsil Bhattiyat Distt. Chamba (HP).

**Subject: - Retrofitting of Government Senior Secondary School Dhulara (Block-B) (SH:- Provision of Retrofitting and Repairing of floor) Under State Disaster Mitigation Fund)**

Pursuant to your furnishing the requisite performance Security amounting to Rs. 43000/- (Rupees Forty Three thousand ) only in the form detailed in clause 1 of GCC & your percentage rate tender dated 10.10.2025 for the subject cited work is hereby accepted by the undersigned on the behalf Governor of HP for Rs. 2762139.92/- (Rupees Twenty Seven Lacs Sixty two thousand one hundred thirty nine and paisa ninety two) only which is 16.50 % below (Sixteen point five zero ) percent below on the amount put to tender subject to the following terms and conditions: -

- 1 The letter of acceptance along with tender documents would constitute a provisional agreement until a formal agreement duly sealed embodying all the conditions up to which the tender has been accepted duly signed, by you.
- 2 The time limit to complete this work is **Two month** which will be reckoned from the 15 days of the issue of this letter.
- 3 All cutting/additions and deletions which remain are authenticated by you as well as by the undersigned may again be authenticated before signing the agreement.
- 4 The work shall be carried out strictly as per PWD Specification and all the terms and conditions of the contract agreement shall be operative and binding upon you.
- 5 The latest fair wages of the labour schedule as per the latest notification of the Govt. dated 20.02.2019 shall be applicable to this tender.
- 6 You have to abide by the stipulations as laid down in the Govt. of HP Mining Policy 2015 for use of aggregates, sand and boulder/stones to be used in the subject cited work.
- 7 1% Labour cess on amount of work done from each bill will be deducted as per provision of building and other construction worker's welfare cess act 1996 and Himachal Pradesh building and other construction workers rule 2008.
- 8 The GST/Income tax as applicable shall be borne by the contractor and shall be deducted from each running bills as per latest instruction of the Govt.
- 9 Material will be procured by the Contractor himself as per Govt. Notification No. PBW (B)C(17)2/2012 dated 07/08/2018.

10 No substitution/deviation in any item be made without the prior approval of the competent authority. The expenditure should not exceed the provision made in the approved estimate.

11 Absurd high rates item should not be executed above the quantities taken in DNIT and absurd lower rates item should be executed fully as per DNIT

12 During the execution of work it may be ensured that the material is obtained from the approved quarry/source and lead should not be less than as taken in the justification.

You are therefore, requested to contact the Assistant Engineer, Sihunta Sub Division, HPPWD, Sihunta for taking over the site layout and start the work immediately by the stipulated date of start otherwise work will be rescinded by imposing penalty under relevant clause of agreement. You are also requested to attend this office to signing the formal agreement within weeks' time positively failing which no payment will be made till the agreement is signed by you.

Yours faithfully,  
For and on behalf of Governor of (HP).

Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

Copy forwarded to the following for information and necessary action: -

- 1 The Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie.
- 2 The Assistant Engineer, Sihunta Sub Division, HPPWD, Sihunta for information and necessary action. He is directed to get the work started from the Contractor at the earliest
- 2 The Assistant Excise and Taxation Commissioner Chamba HP.
- 3 The Income Tax Officer Dalhousie at Banikhet HP.
- 4 The Labour Inspector Dalhousie.
- 5 Account Branch/Drawing Branch in this office.
- 6 Agreement No.. 8.5.....for 2025-26.

*(Signature)*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari

# SCHEDULE OF QUANTITY


**Name of work:- Restoration of rain damage on link Road to village Ganiyar km. 0/0 to 1/425 (SH- C/O R/wall At Rd 1/395 to1/410)**

Estimate Cost - Rs. 463807.00  
Earnest Money - Rs. 9300.00

Time Limit :- One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.75	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	9902.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement iso five sand iso ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	88.20	4642.50	Rupees Four Thousand Six Hundred Forty Two And Paise Fifty Only	Per Cubic Metre	409469.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.50	1210.30	Rupees One Thousand Two Hundred Ten And Paise Thirty Only	Per Cubic Metre	30863.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	33	411.30	Rupees Four Hundred Eleven And Paise Thirty Only	Each	13573.00
<b>Total: -</b>						<b>463807.00</b>

Rate quoted in (%) Above / Below  
Rate quoted in (%) in Words

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

eepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2025-26-

To

14224279

Dated:- 16/03/2026

The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

*[Signature]*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

*[Signature]*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

Certificate

14212-14270 Certified that the tenders called vide this office letter No.PWD-CHW/Tender  
/2025-26.....dated..16/2/26 is emergent nature and in public interest.

*(Signature)*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons: -

- 1 Date of issued/sale of tender form against **23.03.2026**
- 2 Cash payment (nonrefundable). **24.03.2026**


The tender shall be received upto **11.00 AM on 24.03.2026** and will be opened on the day of **24.03.2025 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **23.03.2026**. The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons: -

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on link Road to village Ganiyar km. 0.0 to 1/425(SH-C/O R/wall at RD 1/395 to 1/410)	463807.00	9300.00	Rs. 350/-	One Month	Class-D & C
2	Restoration of rain damage on Various Road Under Chowari Sub Division (Sub Head- Removal of slips in various road).	429162.00	8600.00	Rs. 350/-	One Month	Class-D & C
3	Restoration of rain damage on link Road to village Dangari Km. 0/00 to 3/575 (SH-Removal of slips in Km 0/0 to 3/500).	493500.00	10000.00	Rs. 350/-	One Month	Class-D & C
4	Restoration of rain damage on Prachhore to Naddal Road Km. 0/00 to 3/500 (SH Removal of slips in in Km. 0/00 to 3/500)	488250.00	10000.00	Rs. 350/-	One Month	Class-D & C
5	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in in Km. 25/500 to 40/00)	488250.00	10000.00	Rs. 350/-	One Month	Class-D & C
6	Restoration of rain damage on Chowari to Mandhiar Baloh Fagot Road Km. 0:00 to 13/330 (SH Removal of slips in in Km. 0/00 to 6:00)	486000.00	10000.00	Rs. 350/-	One Month	Class-D & C
7	Restoration of rain damage on Chowari to Mandhiar Baloh Fagot Road Km. 0/00 to 13/330 (SH Hiring of excavator cum loader for removal of slips & Tipper for Shifting of Muck/ Debris in km. 6/500 to 13/300).	485700.00	10000.00	Rs. 350/-	One Month	Class-D & C

8	Restoration of rain damage on Patka to Dalhousie Road Km. 14/00 to 32/00 (SH: Hiring of excavator cum loader for removal of slips & Tipper for Shifting of Muck/Debris in km. 15/00 to 25/00)	484500.00	10000.00	Rs. 350/-	One Month	Class-D & C
9	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH Removal of slips in in Km. 25/00 to 32/00)	483000.00	10000.00	Rs. 350/-	One Month	Class-D & C
10	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in in Km. 37/500 to 42/00)	460983.00	10000.00	Rs. 350/-	One Month	Class-D & C
11	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in in Km. 42/200 to 47/00)	480901.00	10000.00	Rs. 350/-	One Month	Class-D & C
12	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-Hiring of excavator cum loader for removal of slips in in Km. 8/500 to 16/00)	464129.00	10000.00	Rs. 350/-	One Month	Class-D & C
13	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-Hiring of excavator cum loader for removal of slips in in Km. 16/500 to 3/00)	488250.00	10000.00	Rs. 350/-	One Month	Class-D & C
14	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH: Hiring of Tipper and for Shifting of Muck Debris in Km. 25/500 to 40/00)	499500.00	10000.00	Rs. 350/-	One Month	Class-D & C
15	Restoration of rain Damage on Ghatasani Pull to Bhalog Road Km. 0/00 to 7/360 (SH-C/O R/wall at Rd. 4910 to 4/922)	286640.00	6000.00	Rs. 350/-	One Month	Class-D & C
16	Restoration of rain damage on Kamladi to Bakloh Ghatasani Road Km. 0/00 to 5/00 (SH-C/O R/Wall in PCC at Rd. 3/650 to 3/659)	455101.00	9300.00	Rs. 350/-	One Month	Class-D & C
17	Restoration of rain damage on Dhurasappar to Purkhda Road Km. 0/00 to 4/00 (SHC/O R/wall in PCC at Rd. 3/730 to 3/735 & 3/742 to 3/750)	391697.00	7900.00	Rs. 350/-	One Month	Class-D & C
18	Restoration of rain damage on various Road Under Dhundiara Section (SH Removal of slips on various Road Under Dhundiara Section)	478601.00	10000.00	Rs. 350/-	One Month	Class-D & C
19	Restoration of rain damage on Nanikhed to Samlue Road Km. 0/00 to 30/585 (SH - Removal of slips in in Km. 0/00 to 30/585)	475266.00	10000.00	Rs. 350/-	One Month	Class-D & C
20	Repair of DMC Lab at Civil Hospital Chowari (SH-Dismantling of Door Window, Aluminum Work. painting work & miscellaneous work)	99664.00	2000.00	Rs. 350/-	One Month	Class-D & C
21	C/O Balance Work Mortuary at CHC Chowari (SH-Repair of Plaster & Painting Work)	200555.00	4000.00	Rs. 350/-	One Month	Class-D & C

22	Restoration of rain damage on Chowari To Jot Road Km. 0/00 to 23/00 (SH-C/O B/wall at Rd. 0/600 to 0/605)	97019.00	2000.00	Rs. 350/-	One Month	Class-D & C
23	Restoration of Rain Damage on Various Road section Chowari Under Chowari Sub Division (SH- Removal of slips at various roads)	235750.00	4100.00	Rs. 350/-	One Month	Class-D & C
24	Restoration of rain damage on Various Road Under Kakira Sub Division (SH Hiring of Breaker, Excavator Cum Loader for Removal of Slips & Tipper for Shifting of Muck/Debris in Kakira Section)	368630.00	7500.00	Rs. 350/-	One Month	Class-D & C
25	Restoration of rain damage on Various Road in Section Dhundiara-1 Under Sub Division Kakira (SH:- Removal of slips on various roads)	495495.00	10000.00	Rs. 350/-	One Month	Class-D & C
26	Restoration of rain damage on Various Road in Section Kakira Under Sub Division Kakira (SH- Removal of slips on various roads)	496282.00	10000.00	Rs. 350/-	One Month	Class-D & C
27	Restoration of rain damage on Various Road in Section Kakira Under Sub Division Kakira (SH:- Removal of slips on various roads)	494709.00	10000.00	Rs. 350/-	One Month	Class-D & C
28	A/R & M/O HPPWD Rest House at Sihunta (SH-C/O Septic Tank & Toilet Sanitary Work)	168179.00	4000.00	Rs. 350/-	One Month	Class-D & C
29	Restoration of Rain Damage on Motla to Sukhiyar Road Km. 0/00 to 9/00 (SH-C/O wire Crate Work for Protection of Existing R/wall at Rd. 0/450 to 0/475)	195894.00	4000.00	Rs. 350/-	One Month	Class-D & C
30	Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunnhatti Road Km. 25/00 to 40/00 (SH- C/O Edge Wall in Wire Crate at Rd. 35/765 to 35/785 along with Wing Wall at Rd. 35/735 to 35/825)	480829.00	10000.00	Rs. 350/-	One Month	Class-D & C
31	A/R & M/O NR Building Under Chowari Sub Division (SH:- C/o Protection wall & Joinery work, steel work & Flooring work)	277795.00	5600.00	Rs. 350/-	One Month	Class-D & C
32.	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-C/O B/wall at Rd. 0/720 to 0/745)	477113.00	10000.00	Rs. 350/-	One Month	Class-D & C
33	Restoration of rain damage on SSC Road Km. 47/00 to 52/00 (SH: C/O R/wall at Rd. 50/060 to 50/068 & U-shape PCC Drain in between RD 48/00 to 48/250)	427148.00	8600.00	Rs. 350/-	One Month	Class-D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

  
 Executive Engineer,  
 Chowari Division,  
 HPPWD, Chowari.


# SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on link Road to village Ganiyar km. 0/0 to 1/425 (SH- C/O R/wall At Rd 1/395 to1/410)**

Estimate Cost - Rs.	463807.00
Earnest Money - Rs.	9300.00
Time Limit :-	One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.75	400.10	Rupess Four Hundred And Paise Ten Only	Per Cubic Metre	9902.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	88.20	4642.50	Rupess Four Thousand Six Hundred Forty Two And Paise Fifty Only	Per Cubic Metre	409469.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.50	1210.30	Rupess One Thousand Two Hundred Ten And Paise Thirty Only	Per Cubic Metre	30863.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	33	411.30	Rupess Four Hundred Eleven And Paise Thirty Only	Each	13573.00
<b>Total:-</b>						<b>463807.00</b>

Rate quoted in (%) Above / Below  
Rate quoted in (%) in Words

  
**Gaurav Engineer**  
 Executive Engineer  
 Chowari Division  
 HP PW, Chowari

# SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 429162.00  
 Earnest Money :- Rs. 8600.00  
 Time Limit :- One Month.

**Name of work:- Restoration of rain damage on Various Road Under Chowari Sub Division (Sub Head:- Removal of slips in Various Road).**

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2728.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cum	429162.00
<b>Total</b>						429162.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari


## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on link Road to village Dangari Km. 0/00 to 3/575 ( SH :- Removal of slips in Km. 0/00 to 3/500).

Estimated Cost: - Rs. 493500.00  
Earnest Money :- Rs. 10000.00

Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3137.32	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	493500.00
<b>Total: -</b>						<b>493500.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

## SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on Prachhore to Naddal Road Km. 0/00 to 3/500 ( SH :- Removal of slips in in Km. 0/00 to 3/500).**

Estimated Cost: - Rs.	488250.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3103.94	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	488250.00
<b>Total:-</b>						<b>488250.00</b>

Rate quoted in (%) Above / Below  
Rate quoted in (%) in Words


  
 Executive Engineer  
 Chowari Division  
 HP PWB Chowari

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Shahpur Shiunta Chowari Road Km. 24/00 to 47/00 ( SH :- Removal of slips in in Km. 25/500 to 40/00 )

Estimated Cost: - Rs.	488250.00
Earnest Money :- Rs.	10000
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3103.94	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	488250.00
<b>Total: -</b>						<b>488250.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Chowari to Mandhilar Baloh Fagot Road Km. 0/00 to 13/330 ( SH :- Removal of slips in in Km. 0/00 to 6/00 )

Estimated Cost: - Rs. 486000.00  
 Earnest Money :- Rs. 10000.00  
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including cartage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	3089.64	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	486000.00
<b>Total: -</b>						<b>486000.00</b>

Rate quoted in (%) Above / Below  
 Rate quoted in (%) in Words

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on Chowari to Mandhiar Baloh Fagot Road Km. 0/00 to 13/330 (SH :- Hiring of excavator cum loader for removal of slips & Tipper for Shifting of Muck/ Debris in km. 6/500 to 13/330).**

Estimated Cost: - Rs. **485700.00**  
 Earnest Money :- Rs. **10000.00**  
 Time Limit :- **One Month.**

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	230.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	241500.00
2	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	220.00	1110.00	Rupees One Thousand One Hundred Ten Only	Per cum	244200.00
<b>Total: -</b>						<b>485700.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


*(Signature)*  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km. 14/00 to 32/00 ( SH :- Hiring of excavator cum loader for removal of slips & Tipper for Shifting of Muck/ Debris in Km. 15/00 to 25/00)**

Estimated Cost: - Rs.	484500.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	250.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	262500.00
2	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	200.00	1110.00	Rupees One Thousand One Hundred Ten Only	Per cum	222000.00
<b>Total:-</b>						<b>484500.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


  
 Executive Engineer  
 Chowari Division  
 HP PWB Chowari

## SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 ( SH :- Removal of slips in in Km. 25/00 to 32/00 )**

Estimated Cost: - Rs.	483000.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3070.57	157.30	Ruppes One Hundred Fifty Seven And Paise Thirty Only	Per cum	483000.00
<b>Total: -</b>						<b>483000.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
**Executive Engineer**  
 Chowari Division  
 HP PWD Chowari

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Shahrpur Sihunta Chowari Road Km. 24/00 to 47/00 ( SH :- Removal of slips in in Km. 37/500 to 42/00 )

Estimated Cost: - Rs. 460983.00  
 Earnest Money :- Rs. 10000.00  
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2930.60	157.30	Ruppes One Hundred Fifty Seven And Paise Thirty Only	Per cum	460983.00
Total: -						460983.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 ( SH :- Removal of slips in in Km. 42/200 to 47/00 )

Estimated	480901.00
Earnest Money	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3057.22	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	480901.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						Total: -
						480901.00

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH :- Removal of slips in in Km. 8/500 to 16/00 )

Estimated Cost: - Rs.	464129.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2950.60	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	464129.00
<b>Total: -</b>						<b>464129.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH :- Removal of slips in in Km. 16/500 to 23/00)

Estimated Cost: - Rs. 488250.00  
 Earnest Money :- Rs. 10000.00  
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3103.94	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	488250.00
<b>Total: -</b>						<b>488250.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

15

# SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on Shahpur Siluanta Chowari Road Km. 24/00 to 47/00 ( SH :- Hiring of Tipper and for Shifting of Muck  
Debris in Km. 25/500 to 40/00 )**

Estimated Cost: - Rs.	499500.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site , which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	450.00	1110.00	Rupees One Thousand One Hundred Ten Only	Per Hour	499500.00
<b>Total:-</b>						<b>499500.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


  
**Anil Kumar**  
 Executive Engineer  
 Chowari Division  
 HP PWB Chowari

# SCHEDULE OF QUANTITY

Name of work:- Restoration of rain Damage on Chatasani Pall to Bhalog Road Km. 0/00 to 7/360 (SH :- C/O R/wall at Rd. 4/910 to 4/922 )

Estimated Cost: - Rs. 286640.00  
Earnest Money :- Rs. 6000.00  
Time Limit :- One Month.

Sl. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In Fig.	In words			
2	other taxes imposed by the Government. Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	55.92	4610.20	Rupees Four Thousand Six Hundred Ten And Paise Twenty Only	Per Cubic Metre	257802.00	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.40	1250.30	Rupees One Thousand Two Hundred Fifty And Paise Thirty Only	Per Cubic Metre	10503.00	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23	411.00	Rupees Four Hundred Eleven Only	Each	9453.00	
<b>Total:-</b>							<b>286640.00</b>
			<b>Rate quoted in (%) Above / Below</b>				
			<b>Rate quoted in (%) in Words</b>				

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

15

# SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Kamladi to Bakloh Ghatasani Road Km. 0/00 to 5/00 ( SH :- C/O R/Wall in PCC at Rd. 3/650 to 3/659 )

Estimated Cost: - Rs. 455101.00  
 Earnest Money :- Rs. 10000.00  
 Time Limit :- One Month.

16

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	41.58	400.10	Rupees Four Hundred And Paise Ten Only	Per cum	16636.00
2	Providing and laying mechanical mixed and vibrated concrete for plain / reinforced grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20 millimeter (twenty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, drain and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which many arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	23.76	5850.60	Rupees Five Thousand Eight Hundred Fifty And Paise Sixty Only	Per cum	139010.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arrise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.82	4642.30	Rupees Four Thousand Six Hundred Forty Two And Paise Thirty Only	Per cum	273060.00

4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.42	1210.30	Rupees One Thousand Two Hundred Ten And Paise Thirty Only	Per cum	15032.00
5	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32	355.10	Rupees Three Hundred Fifty Five And Paise Ten Only	Per cum	11363.00
<b>Total:-</b>						<b>455101.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Dhurasappara to Purkhada Road Km. 0/00 to 4/00 ( SH :- C/O R/wall in PCC at Rd 3/730 to 3/735 & 3/742 to 3/750 )

Estimated Cost :- Rs. 391697.00  
 Earnest Money :- Rs. 7900.00  
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	41.78	400.10	Rupees Four Hundred And Paise Ten Only	Per cum	16716.00
2	Providing and laying mechanical mixed and vibrated concrete for plain / reinforced grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20 millimeter (twenty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, drain and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which many arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.76	5950.60	Rupees Five Thousand Nine Hundred Fifty And Paise Sixty Only	Per cum	69979.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimeter) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	61.36	4642.50	Rupees Four Thousand Six Hundred Forty Two And Paise Fifty Only	Per cum	284864.00

4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.50	1210.30	Rupees One Thousand Two Hundred Ten And Paise Thirty Only	Per cum	5446.00	
5	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (One) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36	408.10	Rupees Four Hundred Eight And Paise Ten Only	Per each	14692.00	
Rate quoted in (%) Above / Below						Total: -	391697.00
Rate quoted in (%) in Words							


  
 Executive Engineer  
 Chowari Division  
 HP P W B Chowari

# SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 478601.00  
 Earnest Money :- Rs. 100000.00  
 Time Limit :- One Month

**Name of work:- Restoration of rain damage on Various Road Under Dhundiara Section ( SH :- Hiring of excavator cum loader for removal of slips  
 Various Road Under Dhundiara Section )**

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3042.60	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	478601.00
<b>Rate quoted in (%) Above / Below</b>						
<b>Rate quoted in (%) in Words</b>						<b>Total: - 478601.00</b>

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

18

# SCHEDULE OF QUANTITY

**Name of work:- Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 ( SH :- Removal of slips in Km. 0/00 to 30/585 )**

Estimate Cost - Rs. **475266.00**  
Earnest Money - Rs. **10000.00**

Time Limit :- **One Month**

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3021.40	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	475266.00
<b>Total: -</b>						<b>475266.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
**Executive Engineer**  
**Chowari Division**  
**HP PWD Chowari**

# SCHEDULE OF QUANTITY

**Name of Work:- Repair of DMC Lab at Civil Hospital Chowari (SH :- Dismantling of Door Window , Aluminium Work , painting work & miscellaneous work)**

Estimate Cost - Rs. 99664.00  
Earnest Money - Rs. 2000.00  
Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Dismantling wood work wrought framed and fixed in frames other frames , purlin , trusses and rafter of span upto 10 (ten) metres and height between ridge and floor level stacking the serviceable materials and disposal of un-serviceable materials with in 20 metres lead. Sectional area average 40 (forty) sq.cm. square centimetre) Or over as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	0.57	1896.40	Rupees One Thousand Eight Hundred Ninety Six And Paise Forty Only	Per Cubic Metre	1081.00
2	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachments etc. complete and stacking them within 20 (twenty) metres lead Exceeding 3 sqm (three square metre) in area and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	8.00	156.30	Rupees One Hundred Fifty Six And Paise Thirty Only	Each	1250.00
3	Dismantling steel work manually / mechanical means in built section withouts member stacking with in fifty metre and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	101.40	1.60	Rupees One And Paise Sixty Only	Per Killogram	162.00
4	Providing and fixing Coloured anodised aluminium work for Frame of doors with extruded built up standard tubular sections/ appropriate Z sections and other sections of Jindal/ Hindalco as per approved shade make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) as per entire satisfaction and direction of the Engineer - in - charge including haulage of material within all leads and other incidental charges . The rate is including of octroi , royalty, Malkana Sale Tax, Toll tax GST and all other taxes impose by the Government	99.25	475.30	Rupees Four Hundred Seventy Five And Paise Thirty Only	Per Killogram	47174.00

20

5	Providing and fixing Coloured anodised aluminium work. Shutter for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) as per entire satisfaction and direction of the Engineer - in - charge including haulage of material within all leads and other incidental charges . The rate is including of octroi , royalty , Malkana Sale Tax, Toll tax GST and all other taxes impose by the Government	55.40	435.30	Rupees Four Hundred Thirty Five And Paise Thirty Only	Per Killogram	24116.00
6	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 4.0 mm (four millimetre) thickness (weight not less than 10 kg/ sqm)	10.80	1090.00	Rupees One Thousand Ninety Only	Per Square Metre	11772.00
7	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. (eighty five gramme) with wire of dia 0.56 mm (zero point fifty six millimetre) for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws. 40 mm (forty millimetre) thick 2nd (second) class deodar wood. and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.44	3158.00	Rupees Three Thousand One Hundred Fifty Eight Only	Per Square Metre	4548.00
8	15 mm (fifteen millimetre) Cement plaster in single coat on rough side of brick / stone masonry for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80 mm (eighty millimetre) in girth and finished even and smooth Cement Mortar 1:6 (one cement isto six sand) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	7.20	259.60	Rupees Two Hundred Fifty Nine And Paise Sixty Only	Per Square Metre	1869.00
9	Applying birla white care putty over palster surface after thoroughly brushing the surface free from mortar droplets, dust loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	7.20	99.30	Rupees Ninety Nine And Paise Thirty Only	Per Square Metre	715.00
10	Wall painting (two coats) with premium emulsion paint of Asian / Dulux / Begger paint / Nerolac paint (above Dado Skirting) of approved brand and manufacture for interior grade on undecorated concrete / stone / plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metting the surface and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.20	186.60	Rupees One Hundred Eighty Six And Paise Sixty Only	Per Square Metre	1344.00

11	Providing and laying cement concrete mechanically mixed and vibrated grade M-20 mix design to obtain the minimum crushing strength to 20 N /millimetre square with minimum cement contents 310 Kilogramme (Three hundred ten Kilogramme) per cubic metre and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing, shelves and their supports, balconies, beam, girders, bressumers and cantilevers upto all floor level as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	0.17	6638.80	Rupees Six Thousand Six Hundred Thirty Eight And Paise Eighty Only	Per Cubic Metre	1129.00
12	Providing Tor steel reinforcement for RCC work including bending, binding and placing in position complete including cost of binding wire complete upto all floor level and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	20.25	99.80	Rupees fifty nine and paisa fifty seven only	Per Kilogramme	2021.00
13	Providing and fixing 10 mm (ten millimetre) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nicco or equivalent 600 x 600 mm x 10 mm (six hundred into six hundred millimetre into ten millimetre) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12 mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	1.13	2197.00	Rupees Two Thousand One Hundred Ninety Seven Only	Per Square Metre	2483.00
			<b>Total</b>			<b>99664.00</b>
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari


# SCHEDULE OF QUANTITY

(21)

**Name of Work:- C/O Balance Work Mortuary at CHC Chowari ( SH :- Repair of Plaster & Painting Work )**

Estimate Cost - Rs. 200555.00  
Earnest Money - Rs. 4100.00  
Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Repairs to plaster in patches of 2.50 Sqm (two point fifty square metre) and under and 10 mm to 15 mm (ten millimetre to fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 (twenty) metres with:- Cement Mortar 1:6 (one Cement isto six Sand) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	273.2	399.75	Rupees Three Hundred Ninety Nine And Paise Seventy Five Only	Per Square Metre	109212.00
2	Applying birla white care putty over palster surface after thoroughly brushing the surface free from mortar droppes, dust loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	273.20	99.30	Rupees Ninety Nine And Paise Thirty Only	Per Square Metre	27129.00
3	Wall painting (two coats) with premium emulsion paint of Asian / Dulux / Berger paint / Nerolac paint (above Dado Skirting) of approved brand and manufacture for interior grade on undecorated concrete / stone / plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for melting the surface and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	273.20	186.60	Rupees One Hundred Eighty Six And Paise Sixty Only	Per Square Metre	50979.00
4	Painting two or more coats (excluding priming coat ) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stopping with enamel paint white or other than white and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	100.80	131.30	Rupees One Hundred Thirty One And Paise Thirty Only	Per Square Metre	13235.00
<b>Total</b>						<b>200555.00</b>
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY

**Name of Work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH :- C/O B/wall at Rd. 0/600 to 0/605)**

Estimate Cost - Rs. 95205.00  
Earnest Money - Rs. 2000.00  
Time Limit:- One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	11.45	400.70	Rupees Four Hundred And Paise Seventy Only	Per Cubic Metre	4588.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.34	4716.75	Rupees Four Thousand Seven Hundred Sixteen And Paise Seventy Five Only	Per Cubic Metre	86505.00
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3, 7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10	411.20	Rupees Four Hundred Eleven And Paise Twenty Only	Each	4112.00
<b>Rate quoted in (%) Above / Below</b>						
<b>Rate quoted in (%) in Words</b>						
<b>Total:-</b>						<b>95205.00</b>

  
 Executive Engineer  
 Chowari Division  
 HP PWD, Chowari

23

## SCHEDULE OF QUANTITY

**Name of work:- Restoration of Rain Damage on Various Road section chowari Under Chowari Sub Division ( SH :-Removal of slips at various roads)**

Estimated Cost: - Rs. 237551.00  
Earnest Money :- Rs. 4800.00  
Time Limit :- One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying mechanical mixed and vibrated concrete for plain / reinforced grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20 millimeter (twenty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, drain and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which many arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1510.18	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	237551.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						237551.00

  
Executive Engineer  
Chowari Division  
HP PWD Chowari


# SCHEDULE OF QUANTITY

24

Estimate Cost - Rs. 368630.00  
 Earnest Money - Rs. 7400.00  
 Time Limit:- One Month

**Name of Work:- Restoration of rain damage on Various Road Under Kakira Sub Division ( SH :- Hiring of Breaker, Excavator Cum Loader for Removal of Slips & Tipper for Shifting of Muck / Debris in Kakira Section )**

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Hiring of JCB/Excavator with Breaker for hard rock chiseling, wedging out rock (where blasting is prohibited) disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	17.00	2350.00	Rupees Two Thousand Three Hundred Fifty Only	Per Hours	39950.00
2	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	220.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	231000.00
3	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	88.00	1110.00	Rupees One Thousand One Hundred Ten Only	Per Hours	97680.00
<b>Total:-</b>						<b>368630.00</b>
<b>Rate quoted in (%) Above / Below</b>						
<b>Rate quoted in (%) in Words</b>						

  
 Executive Engineer  
 Chowari Division  
 HP PWD, Sitowari

25

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Various Road in Section Dhundhara/Under Sub Division Kakira (SH:- Removal of slips on various roads)

Estimated Cost: - Rs. 495495.00  
Earnest Money :- Rs. 10000.00  
Time Limit :- One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3150.00	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	495495.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						495495.00

  
Executive Engineer  
Chowari Division  
HP PWD Chowari

## SCHEDULE OF QUANTITY

26

Estimated Cost: - Rs. 496282.00  
Earnest Money :- Rs. 10000.00  
Time Limit :- One Month

Name of work:- Restoration of rain damage on Various Road in Section Kakira Under Sub Division Kakira (SH:- Removal of slips on various roads) (Job No.1)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3155.00	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	496282.00
Total: -						496282.00
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				

*Ashu*  
Executive Engineer  
Chowari Division  
HP PWD Chowari


# SCHEDULE OF QUANTITY

27

Estimated Cost: - Rs. 494709.00  
 Earnest Money :- Rs. 10000.00  
 Time Limit :- One Month

Name of work:- Restoration of rain damage on Various Road in Section Kakira Under Sub Division Kakira (SH:- Removal of slips on various roads) (Job No.2)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3145.00	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	494709.00
<b>Total: -</b>						<b>494709.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY

Estimate Cost - Rs. 168179.00  
Earnest Money - Rs. 4000.00  
Time Limit: - One Month

Name of Work:- A/R & M/O HP PWD Rest House at Sihunta (SH:- C/o Septic Tank and Sanitary work).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick jumper work, blasting work both in soft and hard rock chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required lines, grade, width, cutting and trimming of side slopes as shown in the drawing and if water is met within the excavation due to springs, seepage, rain and other causes it shall be removed by the suitable diversion pumping or bailing out and excavation shall be kept dry where ever so required by the contractor at his own cost as directed by the Engineer -in - Charges and disposal of all surplus excavated soil in acquired width or at an approved dumping site including its stacking leveling dressing in all leads and lifts by head load, mechanical transportation or by any other mode of transportation with all cost of labours, machinaries and other incidentals to complete the work as per HPPWD specifications. Any loss to the public and private property during the course of execution and disposal of unserviceable materials shall be absolute responsibility of the contractor which shall have to be compensated by him in all cases.	31.50	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	12603.00
2	Providing and laying mechanically mixed plain cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed / broken stone aggregate 40 mm ( Forty millimetre) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	1.80	5237.90	Rupees Five Thousand Two Hundred Thirty Seven And Paise Ninety Only	Per Cubic Metre	9428.00
3	Random rubble masonry / polygonal rubble masonry (un-coursed / brought to courses) with hard stone of approved quality in foundation and plinth including levelling up with cement concrete 1:6:12 (One cement isto six sand isto twelve graded stone aggregate 20 mm (twenty millimetre) nominal size) at plinth level in Cement mortar 1:6 (one cement isto six sand) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	9.66	6035.10	Rupees Six Thousand Thirty Five And Paise Ten Only	Per Cubic Metre	58299.00
4	Providing form work with steel plates 3.15mm (Three point fifteen millimetre) thick welded with angles iron in frame 30 x 30 x 5mm (Thirty into Thirty into five millimetre) so as to give a fair finish including centering, shuttering, strutting and propping etcetera with wooden battens and ballies heights of propping and centering below supporting floor to ceiling upto all heights and removal of the same for insitu reinforced concrete and plain concrete work in flat surface such as soffit of suspended floor, roofs, landings shelves etcetera and the like floor etcetera upto any thickness as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	9.00	660.60	Rupees Six Hundred Sixty And Paise Sixty Only	Per Square Metre	5945.00

5	Providing form work with steel plates 3.15mm (Three point fifteen millimetre) thick welded with angles iron in frame 30 x 30 x 5mm (Thirty into Thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and propping etcetra with wooden battens and ballies heights of propping and centring below supporting floor to ceiling and removal of the same for insitu reinforced concrete and plain concrete work in Edges of slabs and breaks in floors and walls upto all width and heights as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	12.00	164.10	Rupees One Hundred Sixty Four And Paise Ten Only	Per Running Metre	1969.00
6	Providing and laying cement mechanically mixed and vibrated grade M-20 mix design to obtain the minimum crushing strength to 20 N /millimetre square with minimum cement contents 350 kilogramme (Three hundred fifty kilogramme) per cubic metre and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing, shelves and their supports, balconies, beam, girders, bressumers and cantilevers upto all floor level as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	1.35	8390.30	Rupees Eight Thousand Three Hundred Ninety And Paise Thirty Only	Per Cubic Metre	11327.00
7	Providing Tor steel reinforcement for RCC work including bending, binding and placing in position complete including cost of binding wire complete upto all floor level and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	121.50	97.40	Rupees fifty nine and paisa fifty seven only	Per Kilogramme	11834.00
8	20 mm (twenty millimetre) Cement plaster in single coat on rough side of brick / stone masonry for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80 mm (eighty millimetre) in girth and finished even and smooth Cement Mortar 1:6 (one cement isto six sand) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	42.00	365.70	Rupees Three Hundred Sixty Five And Paise Seventy Only	Per Square Metre	15359.00
9	Providing and fixing 100 mm (one hundred millimetre) sand cast / cast iron spun spigot ans socket soil, waste (lead caulked joints to be measured and paid separately within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	4.40	102.10	Rupees One Hundred Two And Paise Ten Only	Per Running Metre	449.00
10	Providing and fixing plain bend 100 mm (one hundred millimetre) sand cast / cast iron spun fitting and accessories within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	2.00	155.60	Rupees One Hundred Fifty Five And Paise Sixty Only	Each	311.00
11	Providing and fixing Cast iron cowl 100 mm (one hundred millimetre) nominal diameter within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	2.00	80.60	Rupees Eighty And Paise Sixty Only	Each	161.00
12	Providing and fixing cast iron cover with out frame for manhole for frame of internal diamensions 455 x 610mm (four hundred into six hundred ten millimetre) rectangularcast iron cover light duty single seat pattern the weight of cover to be not less then 38 kg (thirty eight Killogram) complete within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	3.00	383.70	Rupees Three Hundred Eighty Three And Paise Seventy Only	Each	1151.00

13	Providing and fixing Vitreous china wash down water closet European type W.C. Pan Star.No.20087 (Twenty thousand eighty seven) (S-10) (S-Ten) of size 57x35x39cm (Fifty seven into thirty five into thirty nine centimetre) of Hindware/Jaugar/Cera of Star white/Snow white shade and its equivalent with integral P or S trap including jointing the trap with soil pipe in cement mortar 1:1 (One Cement isto One Sand) (Earth work and bed concrete to be measured and paid for separately) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	1.00	3812.20	Rupees Three Thousand Eight Hundred Twelve And Paise Twenty Only	Each	3812.00
14	Providing and fixing G.I. / PVC Inlet connection for flush pipe with W.C. Pan as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	8.00	212.10	Rupees Two Hundred Twelve And Paise Ten Only	Each	1697.00
15	Providing and fixing plastic seat solid type white plastic sheet for wash down with C.P. brass hinges and rubbed buffers and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	1.00	629.50	Rupees Six Hundred Twenty Nine And Paise Fifty Only	Each	630.00
16	Providing and fixing 10.00 Ltrs (Ten litres) capacity P.V.C. (Poly Vanyl Chloride) low level flushing cistern I.S. (Indian Standard) marked No. 7231 of Hindware /Cera/ Jaugar star white with a pair of M.S. (mild steel) brackets, with fittings such as lead valve less siphon, 15mm (Fifteen millimetre) nominal size brass ball valve with polythene float, C.P. (Chromium Plated) brass handle unions and couplings for connections with inlet, outlet and overflow pipes, 40mm dia (Forty millimetre) diameter C.P. (Chromium Plated) flush bend including cutting holes in walls and making good the same and connection the flush bend with cistern and closet (overflow pipe to be measured and paid for separately), as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	2064.70	Rupees Two Thousand Sixty Four And Paise Seventy Only	Each	4129.00
17	Providing and fixing vitreous china wash basin with pedestal Garnet No. 10010 of size 55x40cm (fifty five into forty centimetre) of Hindware/Cera/Jaugar of star white/snow white shade make with single hole for pillar tap with CI or M.S. brackets painted white including cutting holes and making good the same but excluding fittings complete as per HPPWD specifications, approved drawings and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	1.00	3252.30	Rupees Three Thousand Two Hundred Fifty Two And Paise Thirty Only	Each	3252.00
18	Providing and fixing vitreous China pedestal for wash basin complete recessed at the back for the reception of pipes and fittings as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	1.00	1291.80	Rupees One Thousand Two Hundred Ninety One And Paise Eighty Only	Each	1292.00
19	Providing and fixing rubber plug for sink or wash basin 32 mm (Thirty two millimetre) dia and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	6.00	68.40	Rupees Sixty Eight And Paise Forty Only	Each	410.00

20	Providing and fixing C.P. brass waste pipe of 32 mm (thirty two millimetre) dia size for sink or wash basin and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	6.00	220.30	Rupees Two Hundred Twenty And Paise Thirty Only	Each	1322.00
21	Providing and fixing C.P. brass angle valve 15 mm (fifteen millimetre) without Nuts and pipe as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	8.00	773.20	Rupees Seven Hundred Seventy Three And Paise Twenty Only	Each	6186.00
22	Providing and fixing PVC connection pipes 30 / 45 cm (thirty / forty five centimetre) long 15 mm (fifteen millimetre) bore as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	6.00	205.30	Rupees Two Hundred Five And Paise Thirty Only	Each	1232.00
23	Providing and fixing 150mm (One hundred fifty millimetre) diametre ISI marked high pressure Polyvinyl chloride P.V.C. spigot and socket soil, waste and ventilating pipes complete as per HPPWD specifications or as directed by the Engineer-in-Charge including filling the joints with approved adhesive and carriage of materials within all leads and lifts and other incidentals charges.	10.00	532.20	Rupees Five Hundred Thirty Two And Paise Twenty Only	Running Metre	5322.00
24	Providing and fixing P.V.C (Polyvinyl chloride) single equal branch of Supreme/Kishan/Finolex or its equivalent medium class confirming to IS-14735-99 with in all leads, lifts of material and other incidentals The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government. 150mm (One hundred fifty millimetre) diameters.	4.00	177.90	Rupees One Hundred Seventy Seven And Paise Ninety Only	Each	712.00
25	Providing and fixing P.V.C (Polyvinyl chloride) collar of Supreme/Kishan/Finolex or equivalent confirming to IS-14735-99 including fitting the joints with approved adhesive with in all leads, lifts of material and other incidentals The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government. 150mm (One hundred fifty millimetre) diameters.	4.00	171.10	Rupees One Hundred Seventy One And Paise Ten Only	Each	684.00
26	Providing and fixing mixer for kitchen sink with casted swinging spout at top of continental series of Jaguar / classic series with approved adhesive with in all leads, lifts of material and other incidentals The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	3.00	2887.50	Rupees Two Thousand Eight Hundred Eighty Seven And Paise Fifty Only	Each	8663.00
		<b>Total</b>				<b>168179.00</b>
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				

  
 Executive Engineer  
 Chowari Division  
 HP PWD, Nowari

## SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 195894.00  
Earnest Money :- Rs. 4000.00

Time Limit :- One Month

Name of work: - Restoration of Rain Damage on Mota to Sukhiyar Road Km. 0/00 to 9/00 (SH:- C/O wire Crate Work for Protection of Existing R/wall at Rd. 0/450 to 0/475)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.46	400.10	Rupees Four Hundred And Paise Ten Only	Per Square Metre	8186.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (twenty five kilogramme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	68.76	2729.90	Rupees Two Thousand Seven Hundred Twenty Nine And Paise Ninety Only	Per Square Metre	187708.00
<b>Total: -</b>						<b>195894.00</b>
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

  
 Executive Engineer  
 Chowari Division  
 HP PWD, Chowari

## SCHEDULE OF QUANTITY

**Name of work:- Restoration of Rain Damage on Nurpur Sanjini Nallah Lahru Tunnahatti Road Km. 25/00 to 40/00 ( SH :- C/O Edge Wall in Wire Crate at Rd. 35/765 to 35/785 along with Wing Wall at Rd. 35/735 to 35/825 )**

Estimated Cost:- Rs. 480829.00  
 Earnest Money :- Rs. 10000.00  
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth within all lead and lift as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including octroi, royalty, Malkana, Tol tax, sale tax, GST or other tax imposed by the Government.	20.00	400.00	Rupees Four Hundred Only	Per cum	8000.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (twenty five kilogramme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	112.50	3065.00	Rupees Three Thousand Sixty Five Only	Per cum	344813.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	1210.00	Rupees One Thousand Two Hundred Ten Only	Per cum	36300.00
4	Providing and laying mechanical mixed and vibrated concrete for plain / reinforced grade M-20 (M-ten) nominal mix 1:2:4(one cement isto three sand isto six graded crushed stone aggregate 20 millimeter (twenty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, drain and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which many arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.50	6793.80	Rupees Six Thousand Seven Hundred Ninety Three And Paise Eighty Only	Per cum	91716.00
<b>Total:-</b>						<b>480829.00</b>

Rate quoted in (%) Above / Below  
 Rate quoted in (%) in Words

  
 Executive Engineer  
 Chowari Division  
 HP PWD Shimwari

30

# SCHEDULE OF QUANTITY

Estimate Cost - Rs. 277795.00  
Earnest Money - Rs. 5600.00

Time Limit: - One Month

**Name of Work:- A/R & M/O NR Building Under Chowari Sub Division (SH :- C/o Protection wall & Joinery work , steel work & Flooring work)**

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all highs / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.20	4642.80	Rupees Four Thousand Six Hundred Forty Two And Paise Eighty Only	Per Cubic Metre	75213.00
2	Half brick masonry in common clay second class bricks building bricks in super structure in cement mortar 1:4 (one cement isto four sand) within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	15.00	749.00	Rupees Seven Hundred Forty Nine Only	Per Square Metre	11235.00
3	Providing and fixing second class deodar wood work in frame of doors, windows, clerestory windows and other frames wrought framed and fixed in position complete within all leads and lifts and as per direction of the Engineer -in - charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government	0.10	121982.30	Rupees One Lakh(s) Twenty One Thousand Nine Hundred Eighty Two And Paise Thirty Only	Per Cubic Metre	12198.00
4	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. (eighty five grame) with wire of dia 0.56 mm (zero point fifty six millimetre) for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws. 40 mm (forty millimetre) thick 2nd (second) class deodar wood. and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.46	3158.00	Rupees Three Thousand One Hundred Fifty Eight Only	Per Square Metre	7769.00
5	Providing and fixing 2nd (second) class deodar wood panelled glazed or panelled and glazed shutter for doors windows and clerestory windows including black enamelled iron butt hinges with necessary screws 40 mm (forty millimetre) thick within all leads and lifts and as per direction of the Engineer -in - charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government	2.46	4648.00	Rupees Four Thousand Six Hundred Forty Eight Only	Per Square Metre	11434.00
6	Providing and fixing 300x16 mm (three hundred into sixteen millimetre) anodized aluminium sliding door bolts anodized colour and shade with bolts and nuts screws etcetra complete within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	2.00	320.70	Rupees Three Hundred Twenty And Paise Seventy Only	Each	641.00

54

7	Providing and fixing 200x10mm (two hundred into ten millimetre) anodized aluminium tower bolts (berrel type) anodized transparent to dyed to required shade and colour with screws etcetra complete within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	4.00	122.80	Rupees One Hundred Twenty Two And Paise Eighty Only	Each	491.00
8	Providing and fixing aluminium handles anodized transparent or dyed to required shade and colour with screws etcetra complete 125 mm (One hundred twenty five millimetre) within all leads and lifts and as per the direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	4.00	82.50	Rupees Eighty Two And Paise Fifty Only	Each	330.00
9	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting with ready mixed paint brushing wood primer pink within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	9.84	67.90	Rupees Sixty Seven And Paise Ninety Only	Per Square Metre	668.00
10	Painting two or more coats (excluding priming coat ) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stoping with enamel paint white or other than white and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	9.84	131.30	Rupees One Hundred Thirty One And Paise Thirty Only	Per Square Metre	1292.00
11	Providing and fixing 0.60mm ( Zero point six millimetre) thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 ( Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5(Five) microns primer coating <i>ie</i> fixing with preprinted iron J or L hooks, bolts and nuts 6mm dia metre with preprinted limpet and rubber washers complete with all accessories as required within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	38	1365.60	Rupees One Thousand Three Hundred Sixty Five And Paise Sixty Only	Per Square Metre	51893.00
12	Steel work welded in built up sections,, trusses and framed work, including cutting, hoising, fixing in position and applying a primming coat of red lead paint. In trusses and trussed purlins in buildings within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	380.00	106.80	Rupees One Hundred Six And Paise Eighty Only	Per Killogram	40584.00
13	Loosening of the ground up to a level of 300mm (Three hundred millimeter) below the sub-grade level, watered graded with motor grader and compacted in layers to meet the requirements of Table 300.1 and 300.2 with three wheel 80-100 (eighty – Hundred) KN static roller for sub-grade construction as per MORD Technical specification section 300 and as per direction and the entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	20.00	67.30	Rupees Sixty Seven And Paise Thirty Only	Per Cubic Metre	1346.00
14	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etcetra complete as per HP PWD specification 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the oct	12.00	780.40	Rupees Seven Hundred Eighty And Paise Forty Only	Per Cubic Metre	9365.00

15	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete grade M-20 (M-Twenty) nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40 mm (Forty millimeter) nominal size) in sub structure and curing complete for 14 (fourteen) days in open foundations for all type of structure including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which may arise at the time of laying water complete for all hights and depths including curing and cost of form work as per drawings and MORD technical specifications caluse 802,803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	8.00	6667.00	Rupess Six Thousand Six Hundred Sixty Seven Only	Per Cubic Metre	53336.00
<b>Total</b>						<b>277795.00</b>
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

  
 Executive Engineer  
 Chowari Division  
 HP PW/B/  
 Chowari

32

## SCHEDULE OF QUANTITY


**Name of Work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 ( SH :- C/O B/wall at Rd. 0/720 to 0/745)**

Estimate Cost - Rs. 477113.00  
Earnest Money - Rs. 10000.00  
Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasing is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.00	400.70	Rupees Four Hundred And Paise Seventy Only	Per Cubic Metre	14425.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	96.00	4652.70	Rupees Four Thousand Six Hundred Fifty Two And Paise Seventy Only	Per Cubic Metre	446659.00
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	39	411.00	Rupees Four Hundred Eleven Only	Each	16029.00
<b>Total: -</b>						<b>477113.00</b>

Rate quoted in (%) Above / Below

Rate quoted in (%) in Words

  
 Executive Engineer  
 Chowari Division  
 HP PWD Chowari

# SCHEDULE OF QUANTITY


35

**Name of Work:- Restoration of rain damage on SSC Road Km. 47/00 to 52/00 ( SH :- C/O R/wall at Rd. 50/060 to 50/068 & U-shape PCC Drain in between RD. 48/00 to 48/250)**

Estimate Cost - Rs. 427148.00  
 Earnest Money - Rs. 8600.00  
 Time Limit:- One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORDD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	55.20	400.70	Rupees Four Hundred And Paise Seventy Only	Per Cubic Metre	22119.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.04	4652.70	Rupees Four Thousand Six Hundred Fifty Two And Paise Seventy Only	Per Cubic Metre	218863.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORDD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.60	1210.00	Rupees One Thousand Two Hundred Ten Only	Per cum	16456.00
4	Providing and laying mechanical mixed and vibrated concrete for plain / reinforced grade M-20 (M-ten) nominal mix 1:3:6(one cement isto three sand isto six graded crushed stone aggregate 20 millimeter (twenty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, drain and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	26.25	6230.30	Rupees Six Thousand Two Hundred Thirty And Paise Thirty Only	Per cum	163545.00

<p>3 Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.</p>	15	411.00	Rupees Four Hundred Eleven Only	Each	6165.00
<p>Rate quoted in (%) Above / Below</p>				Total: -	427148.00
<p>Rate quoted in (%) in Words</p>					

  
 Executive Engineer  
 Chawari Division  
 HP PWB Chawari