

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26  
To

13900-20


Dated 13/3/20

The Executive Engineer (IT Cell)  
HPPWD Nirman Bhawan Nigam Bihar  
HPPWD Shimla


Subject:- Tender Notice

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest

  
Executive Engineer,  
Dehra Division HP.PWD.,  
Dehra

- Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla -  
2 for favour of information please.  
Copy to the Engineer-in-Chief HPPWD Shimla for information please.  
Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of  
information please.  
Copy to the Superintending Engineer 9<sup>th</sup> Circle HPPWD Dehra for favour of  
information please.  
Copy to Notice Board  
Copy to All the head of Branches  
Copy to All the Contractors working under Dehra Division

  
Executive Engineer,  
Dehra Division HPPWD.,  
Dehra.

### H. P. P.W.D. TENDER


Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors ( C&D Class) enlisted in HPPWD.

#### TENDER SCHEDULE:

1. Date and time of receipt of application for tender form: 19.3.2026 upto 05.00 PM
2. Date and time of issue of tender form: 20.03.2026 upto 05.00 PM
3. Date and time of receipt of tenders: 23.03.2026 upto 11.00 AM
4. Date and time of opening of tenders: 23.03.2026 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of rain damages on Jawalamukhi Dehra Jawali Raja Ka Talab oad Km 22/000 to 39/180 (SH:- Construction of Rain Shelter Jhaklehar at RD 25/100). (Under PDNA).	Rs.2,61,520/-	Rs.5000/-	Three Months	350
2	Restoration of rain damages on Jawalamukhi Dehra Jawali Raja Ka Talab oad Km 4/000 to 39/180 (SH:- Construction of Protection wall for culvert at RD . 6/400 to 6/410 ) PDNA	Rs.1,19,214/-	Rs.2400/-	Three Months	350
1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application): Copy of Registration/Latest renewal of enlistment. (i) PAN (Permanent Account No.) (ii) Registration under GST No. (iii) EPF(Employee Provident Fund Account No.) (iv) The proof ownership/hire/lease, buying of required machinery for micro surfacing works. (v)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				

  
Executive Engineer  
HPPWD Division Dehra  
Distt Kangra H.P  
on behalf of Governor of Himachal Pradesh  
HIM LOK SAMPARK

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 2,61,520.00  
 Earnest Money :-Rs. 5,000.00  
 Time Limit :- Two Months.

Name of work:- Restoration of rain damages on Jawalamukhi Dehra Jawail Raja Ka Talab oad Km 22/000 to 39/180 (SH):- Construction of Rain Shelter Shaklehar at RD 25/100). (Under PDNA).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, strutting or bailing out water upto any depth or any height quantum of water including de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as per direction of Engineer-in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming, watering and then disposing of all excavated earth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.62 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	1,920.00
2	Providing and laying cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST and any other taxes imposed by the Government.	5.69 Cubic metre	4955.20	Rupees Four Thousand Nine Hundred Fifty Five And Paise Twenty Only	Per Cubic metre	28,195.00
3	Random rubble masonry with hard stone of approved quality in foundation and plinth including levelling up with cement concrete 1:6:12 (One cement isto Six coarse sand isto Twelve graded stone aggregate 20mm (Twenty millimetre) nominal size upto plinth level including raking out joints in cement mortar 1:6 (One cement : Six coarse sand) complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3.97 Cubic metre	5360.00	Rupees Five Thousand Three Hundred Sixty Only	Per Cubic metre	21,279.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing form work with steel plates 3.15mm (Three point one five millimeters) thick, welded with angle iron in frame 30x30x5mm (Thirty into Thirty into Five millimeters) so as to give a fair finish including centering, shuttering strutting and propping etc, with wooden battens and ballies, height of propping and centering in all heights. below supporting floor to ceiling and removal of the same for in situ reinforced concrete and plain concrete work in Suspended floors, roofs, landings, balconies, shelves and access platform and the like floor, etc. up to any thickness, up to all floor level and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	9.48 Square metre	486.30	Rupees Four Hundred Eighty Six And Paise Thirty Only	Per Square metre	4,610.00
5	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-25 (Twenty five) design mix to obtain the minimum compressive strength of 20N/mm <sup>2</sup> (Twenty newton per square millimetre) with cement contents not less than @ 330 kg/cum (at the rate Three hundred thirty kilogram per cubic metre) or as per approved design mix. All works upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability etcetera including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, drawing, design and as directed by the Government.	2.95 Cubic metre	6934.90	Rupees Six Thousand Nine Hundred Thirty Four And Paise Ninety Only	Per Cubic metre	20,458.00
6	Toll tax, sale tax, GST and any other taxes imposed by the Government. Providing for steel reinforcement of Tata/Sail or preferred make for Reinforced Cement Concrete work including straightening, cutting, bending, placing in position and binding all complete upto all floor level Thermo-Mechanically Treated bars of grade Fe-500D or more etcetera complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	149.40 Kilogram	76.85	Rupees Seventy Six And Paise Eighty Five Only	Per kilogram	11,481.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
7	Supplying and stacking of hard stone (for stone pitching) 22.5 cm (Twenty two point five centimetre) thick at site including watering ramming, consolidating and dressing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	0.88 Cubic metre	969.80	Rupees Nine Hundred Sixty Nine And Paise Eighty Only	Per Cubic metre	853.00
8	40mm (Forty millimetre) thick cement concrete flooring 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (Twenty millimetre) nominal size laid in one layer finished with a floating coat of neat cement complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.00 Square metre	378.95	Rupees Three Hundred Seventy Eight And Paise Ninety Five Only	Per Square metre	4,547.00
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point five) in foundation and plinth above plinth level upto all floor level in cement mortar 1:6 (one cement isto six sand) and curing complete as per approved drawing, design, specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.45 Cubic metre	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic metre	22,425.00
10	Providing and applying 15mm (fifteen millimeters) thick cement plaster with cement mortar 1:6 (one cement isto six sand) in single coat on rough side of brick/concrete/ stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth complete as per HPPWD specifications and as per direction by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	54.00 Square metre	196.45	Rupees One Hundred Ninety Six And Paise Forty Five Only	Per Square metre	10,608.00
11	Steel work of Tata/Sail preferred make, riveted, bolted or welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	750.00 Kilogram me	107.45	Rupees One Hundred Seven And Paise Forty Five Only	Per Kilogram me	80,588.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
12	Providing and fixing 0.60mm (zero point six zero millimetre) thick ISI marked Z-120 (Z-one hundred twenty) pre-painted steel sheet of TATA/Sail/Reliance/Jindal in roofing over steel trusses with hot dip metallic zinc coated sheet with top coat of regular modified polyester (RMP) Organic coating of 20 (TWENTY) microns over 5 (five) microns of primer back coat of polyester of 5 (five) microns over 5 (five) primer coating including finishing with pre-painted, iron J or L hoks, bolts and nuts 6mm (six millimeter) diameter with pre-painted limpet and rubber washer filled with required colour and laid completely with all accessories or required as per direction of Engineer-In-Charge including carriage of materials with in all lead and lift and other incidental as per the direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government	23.14 Square metre	1086.00	Rupees One Thousand Eighty Six Only	Per Square metre	25,130.00
13	Providing and fixing ridges or hips 60cm (Sixty centimetre) over all with 0.60 (zero point six zero millimetre) thick pre-painted steel sheet of TATA/Sail preferred make in roofing with hot dip metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (five) microns of primer back coat of polyester of 5 (five) microns over 5 (five) primer coating including finishing with pre-painted iron J or L hoks, bolts and nuts 6mm (six millimeter) diameter with pre-painted limpet and rubber washer complete with all accessories or required as per direction of Engineer-in-Charge including carriage of materials with in all lead and lift and other incidental. The rate including Royalty, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	5.10 Running metre	721.90	Rupees Seven Hundred Twenty One And Paise Ninety Only	Per Running metre	3,682.00
14	Providing and fixing M.S. black plain sheet 2.00mm (Two point zero zero millimeter) thick in facia/leaves boards/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per HPPWD specifications and as directed by the Engineer-in-Charge. (base members of steel work shall be measured and paid for separately), including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	6.86 Square metre	1692.40	Rupees One Thousand Six Hundred Ninety Two And Paise Forty Only	Per Square metre	11,610.00
15	Painting steel work with Deluxe Multi Surface Paint to give an even shade Two or more coat applied @ 0.90 litr/10 sqm over an under coat of primer applied @0.80 litr/10 sqm of approved brand and manufacture completed and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	40.00 Square metre	89.90	Rupees Eighty Nine And Paise Ninety Only	Per Square metre	3,596.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
16	Applying Birla J.K white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose material and other foreign matters, sand papered smooth to give final matt finish to the surface complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	54.00 Square metre	85.10	Rupees Eighty Five And Paise Ten Only	Per Square metre	4,595.00
17	Finishing walls with weather proof exterior emulsion paint of Asian/Dulux /Berger/Nerdiac Suraksha paints of approved shade having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.67 litre/10 sqm. (One point six seven litre per ten square metre) Over and including priming coat of exterior primer applied @ 2.20litre/10 sqm (Two point two zero litre) per ten square metre complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	54.00 Square metre	110.05	Rupees One Hundred Ten And Paise Five Only	Per Square metre	5,943.00
<b>TOTAL</b>						<b>2,61,520.00</b>
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,  
Dehra Division,  
CHPPWD Dehra.

*Pericate Bill Q quantity  
checked for approval on 26/11/24*

181

**PERCENTAGE BILL OF QUANTITY**

Name of work:- Restoration of rain damages on Jawalamukhi Dehra Jawali Raja Ka Talab road Km 4/0 to 39/180 (SH:- Construction of PWall for Culvert at RD 6/400 to 6/410), PDNA

Estimate Cost :- Rs. 1,19,214.00  
 Earnest Money :- Rs. 2,400.00  
 Time Limit :- Two Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORO Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.10 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,929.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORO technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	26.20 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,06,110.00

No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
3	Providing 100mm (One Hundred millimeter) dia PVC pipe Weep Holes in brick masonry/stone masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORR technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	8.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	2,000.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORR technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.90 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	8,175.00
Total						1,19,214.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

*Per cent by 18% of quantity  
 Check 1 & 2/1/2020 of Rs 1,19,21*

*[Signature]*  
 Executive Engineer,  
 Dehra Division  
 P.P.W.D. Dehra