

Office of the Executive Engineer Bangana Division Himachal Pradesh
Public Works Department Bangana.

Phone No. 01975- 262283

E-mail:- ee-ban-hp@nic.in

No:- PW-BGN-CB/T-1/2025-26-
To

14196-14204

Dated:- 09/03/2026


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.
cc-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender.As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Bangana Division
HPPWD Bangana.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Notice Board.


Executive Engineer
Bangana Division
HPPWD Bangana.

Office of the Executive Engineer Bangana Division Himachal Pradesh
Public Works Department Bangana.



No. 01975-262283

E-mail:- ee-ban-hp@nic.in

CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency
in opening these tenders without press vide this office letter No. PW-BGN/CB/T-1/2025-26-1496-204 dated 09/03/2026

Jamal Chinn
Executive Engineer
Bangana Division
HPPWD Bangana.



Office of the Executive Engineer Bangana Division Himachal Pradesh
Public Works Department Bangana.

Phone No. 01975- 262283

E-mail:- ee-ban-hp@nic.in

NOTICE INVITING TENDER

Scaled percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP from the approved eligible contractors enlisted in HPPWD. for the following works, so as to reach this office on **16.03.2026 up to 10:30 AM** and same will be opened on the same day at **11.00 AM** in presence of the interested contractors or their authorized representative. The application will be received in this office on at **12.03.2026 up to 3.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **13.03.2026** during office hours **up to 4:00 PM**. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc of any post office of HP or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act. Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Restoration of Rain Damages on Various Road Under DBR-Basal Sub Division (Sub Head - Maintenance of Berms, Drains & Removal of Slips in Khurwain Section)	Rs 99826.00	Rs 2000.00	One Month	D & C
2	Restoration of Rain Damages on UAM Road (Sub Head - Maintenance of Berms, Drain & Removal of Slips in Khurwain Section)	Rs 99626.00	Rs 2000.00	One Month	D & C
3	Restoration of Rain Damages on Various Roads Under DBR-Basal Sub Division (Sub Head - Hiring of JCB for Removal of Slips, Road Side Drain, Shoulder Berms & Road Surface in Khurwain Section)	Rs 89775.00	Rs 1800.00	One Month	D & C
4	Restoration of Rain Damages on Piploo Sukrial Road Km 0/000 to 7/240 (Sub Head - Removal of Slips Km 3/450 to 5/015)	Rs 99975.00	Rs 2000.00	One Month	D & C
5	Restoration of Rain Damages on Piploo Sukrial Road Km. 0/000 to 7/240 (Sub Head - Removal of Slips Km. 3/150)	Rs. 99875.00	Rs 2000.00	One Month	D & C
6	Restoration of Rain Damages on Piploo Sukrial Road Km 0/000 to 7/240 (Sub Head - Removal of Slips in Km 5/030 to 6/915)	Rs 99835.00	Rs 2000.00	One Month	D & C
7	Restoration of Rain Damages on Handola Jaghatkhana Km 0/000 to 3/390 (Sub Head - Hiring of Poclaim (Heavy Duty Excavator) From Km. 1/200 to 1/700 in Bihru Section)	Rs 99495.00	Rs. 2000.00	One Month	D & C
8	Restoration of Rain Damages on Handola Jaghatkhana Km 0/000 to 3/390. (Sub Head - Hiring of Poclaim (Heavy Duty Excavator) from Km 1/700 to 3/200 in Bihru Section)	Rs 99830.00	Rs. 2000.00	One Month	D & C
9	Restoration of Rain Damages on Link Road to Harizan Basii Padyola Km 0/000 to 2/000 (Sub Head - Hiring of JCB in Lathiani Section)	Rs 99960.00	Rs 2000.00	One Month	D & C
10	Stock Storage in HPPWD Sub Division DBR-Basal (Sub Head - Supply & Stacking 900MM Dia Hume Pipe in Dhamandri Section)	Rs 92000.00	Rs 1900.00	One Month	D & C
11	Restoration of Rain Damages on Hatli Beri Road Km. 0/000 to 1/105 (Sub Head - Construction of R/Wall from RD. 0/300 to 0/315)	Rs 76404.00	Rs 1600.00	One Month	D & C
12	Restoration of Rain Damages on Link Road Village Dharet to Kodra Km 0/000 to 3/000 (Sub Head - Construction of R/Wall from RD 0/440 to 0/445.80)	Rs 95772.00	Rs. 2000.00	One Month	D & C
13	Repair & Maintenance of HPPWD Rest House at Bangana District Una HP (Sub Head - Repair of VIP Toilet, Joinery Work etc).	Rs 99628.00	Rs 2000.00	One Month	D & C
14	Restoration of Rain Damages on Handola to Jaghatkhana Km 0/000 to 3/390 (Sub Head - Hiring of Tipper Under Section Bihru)	Rs. 99125.00	Rs 2000.00	One Month	D & C
15	Restoration of Rain Damages on Samoor to Lamlehri Road. (Sub Head:- Construction of R/Wall in Km. 2/450 to 2/458.40) Under RRD Head	Rs. 99963.00	Rs. 2000.00	One Month	D & C
16	Restoration of Rain Damages on Samoor to Lamlehri Road. (Sub Head:- Construction of R/Wall in KM. 2/466.80 to 2/475.20) Under RRD Head	Rs. 99925.00	Rs. 2000.00	One Month	D & C
17	Restoration of Rain Damages on Samoor to Lamlehri Road. (Sub Head:- Construction of R/Wall in KM. 2/458.40 to 2/466.80) Under RRD Head	Rs. 99963.00	Rs. 2000.00	One Month	D & C
18	Restoration of Rain Damages on Jogipanga Madanpur Lamlehri Road. (Sub Head:- Construction of R/Wall in KM. 3/200 to 3/208.40) Under RRD Head	Rs. 99940.00	Rs. 2000.00	One Month	D & C

19	Restoration of Rain Damages on Jogipanga Madanpur Lamlehri Road. (Sub Head:- Construction of R/Wall in KM. 3/208.40 to 3/216.80) Under RRD Head	Rs. 99948.00	Rs. 2000.00	One Month	D & C
20	R.R.D on Charara Arloo via Baggi road Km 0/000 to 4/500 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 4/500) Under RRD Head	99687.00	2000.00	One Month	D & C
21	R.R.D on Haili Talpi road Km 0/000 to 7/635 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 7/635) Under RRD Head	99995.00	2000.00	One Month	D & C
22	R.R.D on Lathiani Kodra road Km 0/000 to 8/420 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 2/000) Under RRD Head	99789.00	2000.00	One Month	D & C
23	R.R.D on Lathiani Kodra road Km 0/000 to 8/420 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 2/000 to 4/000)	99935.00	2000.00	One Month	D & C
24	R.R.D on Naloot to Pansari road Km 0/000 to 2/500 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 2/000) Under RRD Head	99909.00	2000.00	One Month	D & C
25	R.R.D on Una Aghar Maundi road Km 19/000 to 37/000 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 19/000 to 30/000)	99684.00	2000.00	One Month	D & C
26	R.R.D on Link road Talmehra to Dechar Rajpura road km 1/285 to 3/525 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 1/285 to 3/525) Under RRD Head	99966.00	2000.00	One Month	D & C
27	R.R.D on Link road to Village Dobar from TMBD road Km 0/000 to 5/375 (SH Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 5/375) Under RRD Head	99827.00	2000.00	One Month	D & C
28	Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH Hiring of JCB for removal of Slips, Roads side drain, Shoulders Berms and road surface in Teuri Section & Dhamandri) Under RRD Head	98411.00	2000.00	One Month	D & C
29	Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH Hiring of Poclair for removal of Slips in Khurwain Section) Under RRD Head	94550.00	1900.00	One Month	D & C
30	Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH Hiring of Poclair for removal of Slips in Khurwain Section) Under RRD Head	94550.00	1900.00	One Month	D & C
31	Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH Hiring of Poclair for removal of Slips in Khurwain Section) Under RRD Head	91500.00	1900.00	One Month	D & C
32	Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH Supply and stacking of Granular Sub-base material) Under RRD Head	97704.00	2000.00	One Month	D & C
33	Restoration of Rain Damages on UAM road Km 2/000 to 19/000 (SH Supply and stacking of Granular Sub-base material) Under RRD Head	95580.00	2000.00	One Month	D & C
34	Restoration of Rain Damages on link road to Village Jarola Km 0/000 to 0/120 (SH Formation cutting from Rd 0/067 to 0/112) Under RRD Head	99090.00	2000.00	One Month	D & C
35	Restoration of Rain Damages on link road to Village Jarola Km 0/000 to 0/090 (SH Formation cutting & C/o B/wall from Rd 0/068 to 0/078) Under RRD Head	99974.00	2000.00	One Month	D & C
36	Restoration of Rain Damages on link road to Village Jarola Km 0/000 to 0/090 (SH Formation cutting & C/o B/wall from Rd 0/080 to 0/090) Under RRD Head	99734.00	2000.00	One Month	D & C

HIM SUCHANA AVAM JAN SAMPARK.

Anil Kumar
 Executive Engineer
 Bangana Division
 HPPWD Bangana
 On behalf of Governor of Himachal Pradesh.

Percentage BOQ

①

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost Rs	99826.00
Name of work:- Restoration of Rain Damages on Various road under DBR-Basal Sub-Division (SH: Maintenance of berms, Drain and Removal of Slips in Khurwain Section)		Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	600.00	Per Square Metre	50.00	30000.00	Rupees Thirty Thousand Only
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	600.00	Per Square Metre	14.00	8400.00	Rupees Eight Thousand Four Hundred Only
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per Running Metre	23.00	4600.00	Rupees Four Thousand Six Hundred Only
4.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	451.00	Per cubic metre	126.00	56826.00	Rupees Fifty Six Thousand Eight Hundred & Twenty Six Only
Total in Figures					99826.00	Rupees Ninety Nine Thousand Eight Hundred & Twenty Six Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ


②

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost Rs	99626.00
Name of work:- Restoration of Rain Damages on UAM road (SH: Maintenance of berms, Drain and Removal of Slips in Khurwain Section)		Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	400.00	Per Square Metre	50.00	20000.00	Rupees Twenty Thousand Only
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	400.00	Per Square Metre	14.00	5600.00	Rupees Five Thousand Six Hundred Only
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per Running Metre	23.00	4600.00	Rupees Four Thousand Six Hundred Only
4.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	551.00	Per cubic metre	126.00	69426.00	Rupees Sixty Nine Thousand Four Hundred & Twenty Six Only
Total in Figures					99626.00	Rupees Ninety Nine Thousand Six Hundred & Twenty Six Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	89775.00
Name of work:- Restoration of Rain Damages on Various road under DBR-Basal Sub-Division (SH: Hiring of J.C.B for removal of Slips, road side drain, Shoulder berms and road surface in Khurwain Section)	Earnest Money Rs	1800.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	85.50	Per Hours	1050.00	89775.00	Rupees Eighty Nine Thousand Seven Hundred & Seventy Five Only
Total in Figures					89775.00	Rupees Eighty Nine Thousand Seven
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD, Bangana

Percentage BOQ

①

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost Rs	99975.00
Name of work:- R.R.D. on Piploo Sukrial road Km 0/000 to 7/240 (SH: Removal of Slips Km 3/450 to 5/015)		Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	799.80	Per cubic metre	125.00	99975.00	Rupees Ninety Nine Thousand Nine Hundred & Seventy Five Only
Total in Figures					99975.00	Rupees Ninety Nine Thousand Nine
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ


⑦ ③

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	99875.00
Name of work:- R.R.D. on Piploo Sukrial road Km 0/000 to 7/240 (SH: Removal of Slips Km 0/000 to 3/150)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	799.00	Per cubic metre	125.00	99875.00	Rupees Ninety Nine Thousand Eight Hundred & Seventy Five Only
Total in Figures					99875.00	Rupees Ninety Nine Thousand Eight
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ


~~6~~ 6

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	99835.00
Name of work:- R.R.D. on Piploo Sukrial road Km 0/000 to 7/240 (SH: Removal of Slips Km 5/030 to 6/915)	Earliest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	798.68	Per cubic metre	125.00	99835.00	Rupees Ninety Nine Thousand Eight Hundred & Thirty Five Only
Total in Figures					99835.00	Rupees Ninety Nine Thousand Eight
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

#7

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Handola Jaghatkhana Km 0/000 to 3/390 (SH:- Hiring of Poclain (Heavy duty Excavator) from Km 1/200 to 1/700 in Bihru Section)

Estimated Cost Rs 99495.00

Earnest Money Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kmg including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	29.70	Per Hours	3350.00	99495.00	Rupees Ninety Nine Thousand Four Hundred & Ninety Five Only
Total in Figures					99495.00	Rupees Ninety Nine Thousand Four
Quoted Rate in Figures					Excess (+)	
					Less (-)	

Authan
 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost	99830.00
Name of work:- Restoration of Rain Damages on Handola Jaghatkhana Km 0/000 to 3/390 (SH:- Hiring of Poclain (Heavy duty Excavator) from Km 1/700 to 3/200 in Bihru Section)		Earnest Money	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kms including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	29.80	Per Hours	3350.00	99830.00	Rupees Ninety Nine Thousand Eight Hundred & Thirty Only
Total in Figures					99830.00	Rupees Ninety Nine Thousand Eight
Quoted Rate in Figures					Excess (+)	
					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

⑨

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost Rs	99960.00
Name of work:- Restoration of Rain Damages on Link road to Harizan Basti Padyola Km 0/000 to 2/000 (SH: Hiring of JCB in Lathiani Section)		Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.20	Per Hours	1050.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine
Quoted Rate in Figures					Excess (+)	
Less (-)						


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost	92000.00
Name of work:- Stock Storage at HP.PWD Sub-Division DBR-Basal (SH: Supply and stacking 900mm dia Hume Pipe in Dhamandri-Section)	Rs	1900.00
	Earnest Money	Rs
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Supply and Stacking RCC 900mm dia Hume pipes NP-2 (2.50 mtr length each pipe) i/c collar approved brand/ISI marked including loading & unloading and stacking properly at site, including carriage of materials within all leads and lifts and including all incidentals and as per drawings and technical specification as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	10.00	Each	9200.00	92000.00	Rupees Ninety Two Thousand Only
Total in Figures					92000.00	Rupees Ninety Two Thousand Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	

Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D. on Hatli Beri Road Km 0/000 to 1/105 (SH: C/o R/wall from Rd 0/300 to 0/315)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	76404.00
Earnest Money Rs	1600.00
Time Limit:	One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks/ where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.20	Per cubic metre	300.00	2160.00	Rupees Two Thousand One Hundred & Sixty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	16.35	Per Cubic metre	4000.00	65400.00	Rupees Sixty Five Thousand Four Hundred Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex, D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1:1 (one) vertical: 20 (twenty horizontal) toward drawing face complete as per direction of Engineer in- Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.00	Each	246.00	3444.00	Rupees Three Thousand Four Hundred & Forty Four Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORI 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.75	Per Cubic metre	800.00	5400.00	Rupees Five Thousand Four Hundred Only
Total in Figures					76404.00	Rupees Seventy Six Thousand Four Hundred & Four Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD, Bangana

Percentage BOQ

14/12

Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana

Name of work:- R.R.D. onLink road Village Dharet to Kodra Km 0/000 to 3/000 (SH: C/o R/wall from Rd 0/440 to 0/445.80)

Estimated Cost
Rs 95772.00


Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	10.08	Per cubic metre	300.00	3024.00	Rupees Three Thousand & Twenty Four Only
2.00	Providing and laying cement concrete 1:5:10(one cement five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.21	Per Cubic metre	3550.00	85946.00	Rupees Eighty Five Thousand Nine Hundred & Fourty Six Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Each	246.00	2460.00	Rupees Two Thousand Four Hundred & Sixty Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604 7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.68	Per Cubic metre	650.00	4342.00	Rupees Four Thousand Three Hundred & Fourty Two Only
Total in Figures					95772.00	Rupees Ninety Five Thousand Seven Hundred & Seventy Two Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

H/13

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Repair & Maintenance of HPPWD Rest House at Bangana Distt. Una HP. (SH: Repair of VIP Toilet, Joinery Work etc.)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	99628.00
Earnest Money Rs	2000.00
Time Limit:	One Month

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make Hindalco, Jindal, Indian Aluminium Company conforming to IS. 733 and IS. 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete for shutters of doors, windows and ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber neoprene gasket required (Fittings shall be paid for separately Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) complete upto all floor level as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	51.10	Per Kilogramme	736.00	37610.00	Rupees Thirty Seven Thousand Six Hundred & Ten Only
2.00	Providing and fixing 12 mm thick Pre-laminated particle board with decorative lamination on both sides flat pressed three layer or graded wood particle board conforming to IS. 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.06	Per Square meter	1732.00	10496.00	Rupees Ten Thousand Four Hundred & Ninety Six Only
3.00	Providing and fixing Float glass panes of nominal thickness 5 mm (five millimetre) make of Modi Float, Saint Govind, Aashai (weight not less than 12.5kg/sqm (twelve point five kilogram per square metre) of renewing glass panes with putty and nails wherever necessary including racking out the old putty including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.39	Per Square meter	1483.00	578.00	Rupees Five Hundred & Seventy Eight Only
4.00	Providing & fixing fly proof Stainless steel (grade 304(three hundred four)) wire gauze of 0.5 mm(zero point five millimetre) dia wire and 1.4 mm (one point four millimetre) aperture on both sides complete to windows, clerestory windows & doors with aluminium snap beading and nuts & bolts complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.43	Per Square meter	1480.00	3596.00	Rupees Three Thousand Five Hundred & Ninety Six Only
5.00	Providing and fixing 18 mm (Eighteen millimetre) thick HDHMR(High density High moisture Resistance board of (Action Tesa/Kitply/Century ply make) in shelves/box for cup board with butt joints and fixing with nails and screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.31	Per Square meter	1950.00	16205.00	Rupees Sixteen Thousand Two Hundred & Five Only
6.00	Providing and fixing Cup Board Shutters with 18 mm (Eighteen millimetre) thick HDHMR(High density High moisture Resistance board of Action TESA / Green Ply/ Kit Ply/ Century Ply make with necessary screws and bright finished stainless steel piano hinges, complete upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.60	Per Square meter	2210.00	3536.00	Rupees Three Thousand Five Hundred & Thirty Six Only
7.00	Providing and fixing 0.7 mm(Zero point seven millimetre) to 0.8 mm (Zero point eight millimetre) thick coloured or plain lamination sheet of Greenlam/ century ply / kit ply or its equivalent make on boards/ply wood sheets with approved adhesive and nails etc complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.12	Per Square meter	1091.00	5586.00	Rupees Five Thousand Five Hundred & Eighty Six Only
8.00	Providing and fixing bright /matt finished Stainless steel handles (size 165mm), ISI marked, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Governmen	8.00	Per Square meter	440.00	3520.00	Rupees Three Thousand Five Hundred & Twenty Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
9.00	Providing and fixing Triple strip vertical type magnetic catcher of approved quality (Hettich/Jodrej) in cupboard / ward robe shutters, including fixing with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	8.00	Per Square meter	93.00	744.00	Rupees Seven Hundred & Forty Four Only
10.00	Providing and fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. in cupboard / ward robe drawer, including fixing with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	4.00	Per Square meter	361.00	1444.00	Rupees One Thousand Four Hundred & Forty Four Only
11.00	Providing and fixing aluminum sliding door bolts 250x10mm, ISI marked Powder coated aluminium (minimum thickness of powder coating 50 micron) transparent or dyed to required colour or shade, with nuts and screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.00	Each	289.00	578.00	Rupees Five Hundred & Seventy Eight Only
12.00	Providing and fixing aluminum tower bolts 200x10mm, ISI marked Powder coated aluminium (minimum thickness of powder coating 50 micron) transparent or dyed to required colour or shade, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	6.00	Each	105.00	630.00	Rupees Six Hundred & Thirty Only
13.00	Providing and fixing aluminum tower bolts 150x10mm, ISI marked Powder coated aluminium (minimum thickness of powder coating 50 micron) transparent or dyed to required colour or shade, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	4.00	Each	90.00	360.00	Rupees Three Hundred & Sixty Only
14.00	Providing and fixing aluminum handles 200mm, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	9.00	Each	92.00	828.00	Rupees Eight Hundred & Twenty Eight Only
15.00	Providing and fixing P.V.C. waste semi rigid pipe for sink or wash basin including P.V.C. waste fittings complete 32mm (thirty two millimetre) dia of Supreme / Fenolax make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	143.00	143.00	Rupees One Hundred & Forty Three Only
16.00	Providing and fixing Stainless Steel Hanger complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	551.00	1102.00	Rupees One Thousand One Hundred & Two Only
17.00	Providing and fixing Stainless Steel towel ring complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	1.00	Each	1907.00	1907.00	Rupees One Thousand Nine Hundred & Seven Only
18.00	Providing and fixing glass shelf with edges round off 600x120 mm, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc. complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	1.00	Each	2403.00	2403.00	Rupees Two Thousand Four Hundred & Three Only
19.00	Providing and fixing corner glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc. complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	1.00	Each	1621.00	1621.00	Rupees One Thousand Six Hundred & Twenty One Only
20.00	Providing and fixing Chromium Plated soap Dish with CP Brass bracket fixed to wooden cleat with C.p brass Screw complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.00	Each	1100.00	2200.00	Rupees Two Thousand Two Hundred Only
21.00	Providing and fixing Chromium Plated liquid soap dispenser with CP Brass bracket fixed to wooden cleat with C.p brass Screw complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	1.00	Each	659.00	659.00	Rupees Six Hundred & Fifty Nine Only
22.00	Providing and fixing Chromium Plated Tumble Holder with CP Brass bracket fixed to wooden cleat with C.p brass Screw complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	4.00	Each	731.00	2924.00	Rupees Two Thousand Nine Hundred & Twenty Four Only
23.00	Providing and fixing unplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	5.00	Each	110.00	550.00	Rupees Five Hundred & Fifty Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
24.00	Providing and fixing Chromium Plated grating of approved quality and colour including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	154.00	308.00	Rupees Three Hundred & Eight Only
25.00	Providing and fixing Chromium Plated waste coupling for wash basin and sink, of approved quality and colour including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	100.00	100.00	Rupees One Hundred Only
Total in Figures					99628.00	Rupees Ninety Nine Thousand Six Hundred & Twenty Eight Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

7/14

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Handola to Jaghatkhana Km 0/000 to 3/390 (SH:- Hiring of Tipper under Section Bihru)

Estimated Cost Rs	99125.00
Earnest Money Rs	2000.00
Time Limit:	One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns. else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Tipper 5.5 cum capacity having lift system for carriage of meterial to different site of work eith in all leads and lifts to the entire satisfaction of the Engineer In-charge. The tipper should work minimum 8.00(Eight hours) from 9.00 A.M. to 5.00P.M. dally. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in charge.. The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	32.50	Per Day	3050.00	99125.00	Rupees Ninery Nine Thousand One Hundred & Twenty Five Only
Total in Figures					99125.00	Rupees Ninery Nine Thousand One
Qouted Rate in Figures					Excess (+)	
Less (-)						

Amal Chandra
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Samoor to Lamlehri Road (SH: C/o R/wall in Km 2/450 to 2/458.40)


Estimated Cost	99963.00
Rs	
Earnest Money	2000.00
Rs	
Time Limit:	One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	12.00	Per cubic metre	381.00	4572.00	Rupees Four Thousand Five Hundred & Seventy Two Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government	21.75	Per Cubic metre.	3980.00	86565.00	Rupees Eighty Six Thousand Five Hundred & Sixty Five Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex D-Plast make having working pressure 4 00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	300.00	2400.00	Rupees Two Thousand Four Hundred Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604 7 8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.56	Per Cubic metre	850.00	6426.00	Rupees Six Thousand Four Hundred & Twenty Six Only
Total in Figures					99963.00	Rupees Ninety Nine
Quoted Rate in Figures						
					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99925.00
Name of work:- Restoration of Rain Damages on Samoor to Lamlehri Road (SH: C/o R/wall in Km 2/466.80 to 2/475.20)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	12.00	Per cubic metre	381.00	4572.00	Rupees Four Thousand Five Hundred & Seventy Two Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement .four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	21.75	Per Cubic metre.	3980.00	86565.00	Rupees Eighty Six Thousand Five Hundred & Sixty Five Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	300.00	2400.00	Rupees Two Thousand Four Hundred Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.56	Per Cubic metre	845.00	6388.00	Rupees Six Thousand Three Hundred & Eighty Eight Only
Total in Figures					99925.00	Rupees Ninety Nine
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost	99963.00
Name of work:- Restoration of Rain Damages on Samoor to Lamlehri Road (SH: C/o R/wall in Km 2/458.40 to 2/466.80)	Earnest Money	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	12.00	Per cubic metre	381.00	4572.00	Rupees Four Thousand Five Hundred & Seventy Two Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water.dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government	21.75	Per Cubic metre.	3980.00	86565.00	Rupees Eighty Six Thousand Five Hundred & Sixty Five Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertica) 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	300.00	2400.00	Rupees Two Thousand Four Hundred Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.56	Per Cubic metre	850.00	6426.00	Rupees Six Thousand Four Hundred & Twenty Six Only
Total in Figures					99963.00	Rupees Ninety Nine
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Jogipanga Madanpur Lamlehri road (SH: C/o R/wall in Km 3/200 to 3/208.40)


Estimated Cost Rs	99940.00
Earnest Money Rs	2000.00
Time Limit:	One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	12.00	Per cubic metre	381.00	4572.00	Rupees Four Thousand Five Hundred & Seventy Two Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed/broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	21.75	Per Cubic metre.	3980.00	86565.00	Rupees Eighty Six Thousand Five Hundred & Sixty Five Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of diameter: D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical: 20 (twenty) horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	300.00	2400.00	Rupees Two Thousand Four Hundred Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604 7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.56	Per Cubic metre	847.00	6403.00	Rupees Six Thousand Four Hundred & Three Only
Total in Figures					99940.00	Rupees Ninety Nine
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD, Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Jogipanga Madanpur Lamlehri road (SH: C/o R/wall in Km 3/208.40 to 3/216.80)

Estimated Cost 999.48.00

Rs

Earnest Money 2000.00

Rs


Time Limit: One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and MORD 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	12.00	Per cubic metre	381.00	4572.00	Rupees Four Thousand Five Hundred & Seventy Two Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement Four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	21.75	Per Cubic metre	3980.00	86565.00	Rupees Eighty Six Thousand Five Hundred & Sixty Five Only
3.00	Providing weep holes in stone masonry plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of flexible D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	300.00	2400.00	Rupees Two Thousand Four Hundred Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.56	Per Cubic metre	848.00	6411.00	Rupees Six Thousand Four Hundred & Eleven Only
Total in Figures					999.48.00	Rupees Ninety Nine
Quoted Rate in Figures			Excess (+)			
			Less (-)			


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana


Name of work:- R.R.D on Charara Arloo via Baggi road Km 0/000 to 4/500 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 4/500)

Estimated Cost Rs	99687.00
Earnest Money Rs	2000.00
Time Limit:	One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1230.00	Per Square Metre	41.30	50799.00	Rupees Fifty Thousand Seven Hundred & Ninety Nine Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per Running Metre	54.14	37898.00	Rupees Thirty Seven Thousand Eight Hundred & Ninety Eight Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per Square Metre	15.70	10990.00	Rupees Ten Thousand Nine Hundred & Ninety Only
Total in Figures					99687.00	Rupees Ninety Nine Thousand Six Hundred & Eighty Seven Only
		Quoted Rate in Figures		Excess (+)		
				Less (-)		


Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

2 3

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D on Hatli Talpi road Km 0/000 to 7/635 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 7/635)


Estimated Cost Rs	99994.00
Earnest Money Rs	2000.00
Time Limit:	One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1244.00	Per Square Metre	41.30	51377.00	Rupees Fifty One Thousand Three Hundred & Seventy Seven Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	695.00	Per Running Metre	54.14	37627.00	Rupees Thirty Seven Thousand Six Hundred & Twenty Seven Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per Square Metre	15.70	10990.00	Rupees Ten Thousand Nine Hundred & Ninety Only
Total in Figures					99994.00	Rupees Ninety Nine Thousand Nine Hundred & Ninety Four Only
Quoted Rate in Figures					Excess (+)	
Quoted Rate in Figures					Less (-)	


Executive Engineer
Bangana Division
HP.PWD. Bangana

22/4

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	99789.00
Name of work:-R.R.D on Lathiani Kodra road Km 0/000 to 8/420 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 2/000)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1224.00	Per Square Metre	41.30	50551.00	Rupees Fifty Thousand Five Hundred & Fifty One Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	705.00	Per Running Metre	54.14	38169.00	Rupees Thirty Eight Thousand One Hundred & Sixty Nine Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	705.00	Per Square Metre	15.70	11069.00	Rupees Eleven Thousand & Sixty Nine Only
Total in Figures					99789.00	Rupees Ninety Nine Thousand Seven Hundred & Eighty Nine Only
Quoted Rate in Figures					Excess (+)	
Less (-)						

Amal Kumar
Executive Engineer
Bangana Division
HP.PWD. Bangana

23/5

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost Rs	99935.00
Name of work:- R.R.D on Lathiani Kodra road Km 0/000 to 8/420 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 7/000)		Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1236.00	Per Square Metre	41.30	51047.00	Rupees Fifty One Thousand & Fourty Seven Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per Running Metre	54.14	37898.00	Rupees Thirty Seven Thousand Eight Hundred & Ninety Eight Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per Square Metre	15.70	10990.00	Rupees Ten Thousand Nine Hundred & Ninety Only
Total in Figures					99935.00	Rupees Ninety Nine Thousand Nine Hundred & Hurty Five Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	

[Signature]
 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

(24)


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost	99909.00
Name of work:-R.R.D on Naloot to Pansai road Km 0/000 to 2/500 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 2/000)	Earrest Money	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1232.00	Per Square Metre	41.30	50882.00	Rupees Fifty Thousand Eight Hundred & Eighty Two Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	702.00	Per Running Metre	54.14	38006.00	Rupees Thirty Eight Thousand & Six Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	702.00	Per Square Metre	15.70	11021.00	Rupees Eleven Thousand & Twenty One Only
Total in Figures					99909.00	Rupees Ninety Nine Thousand Nine Hundred & Nine Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD. Bangana

(25) 7

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Estimated Cost Rs 99684.00

Name of work:-R.R.D on Una Aghar Mandi road Km 19/000 to 37/000 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 19/000 to 30/000)

Earnest Money Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2160.00	Per Square Metre	41.30	89208.00	Rupees Eighty Nine Thousand Two Hundred & Eight Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	150.00	Per Running Metre	54.14	8121.00	Rupees Eight Thousand One Hundred & Twenty One Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	150.00	Per Square Metre	15.70	2355.00	Rupees Two Thousand Three Hundred & Fifty Five Only
Total in Figures					99684.00	Rupees Ninety Nine Thousand Six Hundred & Eighty Four Only
Quoted Rate in Figures				Excess (+)		
Quoted Rate in Figures				Less (-)		

(Signature)
**Executive Engineer
 Bangana Division
 HP.PWD.Bangana**

26 9

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:-R.R.D on Link road Talmehra to Deehar Rajpura road km 1/285 to 3/525(SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 1/285 to 3/525)

Estimated Cost Rs 99966.00

Earnest Money Rs 2000.00


Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1224.00	Per Square Metre	41.30	50551.00	Rupees Fifty Thousand Five Hundred & Fifty One Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll-tax, sale tax or other taxes imposed by the Government.	708.00	Per Running Metre	54.14	38331.00	Rupees Thirty Eight Thousand Three Hundred & Thirty One Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	706.00	Per Square Metre	15.70	11084.00	Rupees Eleven Thousand & Eighty Four Only
Total in Figures					99966.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Six Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

27/10

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost	99827.00
Name of work:-R.R.D on Link road to Village Dobar from TMBD road Km 0/000 to 5/375 (SH: Making up Loss material on Shoulders & C/o Unlined Drain from Km 0/000 to 5/375)		Earnest Money	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1224.00	Per Square Metre	41.30	50551.00	Rupees Fifty Thousand Five Hundred & Fifty One Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	706.00	Per Running Metre	54.14	38223.00	Rupees Thirty Eight Thousand Two Hundred & Twenty Three Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	704.00	Per Square Metre	15.70	11053.00	Rupees Eleven Thousand & Fifty Three Only
Total in Figures					99827.00	Rupees Ninety Nine Thousand Eight Hundred & Twenty Seven Only
Quoted Rate in Figures					Excess (+)	
Less (-)						

Executive Engineer
Bangana Division
HP.PWD. Bangana

26.

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH: Hiring of J.C.B. for removal of Slips, Roads side drain, Shoulders Berms and road surface in Teuri Section & Dhamandri)

Estimated Cost Rs	98411.00
Earnest Money Rs	2000.00
Time Limit:	One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar. moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax.GST. sale tax or other taxes imposed by the Government.	85.50	Per Hours	1151.00	98411.00	Rupees Ninety Eight Thousand Four Hundred & Eleven Only
Total in Figures					98411.00	Rupees Ninety Eight Thousand Four Hundred & Eleven Only
Quoted Rate in Figures				Excess (+)		
				Less (-)		

Amal Kumar
Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ



Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	94550.00
Name of work:- Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH: Hiring of Poclairn for removal of Slips in Khurwain Section)	Earnest Money Rs	1900.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 KmgS including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	31.00	Per Hours	3050.00	94550.00	Rupes Ninety Four Thousand Five Hundred & Fifty Only
Total in Figures					94550.00	Rupes Ninety Four Thousand Five Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				

Signature

**Executive Engineer
Bangana Division
HP.PWD. Bangana**

Percentage BOQ


30 28.

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	94550.00
Name of work:- Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH: Hiring of Poelain for removal of Slips in Khurwain Section)	Earnest Money Rs	1900.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kngs including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary . The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	31.00	Per Hours	3050.00	94550.00	Rupees Ninety Four Thousand Five Hundred & Fifty Only
Total in Figures					94550.00	Rupees Ninety Four Thousand Five Hundred & Fifty Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

3 29


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	91500.00
Name of work:- Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH: Hiring of Poclair for removal of Slips in Khurwain Section)	Earnest Money Rs	1900.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kms including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	30.00	Per Hours	3050.00	91500.00	Rupees Ninety One Thousand Five Hundred Only
Total in Figures					91500.00	Rupees Ninety One Thousand Five Hundred Only
Qouted Rate in Figures				Excess (+)		
Qouted Rate in Figures				Less (-)		


Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	97704.00
Name of work:- Restoration of Rain Damages on various roads under DBR-Basal Sub-Division (SH: Supply and stacking of Granular Sub-base material)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Supply and Stacking of gravel/soil aggergate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008, including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty. Malkana, toll tax, sale tax , goods service tax, labour cess or other taxes imposed by the Government.	92.00	Per cubic metre	1062.00	97704.00	Rupees Ninety Seven Thousand Seven Hundred & Four Only
Total in Figures					97704.00	Rupees Ninety Seven Thousand Seven Hundred & Four Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ


37

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	95580.00
Name of work:- Restoration of Rain Damages on UAM road Km 2/000 to 19/000 (SH: Supply and stacking of Granular Sub-base material)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Supply and Stacking of gravel/soil aggergate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008, including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty. Malkana, toll tax, sale tax , goods service tax, labour cess or other taxes imposed by the Government.	90.00	Per cubic metre	1062.00	95580.00	Rupees Ninety Five Thousand Five Hundred & Eighty Only
Total in Figures					95580.00	Rupees Ninety Five Thousand Five Hundred & Eighty Only
Qouted Rate in Figures		Excess (+)				
Qouted Rate in Figures		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost	99090.00
Name of work:-Restoration of Rain Damages on link road to Village Jarola Km 0/000 to 0/120 (SH: Formation cutting from Rd 0/067 to 0/112)	Earnest Money	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603.1 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or /labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	204.75	Per Cubic metre	240.00	49140.00	Rupees Fourty Nine Thousand One Hundred & Fourty Only
2.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603.1 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or /labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts. A recovery of 13.50cum (thirteen point five zero only) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	135.00	Per Cubic metre	370.00	49950.00	Rupees Fourty Nine Thousand Nine Hundred & Fifty Only
Total in Figures					99090.00	Rupees Ninety Nine Thousand & Ninety Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

33

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:-Restoration of Rain Damages on link road to Village Jarola Km 0/000 to 0/090 (SH: Formation cutting & C/o B/wall from Rd 0/068 to 0/078)

Estimated Cost Rs 99974.00

Earnest Money Rs 2000.00


Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1603 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of an useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	33.00	Per Cubic metre	240.00	7920.00	Rupees Seven Thousand Nine Hundred & Twenty Only
2.00	Earth work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains in ordinary rock / all kind of soil (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, upto all leads and lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all lead and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge all leads and lifts including clearing of jungle Pick Jumper work and than disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, Labour Cess or other taxes imposed by the Government.	10.44	Per Cubic metre.	250.00	2610.00	Rupees Two Thousand Six Hundred & Ten Only
3.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	23.55	Per Cubic metre	3610.00	85016.00	Rupees Eighty Five Thousand & Sixteen Only
4.00	Providing weep holes in stone masonry, plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.00	Each	246.00	4428.00	Rupees Four Thousand Four Hundred & Twenty Eight Only
Total in Figures					99974.00	Rupees Ninety Nine Thousand Nine Hundred & Seventy Four Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD. Bangana

38

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	99734.00
Name of work:-Restoration of Rain Damages on link road to Village Jarola Km 0/000 to 0/090 (SH: Formation cutting & C/o B/wall from Rd 0/080 to 0/090)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per Technical Specification MORD 2014 Clause 1605 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of a useful material for filling in road ways, camber, embankments for grade improvements and disposal of all unuseful material to required width of the road or on approved dumping sites by Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per the direction of Engineer- in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	32.00	Per Cubic metre	240.00	7680.00	Rupees Seven Thousand Six Hundred & Eighty Only
2.00	Earth work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains in ordinary rock / all kind of soil (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, upto all leads and lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all lead and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge all leads and lifts including clearing of jungle. Pick Jumper work and than disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, Labour Cess or other taxes imposed by the Government.	10.44	Per Cubic metre.	250.00	2610.00	Rupees Two Thousand Six Hundred & Ten Only
3.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	23.55	Per Cubic metre	3610.00	85016.00	Rupees Eighty Five Thousand & Sixteen Only
4.00	Providing weep holes in stone masonry, plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	18.00	Each	246.00	4428.00	Rupees Four Thousand Four Hundred & Twenty Eight Only
Total in Figures					99734.00	Rupees Ninety Nine Thousand Seven Hundred & Thirty Four Only
Quoted Rate in Figures		Excess (+)				
Quoted Rate in Figures		Less (-)				

Anil Kumar
Executive Engineer
Bangana Division
HP.PWD, Bangana