HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.: PW/ESDD/CONT/2025-26/- **10515-24** **Dated: 13-03-2026**

To

The Executive Engineer (IT Cell),
Nigam Vihar, Shimla-2.

Subject: **Publishing of Short Term Tender Notice.**

Jai Hind

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender along with Schedule of Quantities for uploading on departmental website as per Notification Pr. SEC(PW) to the Govt. of HP letter No. PBW(B)A9(3)1/2020 dated Shimla-26th July 2021.

It is certified that the works mentioned in the Notice Inviting Tenders are urgent in nature and in public Interest.

DA/NIT,SQs

Executive Engineer
Electrical Division
HP PWD Palampur

Copy forwarded to the following for information and necessary action please:

1. The Superintending Engineer, 2nd Electrical Circle, HP PWD Dharamshala.
2. All the Assistant Engineers Working under this Division.
3. Drawing Branch of this office.
4. The Notice board in this office.

Executive Engineer
Electrical Division
HP PWD Palampur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"Notice Inviting Tenders"

Sealed percentage rate tenders on form 7&8 are hereby invited by the Executive Engineer, Electrical Division, HP PWD Palampur on behalf of the Governor of H.P. for the following work from the approved and eligible contractors enlisted in HP PWD, (Elect.) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act. 1968 so as to reach in his office on or before **20-03-2026** up to 11.00 AM, and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **20-03-2026** up to 4.00 P.M. and the application for issue of tender form shall be received on **19-03-2026** up to 12.00 noon.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	R/M of various non residential buildings (SH:- Providing and fixing computer points in different court Rooms in old court and ADR Building at Dharamshala Distt kangra (H.P).	74,735/-	1500/-	One month	350/-
2	R/M of type 3 qtr C-16 at chellian Dharamshala district Kangra (S.H- providing and fixing light point, 5amp & 15 amp power plugs and gyser and other accessories).	25,783/-	500/-	One month	350/
3	R/M of Various Non Residential Building (SH:-Providing and laying armoured cable for solar conection in old court building at Dharamshala Distt Kangra (H.P).	32,130/-	700/-	One month	350/
4	Repair and Maintenance of E.I. to various Govt. Non—Residential Buildings at ESD Dharamshala Distt. Kangra. (SH:-Replacement of damaged battery in lifts and in inverter in Circuit House Dharamshala District Kangra H.P)	88,019/-	1800/-	One month	350/
5	Repair and Maintenance of E.I. to various Govt. Non—Residential Buildings at ESD Dharamshala Distt. Kangra. (SH:-Providing and fixing old and damaged RCCB's, DP Isolator, MCB's replacement of LED Down lighters and wires,cable and campus light in Circuit House before the visit of Hon'ble President of india)	88,617/-	1800/-	Six months	350/
6	Repair and Maintenance of E.I. to various down lighter and other accessories and Providing skilled technician for Vidhan Sabha winter session in circuit house at Dhramshala District Kangra H.P).	70,486/-	1400/-	One month	350/
7	Repair and Maintenance of Portable Fire Extinguishers installed in 500 Bedded Hospital Dr. RPGMC Tanda.(SH: Refilling of Portable Fire Extinguishers of different Capacity and type of casualty block , treatment & service block to 4th floor etc. 500 bedded hospital Dr. RPGMC Tanda in Distt. Kangra (H.P).for the year 2025-2026.	93,540/-	1900/-	One month	350/
8	Repair and Maintenance of Portable Fire Extinguishers installed in 500 Bedded Hospital Dr. RPGMC Tanda.(SH: Refilling of Portable Fire Extinguishers of different Capacity and type at Private Ward Block, Record Room and Reception area, Blood Bank area and Electrical Sub station and Medicine store area etc. of 500 Bedded Hospital in Dr. RPGMC Tanda for the year 2026-27.	74,960/-	2000/-	One month	350/
9	C/O Health Sub-Centre (First Floor)at Kahan pat in Tehsil Palampur Distt Kangra (HP) (SH:- Providing E.I. therein).	98,659/-	2000/-	Two years	350/
10	Refilling of portable Fire Extinguishers installed in School of Nursing of Critical Care Skill lab/stimulation lab in Dr. RPGMC Tanda in Distt. Kangra (HP) for the year 2025-26.	20510/-	500/-	One Month	350/-

HIM SUCHNA AVAM JAN SAMPARK VIBHAG

This is certified that the above works are required to be carried out immediately being emergent nature of work in Public Interest. The Tender documents shall be issued only to those contractor/firm who fulfill the following criteria/documents with the application.

Conditions:

1. The contractor should have the EPF registration certificate should be attached with application.
2. The GST registration certificate.
3. The contractor should produce a copy of latest enlistment/renewal.
4. The latest ITR filed should be attached with application.
5. The bidders enlisted in a particular class shall be eligible to tender for his own class or one step below.
6. The bidder should attach authonzation and work done certificate with application for Specialized Jobs.
7. In case of Holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
8. Ambiguous/telephonic/conditional tenders or tenders fax/email/whatsapp shall not be considered and will be summarily be rejected.
9. The FDR duly pledged should be attached separately with each tender.
10. Only two number tender forms will be issued to the eligible contractor.
11. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected.
12. The Executive Engineer, Electrical Division, HP PWD Palampur reserves the right to reject any tender without assigning any reasons.

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-R/M of various non residential buildings (SH:- Providing and fixing computer points in different court Rooms in old court and Adr Building at Dharamshala distt kangra (H.P).			(1)	ESTIMATED COST:74,735/-only. EARNEST MONEY: Rs.1500-/-only TIME ALLOWED:-One month		
SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1.00	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / heavy class PVC conduit having wall thickness minimum 2 mm, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.					
1.01	**Group C.**	1	1202	Rs. One thousand two hundred two only	Per Point	1202
2.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed pvc conduit as required. **Make: finolex/Plaza/Anchor.**					
2.01	**2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire**	94	198	Rs. One hundred ninety eigh only	Per metre	18612
2.02	**2 X 4 sq. mm + 1 X 4 sq. mm earth wire**	30	311	Rs.three hunere elevn only	Per metre	9330
2.03	**4 X 4 sq. mm + 2 X 4 sq. mm earth wire**	36	524	Rs. Five hundred twenty four only	Per metre	18864
3.00	Supplying and fixing following rating Modular switch /socket in the existing switch box / cover plate including connections etc. as required.					

4.00	Supplying and fixing 6 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
4.01	**Single pole 6 Amp (Make:- Anchor/ Schneider/ Legrand/L&T)**	6	239	Rs. Two hundred thirty nine only	Each	1434
4.02	**Single pole 16/32 Amp (Make:- Anchor/ Schneider/ Legrand/L&T)**	5	239	Rs. Two hundred thirty nine only	Each	1195
5.00	Supplying and fixing following rating, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
5.01	**40 Amps. (Make:- Anchor/ Schneider/ Legrand/L&T)**	1	426	Rs. Four hundred twenty six only	Each	426
6.00	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).					
6.01	**Double door-8 way (Make:- Schneider/ Legrand/L&T)**	2	1703	Rs. One thousand seven hundred three only	Each	3406
7.00	Providing and installation exhaust fan of following sizes in the existing opening, including making the hole to suit the size of the above fan, making good the damages, connections, testing and commissioning etc. as required.					
7.01	Exhaust Fan, heavy duty) 300 mm sweep (Make: Usha, Model: Aeroclean LD)/Bajaj (Model: Freshee)/Anchor (Model: Anmol)/Crompton(Model: Drift air Plus) .	1	5436	Rs. Five thousand four hundred thirty six only	Each	5436

8.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required.	25	469	Rs. Four hundred sixty nine only	Each	11725
9.00	Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	5	621	Rs. Six hundred twenty only	Each	3105
	Total:-					**74735**

Draft Schedule of Quantity Checked & Approved
Rs. Rs. 74,735/-

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-R/M of type 3 qtr C-16 at chellian Dharamshala district kangra (S.H- providing and fixing light point, 5amp & 15 amp power plugs and gyser and other accessories).		(2)	ESTIMATED COST:25,783/-only. EARNEST MONEY: Rs.500-/-only TIME ALLOWED:-One month		
SR. NO.	DESCRIPTION	job No / RATES	WORDS	UNIT	AMOUNT
1.00	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / heavy class PVC conduit having wall thickness minimum 2 mm, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.				
1.01	**Group C.**	1 / 1202	Rs. One thousand two hundred two only	Per Point	1202
3.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required . **Make: finolex/Plaza/Anchor.**				
3.02	**2 X 4 sq. mm + 1 X 4 sq. mm earth wire**	15 / 311	Rs. Three hundred elevn only	Per Metre	4665
6.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. **Make: Schneider (Livia)/ Legrand (Myrius) /L&T(Entice).**	1 / 469	Rs. Four hundred sixty nine only	Each	469
8.00	Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	2 / 621	Rs. Six hundred twenty one only	Each	1242

11.00	Supplying and fixing Ding-Dong / Electronic musical bell, suitable for D.C./A.C. single phase, 230 volts complete as required:- **Make: Anchor/ Goldmedal/ Havells**	1	206	Rs. Two hundred six only	Each	206
13.00	Supplying and fixing 6 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
13.02	**Single pole 16 Amp (Make:- Schneider/ Legrand/L&T)**	2	239	Rs. Hundred thirty nine only	Each	478
18.00	Supplying and fixing LED Bulb of 12 watt with polycarbonate diffuser on the existing light point as required complete in all respect.	5	187	Rs. One hundred eighty seven only	Each	935
29.00	Providing and installation of stationary storage type Electric water heater (Geyser) of various sizes by means of expansion-bolts with nuts and washers, including embedding of expansion-bolts in the wall, making good the damages, electrical connections, testing etc. complete as required:-	1	12806	Rs. Twelve thousand eight hundred six only	Each	12806
30.00	**Supplying and fixing batten/ angle holder including connection etc. as required.**	4	95	Rs. Ninety five only	Each	380
31.00	Providing and fixing LED TUBE 4 FEET Light of IP20 Led fixture 20 W+/- 1W with Surface Mounted 2 Feet with Polycarbonate diffuser with Extruded aluminium housing having minimum system lumen output 1000 lumens and system lumen efficacy of 100 lm/W with P.F.>0.95 with THD<20% ,CRI 80. The LEDs used in the luminaire shall have CCT of ANSI Bin 6500 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.					
31.01	**LED fixture 20 Watt Surface Mounted 4 Feet TUBE LED Lamp Makes:- Philips/ Wipro/ Bajaj/ Leksa.**	5	680	Rs. Six hundred eighty only	Each	3400
	Total:-					**25783**

Detail Schedule of Quantity Checked & Approved for Rs. 25783/- only.

Executive Engineer
Electrical Division
HP PWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-R/M of Various Non Residential Building (SH:-Providing and laying armoured cable for solar conection in old court building at Dharamshala distt kangra (H.P).			ESTIMATED COST:32,130/-only. EARNEST MONEY: Rs.700-/-only TIME ALLOWED:-One month		
SR. NO.	DESCRIPTION	job No / RATES	WORDS	UNIT	AMOUNT
10.00	Providing & Laying of one number aluminium conductor, PVC insulated and PVC sheathed armoured/ XLPE power cable, 1.1 KV grade of following sizes on wall surface as required. **Make: finolex/Havells/Grandley.**				
10.01	**Armoured cable 10 sq. mm (Two core)**	126 / 255	Rs. Two hundred fifty five only	Per Metre	32130
	Total:-				**32130**

Draft Schedule of Quantity checked & Approved for Rs. 32130-/only

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of E.I. to various Govt. Non--Residential Buildings at ESD Dharamshala Distt. Kangra. (SH:-Replacement of damaged battery in lifts and in inverter in Circuit House Dharamshala District Kangra H.P)		(4)	**ESTIMATED COST:88,019-/-only.** **EARNEST MONEY: Rs.1800-/-only** **TIME ALLOWED:- One Month**

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1.00	Supplying, erection, testing & commissioning of batteries having following capacity sealed maintenance free-lead acid battery with suspended electrolyte (leak proof) suitable for different capacities UPS System etc. as required complete in all respects and to the best satisfaction of Engineer-in-Charge.					
1.01	**Battery 12 Volt 200 Ah Makes:- Exide /Amron/ Quanta.**	3	23120	Rs. Twenty three thousand one hundred twenty only	Each	69360
2.00	Supplying and drawing copper conductor, multicore cable in the existing surface/ recessed steel/ PVC conduit as required complete in all respects.					
2.01	**Three core 2.5 sqmm**	5	155	Rs. One hundred fifty five only	Per metre	775

3.00	Providing and Fixing of IP20 LED SPOT LIGHT 10 W +/- 1 W LED light with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing,pressure die cast heat sink and P.F.>0.95 with THD<10% ,CRI 80.The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70 . The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.	2	1633	Rs. One thousand six hundred thirty three only	Each	3266
4.00	Supplying, erection, testing & commissioning of batteries having following capacity sealed maintenance free-lead acid battery with suspended electrolyte (leak proof) suitable for different capacities UPS System etc. as required complete in all respects and to the best satisfaction of Engineer-in-Charge.					
4.01	**Battery 12 Volt 7 Ah Makes:- Exide /Amron/ Quanta.**	8	1370	Rs. One thousand three hundred seventy only	Each	10960
5.00	**SITC of one no bell indiactor 6 way in circuit house kitchen**	1	2416	Rs. Two thousand four hundred sixteen only	Each	2416
6.00	Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	2	621	Rs. Six hundred twenty one only	Each	1242
	Total:-					**88019**

Deviation Schedule of Quantity Checked & Approved
for Rs- 88019/-Only

Executive Engineer
Electrical Division
HP PWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of E.I. to various Govt. Non--Residential Buildings at ESD Dharamshala Distt. Kangra. (SH:-Providing and fixing old and damaged RCCB's, DP Isolator, MCB's replacement of LED Down lighters and wires,cable and campus light in Circuit House before the visit of Honourable President of india)		(5)	ESTIMATED COST:88,617-/-only. EARNEST MONEY: Rs.1800-/-only TIME ALLOWED:- Six Months

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. **Make: ~~KEI~~/Plaza/Anchor.** Finolex					
1.01	**2 X 4 sq. mm + 1 X 4 sq. mm earth wire**	65	395	Rs. Three hundred ninety five only	Per metre	25675
2.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. **Make: ~~KEI~~/Plaza/Anchor.** Anchor					
2.01	**3 X 1.5 sq. mm**	34	100	Rs. One hundred & one only	Per metre	3400
3.00	Supplying and fixing following rating Modular switch /socket in the existing switch box / cover plate including connections etc. as required.					
3.01	**6 A.P. 5/ 6 Amps one way Modular switch.**	5	115	Rs. One hundred fifteen only	Each	575
3.02	**6 A.P. 5/ 6 Amps two way Modular socket.**	4	159	Rs. One hundred fifty nine only	Each	636

3.03	**S.P. 15/16 Amps two way Modular switch.**	4	214	Rs. Two hundred forteen only	Each	856
3.04	**S.P. 15/ 16 Amps two way Modular socket.**	3	306	Rs. Three hundred & six only	Each	918
3.05	**Blank plate modular**	2	75	Rs. Seventy five only	Each	150
4.00	Supplying & fixing following size modular base and cover plate on the existing modular metal boxes as required:-					
4.01	**Modular base and cover plate, 8 module**	1	480	Rs. Four hundred eighty only	Each	480
5.00	Supplying and fixing stepped type Modular fan regulator on the existing modular box including making connections etc. as required.	3	729	Rs. Seven hundred twenty nine only	Each	2187
6.00	Providing and laying of one No. aluminium conductor, PVC insulated and PVC sheathed, armoured/XLPE power cable, working voltage 1100 volts grade direct in ground; to be laid 1 meter below the ground level including excavation and refilling the trench etc.as required, but excluding sand cushioning and protective covering:-					
6.01	**Armoured cable 6 sq. mm (twin core)**	117	298.00	Rs. Two hundred ninety eight only	Meter	34866
7.00	Supply and fixing PVC street light box SINTEX make of size 175mm X 225mm X 100mm complete with fixing in the existing wall including making good the damage etc. as required complete in all respects.	8	988.00	Rs. Nine hundred eighty eight only	Each	7904
7.01	**Supplying and fixing call bell/ buzzer suitable for single phase, 230 volts, complete as required.**	4	206	Rs. Two hundred six only	Each	824

8.00	Supplying and fixing 6 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
8.01	**Single pole 6 Amp (Make:- Anchor/ Schneider/ Legrand/L&T)**	7	239	Rs. Two hundred thirty nine only	Each	1673
8.02	**Single pole 16/32 Amp (Make:- Anchor/ Schneider/ Legrand/L&T)**	3	239	Rs. Two hundred thirty nine only	Each	717
9.00	Supplying and fixing following rating, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
9.01	**40 Amps. (Make:- Anchor/ Schneider/ Legrand/L&T)**	2	426	Rs. Four hundred twenty six only	Each	852
9.02	**63 Amps. (Make:- Anchor/ Schneider/ Legrand/L&T)**	1	530	Rs. Five hundred thirty only	Each	530
	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
	63 Amps. 4 pole (Make:- Anchor/ Schneider/ Legrand/L&T)/SCI	2	3187	Rs. Three thousand one hundred eighty seven only	Each	6374
	Total:-					**88617**

Draft Schedule of Quantity Checked & Approved for Rs 88,617-/-

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of E.I. to various downlighter and other accessories and Providing skilled technician for vidhan sabha winter session in circuit house at Dhramshala District Kangra H.P).	(6)	ESTIMATED COST:70,486-/-only. EARNEST MONEY: Rs.1400-/-only TIME ALLOWED:- One Month

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1.00	Providing and fixing LED tube fixture 1x18 watt suitable for surface application with the use of the latest technology 18 watt (1800 Lumen) 6000K and it should be compatible with specification i.e. Power Factor ≥ 0.9, Harmonic Distortion ≤10% and efficacy ≥ 100 Lumens per watt, CRI rating> 80 suitable for input voltage: AC 220-240 V, 50 Hz, complete with all accessories, connections, testing and commissioning etc. as required. **Makes: Havells/ Bajaj/ Philips /Wipro.**	4	867	Rs. Eight hundred sixty seven only	Each	3468
2.00	Providing and fixing surface/recess mounting Square/Round LED downlighter suitable for surface application with the use of the latest technology15 watt (1800 Lumen) 6000K and it should be compatible with specification i.e. Power Factor ≥ 0.9, Harmonic Distortion ≤10% and efficacy ≥ 100 Lumens per watt, CRI rating> 80 suitable for input voltage: AC 220-240 V, 50 Hz, complete with all accessories, connections, testing and commissioning etc. as required. **Makes : Panasonic/ Philips/ Bajaj/Wipro.**					

2.01	**led 10/ watt surface/ recess**	3	805	Rs. Eight hundred & five only	Each	2415
2.02	**led 15 watt surface/ recess**	8	1662	Rs. One thousand six hundred sixty two only	Each	13296
2.03	**led 18 watt surface/ recess**	5	1821	Rs. One thousand eight hundred twenty one only	Each	9105
3.00	Supplying and fixing of LED Post Top fixture, 35 watt, Pure polyester UV resistant powder coated die cast aluminium housing with PMMA clear diffuser for uniform illumination complete with all accessories, including connections, testing and commissioning etc. as required complete in all respects.					
3.01	**35 watt LED Post Top fixture.**	2	7733	Rs. Seven thousand seven hundred thirty three only	Each	15466
4.00	Providing skilled electrician for 10 days to carry out electrical work eg. wiring testing trouble shooting and catering minor electrical works in the circuit house new and old block there of.	1	26736	Rs. Twenty six thousand seven hundred thirty six only	Per job	26736
	Total:-					**70486**

Draft Schedule of Quantity Checked & Approved
for Rs. 70,486-/-

Executive Engineer
Electrical Division
HP PWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of Portable Fire Extinguishers installed in 500 Bedded Hospital Dr. RPGMC Tanda.(SH: Refilling of Portable Fire Extinguishers of different Capacity and type of casulty block , treatment & service block to 4th floor etc. 500 bedded hospital Dr. RPGMC Tanda in Distt. Kangra (H.P).for the year 2025-2026.

(7)

ESTIMATED COST:93,540-only.
EARNEST MONEY: Rs.1900-/-only
TIME ALLOWED:-One month

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Refilling of Portable Fire extinguishers,CO2 type 4.5 kg. Capacity complete in all respect.	15	1450	Rs. One thousand four hundred fifty only	Each	21750
2	Refilling of Portable Fire extinguishers Water type (S/P) Capacity 9 litrs. complete in all respect.	17	800	Rs. Eight hundred only	Each	13600
3	Refilling of Portable Fire extinguishers ABC type (filled with 50 Map Powder) 6 kg capacity complete in all respect.	15	1590	Rs. One thousand five hundred ninety only	Each	23850
4	Refilling of Portable Fire extinguishers Mechanical Foam type 9 liters Capacity. Complete in all respect.	15	1100	Rs. One thousand one hundred only	Each	16500
5	Refilling of Portable Fire extinguishers clean gent modular type 5 kg. capacity.	3	2500	Rs. Two thousand five hundred only	Each	7500
5	Replacement of ABC Cylinder Pipe	4	560	Rs. Five hundred sixty only	Each	2240
6	Replacement of Water Type Cylinder Pipe	5	600	Rs. Six hundred only	Each	3000
7	Replacement of Co2 Cylinder Discharge Pipe with 1 Mtrers Hose and Horn.	6	850	Rs. Eight hundred fifty only	Each	5100
	Total:-					**93540**

Draft Schedule of Quantity checked & Approved for Rs. 93,540-by

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of Portable Fire Extinguishers installed in 500 Bedded Hospital Dr. RPGMC Tanda.(SH: Refilling of Portable Fire Extinguishers of different Capacity and type at Private Ward Block, Record Room and Reception area,Blood Bank area and Electrical Sub station and Medecine store area etc.of 500 Beded Hospital in Dr. RPGMC Tanda for the year 2026-27.

ESTIMATED COST:74,960-/-only.
EARNEST MONEY: Rs.2000-/-only
TIME ALLOWED:- One Month

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Refilling of Portable Fire extinguishers,CO2 type 4.5 kg. Capacity as required complete in all respect.	15	1450.00	Rs. One thousand four hundred fiftty only	Each	21750
2	Refilling of Fire extinguishers,CO2 type 9.0 kg. Capacity as required complete in all respect.	1	2750.00	Rs. One thousand seven hundred fifty only	Each	2750
3	Refilling of Portable Fire extinguishers Water Co2 Gas Cartridge type capacity 9 litrs. as required complete in all respect.	8	750.00	Rs, seven hundred fifty only	Each	6000
4	Refilling of Portable Fire extinguishers Water type(S/P) Capacity 9 litrs. as required complete in all respect.	10	800.00	Rs. Eight hundred only	Each	8000
5	Refilling of Portable Fire extinguishers ABC type (filled with 50 Map Powder) 6 kg.capacity as required complete in all respect.	14	1590.00	Rs. One thousand five hundred nnety only	Each	22260

6	Refilling of Portable Fire extinguishers Mechanical Foam type 9 liters Capacity as required complete in all respect.	10	1100.00	Rs. One thousand one hundred only	Each	11000
7	Refilling of Fire extinguishers DCP type Trollye on mounted wheel 25 kg Capacity as required complete in all respect.	1	3200.00	Rs. Three thousand two hundred only	Each	3200
	Total:					**74960**

Draft Schedule of Quantity Checked & Approved for
Rs 74,960-/-

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- C/O Health Sub-Centre (First Floor)at Kahan pat in Tehsil Palampur Distt Kangra (HP) (SH:- Providing E.I. therein).		(9)	ESTIMATED COST:98,659/-only. EARNEST MONEY: Rs.2000-/-only TIME ALLOWED:-Two Years		
SR. NO.	DESCRIPTION	job No RATES	WORDS	UNIT	AMOUNT
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. **Make: finolex/Havell/Anchor/ Anchor (Roma)/ Legrand (Myrius) /L&T(Entice).**				
	Group C.	14 1650.00	Rs. One thousand six hundred fifty only	Per Point	23100
2	Wiring for power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required. **Make: finolex/Plaza/Anchor.**	15 395.00	Rs. Three hundred ninety five only	Per Meter	5925
3	Wiring for power plug with 4X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 2 Nos 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required. **Make: finolex/Plaza/Anchor.**	18 703.00	Rs. Seven hundred three only	Per Meter	12654

4	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required **Make: finolex/Havells/Anchor.**					
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	15	332.00	Rs. Three hundred thirty two only	Per Meter	4980
	2 X 6 sq. mm + 1 X 6 sq. mm earth wire	2	564.00	Rs. Five hundred sixty four only	Per Meter	1128
5	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. **Make: finolex/Plaza/Anchor.**					
i	**3 x 2.5 sq. mm**	10	151.00	Rs.one hundred fifty one only	Per Meter	1510
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 , 3pin 5/6 amp modular socket outlet and 15/16 amp&5 /6 amp modular switch, connection etc. as required.	3	829	Rs. Eight hundred twenty nine only	Each.	2487
	Make :- Schenider/L&T/Legrand					
7	Supplying and fixing suitable size G I box with modular plate and cover in front on surface or in recess including providing and fixing 6 pin 15/16 amps modular socket outlet and 15/16 amps, modular switch, connections etc. as required.	1	621	Rs. Six hundred twenty one only	Each.	621
	Make :- Schenider/L&T/Legrand					
8	Providing and installation exhaust fan of following sizes in the existing opening, including making the hole to suit the size of the above fan, making good the damages, connections, testing and commissioning etc. as required.					

	Exhaust Fan, Light duty, (Domestic) 300 mm sweep (Make: Usha, Model: Aeroclean LD)/Bajaj/Anchor.	2	2567.00	Rs. Two thousand five hundred sixty seven only	Each	5134
9	Providing, Installation, testing and commissioning of BLDC ceiling fan with socket type regulator, including wiring the down rods of standard length (up to 30 cm) with 16/0.20 mm twin twisted flexible, cotton braided, copper cable, including providing and fixing phenolic laminated sheet cover on the fan box and earthing etc. as required. 5 Star rating with Five years warranty.					
	Ceiling Fan 1200 mm sweep BLDC 5 Star rating (Make: Havells Model: Efficiencia Neo BLDC/ Bajaj/Crompton.	3	4323.00	Rs. Four thousand three hundred twenty three only	Each	12969
10	Providing and installation of IP40 LED fixture 40 W+/- 1W with Surface Mounted 4 Feet Batten Fixture with system efficacy ≥100lm/W with Aluminium housing, P.F.>0.95 with THD<10% ,CCT 6500 K,CRI> 80,Surge Protection 2 Kv.The LED with Useful life of 50000 Hrs at L70 with 5-years warranty.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.					
	LED Batten 40W, 4 feet long (Make: Panasonic, / Bajaj/ Phillps.	5	2417.00	Rs. Two thousand four hundred seventeen only	Each	12085

11	Providing and Fixing of IP20 LED fixture of 18 watt +/- 1 W LED Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing,pressure die cast heat sink and P.F.>0.95 with THD<10% ,CRI 80.The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70 . The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.					
	LED 18 W, (Make: Panasonic, / Bajaj/ Phillps.	4	1821.00	Rs. One thousand eight hundred twenty one only	Each	7284
13	Providing and fixing of IP65 LED Bulk head 10 W+/- 1W with with system efficacy ≥ 100lm/W with Aluminium housing P.F.>0.95 with THD<10%,CCT 5700 K,CRI> 70, Surge Protection 4 Kv.The LED with Useful life of 50000 Hrs at L70 with 5- years warranty.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.					
	Bulk Head Light LED 10 W (Make:- Wipro /Philips/Leksa.	1	1420.00	Rs. One thousand four hundred twenty only	Each	1420
14	Supplying and fixing 6 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					

	Single pole (Make:- Anchor/ Legrand/L&T)	7	239.00	Rs. Two hundred twenty nine only	Each	1673
15	Supplying and fixing following rating, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
	63 Amps. (Make:- Anchor/ Legrand/L&T)	1	530.00	Rs. Five hundred thirty only	each	530
16	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
	63 Amps. (Make:- Anchor/ Legrand/L&T)	1	3104.00	Rs. Three thousand one hundred four only	each	3104
17	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)					
	Double door-12 way (Make:- Anchor/ Legrand/L&T)	1	2055.00	Rs. Two thousand fifty five only	each	2055
	Total:-					**98659**

Agt Schedule of Quantity checked & Approved Rs
Rs. 98,659-00/-

Executive Engineer
Electrical Division
HP PWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Refilling of portable Fire Extinguishers installed in School of Nursing of Critical care skill lab/simulation lab in Dr. RPGMC Tanda in Distt. Kangra (H.P).for the year 2025-2026.			10	**ESTIMATED COST:20,510/-only. EARNEST MONEY: Rs.500-/-only TIME ALLOWED:- One Month**		
SR. NO.	**DESCRIPTION**	**job No**	**RATES**	**WORDS**	**UNIT**	**AMOUNT**
1	Refilling of Portable Fire extinguishers,CO2 type 4.5 kg. Capacity as required complete in all respect.	7	1450.00	Rs. One thousand four hundred fifty only	Each	10150
2	Refilling of Portable Fire extinguishers Water type (S/P)Capacity 9 litrs complete in all respect.	5	800.00	Rs. Eight hundred only	Each	4000
3	Refilling of Portable Fire extinguishers ABC type(filled with 50 Map Powder) 6kg capacity as required complete in all respect.	4	1590.00	Rs. One thousand five hundred ninety only	Each	6360
	Total:-					**20510**

Executive Engineer
Electrical Division
HPPWD Palampur