HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT

No.PW/NESD/NIQ/2025-26- 464-67 Dated:- 3/3/2026

To

The Executive Engineer (IT)
Nirman Bhawan HPPWD
Shimla-02

Subject:- **Publication of tender Notice.**

Respected Sir,

In connection to the above cited subject enclosed please find herewith the tender notice of works as given in the notice inviting tender for uploading on the department website as per Notification vide Pr. Secy. (PW) to Govt. of Himachal Pradesh letter No PBW (B) /2020 Dated:-27th may 2021 and PBW (B) A03) /2020 dated:-16th july 2021 as the works mentioned in the tender notice is (are) urgent in the nature of public interest.

DA:-AS Above

Assistant Engineer
Electrical Sub Division
HP.PWD, Nahan

Copy to :-

1. Superintending Engineer Electrical 1st circle HPPWD Kasumpti Shimla-9 for favour of information please.
2. Copy to Executive Engineer Electrical Division No. 1 HPPWD Kasumpti Shimla-9 for favour of information please.
3. Copy to Computer cell O/o Executive Engineer (I.T.) Cell , Nirman Bhawan HPPWD Shimla-09.

Assistant Engineer
Electrical Sub Division
HP.PWD, Nahan

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items/ percentage rate tender (s) on PWD form No.6, 7 & 8 are hereby invited by the Assistant Engineer, Electrical Sub Division HP.PWD,Nahan on behalf of Governor of HP for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD electrical wing as per the latest instructions so as to rach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening the tenders. The undersigned reserves the right to accept/ reject any application/tender or all the tenders without assigning any reason.

Date of receipt of application for the tender form — **10-03-2026 upto 12:00 PM**
Date of issue / Sale of the tender forms — **10-03-2026 from 02:00 PM To 04:00 PM**
Date of Opening of the tenders — **11-03-2026 at 11:00 AM**

The tender shall be received upto 10:30 AM on 10-03-2026 and will be opened on the same day at 11:00 AM in the presence of the intending contractor or their autharized representatives who may like to present. The tender form can be had from this office against cash payment (Non refundable) on 10-03-2026 from 2:00 PM to 4:00 PM.

The earnest money in the shape of National Savings Certificate / Deposit at call/ time Deposit/Account/in any of the Post Office/ Nationalized bank in H.P. duly pledged in favour of Assistant Engineer Electrical Sub Division HPPWD Nahan must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected.

SNo	Name of work	Estimated cost	Earnest Money	Time Limit	Cost of form	Eligible class of contractor
1	Replacement of burnt/damaged outdoor luminaire at Various HPPWD Rest house in Electrical Section Nahan I &II under Electrical Sub Division, Nahan . District Sirmour HP	96382	2000	1 Month	350	D & C
2	R/M of E.I in Govt. N/R Building Under Electrical Sub-Division Nahan for Paonta Section, Distt. Sirmour (H.P)	99300	2000	15 Days	350	D & C
3	AMC of 4 Nos D.G Set 5 KVA installed in Court complex Nahan & Paonta sahib under ESD Nahan for the year 2026-27. Distt. Sirmour (H.P	98000	2000	1 Year	350	Specialized
4	Annual Repair & maintenance of Air Conditioners installed in various PWD Rest Houses under ESD Nahan for the year 2026-27 for Nahan Section No-2 .	28500	600	1 Year	350	Specialized
5	LAN work at Tehsil office Building at Paonta Sahib District Sirmour (H.P.)	56210	1150	1 Month	350	D & C
6	Annual Repair & maintenance of Air Conditioners installed in various Govt NR Buildings under Electrical Sub Division Nahan (Paonta Section) for the year 2026-27.	98800	2000	1 Year	350	Specialized

Cetified that tender of above works are being called of emergent nature in exigency of public interest.

Terms & conditions :-

1. The undersigned reserve the rights to reject the tender at any time without assigning any reason.
2. No contractor or his accredited agent shall be permitted to participate in the completion unless he hold a valid wiring licence and has been duly registered the appropriate class in the department.
3. No person/persons other than the contractor shall be issued tender document unless he /they hold power of attorney duly registered under law.
4. The Latest renewal enlistment order must accompany the application failing which tender documents shall not be issued.
5. The tender of those contractors who are registered under the Himachal Pradesh general sales tax act.1968 and who have cleared all the dues on account of tax be entertained.

6 The tender amount should be in the limit of (+) 5 % to (-) 10%, as per notification 07.10.2021 and 10.05.2023 shall be applicable for bid price lower than -10% and more than +5%

Assistant Engineer,
Electrical Sub Division,
HP.PWD,Nahan

No.PW-NESD-NIQ-2025-26- 448-63 **Dated:-03-03-2026**

Copy forwarded to the following:-

1 Engineer in Chief HP.PWD Shimla for information please.
2 Chief Engineer(South)Nirman Bhawan Nigam Vihar Shimla for information please.
3 Superintending Engineer, 1st Electrical Circle,HP.PWD Shimla-9 for information please..
4 The Executive Engineer (IT) O/O Engineer In Chief HPPWD Shimla Through email:-eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5 Executive Engineer, Electrical Division No.1 HP.PWD,Shimla-9 for information please.
6 Assistant Engineer Electrical Sub Division No.I & II.
7 All the approved contractor in Electrical
8 Notice Board

Assistant Engineer,
Electrical Sub Division,
HP.PWD,Nahan

					Estimated:-95 Estimated:-96382	
DNIT					Earnest Mon Earnest Money:-2000	
Name of work:-Replacement of Brunt/Damaged Outdoor Luminaire at Various HPPWD Rest House in Electrical Section Nahan I&II, Under Electrical SubDivision Nahan , District Sirmour HP					Time Limit:-1 Time Limit:-1 Month	
S.No.	**Description**	**Qty.**	**Unit**	**Rate**	**Amount**	
1	Supplying, Installation, testing & commissioning of LED post top luminary with High pressure die cast aluminum housing & with ingress protection of IP65. The luminaire should have high power LED modules with complete system consumption 25-40W for lighting 360°(Degree) around the pole . system efficiency not less than, 80 lm / watt. CCT 3000-5700K with electronic driver having PF > 0.9, THD < 20%, 2.5KA SPD . The fixture should have suitable dia. for existing pole entry complete with driver, and all electrical accessories complete as required with minimum Two years Warrenty on Manufacturing defects. make :- Bajaj, havells, Twinkle or any other Approved by the engineer in Charge .					
i	LED Post Top 40 Watt	4	Each	13235	52940	Fifty two thousand nine hundred forty
ii	LED Post Top 25 Watt	4	Each	9118	36472	Thirty six thousand four hundred seventy two
2	S/E of LED Street Light Driver IP66 in the Existing Street Light including carriage, erection, making connections testing and commissioning etc as required.The Specification of the Driver is as under :- Electronic Driver :- Drive current (LED) :-As per OEM. Operating voltage :-140 V to 270 V AC supply or better Type of driver :-Constant current output driver PF:->0.95 THD :-Less than 10% Surge Protection :-(10 KV minimum External) (4 KV Internal) Efficiency Driver:->85% Protection:-Shall have under voltage and over voltage protection. Guarantee of LED driver :-2 years against manufacturing defect.					
i	40-50 Watt LED Driver	5	Each	1394	6970	Six thousand nine hundred seventy
	Total(₹)				96382	

Lump Sum recovery from dismantled material Rs. 1500/-

1. Recovery of useful materials/dismantled materials will be recovered upon contractor @ Rs: 1500/-only.
2. It is certified that the tender is being called on emergent nature in exigency of public interest.

Assistant Engineer
Electrical Sub Division
HPPWD Nahan

DNIT No 276 for the year 2025-26 duly approved for Rs- 96382/-only

Executive Engineer,
Electrical Division No-I
HPPWD, Kasumpti Shimla

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 99300
Earnest Money Rs. :- 2000.00
Time:- 15 Days

Name of work:-R/M of EI in Govt. N/R Building Under Electrical Sub Division Nahan for Paonta Section , District Sirmour HP

Sl. No.	Items of work	Qty	Unit.	Rate		Amount.
				In figuers	In words	
1	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.					
i	2 X 10 sq. mm + 1 X 6 sq. mm earth wire	16	Mtr	688	Rupees Six Hundred EightyEight Only	11008
ii	4 X 10 sq. mm + 2 X 6 sq. mm earth wire	20	Mtr	1164	Rupees One Thousand One Hundred SixtyFour Only	23280
2	Rewiring for light point/ fan point/exhaust fan point/call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required					0
i	Group-C	7	Point	739	Rupees Seven Hundred ThirtyNine Only	5173
3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.					0
i	3 x 1.5 sq. mm	40	Mtr	93	Rupees NinetyThree Only	3720
ii	3 x 2.5 sq. mm	45	Mtr	137	Rupees One Hundred ThirtySeven Only	6165
iii	3 x 4 sq. mm	35	Mtr	205	Rupees Two Hundred Five Only	7175
4	Supplying and fixing following rating, followings poles 10ka 240/415v 'C' curves miniature circuit braker suitable for inductive load of following poles in the exsisting MCB DB complete with connections, testing and commissioning etc. as required.					0

i	40 A DP	7	Each	1330	Rupees One Thousand Three Hundred Thirty Only	9310
ii	63 A DP	8	Each	1479	Rupees One Thousand Four Hundred SeventyNine Only	11832
5	Supplying and fixing following rating, follwing pole, 240/415 V(four pole), residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
i	40A	3	Each	3279	Rupees Three Thousand Two Hundred SeventyNine Only	9837
ii	63A	4	Each	2950	Rupees Two Thousand Nine Hundred Fifty Only	11800
					Total:-	**99300**

Draft Scheduled of quantity amounting to Rs.99300/-recommonded only is recommonded for approval please.

Less dismantle Credit @ ₹ 1000/- Only

1. Recovery of usefull material/dismantled materials vested to be taken from Contractor @ 1000/- only
2. It is certified that the tender is being called on emergent nature in exigency of electric interest.

Rupees NinetyNine Thousand Three Hundred Only

Assistant Engineer,
Electrical Sub Division
HP. PWD. Nahan

DNIT No. 27 for the year 2025-26 duly approved for Rs-99300/-only

Executive Engineer,
Electrical Division No-1,
HPPWD, Kasumpti, Shimla-9

DNIT

Estimated Cost:-98000
Earnest Money:-2000
Time Limit:- 1 Year

Name of work : AMC of 4 Nos D.G Set 5 KVA installed in Court complex Nahan & Paonta sahib under ESD Nahan for the year 2026-27, Distt. Sirmour (H.P)

S.No.	DESCRIPTION	QTY.	Unit	RATE	Rate in Words	AMOUNT
1.00	**A.M.C of 5 KVA D.G sets installed in Various N/R buildings i.e. Court Complex at Nahan & Paonta sahib . The following will be the scope of Preventive Maintainance**	4	p/job	24500	Twenty Four Thousand Five Hundred only	98000
1.01	Four Visits in a Year to check the genral condition of a Machine & check and set operation parameters as specified by company					
1.02	Service of D.G sets will be carried out strictly as per KOEL Norms and all spare parts will be charged extra					
1.03	Lube oil and filter change will be carried out strictly as per KOEL Norms					
1.04	Replacement of Air cleaner element as per KOEL Norms					
1.05	Check and monitor the performance during each visit					
1.06	To check ,ensure optimum performance of Sub-Assemblies of Machine					
1.07	To check fuel timings tappet clearance etc for Diesel Engines and reset the same as required.					
1.08	To check all the fasteners					
1.09	To check and set operation of warning devices					
1.10	To check and set operational parameters of breakdown of Engines					
1.11	Labour charges will not claim for above mentioned work					
2.00	**Conditions :-**					
2.01	The minimum two number of services is required during a year					
2.02	The unlimited emergency visit will be carried out as per requirement					
	Total					98000

Certified that tender of above work are being called of emergent nature of exigency in public interest .

Assistant Engineer
Electrical Sub. Division
H.P.P.W.D Nahan

DNIT No for the year 2025-26 duly approved for Rs 98000/- only

Executive Engineer,
Electrical Division No-1,
HPPWD, Kasumpti, Shimla-9

DNIT

Estimated cost:- 28500
Time Limit:- 1 Year
Earnest Money:- 600

Name of Work:- Annual Repair & maintainance of Air Conditioners installed in various PWD Rest Houses under ESD Nahan for the year 2026-27 for Nahan Section No-2 .

Sr.No.	Description	Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Annual repair & maintenance of various types different capacity air conditioners presently in various Govt building under the control of Electrical sub Division HP PWD Nahan i/c the cost of all types of spare parts 3 No. services due from time to time as per rules including the cost of rewinding of compressor of various make and capacity and including of all spare parts and including of fan motor rewinding in all respect including gas filling (F.22)					
(i)	Split type air conditioners 1.5 ton capacity	4	Each	4600	Forty Six Hundred	18400
(ii)	Window type air conditioners 1.5 ton capacity	1	Each	4500	Forty Five Hundred	4500
2	Repair of PCB in main control of air conditioners and voltage stabilizer	2	Each	2800	Twnety Eight Hundred	5600
	Total					28500

It is Certified That the tender is being called on emergent nature in exigency of public interes.

Assistant Engineer
Electrical Sub-Division
HPPWD Nahan

DNIT No. for the year 2025-26 duly approved for Rs 28500/- only

Executive Engineer,
Electrical Division No-1,
HPPWD, Kasumpti, Shimla-9

DRAFT OF SCHEDULE OF QUANTITY

Name of Work :-LAN work at Tehsil Office Building at Poanta Sahib,District Sirmour (H.P.)

Estimated Cost:-56210
Earnest Money:-1150/-
Time Limit:-1 Month

Sr. No.	DESCRIPTION	Quantity	Unit	Rate		Amount
				Figure	Words	
1	Supplying and drawing of UTP 4 pair CAT 6 LAN Cable in the existing surface/ recessed Steel/ PVC conduit as required.					
1.01	1 run of cable	90	per mtr	54	Fifty Four	4860
1.02	2 run of cable	90	per mtr	93	Ninety Three	8370
1.03	3 run of cable	60	per mtr	133	One Hundred Thirty Three	7980
2	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
2.01	25 mm	280	per mtr	125	One Hundred Twenty Five	35000
	Total					
					Total	**56210**

Certified that the tender of the above work are being called of emergent nature of exigency in public interest.

Assistant Engineer
Electrical Sub. Division
H.P.P.W.D Nahan

DNIT No for the year 2025-26 duly approved for Rs. 56120/- only.

Executive Engineer
Electrical Division No. I
H.P.W.D, Kasumpti, Shimla-9

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 98800
Earnest Money Rs. :- 20000
Time:- 1 Year

Name of work:-Annual Repair & maintainance of Air Conditioners installed in Various Govt. N/R Building Under Electrical Sub Division Nahan (Paonta Section) for the year 2026-27

Sl. No.	Items of work	Qty	Unit.	Rate		Amount.
				In figuers	In words	
1	Annual repair & maintenance of various types different capacity air conditioners presently in various Govt building under the control of Electrical sub Division HP PWD Nahan i/c the cost of all types of spare parts 3 No. services due from time to time as per rules including the cost of rewinding of compressor of various make and capacity and including of all spare parts and including of fan motor rewinding in all respect including gas filling (F.22)					
i	Split type air conditioners 1.5 ton capacity	9	Each	4600	Rupees Four Thousand Six Hundred Only	41400
ii	Split type air conditioners 2 ton capacity	6	Each	4700	Rupees Four Thousand Seven Hundred Only	28200
ii	Window Type A.C. 1.5 Ton capacity	4	Each	4500	Rupees Four Thousand Five Hundred Only	18000
2	Repair of PCB in main control of air conditioners and voltage stablizers	4	Each	2800	Rupees Two Thousand Eight Hundred Only	11200
					Total:-	**98800**

Draft Scheduled of quantity amounting to ₹ 98800/- only only is recommonded for approval please.

Assistant Engineer,
Electrical Sub Division
HP. PWD. Nahan

DNIT No. for the year 2025-26 duly approved for Rs. 98,800/- only

Executive Engineer,
Electrical Division No-1,
HPPWD, Kasumpti, Shimla-9