

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NO.PW- GHD-EA-I- /Tender/2026-  
To

1557377 Dated:- 16-03-2026

The Executive Engineer (IT-Cell),  
Nirman Bhawan Nigam Vihar Shimla-2  
Himachal Pradesh Shimla -2.  
Email:-ee-pwd-hp@nic.in

**SUBJECT: - Publication of Tender Notice.**

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 17.03.2026.

DA:-As above.

Executive Engineer,  
Ghumarwin, Division.  
HP.PWD. Ghumarwin  
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.

-sd-  
Executive Engineer,  
Ghumarwin, Division.  
HP.PWD. Ghumarwin.  
On behalf of Governor of Himachal Pradesh

**\*NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **24-03-2026 up to 11.00 AM (if holiday then next working day)**, and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 23-03-2026 up to 4.00 P.M and the application for issue of tender form shall be **received on 23-03-2026 up to 11.30 AM (if holiday then next working day)**. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	Restoration of rain damages on Harlog Mehran Tiun Khas road km 0/00 to 5/500 (SH: P/L Cement Concrete Pavement at link road to village Mehra in near tiun khas tower GP Tiun Khas in km 0/00 to 0/110 under PDNA Year 2023.	Rs.494375/-	Rs.9900/-	Rs.350/-	One Month
2.	Restoration of rain damages on Taruntra to Barota road km 0/00 to 3/825 (SH: C/o of cement concrete road to village Chota Shimla in km 0/050 to 0/124 under PDNA 2023	Rs.321623/-	Rs.6500/-	Rs.350/-	One Month
3.	Restoration of rain damages on Khanger Bari Kotla Thalotu road km 0/00 to 5/00 (SH: C/o B/wall at RD 0/325 to 0/345 and providing and laying Granular sub base at rD 0/305 to 0/355 (under PDNA year 2023).	Rs.479259-	Rs.9600/-	Rs.350/-	One Month
4.	Restoration of rain damages on link road to village Kothi Baddu km 0/00 to 2/260 (SH: Providing and laying "W" metal beam crash barrier at RD 2/180 to 2/210 under PDNA year 2023.).	Rs.107100/-	Rs.2200/-	Rs.350/-	One Month
5.	Restoration of rain damages on GTB road to village Baloh km 0/00 to 1/510 (SH: P/L interlocking paver Block on link road Saheed Udam Singh at RD 0/105 to 0/170) under PDNA year 2023.	Rs.499891/-	Rs.10000/-	Rs.350/-	One Month

**Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road sinking etc.) in the public interest.**

**Terms and Conditions:-**

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division, HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

Executive Engineer,  
Ghumarwin Division  
HP.PWD, Ghumarwin

## Draft Schedule of Quantity

Estimated Cost:- Rs. 4,94,375.00

Earnest Money:- Rs. 9,900.00

Time :- One month

**Name of Work:- Restoration of rain damages on Harlog Mehran Tiun Khas road km 0/00 to 5/500 (SH:- Providing and laying Cement concrete Pavement at link road to village Mehra in near Tiun Khas Tower G.P. Tiun Khas in km 0/00 to 0/110 ) .(Under PDNA Year 2023).**

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in surface excavation not exceeding 30 cm (thirty centimetre) in depth but exceeding 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth upto 50 m (fifty metre) and lift upto 1.5 m (One point five metre), as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	332.50	Per square metre	80.00	Rupees Eighty Only	26600.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	38.50	Per cubic metre	1500.00	Rupees One Thousand Five Hundred Only	57750.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering All work up to plinth level. 1:1.5 :3(One cement is to one point five coarse sand is to three crushed graded stone aggregate 20 mm (twenty milimetre) nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.75	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	410025.00
<b>Total</b>						<b>494375</b>

Draft Schedule of Quantity No 478 for  
the year 2025-26 appoosed for Rs 4,94,375/only  
(Four lakhs Ninety four Thousand Three  
Hundred Seventy five only)

Executive Engineer,  
Ghumarvin Division,  
H.P. PWD, Ghumarvin.

*(Signature)*

## Draft Schedule of Quantity

Estimated Cost:- Rs. 3,21,623.00

Earnest Money:- Rs. 6,500.00

Time :- One month

**Name of Work:-Restoration of rain damages on Taruntra to Barota road km 0/00 to 3/825(SH:-Construction of cement concrete road to village Chota Shimla in km 0/050 to 0/124)(Under PDNA Year 2023).**

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and MORD technical specification 2014 clause 305 (Three zero five) and as per direction of the Engineer-in-Charge. The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.71	Per Cubic metre	250.00	Rupees Two Hundred Fifty Only	16928
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre)spread thickness (finished work including materials and labour)as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.57	Per cubic metre	1500.00	Rupees One Thousand Five Hundred Only	33855
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundation complete as per drawing and MORD technical specification clauses 802, 803, 1202 & 1203. Nominal Mix 1:4:8 (one cement is to four sand is to eight crushed graded stone aggregate) 40mm (forty millimeter) as per direction of Engineer-in-Charge including carriage of materials with with in all leads and lifts and other incidental. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.57	Per Cubic metre	4900.00	Rupees Four Thousand Nine Hundred Only	110593.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level. 1:1.5 :3(One cement is to one point five coarse sand is to three crushed graded stone aggregate 20 mm (twenty milimetre) nominal size.The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.57	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	160247
<b>Total</b>						<b>321623</b>

Draft Schedule of Quantity No 477 for the year 2025-26 approved for Rs 3,21,623/- only (Three lakhs Twenty one Thousand Six Hundred Twenty Three only)

Executive Engineer,  
Ghumarwin Division,  
HP, PWD, Ghumarwin.

[Signature]

## Draft Schedule of Quantity

Estimated Cost:- Rs. 4,79,259.00

Earnest Money:- Rs. 9,600.00

Time :- One month

**Name of Work:- Restoration of rain damages on Khanger Bari Kotla Thalotu road km 0/00 to 5/00(SH:- Construction of Breast wall at RD 0/325 to 0/345 and Providing and laying Granular sub-base at RD 0/305 to 0/355) .(Under PDNA Year 2023).**

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and MORD technical specification 2014 clause 305 ( Three zero five ) and as per direction of the Engineer-in-Charge .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.88	Per cubic metre	250.00	Rupees Two Hundred Fifty Only	18220.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.11	Per Cubic Metre	4900.00	Rupees Four Thousand Nine Hundred Only	225939.00
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	38.00	Each	325.00	Rupees Three Hundred Twenty Five Only	12350.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3(One cement is to one point five coarse sand is to three crushed graded stone aggregate 20 mm (twenty milimetre) nominal size.The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.50	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	159750.00

5	<p>Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads &amp; lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	35.00	Per Cubic metre	1800.00	Rupees One Thousand Eight Hundred Only	63000.00
Total						479259

*Draft Schedule of Quantity No 479 for the year 2025-26 approved for Rs 4,79,289/- only (Four lakhs Seventy Nine Thousand Two Hundred fifty nine only)*

Executive Engineer,  
Ghumarwin Division,  
HP PWD, Ghumarwin.



## Draft Schedule of Quantity

Estimated Cost:- Rs.	1,07,100.00
Earnest Money:- Rs.	2,200.00
Time :-	One month

**Name of Work:- Restoration of rain damages on link road to village Kothi Baddu Km 0/00 to 2/260 (SH:- Providing and Laying "W" metal beam crash barrier at RD 2/180 to 2/210) .(Under PDNA Year 2023).**

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing and erecting type-A"W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail to be kept 70cm (seventy centimeter) above road/ground level and to be fixed on ISMC series channel vertical post 150x75x5mm (one hundred fifty into seventy five into five millimetre) to be spaced 2 metre (two metre) centre to centre to be kept 1.80 mtr(one point eight zero metre) high and to be kept 1.10 mtr (one point one zero metre) below ground/road level. All steel 4 part and fitments to be galvanized by hot dip process. All fittings to confirm to IS: 1367 and IS 1364 as amended upto date, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm (one hundred fifty into seventy five into five millimeter) and 330mm (three hundred thirty millimetre) long complete as per clause 810 confirming to MORTH &H including all fittings required for erection at road site of materials. including Earth work and Post concrete 1:3:6 and other incidentals as per the direction of Engineer-in Charge.The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Per Running metre	3570.00	Rupees Three Thousand Five Hundred Seventy Only	107100
<b>Total</b>						<b>107100</b>

Draft Schedule of Quantity No-462 for  
the year 2025-26 approved for Rs 1,07,100/- only  
(one Lakh Seven Thousand one Hundred only)

Executive Engineer,  
Ghumarwin Division,  
M.P. PWD, Ghumarwin

## Draft Schedule of Quantity

Estimated Cost:- Rs. 4,99,891.00

Earnest Money:- Rs. 10,000.00

Time :- One month

**Name of Work:- Restoration of rain damages on G.T.B. road to village Baloh km 0/00 to 1/510 (SH:- Providing and laying Interlocking Paver Block on Link road Shaheed Udam Singh at RD 0/105 to 0/170) .(Under PDNA Year 2023).**

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in surface excavation not exceeding 30 cm (thirty centimetre) in depth but exceeding 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth upto 50 m (fifty metre) and lift upto 1.5 m (one point five metre), as directed by Engineer-in- Charge: all kind of soil .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	198.25	Per square metre	82.00	Rupees Eighty Two Only	16257
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.83	Per Cubic Metre	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	96176
3	Providing and laying approved factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick (fifty milimetre) compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in - Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	198.25	Per square metre	1400.00	Rupees One Thousand Four Hundred Only	277550
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3(One cement is to one point five coarse sand is to three crushed graded stone aggregate 20 mm (twenty milimetre) nominal size.The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.48	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	109908.00
<b>Total</b>						<b>499891</b>

*Draft Schedule of Quantity No. 460 for the year 2025-26 approved for Rs. 4,99,891 /- [Four lakh Ninety Nine thousands Eight Hundred Ninety one only].*

Executive Engineer,  
Ghumarwin Division,  
M.P. PWD, Ghumarwin.