

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW/CB/2nd C/Tender case/2025-26 8659-88

Dated: 03/03/2026

To

✓ The Executive Engineer,
HP.PWD. Nirman Bhawan, Nigam Vihar,
Shimla.

Subject:- Publication of tender Notice on departmental site.

Sir,

In this context, it is submitted that the tender notice is being enclosed herewith for up loading on Department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A-(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/As above.


Executive Engineer,
Indora Division, HPPWD,
Indora.

Copy forwarded for information to following for information please:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Various Contractors.
4. Notice Board.

DA/As above.

Executive Engineer,
Indora Division, HPPWD, Indora
Telephone No. 01893-242336
e-mail- eepwd-indora-hp@gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Scaled item rate tenders on the form 6 & 8 are hereby invited by the Executive Engineer, Indora Division HPPWD., Indora on behalf of the worthy Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP.PWD. The application for purchase of tender form should be reached in this office on dated 03.03.2026 up to 1.00 PM and tender form will be issued from this office against cash payment (Nonrefundable) up to 4.00 PM on same day. The tender will be opened on 10.03.2026 at 11.00 PM in presence of the contractor or their authorized representatives who may like to be present.

The Earnest Money in shape of National Saving Certificate/ time deposit account/saving account in any nationalized bank in HP duly pledged in favour of the Executive Engineer, Indora division, HPPWD., Indora will be received along with application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders will be kept open for 90 days from the date of opening of tender. The Executive Engineer, Indora Division, HP.PWD. Indora reserves the right to reject any or all tenders without assigning any reason. The contractor should append their Enlistment/ Renewed Certificate/ Sale Registration Number with the application for issue of tender form. If any of the mentioned above date happens to be holiday the same should be processed on next working day.

Sr. No.	Name of work	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit.	Cost of form	Eligible class of Contractor.
1.	R/R on NH-AI Military Station (Nangal Bhoor to Shekhupura road) (SH:- P/L G-III & repair of Pot holes in front of the Army Gate (inside the Campus) Deposit work.	84540	1700	One Month.	350	ClassA- D
2.	Restoration of Rain damages to Haler Khad bridge to Indpur via Changrara road Km. 0/0 to 3/245 (SH:- C/O U-Shape drain at RD. 0/995 to 1/026) (LHS).	84435	1700	One Month.	350	Class- D
3.	R/R on NH-AI Military Station (Nangal Bhoor to Shekhupura road) (SH:- P/L G-III & repair of Pot holes in front of the Army Gate (inside the Campus) Deposit work.	84540	1700	One Month.	350	ClassA- D
4.	Restoration of Rain damages to Haler Khad bridge to Indpur via Changrara road Km. 0/0 to 3/245 (SH:- C/O U-Shape drain at RD. 0/947.50 to 0/995 (LHS).	84131	1700	One Month.	350	Class- D
5.	Restoration of Rain damages on Mohlti Indora AL-I 0/0 to 10/0 (SH:- Maintenace of Earthen Shoulder/ Berms both sides between Km. 5/0 to 6/0).	83688	1700	One Month.	350	Class- D
6.	Restoration of Rain damages to Haler Khad bridge to Indpur via Changrara road Km. 0/0 to 3/245 (SH:- C/O U-Shape drain at RD. 0/900 to 0/947.50 (LHS).	84165	1700	One Month.	350	Class- D
7.	C/O road from Sahoura Nara Brahmna Tappa from km 0/00 to 4/575. (SH:- Providing and Fixing of NABARD Informatory Sign board). under NABARD	80630	1650	One Month.	350	Class- D
8.	Restoration of Rain damages on various roads under HP.PWD Sub Division Indora (SH:- Hiring of excavator cum loader (J.C.B)	84677	1700	One Month.	350	Class- D
9.	C/O Balance work for the C/O Baleer to Dainkwan via Samoon Randoh road from km 0/00 to 5/865. (SH:- Providing and Fixing of NABARD Informatory Sign board). under NABARD.	80630	1650	One Month.	350	Class- D
10.	Restoration of Rain damages on various roads under HP.PWD Sub Division Indora (SH:- Hiring of excavator cum loader (J.C.B) under Indora Section.	83681	1700	One Month.	350	Class- D

TERMS AND CONDITIONS:-

1. The contractor/Firm shall have his GST No. & copy of the same be attached with the application.
2. The intending Contractors/firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender for The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender form. In this regard, the contractor has submitted an affidavit that he is not having more than two work
5. The intending contractors are required to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The Executive Engineer reserves the right to reject/accept any or all tenders without assigning any reasons.


Executive Engineer
Indora Division, HPPWD.,
Indora.

Copy to the following for information and necessary action:-

1. The Superintending Engineer, 9th Circle, HP.PWD. Nurpur.
2. All Assistant Engineer working under this office.
3. Notice Board.

Executive Engineer,
Indora Division, HPPWD.,
Indora.

SCHEDULE OF QUANTITY

Name of work:- R/R on NH-A1 Military Station (Nangal Bhoor to Shekhupura) road.

Estimated Cost Rs 84540.00
Earnest Money Rs 1700.00

Sub Head :- P/L G-II & repair of Pot Holes in front to the Army Gate (Inside the Campus). (Deposit Work)

Time limit:- Two month

S.No.	Description	Qty	Rate (l/call taxes except GST)	Unit	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density, Grading 3 as per Technical Specification Clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - In-Charge including cartage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	5.14	1405.30	P/cum	7223.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(Viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point six) cubic meter of fine aggregate per ten square meter premixed with VG-10(Viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including cartage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	275.64	280.50	P/sqm	77317.00
TOTAL					84540.00

*DNT checked and approved for Rs.84540/-only.
C.B. Eigny four thousand Five hundred Forty Jorey.*

Executive Engineer
Indora Division
HPPWD Indora

272

SCHEDULE OF QUANTITY
Name of Work:- Restoration of Rain damages to Haler Khad bridge to Indpur via Changrara road km 0/00 to 3/245. (SH:- C/O U-shaped drain at RD 0/995 to 1/026) L.H.S

S.No.	Description of Items	Quantity	Units	Estimated Cost :-Rs. 84435/-		Amount
				Earrest Money:- Rs. 1700/-	Time Limit :- One Month	
				Rates U/c all taxes except GST	words	
1	Earth work in excavation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise cut during dewatering complete as per drawing and MORO Technical Specification section 300 & 1600 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	16.74	Per Cubic Meter	339.15	Rupees three hundred thirty nine and paise Fifteen only.	5677.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement is to three sand is to six graded crushed stone aggregate (40mm) forty millimeters nominal size) on ground or under water in open foundations for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete as per the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	11.17	Per Cubic Meter	4408.59	Rupees Four thousand four hundred Eleven and Paise Twenty two only.	49244.00
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per HPPWD specifications or as directed by the Engineer-in-Charge and carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	403.20	Per Kilogram	73.20	Rupees Seventy three and paise Twenty only.	29514.00
Total:-						84435.00

*DWT checked and approved for R. 84435/- only.
 (R. Eighty Four thousand Four hundred and thirty Five)*

Executive Engineer
 Indora Division
 HPPWD Indora

SCHEDULE OF QUANTITY

Name of work - R/R on NH-11 Military Station (Nangal Moor to Shekhpura) road.

Estimated Cost Rs 84540.00
Earnest Money Rs 1700.00

(2422)

Sub Head :- P/L G-III & repair of Pot Holes in front to the Army Gate (Gadsbade Campus). (Deposit Work)

Time limit: Two months

S.No.	Description	Qty	Rate (If all taxes except GST)	Unit	Amount
1	Providing laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand padding, rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber, applying and brooming stone screening to fill up the voids of coarse aggregate, watering and compacting to the required density, grading 3 as per Technical Specification Clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	5.14	1405.30	P/sqm	7227.60
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity grade - 10) grade conforming to IS-73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including, providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate of 2.3 cum per 10 sqm. (Zero point two seven cubic meter) per ten square meter, premixed with bitumen binder VG-10 (viscosity grade-ten) at the rate of 1.46 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06 (zero point zero six) kg. (six decimal eight kilogramme) per M ² technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	275.64	280.50	P/sqm	77317.80
TOTAL					84540.00

*DUT checked and Approved For R. G. Singh /
(R. Singh) four thousand Five hundred
(Forty) only.*

Executive Engineer
Indora Division
HPPWD Indora

4

871

Name of Work:- Restoration of Rain damages to Haler Khad bridge to Indpur via Changrara road km 0/00 to 3/245. (SH:- C/O U-shaped drain at RD 0/947.50 to 0/995) L.H.S

Estimated Cost :-Rs. 84131/-
Earnest Money:- Rs. 1700/-

Time Limit :- One Month

Sr.N o.	Description of Items	Quantity	Units	Rates		Amount
				Rate/Unit taxes except GST	Words	
1	Earth work in excavation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping or bailing out water. (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octon, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	25.65	Per Cubic Meter	339.15	Rupees three hundred thirty nine and paise Fifteen only.	8699.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement is to three sand is to six graded crushed stone aggregate (40mm) forty millimeters nominal size) on ground or under water in open foundations for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900, 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including octon, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	17.10	Per Cubic Meter	4411.22	Rupees Four thousand four hundred Eleven and Paise Twenty two only.	75432.00
Total:-						84131.00

DNT checked and approved for B. 84131/- only.
Rs. Eighty Four thousand One hundred thirty one

Executive Engineer
Indora Division
MDDW/Indora


246

Name of Work:- Restoration of Rain damages on Mohll Indora AL-1 road km 0/00 to 10/00. (SH:- Maintenance of Earthen shoulder/ berms both sides between km 5/00 to 6/00)

Estimated Cost :-Rs. 83688/-
 Earnest Money:- Rs 1700/-
 Time Limit :- One Month

Sr. No.	Description of Items	Quantity	Units	Rate i/c all taxes except GST	words	Amount
1	Making up loss of materials/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads of 1000m as per technical specification clause 1903 as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate is including octori, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	1851.50	Per Square Meter	45.20	Rupees forty five and paise two zero only	83688.00
Total:-						83688.00

Bill checked and approved For Rs. 83688/-
 Rs. Eighty three thousand six hundred.
 Eighty Eight


 Executive Engineer
 Indora Division
 HPPWD Indora

870

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages to Haler Khad br Jdge to Indpur via Changrara road km 0/00 to 3/245. (SH:- C/o U-shaped drain at RD 0/900 to 0/947.50) L.H.S

Sr.N o.	Description of Items	Quantity	Units	Estimated Cost :-Rs. 84165/- Earnest Money:-Rs. 1700/- Time Limit :- One Month	Rates for all taxes except GST	Words	Amount
1	Earth work in excavation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	25.65	Per Cubic Meter	339.15	Rupees three hundred thirty nine and paise Fifteen only.	8599.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate (40mm) forty millimeters nominal size) on ground or under water in open foundations for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800,900, 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government but excluding GST.	17.10	Per Cubic Meter	4413.22	Rupees Four thousand four hundred thirteen and Paise twenty two only.	75466.00	
Total:-						84165.00	

DNI Checked and approved for B. 84165/- entry.
(B. Figure four thousand one hundred sixty five)

Executive Engineer
Indora Division
HPPWD Indora

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under HPPWD Sub Division
Indora.

Estimated cost Rs.:- 84677.00
Earnest Money Rs.:- 1700.00

(SH:- Hiring of excavator cum loader. (J.C.B)

Time limit:- One month

Sr. No	Description of items	Quantity	Rate (/c all taxes except GST)		Amount
			In words	In figures	
1	Deployment of excavator cum loader (JCB) for removal of slips,trees and such like activities repair of berms, earthen shoulders and katcha drain on hiring basis in all kind of classification of soil complete in all respect as per direction of Engineer-in-charge. The cost of lubricant, diesel oil, operator, maintenance cost etc. will be borne by the contractor.	3		5	84677.00 ✓
		85.00 Hours	996.20	Rupees Nine Hundred Ninety Six and Paise Two Zero only	
Total:-					84677.00

Terms and Conditions:-

- Hire charges should be quoted for per hour per working day for six hour.
- Hire charges should be including of all expenses i.e. fuel, lubricant and on account of establishment for major /minor repair, loading and deployment of all equipment required.
- Hire charges should be payable after signing of contract agreement and entire satisfaction as per direction of the Engineer-in-charge and transportation expenses shall be payable by the Government.
- Charges also include insurance of machinery and driver and establishment and the department shall not be responsible for fatal/non fatal accident.
- The minimum quantity to be execution cubical contents shall be measured as per HPPWD specification.
- No deviation shall be allowed in any case.

*DUT checked and approved for Rs. 84677/- only.
(Rs. Eighty four thousand & 77/- only)
Seventy seven only.*

Executive Engineer
Indora-Division
HPPWD Indora

973

SCHEDULE OF QUANTITY

9

295

Name of Works: Balance work for the C/o Balcer to Dalhousie via Samoon Landoh road from lan 0/00 to 5/065. (Silt- Providing and Ailing of MIBAND Informatory sign board). *Culver N (NSA RD).*

Sr. No.	Description of items	Quantity	Rate (1/c all taxes except GST)	Unit	Amount (in Rs.)	Estimated Cost: Rs		
						Exempt Money: Rs	Time limit:	Two Month
1	Providing and fixing of typical MIBAND Informatory sign board with Logo as per M.O.R.D specifications and drawing. Three M.S plates of 1.6mm (One Four Six millimeter) thick top and middle plate duly welded with M.S flat iron 25mm x 5mm (Twenty five millimeter into five millimeter back on edges. The lower plate will be welded with M.S angle iron frame of 25mm x 25mm x 5mm (Twenty five millimeter into twenty five millimeter into five millimeter). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 Nos. (Two Nos.) 38mm x 35mm (seventy five millimeter into 450mm x 600mm (Four hundred fifty millimeter into four hundred fifty millimeter into six hundred millimeter). 600mm (Six hundred millimeter) below ground level. All M.S will be give enamelled on both sides. Lettering and painting arrows. border etc will be painted with ready mixed synthetic enamel as per drawing and M.O.R.D technical specification and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all heads, bits and other incidental. The rate including octroi, royalty, mahkama toll tax or other taxes imposed by the Government but excluding GST.	200	13700.00	Each	27000.00			
2	Providing and fixing of typical Informatory sign board Logo as per M.O.R.D specification and drawing. Three M.S plates of 1.6 mm (one point six millimeter) thick top and middle plate duly welded with M.S flat iron 25mm x 5mm (Twenty five millimeter into five millimeter) size on back on edges. The lower plate will be welded with M.S angle iron frame of 25mm x 25mm x 5mm (Twenty five millimeter into five millimeter). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 Nos. (Two Nos.) 38mm x 35mm (seventy five millimeter into 450mm x 600mm (Four hundred fifty millimeter into four hundred fifty millimeter into six hundred millimeter). 600mm (Six hundred millimeter) below ground level. The top most diamond plate will be welded to middle plate by 47mm x 25mm (Twenty seven millimeter into forty seven millimeter) of 12 SWG (Twelve standard wire gauge) steel tubes posts duly embedded in cement concrete M-15 (M fifteen) nominal mix 1:2:5. 5 (One cement. Two and half sand. Five graded or crushed stone aggregate 40mm/40 millimeter) grade blocks of 450mm x 450mm x 60mm (Four hundred fifty millimeter into four hundred fifty millimeter into six hundred millimeter). 600mm (Six hundred millimeter) below ground level. The top most diamond plate will be welded to middle plate by 47mm x 25mm (Twenty seven millimeter into forty seven millimeter) of 12 SWG (Twelve standard wire gauge) steel plate cube. All M.S will be give enamelled on both sides. Lettering and painting arrows. borders etcetera will be painted with ready mixed synthetic enamel paint of superior quality to required shade and colour. All sections of finished posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing and M.O.R.D. technical specifications section 1700 and as per direction of Engineer - In Charge including carriage of materials within all heads, bits and other incidental. The rate is including octroi, royalty, Mahkama toll tax and any other taxes imposed by the Government but excluding GST.	3.00	176.10 00	Each	52030.00			
Total:						80630.00		
ADD GST @18%						14513.00		
Grand Total:						95143.00		

*DIT checked and approved for B. 80630-00
 (B. Biguty turnover) Six hundred rupees*

*Executive Engineer
 Indora Division
 HPPWD Indora*

269

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under HPPWD Sub Division Indora.

Estimated cost Rs.:- 83681.00

Earnest Money Rs.:- 1700.00

(SH:- Hiring of excavator cum loader. (J.C.B) UNDER INDORA SECTION

Time limit:- One month

Sr. No	Description of Items	Quantity	Rate (I/c all taxes except GST)		Amount
			In words	In figures	
1	Deployment of excavator cum loader (JCB) for removal of slips, trees and such like activities repair of berms, earthen shoulders and katcha drain on hiring basis in all kind of classification of soil complete in all respect as per direction of Engineer-in-charge. The cost of lubricant, diesel oil, operator, maintenance cost etc. will be borne by the contractor.	84.00 Hours	996.20	Rupees Nine Hundred Ninety Six and Paisa Two Zero only	83681.00 ✓
Total:-					83681.00 ✓

Terms and Conditions:-

- Hire charges should be quoted for per hour per working day for six hour.
- Hire charges should be including of all expenses i.e. fuel, lubricant and on account of establishment for major /minor repair, loading and deployment of all equipment required.
- Hire charges should be payable after signing of contract agreement and entire satisfaction as per direction of the Engineer-in-Charge and transportation expenses shall be payable by the Government.
- Charges also include insurance of machinery and driver and establishment and the department shall not be responsible for fatal/non fatal accident.
- The minimum quantity to be execution cubical contents shall be measured as per HPPWD specification.
- No deviation shall be allowed in any case.

DNIT checked and approved for Rs. 83681/- only. (B. Egbuy Hire Financially checked Egbuy only)

Executive Engineer
Indora Division
HPPWD Indora