



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 10667-76 dated 02/03/2026.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **07.03.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **06.03.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **06.03.2026 up to 11:00 AM.** The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	A/R & M/O on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:-Providing and fixing of informatory sign boards at various location)	98000.00	2000.00	Two Month	350/-
2	A/R & M/O on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-Providing and fixing of informatory sign boards at various location)	98000.00	2000.00	Two Month	350/-
3	Restoration of rain Damages on Alampur to Harsipattan road Km 8/00 to 19/00 (SH:-Providing Pusta to scoured base of existing Hume pipe culvert at RD 12/110 to 12/118 and 12/205 to 12/214) PDNA	497536.00	10000.00	Two Month	350/-
4	Restoration of rain Damages on Suan Bhodi Khajar road Km 0/00 to 6/045 (SH:-C/O R/wall at RD 5/636 to 5/641.20) Under PDNA	168140.00	3400.00	Two Month	350/-
5	A/R & M/O on Bheri Bhallunder Dalli Kuhan road Km 0/00 to 10/250 (SH:-C/O R/wall at Rd 2/00 to 2/012.20)	299499.00	6000.00	Two Month	350/-
6	R/O (Repair of) /A/R & M/O Link road from Mandh Khad Pull to Bari via nadol Bhoota Da Gaon Km 0/00 to 3/500 (SH:-P/L CC pavement at Rd 0/160 to 0/218.20) SDF/2025/1216	199396.00	4000.00	Two Month	350/-
7	A/R & M/O on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:-Providing and fixing of informatory sign boards at various location)	98000.00	2000.00	Two Month	350/-
8	Restoration of rain Damages on Alampur to Harsipattan road Km 8/00 to 19/00 (SH:-Providing 3rd step to R/wall Rd 14/600 to 14/626) PDNA	498175.00	10000.00	Two Month	

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur


On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 10667-76

Dated: 02/03/2026

Copy to the following for information and necessary action:-


1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineers under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

1


SCHEDULE OF QUANTITY						
Name of work :-A/R & M/O on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:-Providing and fixing of informatory sign boards at various location)					Estimated cost Rs.	98000.00
					Earnest Money Rs.	2000.00
					Time Limits	Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing informatory sign boards single side size 600x600 mm (Six Hundred into six hundred size) with retroflective sheeting fixed over 3mm thick aluminum composite material sheeting to back supported frame of 20x20x3 mm angle iron dully powder coated with aluminium pop rivets supported over a square MS pipe 47mm of 3meter length duly painted black and white along with GI nuts, bolts and washer as per specification including all leads ,lifts and carriage of materials by all modes of transpiration and as per the direction of Engineer-in Charge.The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government	5.00	5500.00	Rupees Five Thousand Five Hundred Only	Each	27500.00
2	Providing and fixing informatory sign boards single side size600*900 mm and 900*1200 mm (six hundred into nine hundred and nine hundred into twelve hundred size) with retroflective sheeting fixed over 3mm thick Aluminum composite material sheeting to back supported frame 25*25*3 mm angle iron dully powder coated with aluminum with aluminum pop rivets supported over a pair (2Nos) of squares MS pipe 47 mm of 3m length duly painted black and white along with GI nuts, bolts and washer as per specification including all leads , lifts and carriage of material s by all modes of transpiration and as per the direction of Engineer -in-Charge The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government					
	Size 600*900 (six hundred into nine hundred)	3.00	9000.00	Rupees Nine Thousand Only	Each	27000.00
	Size 900*1200 (nine hundred and nine hundred into twelve hundred)	3.00	14500.00	Rupees Fourteen Thousand Five Hundred Only	Each	43500.00
	Total					98000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)				%
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

2

SCHEDULE OF QUANTITY


Name of work :-A/R & M/O on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-Providing and fixing of informatory sign boards at various location)			Estimated cost Rs.		98000.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing informatory sign boards single side size 600x600 mm (Six Hundred into six hundred size) with retroflective sheeting fixed over 3mm thick aluminum composite material sheeting to back supported frame of 20x20x3 mm angle iron dully powder coated with aluminium pop rivets supported over a square MS pipe 47mm of 3meter length duly painted black and white along with GI nuts, bolts and washer as per specification including all leads ,lifts and carriage of materials by all modes of transpiration and as per the direction of Engineer-in Charge.The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government	5.00	5500.00	Rupees Five Thousand Five Hundred Only	Each	27500.00
2	Providing and fixing informatory sign boards single side size600*900 mm and 900*1200 mm (six hundred into nine hundred and nine hundred into twelve hundred size) with retroflective sheeting fixed over 3mm thick Aluminum composite material sheeting to back supported frame 25*25*3 mm angle iron dully powder coated with aluminum with aluminum pop rivets supported over a pair (2Nos) of squares MS pipe 47 mm of 3m length duly painted black and white along with GI nuts, bolts and washer as per specification including all leads , lifts and carriage of material s by all modes of transpiration and as per the direction of Engineer -in-Charge The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government					
	Size 600*900 (six hundred into nine hundred)	3.00	9000.00	Rupees Nine Thousand Only	Each	27000.00
	Size 900*1200 (nine hundred and nine hundred into twelve hundred)	3.00	14500.00	Rupees Fourteen Thousand Five Hundred Only	Each	43500.00
	Total					98000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)				%
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 8/00 to 19/00 (SH:- Providing Pusta to scoured base of existing Hume pipe culvert at RD 12/110 to 12/118 and 12/205 to 12/214) PDNA		Estimated cost Rs.	497536.00			
		Earnest Money Rs.	10000.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	118.25	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	29563.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	94.54	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Metre	467973.00	
Total						497536.00	
Quoted Rate (in Figures) Percentage						Excess (+)	%
G.Total in Figures						Less (-)	%
G.Total in Words							




Executive Engineer,
Jaisinghpur Division,
HPWD Jaisinghpur

(4)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Suan Bhodi Khajar road Km 0/00 to 6/045 (SH:-C/O R/wall at RD 5/636 to 5/641.20) Under PDNA		Estimated cost Rs.		168140.00		
		Earnest Money Rs.		3400.00		
		Time Limits		Two Month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.00	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	3825.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	39.52	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	152152.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	20.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5000.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	7.54	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre.	7163.00
Total						168140.00
Quoted Rate (in Figures) Percentage		Excess (+)		%		
		Less (-)		%		
G.Total in Figures						
G.Total in Words						




Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

(5)

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O on Bheri Bhallunder Dalli Kuhan road Km 0/00 to 10/250 (SH:-C/O R/wall at Rd 2/00 to 2/012.20)		Estimated cost Rs.	299499.00			
		Earnest Money Rs.	6000.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.82	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	6955.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	70.03	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	262613.00

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	20.98	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	19931.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	40.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	10000.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	299499.00
		Less (-)			%	
G.Total in Figures						
G.Total in Words						




Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur

2

SCHEDULE OF QUANTITY


Name of work :-R/O (Repair of) /A/R & M/O Link road from Mandh Khad Pull to Bari via nadol Bhoota Da Gaon Km 0/00 to 3/500 (SH:-P/L Cc pavement at Rd 0/160 to 0/218.20) SDF/2025/1216		Estimated cost Rs.	199396.00			
		Earnest Money Rs.	4000.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	13.76	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	28896.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	27.50	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	170500.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	199396.00
	G.Total in Figures				%	
	G.Total in Words					



Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

7

SCHEDULE OF QUANTITY							
Name of work :-A/R & M/O on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:-Providing and fixing of informatory sign boards at various location)					Estimated cost Rs.		98000.00
					Earnest Money Rs.		2000.00
					Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and fixing informatory sign boards single side size 600x600 mm (Six Hundred into six hundred size) with retroflective sheeting fixed over 3mm thick aluminum composite material sheeting to back supported frame of 20x20x3 mm angle iron dully powder coated with aluminium pop rivets supported over a square MS pipe 47mm of 3meter length duly painted black and white along with GI nuts, bolts and washer as per specification including all leads ,lifts and carriage of materials by all modes of transpiration and as per the direction of Engineer-in Charge.The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government	5.00	5500.00	Rupees Five Thousand Five Hundred Only	Each	27500.00	
2	Providing and fixing informatory sign boards single side size600*900 mm and 900*1200 mm (six hundred into nine hundred and nine hundred into twelve hundred size) with retroflective sheeting fixed over 3mm thick Aluminum composite material sheeting to back supported frame 25*25*3 mm angle iron dully powder coated with aluminum with aluminum pop rivets supported over a pair (2Nos) of squares MS pipe 47 mm of 3m length duly painted black and white along with GI nuts, bolts and washer as per specification including all leads , lifts and carriage of material s by all modes of transpiration and as per the direction of Engineer -in-Charge The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government						
	Size 600*900 (six hundred into nine hundred)	3.00	9000.00	Rupees Nine Thousand Only	Each	27000.00	
	Size 900*1200 (nine hundred and nine hundred into twelve hundred)	3.00	14500.00	Rupees Fourteen Thousand Five Hundred Only	Each	43500.00	
Total						98000.00	
Quoted Rate (in Figures) Percentage		Excess (+)				%	
		Less (-)				%	
G.Total in Figures							
G.Total in Words							


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

8

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 8/00 to 19/00 (SH:- Providing 3rd step to R/wall Rd 14/600 to 14/626) PDNA

Estimated cost Rs.	498175.00
Earnest Money Rs.	10000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	76.70	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	325975.00
2	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	156.00	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	148200.00
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	96.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	24000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	498175.00
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Chand

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur