



Office of  
Executive Engineer B&R Division HP.PWD. Joginder Nagar  
Himachal Pradesh Public Works Department, Mandi-175015  
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

**"NOTICE INVITING TENDER"**

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed ON 20-03-2026 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 19-03-2026 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on the same day from 3.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of rain damages on Trimbali Ropra Chakrog road km. 0/00 to 2/500 (SH:- Providing and laying Cement Concrete pavement at km. 0/00 to 0/099 under PDNA 2023.	Rs. 3,31,774/-	Rs.6,600/-	Rs. 350/-	Class "D"	Three Months
2	A/R & M/O Residential Buildings under Joginder Nagar Division, HP PWD, Joginder Nagar, Distt. Mandi (SH:- Providing and applying painting distempering, tile work, Providing and Fixing Almirah/Cup board and Sanitary work etc. for Type-II Quarter Near Rest House Joginder Nagar.	Rs. 96,144/-	Rs.1,900/-	Rs. 350/-	Class "D"	Two months
3	Restoration of Rain Damages on Link road from NH-154 to H PWD, Rest House Joginder Nagar (SH:- Construction of U-Shape Drain Shape Drin with steel grating LHS at km. 0/060 to 0/128)	Rs.4,66,758/-	Rs.9,300/-	Rs. 350/-	Class "D"	Three Months
4.	Restoration of rain damages on Said Jagmohan Link road Bashai (SH:- Construction of Retaining wall at km. 0/235 to 0/241 and 0/265 to 0/280).	Rs.4,68,211/-	Rs.9,400/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.  
District Mandi (HP) for on behalf of  
Governor of Himachal Pradesh  
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2026-27-33310-59

Dated:- 27/02/26

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.

7-1

657

ENo 476

**DNIT/DRAFT SCHEDULE OF QUANTITY**

**Particulars of Work:** Restoration of Rain Damages on Trimbali Ropra Chakrog Road km 0/00 to 2/500 Providing and Laying Cement Concrete Pavement at km 0/00 to 0/099 under PDNA 2023)

Estimate Cost: 3,31,774.00  
 Earnest Money: 6,600.00  
 Time Limit : Three Months

Description of work	No. or Qty.	Unit	Rate		AMOUNT
			Figures	Words	
Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel hannels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	39.63	Per Cubic metre	8,371.80	Rupees Eight Thousand Three Hundred Seventy One And Paise Eighty Only	3,31,774.00
<b>Total</b>					<b>3,31,774.00</b>

*Draft schedule of quantity checked and approved by P.F. 331774.00. (X) three less thirty one thousand seven hundred seventy four only*

*[Signature]*  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar

## DNIT/SCHEDULE OF QUANTITY

of Work : A/R & M/O Residential Buildings under Joginder Nagar Division HPPWD Joginder Nagar Distt. (H.P.) (SH: Providing and Applying painting distemper, tile work, Providing and fixing Almirah/ Cup and Sanitary work etc. for Type-II Quarter Near Rest house Joginder Nagar)

Estimate Cost: 96,144.00  
Earnest Money: 1,900.00  
Time Limit : Two Months

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Providing and fixing Stainless Steel A ISI 304 (18/8) Kitchen sink with drain board of size 610x460 mm (Six hundred ten by four hundred sixty millimeter) bowl depth 200mm (two hundred millimeter) per IS:13983 with C.I. brackets and stainless steel plug 40 mm (forty millimeter), including painting of fittings and brackets, cutting and making good the walls wherever required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.00	Each	2112.00	Rupees Two Thousand One Hundred Twelve Only	2,112.00
Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.00	Each	4604.30	Rupees Four Thousand Six Hundred Four And Paise Thirty Only	4,604.00
Providing and fixing 8 mm (eight millimeter) dia C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.00	Each	453.80	Rupees Four Hundred Fifty Three And Paise Eighty Only	454.00
Providing and fixing 15 mm (fifteen millimeter) nominal bore C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 .The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.00	Each	203.30	Rupees Two Hundred Three And Paise Thirty Only	203.00

J-2

681

681

**Description of work**

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
<p>providing and laying vitrified floor tiles of size 600x600 mm (six hundred by six hundred millimeter) (thickness to be specified by the manufacturer) with water absorption less than 08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimeter) thick cement mortar 1:4 (one cement to four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogramme per square meter) including grouting the joints with white cement and matching pigments etc., complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive of taxes levy by the government time to time including GST.</p>	3.25	Per Square Metre	1322.20	Rupees One Thousand Three Hundred Twenty Two And Paise Twenty Only	4,297.00
<p>providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% (Zero point zero eight percentage) and conforming to IS: 15622, of approved brand &amp; manufacturer, in all colours and shade, in skirting, of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.</p>	36.80	Per Square Metre	805.20	Rupees Eight Hundred Five And Paise Twenty Only	29,631.00
<p>applying one coat ( excluding priming coat) on previously painted wood and wood based surface with ready mixed paint brushing to give an even shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.</p>	26.49	Per square metre	83.10	Rupees Eighty Three And Paise Ten Only	2,201.00
<p>applying two coats with acrylic emulsion paint, having VOC ( Volatile Organic Compound) content less than 50grams/litre, (Fifty) of approved brand and manufacture, including applying additional coats where ever required, to achieve even shade and colour, cleaning the surface of all dust and other foreign matter and sand papering as required complete. The rates are inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.</p>	93.60	Per Square Meter	109.00	Rupees One Hundred Nine Only	10,202.00

**Description of work**

No. or Qty.	Unit	Rate		AMOUNT Rs. P
		Figures	Words	
40.55	Per Square Meter	57.60	Rupees Fifty Seven And Paise Sixty Only	2,336.00
11.55	Per Square Meter	1672.30	Rupees One Thousand Six Hundred Seventy Two And Paise Thirty Only	19,315.00
11.55	Per Square Meter	901.90	Rupees Nine Hundred One And Paise Ninety Only	10,417.00
20.00	Each	56.40	Rupees Fifty Six And Paise Forty Only	1,128.00
20.00	Each	62.20	Rupees Sixty Two And Paise Twenty Only	1,244.00

distemping with oil bound on decorated wall surface (two coat) washable distemper of approved and manufacture on old work to give an even shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required complete. The rates are inclusive of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.

providing and fixing 19mm (nineteen millimeter) thick water proof termite resistant commercial board including shelves. Back side of the box shall be of 6mm thick ply and all cut portion of the shelves shall be finished with 6mm hard wood edging. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.

providing and fixing 1.00mm (one millimeter) thick coloured or plain lamination sheet (summica) on boards/ply wood sheets with approved adhesive and nails etc complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.

providing and fixing anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 100mm (one hundred millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.

providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 150x10mm (One hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.

**Description of work**

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Providing and fixing Water Heater having capacity of 25 liter of input wattage of 2.0 kilowatt 230-240 voltage include glass-lined inner tanks, magnesium anodes for corrosion protection, 5-star energy ratings, support 8-bar pressure include all necessary fittings. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.00	Each	8000.00	Rupees Eight Thousand Only	8,000.00
<b>Total</b>					<b>96,144.00</b>

*Draft schedule of quantity prepared for ₹ 96,144.00/-  
 (Ninety six thousand one hundred forty four only.)*

  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar

JC3

EN0437/24-25

592

**PERCENTAGE RATE BILL OF QUANTITY**

**Tender inviting authority:**

**Name of work:-** Restoration of Rain Damages on link road from NH-154 to HPPWD Rest House Joginder Nagar (Sub Head:- Construction of U Shape Darin with Steel Grating LHS at km 0/060 to 0/128 )

**Contact No:**

Name of the Bidder/Bidding Firm/Company					Estimated Cost : Rs. 466758.00/- only	
					Earnest Money Cost : Rs. 9300.00/- only	
					Time:- Three months	
Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes excluding GST in Rs. P.	Total amount with all taxes excluding GST in Rs. P.	Total amount with all taxes excluding GST in words
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	24.48	Per cubic metre	517.65	12,672.00	Rupees Thousand Six Hundred Seventy Two Only
		3		5	6	7

Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes excluding GST in Rs. P.	Total amount with all taxes excluding GST in Rs. P.	Total amount with all taxes excluding GST in words
1		3	4	5	6	7
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.42	Per cubic metre	6,511.20	1,39,470.00	Rupees One Lakh(s) Thirty Nine Thousand Four Hundred Seventy Only
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2721.59	Per Kilogramme	115.60	3,14,616.00	Rupees Three Lakh(s) Fourteen Thousand Six Hundred Sixteen Only
	<b>Total</b>				<b>4,66,758.00</b>	

*Draft schedule of quantity approved for ₹ 466,758.00/-  
(₹ four less sixty six thousand seven hundred fifty eight only)*

*Executive Engineer,  
B&R Division HP.PWD.,  
Joginder Nagar.*

686

EN-3 492

3

PERCENTAGE RATE BILL OF QUANTITY

Name of work: - Restoration of rain Damages on Sahid Jagmohan link road BashaI  
(SH: Construction of Retaining wall at km 0/235 to 0/241 and 0/265 to 0/280)

Contact No:

Estimated Cost : Rs. 468211.00/- only

Earnest Money Cost : Rs. 9400.00/- only

Time:- Three months

Name of the Bidder/Bidding Firm/Company						
Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	2	3	4	5	6	7
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . The rate is inclusive all taxes levy by the government time to time including GST.	21.00	Per Cubic metre	648.00	13,608.00	Rupees Thirteen Thousand Six Hundred Eight Only
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size ) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	66.36	Per Cubic metre	6,321.65	4,19,505.00	Rupees Four Lakh(s) Nineteen Thousand Five Hundred Five Only

Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	2	3	4	5	6	7
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	20.79	Per cubic metre	1,149.10	23,890.00	Rupees Twenty Three Thousand Eight Hundred Ninety Only
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (V): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	34.00	each	329.65	11,208.00	Rupees Eleven Thousand Two Hundred Eight Only
	<b>Total</b>				<b>4,68,211.00</b>	

*Draft schedule of quantity approved for ₹ 4,68,211/-  
(Four Lax sixty eight thousand two hundred eleven only)*

*Executive Engineer,  
B&R Division HP.PWD.,  
Joginder Nagar.*