

NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **16.03.2026 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **13.03.2026 up to 4.30 P.M.** The tender applications for issue of tender forms will be received in this office on **13.03.2026 up to 11.30 A.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	C/O approach road to Degree College Matour km. 0/00 to 0/270)(SH- P/L GSB and G-II at RD 0/205 to 0/270)(Deposit work)	99715/-	2000/-	350/-	Two Month
2.	C/O approach road to Degree College Matour km. 0/00 to 0/270)(SH- P/L GSB and G-II at RD 0/140 to 0/205)(Deposit work)	99715/-	2000/-	350/-	Two Month
3.	C/O approach road to Degree College Matour km. 0/00 to 0/270)(SH- P/L GSB and G-II at RD 0/090 to 0/140)(Deposit work)	99715/-	2000/-	350/-	Two Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)


(On behalf of Governor of Himachal Pradesh)

Dated:  5/3/26

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

8156-90

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF APPROACH ROAD TO DEGREE COLLEGE MATOUR KM. 0/00 TO 0/270 (SH- PROVIDING AND LAYING GSB AND G-II AT RD 0/205 TO 0/270)									
Sr. No	Description of work	Qty	Unit	Rates		Estimated Cost:- Earnest Money:- Time Limit:-	Two Month AMOUNT	99715.00 2000/-	
				In Figures	In Words				
1	Preparation of sub grade by dressing to combor(Earth Work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per hp.pwd specifications. as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	238.88	Per Square metres	1.90	Rupees One - Paise Ninety Only		454.00		
2	Consolidation of sub grade with road roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD. specifications as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidentals.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.	238.88	Per Square metres	1.05	Rupees One - Paise Five Only		251.00		
3	Construction of gravel/soil-aggregate base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 KN static roller to achieve the desire density. complete as per Technical specifications Clause 402.as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.	35.84	Per Cubic metres	1500.00	Rupees One Thousand Five Hundred Only		53760.00		

<p>4 Providing ,laying, spreading and compacting stone aggregates of specific size to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stage to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstics of coarse aggregate, watering and compacting to the required density Grading-II(63mm to 45mm)as per technical Specifications Clause 405. as per Technical specifications Clause 402.as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.</p>	17.91	Per Cubic metres	2526.50	Rupees Two Thousand Five Hundred & Twenty Six - Paise Fifty Only	45250.00
EXCESS =					
	%				
LESS =					
	%				
Total:					99715.00

EXCESS =

%

LESS =

%


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.


SCHEDULE OF QUANTITY

Sr. No		Description of work	Qty	Unit	Rates		AMOUNT
					In Figures	In Words	
NAME OF WORK :- CONSTRUCTION OF APPROACH ROAD TO DEGREE COLLEGE MATOUR KM. 0/00 TO 0/270 (SH- PROVIDING AND LAYING GSB AND G-II AT RD 0/140 TO0/205)							
Estimated Cost:-							99715.00
Earnest Money:-							2000/-
Time Limit:-							Two Month
1		Preparation of sub grade by dressing to combor(Earth Work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per hp.pwd specifications. as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	238.88	Per Square metres	1.90	Rupees One - Paise Ninety Only	454.00
2		Consolidation of sub grade with road roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD. specifications as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the	238.88	Per Square metres	1.05	Rupees One - Paise Five Only	251.00
3		Construction of gravel/soil-aggregate base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC,and compacting with three wheel 80-100 KN staticroller to achieve the desire density. complete as per Technical specifications Clause 402.as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.	35.84	Per Cubic metres	1500.00	Rupees One Thousand Five Hundred Only	53760.00

<p>4 Providing ,laying, spreading and compacting stone aggregates of specific size to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stage to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstics of coarse aggregate, watering and compacting to the required density Grading-II(63mm to 45mm)as per technical Specifications Clause 405. as per Technical specifications Clause 402.as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.</p>	17.91	Per Cubic metres	2526.50	Rupees Two Thousand Five Hundred & Twenty Six - Paise Fifty Only	45250.00
EXCESS =					
LESS =					
	Total:				99715.00

%

%


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF APPROACH ROAD TO DEGREE COLLEGE MATOUR KM. 0/00 TO 0/270 (SH:- PROVIDING AND LAYING GSB AND G-II AT RD 0/090 TO 0/140)		Estimated Cost:-		99715.00		
		Earnest Money:-		2000/-		
		Time Limit:-		Two Month		
Sl. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Preparation of sub grade by dressing to combor(Earth Work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per hp.pwd specifications. as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	238.88	Per Square metres	1.90	Rupees One - Paise Ninety Only	454.00
2	Consolidation of sub grade with road roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD. specifications as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.	238.88	Per Square metres	1.05	Rupees One - Paise Five Only	251.00
3	Construction of gravel/soil-aggregate base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC,and compacting with three wheel 80-100 KN staticroller to achieve the desire density. complete as per Technical specifications Clause 402.as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.	35.84	Per Cubic metres	1500.00	Rupees One Thousand Five Hundred Only	53760.00

4	Providing ,laying, spreading and compacting stone aggregates of specific size to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stage to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstics of coarse aggregate, watering and compacting to the required density Grading-II(63mm to 45mm)as per technical Specifications Clause 405. as per Technical specifications Clause 402.as per the direction of the Engineer -in-Charge including carriage of material with in all leads,lifts and other incidental.The rate including of octroi,royality,Malkhana, toll tax, GST or other taxes imposed by the government.	17.91	Per Cubic metres	2526.50	Rupees Two Thousand Five Hundred & Twenty Six - Paise Fifty Only	45250.00
Total:						99715.00

EXCESS = _____ %

LESS = _____ %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.