

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

15080

Dated:- 12 ³/₂₀₂₆

To

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

**Executive Engineer,
B&R Division,
HP PWD Karsog**

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in**

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **19.03.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 18.03.2026** for which the application should reach in this office **upto 1.00 PM 18.03.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 2/720 to 2/733) under PDNA 2023	4,98,291/-	10,000/-	One Month	350/-
2	R/R damages on Link road to village Parlog Km. 0/00 to 2/00 (SH:- removal of slips, unlined drain and maintenance of berms in RDs between Km. 0/00 to 2/00) under PDNA 2023	2,54,542/-	5,100/-	Two Months	350/-
3	R/R damages on Kotlu Nanj road Km. 0/00 to 6/120 (SH:- C/o PCC R/wall at RD 1/285 to 1/298) under PDNA 2023	3,61,166/-	7,300/-	Two Months	350/-
4	R/R damages on Mahog Shakelar via Navidhar road KM. 0/00 to 9/00 (SH:- Removal of slips at various RDs in Km. 0/00 to 4/146) under PDNA	4,99,348/-	10,000/-	One Month	350/-
5	R/R damages on Khadargali to Somakothi road Km. 0/00 to 4/110 (SH:- Removal of slips at various RDs in KM. 0/00 to 4/010) under PDNA	4,98,867/-	10,000/-	One Month	350/-

TERMS & CONDITIONS:-

- No tender form will be issued to those contractors who are not registered under HPGST Act.
- The Contractor/firm should be registered as or dealer GST NO.
- If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
- No tender form will be issued to those contractors who are not registered under EPF Act.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- The earnest money for the above work should be attached with the application.
- The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
- As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

**Executive Engineer
B&R Division
HPPWD Karsog**

No. PW-E-Tender-NIT/2025-26-

15075-79

Dated:-

12-3-2028

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog


Percentage Schedule Of Quantity

Estimated Cost 498291.00
Earnest Money 10000.00
Time One Month

Name of Work:- R/R Damages on AIsindi Tattapani via Dhundhan road Km. 0/00 to 5/00 (SH:-Providing Retaining Wall at RD 21720 to 21733) under PDNA-2023

Sub-Head and items of works.

Sr.No.	Description	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	50.12	Per Cubic Meter	390.20	19557.00	Rupees Nineteen Thousand Five Hundred Fifty Seven and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.96	Per Cubic Meter	5500.00	456280.00	Rupees Four Lakhs Fifty Six Thousand Two Hundred Eighty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	33.00	Each	373.15	12314.00	Rupees Twelve Thousand Three Hundred Fourteen and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.45	Per Cubic Meter	1200.00	10140.00	Rupees Ten Thousand One Hundred Forty and Paise Zero Only
Total In Figures					498291.00	
Quoted Rate in Figures						
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money

254542.00
5100.00

Time

Two Months

Name of Work:- R/R Damages on Link road to village Parlog Km. 0/00 to 2/00(SH):- Removal of slips, Unlined drain & Maintenance of berms in RD's Between 0/00 to 2/00)Under PDNA 2023.

Sub-Head and Items of works.

Sr.No.	Name of Work:- R/R Damages on Link road to village Parlog Km. 0/00 to 2/00(SH):- Removal of slips, Unlined drain & Maintenance of berms in RD's Between 0/00 to 2/00)Under PDNA 2023.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance.-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3 5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1116.05	Per Cubic Meter	120.00	133926.00	Rupees One Lakh Thirty Three Thousand Nine Hundred Twenty Six and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm (zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in - charge with in all lead and lifts and other incidentals.	1200.00	Per Running Meter	21.30	25560.00	Rupees Twenty Five Thousand Five Hundred Sixty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4160.00	Per Square Meter	22.85	95056.00	Rupees Ninety Five Thousand Fifty Six and Paise Zero Only
Total In Figures					254542.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
DPPWD, Karsog.

Percentage Schedule of Quantity.

Estimated Cost
Earnest Money

361166
7300
Two Months

Time

Name of Work:- R/R Damages on Kotlu Nanj road Km 0/00 to 6/120 (SH:- C/O PCC R/wall at RD 1/285 to 1/298), Under PDNA 2023,

Sub-Head and Items of works.


Sr.No.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST
1	19.76	Per Cubic Metre	390.20	7710.00	Rupees Seven Thousand Seven Hundred Ten and Paise Zero Only
2	59.80	Per Cubic Metre	5500.00	328900.00	Rupees Three Lakhs Twenty Eight Thousand Nine Hundred and Paise Zero Only
3	20.00	Each	373.15	7463.00	Rupees Seven Thousand Four Hundred Sixty Three and Paise Zero Only
3	11.70	Per Cubic Metre	1460.95	17093.00	Rupees Seventeen Thousand Ninety Three and Paise Zero Only
Total in Figures				361166.00	
Quoted Rate in Figures					
Quoted Rate in Words					

Executive Engineer,
Karsog Division,
HIPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 499348
 Earnest Money 10000
 Time One Month


Name of Work: RR Damages on Malog Shakelar via Navidhar road Km. 0/00 to 9/00 (SH:- Removal of slips at various RD's in Km 0/00 to 4/145) Under PDNA.		Sub-Head and Items of works.							
Sl.No.		No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST in Words			
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts seeking the servicable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3950.54	Per Cubic Meter	126.40	499348.00	Rupees Four Lakhs Ninety Nine Thousand Three Hundred Forty Eight and Paise Zero Only			
Total in Figures					499348.00				
Quoted Rate in Words									
Quoted Rate in Figures									


 Executive Engineer,
 Karsog Division,
 CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 498967
 Earnest Money 10000
 Time One Month

Name of Work:- gfr Damages on Khadar gali to Somakothi road Km. 0000 to 411101SH:- Removal of slips at various RD's in Km 0000 to 4000) Under PDNA.		Sub-Head and items of works.						
Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words		
1	Removal of land slide clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3947.52	Per Cubic Meter	126.40	498967.00	Rupees Four Lakhs Ninety Eight Thousand Nine Hundred Sixty Seven and Paise Zero Only		
Total in Figures					498967.00			
Quoted Rate in Figures								
Quoted Rate in Words								


 Executive Engineer,
 Karsog Division,
 CHPPWD, Karsog.