

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-MDI(P)E-Tender-NIT/2025-26-

18426-32 Dated: 6/3/25

To

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,  
Mandi Division No.1,  
HP. PWD at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,  
Mandi Division No.1,  
HP. PWD. at Padhar

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**\*NOTICE INVITING TENDER\***

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 16.03.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 13.03.2026 upto 12:00 Noon.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Kamand Neri road at RD 0/0 to 6/00. (PDNA-2023) (SH:- Construction of 900mm dia Hume Pipe Culvert at RD 4/900 with both side wing wall)	3,81,674.93	7600/-	350/-	One month
2	Restoration of rain damages on Kamand Neri road at RD 0/0 to 6/00. (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 4/250 to 4/258 and 5/525 to 5/535)	3,84,871.05	7700/-	350/-	One month
3	Restoration of rain damages on Kamand Neri road at RD 0/0 to 6/00. (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 4/890 to 4/897.50 and 4/904 to 4/911.50)	4,34,992.95	8700/-	350/-	One month
4	Restoration of rain damages on Kamand Neri road at RD 0/0 to 6/00. (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 3/895 to 3/905 and 4/240 to 4/247.50)	3,74,160.31	7500/-	350/-	One month
5	Restoration of rain damages on Kamand Neri road at RD 0/0 to 6/00. (PDNA-2023) (SH:- Construction of Breast wall at RD 3/630 to 3/645 and 3/795 to 3/805)	4,99,317.03	10,000/-	350/-	One month
6	Restoration of rain damages on Kamand Neri road at RD 0/0 to 6/00. (PDNA-2023) (SH:- Construction of Breast wall at RD 5/725 to 5/750)	4,99,317.03	10,000/-	350/-	One month
7	Restoration of rain damages on Shegali Prashar road Km 0/00 to 22/510 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 6/630 to 6/642.50)	4,97,542.04	10,000/-	350/-	One month
8	Restoration of rain damages on Shegali Prashar road Km 0/00 to 22/510 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 5/520 to 5/538)	4,98,654.69	10,000/-	350/-	One month
9	Restoration of rain damages on Shegali Prashar road Km 0/00 to 22/510 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 7/330 to 7/348)	4,98,654.69	10,000/-	350/-	One month

10	Restoration of rain damages on Pakhri Galu Baragaun road Km 0/00 to 5/830 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 4/085 to 4/093)	2,06,658.97	4100/-	350/-	One month
11	Restoration of rain damages on Pakhri Galu Baragaun road Km 0/00 to 5/830 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 1/510 to 1/529.30)	4,99,205.07	10,000/-	350/-	One month
12	Restoration of rain damages on Pakhri Galu Baragaun road Km 0/00 to 5/830 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 3/565 to 3/575)	3,56,280.55	7100/-	350/-	One month
13	Restoration of rain damages on Pakhri Galu Baragaun road Km 0/00 to 5/830 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 5/750 to 5/760)	2,61,741.99	5200/-	350/-	One month
14	Restoration of rain damages on Sahal Garlog road Km 0/00 to 7/530 (PDNA-2023) (SH:- Construction of Breast wall at R.D. 1/552 to 1/560)	2,57,339.81	5100/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

**TERMS AND CONDITIONS:-**

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

  
 Executive Engineer,  
 Mandi Division No. 1,  
 HPPWD, at Padhar Distt. Mandi (H.P.)  
 on behalf of Governor of Himachal Pradesh

1

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 381674.93  
 Earnest Money Rs:- 7600.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Kamand Neri road at RD 0/00 to 6/00. (PDNA -2023). (Sub Head: - Construction of 900mm dia Hume Pipe Culvert at RD 4/900 with both side wing wall).

Contract No. :  
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.
1	Excavation in soil in hilly area in ordinary rock not required blasting by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5 meter (one point five) and lead upto 20 (twenty meter) as per technical specification clause 1603.2. Including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	6.67	Per cubic metre	162.70	Rupees One Thousand Eighty Five and Paise Twenty One Only	1085.21
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	47.22	Per cubic metre	522.50	Rupees Twenty Six Hundred Seventy Two and Paise Forty Five Only	24672.45
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.10	Per cubic metre	4733.10	Rupees Five Thousand Two Hundred Six and Paise Forty One Only	5206.41
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203.-Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.27	Per cubic metre	5189.40	Rupees Eleven Thousand Seven Hundred Seventy Nine and Paise Ninety Four Only	11779.94
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.64	Per cubic metre	5369.80	Rupees Fifty One Thousand Seven Hundred Sixty Four and Paise Eighty Seven Only	51764.87
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.50	Per Running metre	3954.60	Rupees Twenty Nine Thousand Six Hundred Fifty Nine and Paise Fifty Only	29659.50
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Per cubic metre	1512.10	Rupees Nine Thousand Seventy Two and Paise Sixty Only	9072.60

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
8	Providing concrete for plain/reinforced concrete in super structure complete as per drawings and technical specifications clause 800, 1205.4, & 1205.5. Plain cement concrete 1:2:4 (one cement : two sand : four graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	0.45	Cubic metre	5928.40	Rupees Two Thousand Six Hundred Sixty Seven and Paise Seventy Eight Only	2667.78	Rupees Two Thousand Six Hundred Sixty Seven and Paise Seventy Eight Only
9	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	48.95	Per cubic metre	4904.60	Rupees Two Lakh Forty Thousand Eighty and Paise Seventeen Only	240080.17	Rupees Two Lakh Forty Thousand Eighty and Paise Seventeen Only
10	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	284.30	Rupees Five Thousand Six Hundred Eighty Six Only	5686.00	Rupees Five Thousand Six Hundred Eighty Six Only
<b>Total in figure :</b>					<b>381674.93</b>		<b>Rupees Three Lakh Eighty One Thousand Six Hundred Seventy Four and Paise Ninety Three Only</b>
<b>Total in Words :</b>							<b>Rupees Three Lakh Eighty One Thousand Six Hundred Seventy Four and Paise Ninety Three Only</b>

Executive Engineer,  
Mandi Division No.1,  
HP. PWD. at Padhar,

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 384871.05

Earnest Money Rs:- 700.00

Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Kamand Neri road at RD 0/00 to 6/00. (PDNA -2023). (Sub Head: - Construction of Retaining wall at R.D. 4/250 to 4/258 and 5/525 to 5/535).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.62	Per cubic metre	522.50	10251.45	Rupees Ten Thousand Two Hundred Fifty One and Paise Forty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	69.30	Per cubic metre	4904.60	339888.78	Rupees Three Lakh Thirty Nine Thousand Eight Hundred Eighty Eight and Paise Seventy Eight Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.00	Each	284.30	10234.80	Rupees Ten Thousand Two Hundred Thirty Four and Paise Eighty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.20	Per cubic metre	1512.10	24496.02	Rupees Twenty Four Hundred Ninety Six and Paise Two Only
<b>Total in figure :</b>					<b>384871.05</b>	<b>Rupees Three Lakh Eighty Four Thousand Eight Hundred and Paise Five Only</b>
<b>Total in Words :</b>						<b>Rupees Three Lakh Eighty Four Thousand Eight Hundred Seventy One and Paise Five Only</b>

Executive Engineer,  
Mandi Division No.I,  
HP. PWD. at Padhar

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 434992.95  
 Earnest Money Rs:- 8700.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Kamand Neri road at RD 0/00 to 6/00. (PDNA -2023). (Sub Head: - Construction of Retaining wall at R.D. 4/890 to 4/897.50 and 4/904 to 4/911.50).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.80	Per cubic metre	522.50	Rupees Eight Thousand Seven Hundred Eight Only	8778.00	Rupees Eight Thousand Seven Hundred Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	81.00	Per cubic metre	4904.60	Rupees Three Lakh Ninety Seven Thousand Two and Paise Sixty Only	397272.60	Rupees Three Lakh Ninety Seven Thousand Two and Paise Sixty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	284.30	Rupees Eight Thousand Five Hundred Twenty Nine Only	8529.00	Rupees Eight Thousand Five Hundred Twenty Nine Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.50	Per cubic metre	1512.10	Rupees Twenty Thousand Four Hundred Thirteen and Paise Thirty Five Only	20413.35	Rupees Twenty Thousand Four Hundred Thirteen and Paise Thirty Five Only
<b>Total in figure :</b>						<b>434992.95</b>	<b>Rupees Four Lakh Thirty Four Thousand Nine Hundred Ninety Two and Paise Ninety Five Only</b>
<b>Total in Words :</b>							<b>Rupees Four Lakh Thirty Four Thousand Nine Hundred Ninety Two and Paise Ninety Five Only</b>

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 374160.31  
 Earnest Money Rs:- 7500.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Kamand Neri road at RD.0/00 to 6/00. (PDNA -2023). (Sub Head: - Construction of Retaining wall at R.D. 3/895 to 3/905, 4/240 to 4/247.50).

Contract No. :  
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.99	Per cubic metre	522.50	9922.28	Rupees Nine Thousand Nine Hundred Twenty Two and Paise Twenty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	67.38	Per cubic metre	4904.60	330471.95	Rupees Three Lakh Thirty Thousand Four Hundred Seventy One and Paise Ninety Five Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	35.00	Each	284.30	9950.50	Rupees Nine Thousand Nine Hundred Fifty and Paise Fifty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.75	Per cubic metre	1512.10	23815.58	Rupees Twenty Three Thousand Eight Hundred Fifteen and Paise Fifty Eight Only
<b>Total in figure :</b>					<b>374160.31</b>	<b>Rupees Three Lakh Seventy Four Thousand One Hundred Sixty and Paise Thirty One Only</b>
<b>Total in Words :</b>						<b>Rupees Three Lakh Seventy Four Thousand One Hundred Sixty and Paise Thirty One Only</b>

Executive Engineer,  
 Mandi Division No.I,  
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 499317.03  
 Earnest Money Rs:- 10000.00  
 Time:- One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.  
**Name of work :-** Restoration of rain damages on Kamand Neri road at RD 0/00 to 6/00. (PDNA -2023). (Sub Head: - Construction of Breast wall at R.D. 3/630 to 3/645, 3/795 to 3/805).

**Contract No. :**

**Bidder Name :**

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area in ordinary rock not required blasting by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5 meter (one point five) and lead upto 20 (twenty meter) as per technical specification clause 1603.2. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	42.00	Per cubic metre	162.70	6833.40	Rupees Six Thousand Eight Hundred Thirty Three and Paise Forty Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.75	Per cubic metre	522.50	11886.88	Rupees Eleven Thousand Eight Hundred Eighty Six and Paise Eighty Eight Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	96.25	Per cubic metre	4904.60	472067.75	Rupees Four Lakh Seventy Two Thousand Sixty Seven and Paise Seventy Five Only
4	Providing weep hole in brick masonry/ plain reinforced concrete abutment , wing wall, return wall with 100mm-dia.(one hundred-millimetre diameter) PVC pipe-extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	284.30	8529.00	Rupees Eight Thousand Five Hundred Twenty Nine Only
<b>Total in figure :</b>					499317.03	Rupees Four Lakh Ninety Nine Thousand Three Hundred Seventeen and Paise Three Only
<b>Total in Words :</b>						Rupees Four Lakh Ninety Nine Thousand Three Hundred Seventeen and Paise Three Only

Executive Engineer,  
 Mandi Division No. I,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 499317.03  
 Earnest Money Rs:- 10000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Kamand Neri road at RD 0/00 to 6/00. (PDNA -2023). (Sub Head: - Construction of Breast wall at R.D. 5/725 to 5/750).  
 Contract No. :  
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area in ordinary rock not required blasting by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5 meter (one point five) and lead upto 20 (twenty meter) as per technical specification clause 1603.2. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	42.00	Per cubic metre	162.70	6833.40	Rupees Six Thousand Eight Hundred Thirty Three and Paise Forty Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.75	Per cubic metre	522.50	11886.88	Rupees Eleven Thousand Eight Hundred Eighty Six and Paise Eighty Eight Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	96.25	Per cubic metre	4904.60	472067.75	Rupees Four Lakh Seventy Two Thousand Sixty Seven and Paise Seventy Five Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204:3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	284.30	8529.00	Rupees Eight Thousand Five Hundred Twenty Nine Only
<b>Total in figure :</b>					499317.03	Rupees Four Lakh Ninety Nine Thousand Three Hundred Seventeen and Paise Three Only
<b>Total in Words :</b>						Rupees Four Lakh Ninety Nine Thousand Three Hundred Seventeen and Paise Three Only

Executive Engineer,  
 Mandi Division No. I,  
 HP. PWD. at Padhar.


**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 497542.04  
 Earnest Money Rs:- 10000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Shegali Prashar road km. 0/00 to 22/ 510. (PDNA -2023). (Sub Head:- Construction of retaining wall at Rds. 6/630 to 6/642.50).

Contract No. :  
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.50	Per cubic metre	522.50	11755.73	Rupees Eleven Thousand Seven Hundred Fifty Five and Paise Seventy Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	93.38	Per cubic metre	4903.90	457926.18	Rupees Four Lakh Fifty Seven Thousand Nine Hundred Twenty Six and Paise Eighteen Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.00	Each	285.50	10849.00	Rupees Ten Thousand Eight Hundred Forty Nine Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.25	Per cubic metre	1512.10	17011.13	Rupees Seventeen Thousand Eleven and Paise Thirteen Only
<b>Total in figure :</b>					<b>497542.04</b>	<b>Rupees Four Lakh Ninety Seven Thousand Five Hundred Forty Two and Paise Four Only</b>
<b>Total in Words :</b>						<b>Rupees Four Lakh Ninety Seven Thousand Five Hundred Forty Two and Paise Four Only</b>

  
 Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 498654.69  
 Earnest Money Rs:- 10000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Shegali Prashar road km. 0/00 to 22/510. (PDNA -2023). (Sub Head:- Constrction of retaining wall at Rds. 5/520 to 5/538).  
 Contract No. :  
 Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.68	Per cubic metre	522.50	11849.26	Rupees Eleven Thousand Eight Hundred Forty Nine and Paise Twenty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	91.13	Per cubic metre	4903.90	446892.41	Rupees Four Lakh Forty Six Thousand Eight Hundred Ninety Two and Paise Forty One Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	54.00	Each	285.50	15417.00	Rupees Fifteen Thousand Four Hundred Seventeen Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.20	Per cubic metre	1512.10	24496.02	Rupees Twenty Four Thousand Ninety Six and Paise Two
<b>Total in figure :</b>					498654.69	<b>Rupees Four Lakh Ninety Eight Thousand Six Hundred Fifty Four and Paise Sixty Nine Only</b>
<b>Total in Words :</b>						<b>Rupees Four Lakh Ninety Eight Thousand Six Hundred Fifty Four and Paise Sixty Nine Only</b>

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 498654.69  
 Earnest Money Rs:- 10000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhat.

Name of work :- Restoration of rain damages on Shegali Prashar road km. 0/00 to 22/ 510. (PDNA -2023). (Sub Head:- Construction of retaining wall at Rds. 7/330 to 7/348).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.68	Per cubic metre	522.50	11849.26	Rupees Eleven Thousand Eight Hundred Forty Nine and Paise Twenty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	91.13	Per cubic metre	4903.90	446892.41	Rupees Four Lakh Forty Six Thousand Eight Hundred Ninety Two and Paise Forty One Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	54.00	Each	285.50	15417.00	Rupees Fifteen Thousand Four Hundred Seventeen Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.20	Per cubic metre	1512.10	24496.02	Rupees Twenty Four Hundred Ninety Six and Paise Two
<b>Total in figure :</b>					<b>498654.69</b>	<b>Rupees Four Lakh Ninety Eight Thousand Six Hundred Fifty Four and Paise Sixty</b>
<b>Total in Words :</b>					<b>Rupees Four Lakh Ninety Eight Thousand Six Hundred Fifty Four and Paise Sixty Nine Only</b>	

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhat.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 206658.97  
 Earnest Money Rs:- 4100.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD. at Padhar.

Name of work :- Restoration of rain damages on Pakhri Galu Baragaun road km. 0/00 to 5/830. (PDNA -2023). (Sub Head: - Construction of retaining wall at R.D. 4/085 to 4/093).

Contract No.:

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.36	Per cubic metre	522.50	10115.60	Rupees Ten Thousand One Hundred Fifteen and Paise Sixty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.04	Per cubic metre	4674.70	187174.99	Rupees One Lakh Eighty Seven Thousand One Hundred Seventy Four and Paise Ninety Nine Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	Each	274.80	2473.20	Rupees Two Thousand Four Hundred Seventy Three and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.56	Per cubic metre	1512.10	6895.18	Rupees Six Thousand Eight Hundred Ninety Five and Paise Eighteen Only
<b>Total in figure :</b>					<b>206658.97</b>	<b>Rupees Two Lakh Six Thousand Six Hundred Fifty Eight and Paise Seven Only</b>
<b>Total in Words :</b>						<b>Rupees Two Lakh Six Thousand Six Hundred Fifty Eight and Paise Ninety Seven Only</b>

Executive Engineer,  
 Mandi Division No.I,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 499205.07  
 Earnest Money Rs:- 10000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Pakhri Galu Baragaun road km. 0/00 to 5/830. (PDNA -2023). (Sub Head: - Construction of retaining wall at R.D. 1/510 to 1/529.30).  
 Contract No. :  
 Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	46.70	Per cubic metre	522.50	24400.75	Rupees Twenty Four Thousand Four Hundred and Paise Seventy Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	96.60	Per cubic metre	4674.70	451576.02	Rupees Four Lakh Fifty One Thousand Five Hundred Seventy Six and Paise Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	274.80	6595.20	Rupees Six Thousand Five Hundred Ninety Five and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.00	Per cubic metre	1512.10	16633.10	Rupees Sixteen Thousand Six Hundred Thirty Three and Paise Ten Only
<b>Total in figure :</b>					<b>499205.07</b>	<b>Rupees Four Lakh Ninety Nine Thousand Two Hundred Five and Paise Seven Only</b>

**Total in Words :** Rupees Four Lakh Ninety Nine Thousand Two Hundred Five and Paise Seven Only

  
 Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 356280.55  
 Earnest Money Rs:- 7100.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP,PWD. at Padhar.

Name of work : Restoration of rain damages on Pakhri Galu Baragaun road km. 0/00 to 5/830. (PDNA -2023). (Sub Head: - Construction of Retaining wall at RDs 3/565 to 3/575).

Contract No:-

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.90	Per cubic metre	522.50	19280.25	Rupees Nineteen Thousand Two Hundred Eighty and Paise Twenty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.74	Per cubic metre	4738.40	316240.82	Rupees Three Lakh Sixteen Thousand Two Hundred Forty and Paise Eighty Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	276.80	4428.80	Rupees Four Thousand Four Hundred Twenty Eight and Paise Eighty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage-of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.80	Per cubic metre	1512.10	16330.68	Rupees Sixteen Thousand Three Hundred Thirty and Paise Sixty Eight Only
<b>Total in figure :</b>					<b>356280.55</b>	<b>Rupees Three Lakh Fifty Six Thousand Two Hundred Eighty and Paise Fifty Five Only</b>
<b>Total in Words :</b>					<b>Rupees Three Lakh Fifty Six Thousand Two Hundred Eighty and Paise Fifty Five Only</b>	

Executive Engineer,  
 Mandi Division No. I,  
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 261741.99  
 Earnest Money Rs:- 5200.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Pakhri Galu Baragaun road km. 0/00 to 5/830. (PDNA -2023). (Sub Head: - Construction of Retaining wall at RDs 5/750 to 5/760).

Contract No:-

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.20	Per cubic metre	522.50	12644.50	Rupees Twelve Thousand Six Hundred Forty Four and Paise Fifty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	50.05	Per cubic metre	4738.40	237156.92	Rupees Two Lakh Thirty Seven Thousand One Hundred Fifty Six and Paise Ninety Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	276.80	3321.60	Rupees Three Thousand Three Hundred Twenty One and Paise Sixty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage-of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.70	Per cubic metre	1512.10	8618.97	Rupees Eight Thousand Six Hundred Eighteen and Paise Ninety Seven Only
<b>Total in figure :</b>					<b>261741.99</b>	<b>Rupees Two Lakh Sixty One Thousand Seven Hundred Forty One and Paise Ninety Nine Only</b>
<b>Total in Words :</b>					<b>Rupees Two Lakh Sixty One Thousand Seven Hundred Forty One and Paise Ninety Nine Only</b>	

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 257339.81  
 Earnest Money Rs:- 5100.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP. PWD. at Padhar.

Name of work :- Restoration of rain damages on Sahal Garlog road km. 0/00 to 7/530. (PDNA -2023). (Sub Head:- Construction of Breast wall at R.D. 1/552 to 1/560).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.36	Per cubic metre	491.80	6570.45	Rupees Six Thousand Five Hundred Seventy and Paise Forty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	53.39	Per cubic metre	4635.80	247505.36	Rupees Two Lakh Forty Seven Thousand Five Hundred Five and Paise Thirty Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	272.00	3264.00	Rupees Three Thousand Two Hundred Sixty Four Only
<b>Total in figure :</b>					257339.81	Rupees Two Lakh Fifty Seven Thousand Three Hundred Thirty Nine and Paise Eighty One Only
<b>Total in Words :</b>					Rupees Two Lakh Fifty Seven Thousand Three Hundred Thirty Nine and Paise Eighty One Only	

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.