

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
H.P.W. (B) (3) TR-NIT-2025-26- 23986-2/18 Dated:- 10-03-2026

To

✓
The Executive Engineer (R Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla 2 the 03 01 2024 and PWD-B-A0(3)/2/2025-300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhama
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Dist. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhama
Ph. 0177-2790534

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhama on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **19.03.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **18.03.2026 up to 5.00 PM** and the application for issue of tender form shall be received on **17.03.2026 up to 4:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhama must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on DGBR to Grawon road Km. 0/00 to 1/785 (SH: Protection works, R/Wall at Km. 0/045 to 0/057 & 0/105 to 0/115)PCC	479996/-	9600/-	One month	Rs.350/-
2	R/R damages on DGBR to Grawon road Km. 0/00 to 1/785 (SH: Protection works, R/Wall at Km. 0/240 to 0/247 & 0/590 to 0/607) PCC.	489538/-	9800/-	One month	Rs.350/-
3	R/R damages on Kadharghat to Domehar road Km. 0/00 to 5/00 (SH: Protection works, R/Wall at Km. 2/405 to 2/414 & 2/420 to 2/428)PCC.	424360/-	8500/-	One Month	Rs.350/-
4	R/R damages on Bag to Kayalu road Km. 0/00 to 10/500 (SH: C/O R/wall at Rds. 7/805 to 7/820).	456207/-	9100/-	One Month	Rs.350/-
5	BSP/2024/65 C/o link road Himri Reog Mohal (BASP) (SH: R/Wall at Rd. 1/405 to 1/415) (Under BASP).	228045/-	4600/-	One month	Rs.350/-
6	R/R damages on Karyali to Shara Nallah road Km. 0/00 to 6/00 (SH: Protection works R/Wall at Km. 5/042 to 5/055). (PCC).	499080/-	10000/-	One Month	Rs.350/-
7	BSP/ 2023/252 C/O R/Wall in link road Malgi pul to Dharogra Mohal (BASP) (SH: C/O R/Wall at Rd. 0/375 to 0/385 & Rd. 7/950 to 7/955).	293688/-	5900/-	One month	Rs.350/-
8	C/O link road Himri Reog Mohal (BASP) (SH: C/O B/Wall at Rd. 0/550 to 0/570) (Wire Crate).	499041/-	10000/-	One Month	Rs.350/-

9	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: P/L Kharanja stone soling in various Rds. 0/00 to 12/375 for crest correction of road).	497584/-	10000/-	One month	Rs.350/-
10	R/R damages on Shakoh to Hanuman Mandir road Km. 0/00 to 1/250 (SH: C/O R-Wall between Km. 1/228 to 1/241.45).	499352/-	10000/-	One month	Rs.350/-
11	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O R-Wall between Km. 8/045 to 8/060).	418128/-	10000/-	One month	Rs.350/-
12	A/R & M/O Rest House at Taradevi (SH: Providing Furnishing items in H.P.P.W.D. rest house).	498030/-	10000/-	One month	Rs.350/-
13	S/R to Distt. Court Complex Shimla (SH: painting, Distempering in CBI Court & Miscellenous work in Gents & Female in Block-A).	494762/-	10000/-	One month	Rs.350/-
14	R/R damages on Phayal Rampuri via Matholi road Km. 0/00 to 5/200 (SH: C/O R-Wall at Rd. 0/975 to 0/985).	234260/-	4700/-	One month	Rs.350/-
15	R/R damages on Badamin to Basantpur road Km. 0/00 to 7/000 (SH: C/O R-Wall at Rds. 5/975 to 5/980).	478546 /-	10000/-	One Month	Rs.350/-
16	R/R damages on Badamin to Basantpur road Km. 0/00 to 7/000 (SH: C/O R-Wall at Rds. 0/256 to 0/260).	499224 /-	10000/-	One Month	Rs.350/-
17	R/R damages on Bag to Kangri road Km. 0/00 to 7/250 (SH: C/O R-Wall at Rd. 0/645 to 0/657).	343849/-	6900/-	One Month	Rs.350/-
18	R/R damages on Slapper Tatapani Suni Luhri road Km. 72/000 to 86/000 (SH: Hiring of JCB for removal of slips on Rds. 81/960 to 82/015).	499907/-	10000/-	One month	Rs.350/-
19	R/R damages on Badamin to Basantpur road Km. 0/00 to 7/000 (SH: C/O R-Wall at Rds. 0/260 to 0/263).	376575/-	7600/-	One Month	Rs.350/-
20	R/R damages on Hari Devi Seri road Km. 0/00 to 3/600 (SH: C/O R/Wall at Rd. 0/780 to 0/792).	268492/-	5000/-	One month	Rs.350/-
21	R/R damages on Banuti Dayla road Km. 0/00 to 1/00 (SH: C/O wire crate wall at Rd. 0/985 to 1/00) Job No.II.	499136/-	10000/-	One month	Rs.350/-
22	R/R damages on Banuti Pahal road via Nehwat Km. 0/00 to 17/105 (SH: Correction layer providing and laying stone soling grade-III in various Rds.) Job No.II.	491639/-	10000/-	One month	Rs.350/-
23	R/R damages on Banuti Pahal road via Nehwat Km. 0/00 to 17/105 (SH: Correction layer providing and laying stone soling grade-III in various Rds.) Job No.I.	491639/-	10000/-	One month	Rs.350/-
24	A/R & M/O Sangti Neri road Km. 0/00 to 6/645 (SH: C/O V-shape drain in Km. 0/200 to 1/200).	442000 /-	9000/-	One Month	Rs.350/-
25	C/O link road from Kiaty Gaushala to Mashobra in Km. 0/00 to 1/760 (SH: C/O R-wall at Rd. 0/244 to 0/255.50).	485645/-	10000/-	One Month	Rs. 350/-
26	A/R & M/O Type -II Quarter at Power house Totu (SH: P/L tiles, Painting & Distempering etc.).	403151/-	8000/-	One month	Rs.350/-
27	R/R damages on Didoghatti Karechi road Km. 0/00 to 8/825 (SH: C/O B-Wall at Rd.3/995 to 4/030).	445733/-	9000/-	One month	Rs.350/-
28	R/R damages on link road from Petrol Pump Hiranagar to village Jablog Km. 0/00 to 0/760 (SH: C/O B-Wall at Rd.0/738 to 0/760 & Edge wall at Rd. 0/725 to 0/760).	430252/-	9000/-	One month	Rs.350/-
29	R/R damages on Banuti Pahal road via Nehwat in Km. 0/00 to 17/105 (SH: C/O B-Wall at Rd.4/480 to 4/515).	440388/-	9000/-	One month	Rs.350/-
30	R/R damages on Hiranagar Dhamoon road Km. 0/00 to 8/00 (SH: C/O R-Wall at Rd.6/680 to 6/690).	390509/-	8000/-	One month	Rs.350/-
31	R/R damages on various roads under Totu sub division (SH: Supplying & Stacking VI pot seal bag cold mix).	297600/-	6000/-	One month	Rs.350/-
32	R/R damages on Devnagar Moolbari road Km. 0/00 to 1/200 (SH: P/L WBM Grade -III for correction in various Rds.).	267430/-	5000/-	One month	Rs.350/-
33	R/R damages on Badheri section under Jutogh sub division (SH: Hiring of JCB for removal of snow/slips).	197100/-	4000/-	One month	Rs.350/-

one month
Rs.350/-

34	C/O Ambulance road to Uparli Fathachi Km. 0/00 to 0/750 (SH: C/O R/Wall at Rd. 0/500 to 0/504 & 0/098 to 0/107).	409576/-	8200/-	One Month	Rs.350/-
35	R/R damages on Hiranagar Sharog road Km. 0/00 to 5/000 (SH: C/O R-Wall at Rd. 0/681 to 0/690).	485919/-	10000/-	One month	Rs.350/-
36	R/R damages on Didoghatti Karechi road Km. 0/00 to 12/00 (SH: C/O R/Wall at Rd. 3/986 to 3/993).	198394/-	4000/-	One month	Rs.350/-
37	C/O link road from Pahal to Ghat in Km. 0/00 to 2/00 (SH: Formation Cutting in Km. 0/855 to 1/125).	468111/-	9000/-	One month	Rs.350/-
38	A/R & M/O Ghanahatti Bhajol road Km. 0/00 to 14/000 (SH: C/O Improvement of sharp curve in various Rds. 0/000 to 1/225).	479891/-	10000/-	One month	Rs.350/-
39	R/R damages on Shimla Nalagarh road Km. 7/00 to 22/00 (SH: C/O R-Wall at Rd. 14/150 to 14/162).	324881/-	6000/-	One month	Rs.350/-
40	R/R damages on Ghanahatti Parech road Km. 0/00 to 0/800 (SH: C/O R-Wall at Rd. 1/725 to 1/742).	483149/-	10000/-	One month	Rs.350/-
41	R/R damages on link road to village Panti in Km. 0/00 to 0/660 (SH: C/O R/Wall in B/W Km. 0/340 to 0/352).	340771/-	7000/-	One month	Rs.350/-
42	R/R damages on Nehra Bhukoo road Km. 0/00 to 8/00 (SH: C/O R-Wall at Rds. 6/910 to 6/920).	335966/-	7000/-	One month	Rs.350/-
43	R/R damages on Thachi Seri Shalli road Km. 0/00 to 3/285 (SH: C/O B-Wall at Rds. 0/380 to 0/380.50) from road level to Govt. Primary School Thachi building).	464367/-	9000/-	One month	Rs.350/-
44	R/R damages on Bhajyar Devidhar road Km. 0/00 to 2/200 (SH: C/O R-Wall at Rds. 1/289 to 1/299.50).	498519/-	10000/-	One month	Rs.350/-
45	R/R damages on Gharog Nalta road Km. 0/00 to 7/00 (SH: C/O R-Wall at Rds. 4/010 to 4/050).	488184/-	10000/-	One month	Rs.350/-
46	A/R & M/O Judicial Academy at Ghandal Shimla (SH: P/F Ralling, providing and applying putty and painting in Admin Block etc.).	485895/-	10000/-	One month	Rs.350/-
47	Routine Maintenance of Playground of Govt. Sr. Sec. School Dargi Distt. Shimla (SH: C/O R/Wall towards valley side protect the playground of GSSS Dargi in Km. 0/012 to 0/017.60) Deposit work.	495991/-	10000/-	One month	Rs.350/-
48	Routine Maintenance of Playground of Govt. Sr. Sec. School Dargi Distt. Shimla (SH: C/O R/Wall towards valley side protect the playground of GSSS Dargi in Km. 0/000 to 0/011.50) Deposit work.	496791/-	10000/-	One month	Rs.350/-
49	A/R & M/O Judicial Academy at Ghandal Shimla (SH: P/F of Cupboards in Liabrary of Administrative Block & Painting work etc.) Job No. 1.	497917/-	10000/-	One month	Rs.350/-
50	A/R & M/O Judicial Academy at Ghandal Shimla (SH: P/F of Cupboards in Liabrary of Administrative Block & Painting work etc.) Job No. 2.	499387/-	10000/-	One month	Rs.350/-
51	C/O Veterinary Hospital at Dargi, Distt. Shimla (SH: C/O additional room at first floor & providing & fixing of steel stairs from ground floor to first floor along with repair of rooms at ground floor of veterinary hospital building at Dargi)	371764/-	7000/-	One month	Rs.350/-
52	C/O link road Palkari Makri Km. 0/00 to 1/600 (SH: C/o V-Shape drain in Km. 0/000 to 0/450 & 0/550 to 0/800).	448333/-	9000/-	One month	Rs.350/-
53	R/R damages on various roads of Sunni Sub Division, Shimla (SH: Hiring of JCB for removal of slips on various Rds. of various roads).	473970/-	9500/-	One month	Rs.350/-
54	C/O link road from Chebri to Piplughat Km. 0/00 to 3/870 (SH: C/O R/Wall (Wire crate) at Rd. 3/580 to 3/595) Under MMGSY.	477016/-	10000/-	One month	Rs.350/-
55	R/R damages on Shoghi Salana road Km. 0/000 to 8/000 (SH: Hiring of JCB for removal of slips on various Rds. of road).	355496/-	7100/-	One month	Rs.350/-
56	R/R damages on Taradevi Ghamber road, Km. 0/000 to 11/520 (SH: C/O R/Wall in between Km. 9/300 to 9/312.50).	494218/-	10000/-	One month	Rs.350/-
57	R/R damages on (i) Ghanahatti Nehra Shaltu Dargot road Km. 0/00 to 5/450 (ii) Ghanahatti Nehra Bhukoo road Km. 0-/00 to 8/00 (SH: C/O unlined drain, Maintenance of hume pipe culvert, earthen shoulder etc.).	427675/-	8600/-	One month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No, GST No, copy of enlistment renewed letter and EPF certificate alongwith FIDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shigala Rural Division
H.P.P.W.D. Dhani

Certificate

Certified that the tenders called vide this notice inviting tender for 57 (Fifty seven) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shigala Rural Division
H.P.P.W.D. Dhani.

Schedule Of Quantity						Estimated Cost:- 4,79,996.00	
Name of Work :- R/R Damages on DGBR to Grawon Road km 0/00 to 1/785 (SH:- Protection works , R/wall at km 0/045 to 0/057 & 0/105 to 0/115 (PCC)						Earnest Money:- 9,600.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	36.74	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	7311
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	5.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1939
3	Providing concrete for plain/ reinforced concrete 1:4:8 in (20mm crushed stone agg) In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203	91.84	Cum	4900.00	Rupees Four Thousand Nine Hundred Only	Per cubic metre	450016
4	Providing weap holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7	35.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	6650
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (1) Granular material	14.08	Cum	1000.00	Rupees One Thousand Only	Per cubic metre	14080
	Total Rs.						479996
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharsi

Schedule Of Quantity						Estimated Cost:- 4,89,538.00	
Name of Work :- R/R Damages on DGBR to Grawon Road km 0/00 to 1/785 (SH:- Protection works , R/wall at km 0/240 to 0/247 & 0/590 to 0/607 (PCC)						Earnest Money:- 9,800.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	38.07	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	7576
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	5.63	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2007
3	Providing concrete for plain/ reinforced concrete 1:4:8 in (20mm crushed stone agg) In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203	93.55	Cum	4900.00	Rupees Four Thousand Nine Hundred Only	Per cubic metre	458395
4	Providing weap holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7	38.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	7220
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (1) Granular material	14.34	Cum	1000.00	Rupees One Thousand Only	Per cubic metre	14340
Total Rs.							489538
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharam

Schedule Of Quantity						Estimated Cost:- 4,24,360.00	
Name of Work :- R/R damages on Kadharghat to Domehar Road km 0/00 to 5/00 (SH:- Protection works R/wall at km 2/405 to 2/414 & 2/420 to 2/428 (PCC)						Earnest Money:- 8,500.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	36.49	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	7262
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable materials	4.82	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1718
3	Providing concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203.	81.20	Cum	4900.00	Rupees Four Thousand Nine Hundred Only	Per cubic metre	397880
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	35.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	6650
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. granular material	10.85	Cum	1000.00	Rupees One Thousand Only	Per cubic metre	10850
Total Rs.							424360
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharni.

Schedule Of Quantity						Estimated Cost:- 4,56,207.00	
Name of Work :- R/D Bag to Kayalu Road km 0/00 to 10/500 (SH:- C/O R/wall at Rd 7/805 to 7/820)						Earnest Money:- 9,100.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	40.95	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	8149
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	5.10	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1818
3	Providing concrete for plain/ reinforced concrete 1:4:8 in (20mm crushed stone agg) In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203	87.60	Cum	4900.00	Rupees Four Thousand Nine Hundred Only	Per cubic metre	429240
4	Providing weap holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7	35.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	6650
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (1) Granular material	10.35	Cum	1000.00	Rupees One Thousand Only	Per cubic metre	10350
Total Rs.							456207
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhara

Schedule Of Quantity						Estimated Cost:- 2,28,045.00	
Name of Work :- BSP / 2024/65 C/O Link road Himri Reog Mohal (BASP) (SH:- R/wall at Rd 1/405 to 1/415) (Under BASP)						Earnest Money:- 4,600.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	14.40	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	2866
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	2.55	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	909
3	Providing concrete for plain/ reinforced concrete 1:4:8 in (20mm crushed stone egg) In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203	42.60	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	213000
4	Providing weap holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7	23.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	4370
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (1) Granular material	6.90	Cum	1000.00	Rupees One Thousand Only	Per cubic metre	6900
Total Rs.							228045
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharm.

Order Ministry
 18/1981
 Schedule of Quantity
 Name of Work :- Restoration of Rain Damages on Karyali to Shara Nallah road km 0/00 to 6/00 (SH: Protection
 Location of Work :-
 Works, R/walls at km 05/042to 05/055 (PCC)
 Estimated Cost:- 499080.00 Only.
 Earnest Money: 10000.00 Only.
 Time:- One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure 5	In word 6		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with the lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1	24.05	per cum	₹ 199.00	Rupees One Hundred Ninety Nine Only	per cum	4786.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 I/c setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50 metre, dressing of sides and bottom and back filling in tranches with excavated suitable material.	5.20	per cum	₹ 356.50	Rupees Three Hundred Fifty Six and Fifty Paise	per cum	1854.00
3	Providing concrete for plain/reinforced concrete 1:4:8 (in 20 mm aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803. 1202 & 1203.	95.03	per cum	₹ 5,000.00	Rupees Five Thousand Only	per cum	475150.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(V) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	13.00	Nos.	₹ 190.00	Rupees One Hundred Ninety Only	Nos.	2470.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material.	14.82	per cum	₹ 1,000.00	Rupees One Thousand Only	per cum	14820.00
Amount procured by the contractor in percentage		Rs.		Total			499080.00
Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted							

Executive Engineer
 Shimla Rural Division
 HPPWD Dhami

Schedule Of Quantity

Name of Work :- BSP/ 2023/252 C/O R/wall in link road Malgi Pul to Dharogra Mohal (BASP) (SH:- C/O R/wall at Rd 0/375 to 0/385 & Rd 7/950 to 7/955)

Estimated Cost:- 2,93,688.00
Earnest Money:- 5,900.00
Time:- One Months.

No	Description of Work	No. of Qty.		Rate In figures	In words	Unit	Amount
		3	4				
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	16.50	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	3284
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and ahead of 50 mm dressing of sides and bottom and backfilling in trenches with excavated suitable material	3.35	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1194
	Providing concrete plain/ reinforced concrete 1:4:8 (20mm crushed stone agg) in open foundations complete as per drawings and technical specification clause 802, 803, 1202 and 1203.	55.00	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	275000
	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of 1(N) 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204,3,7	24.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	4560
	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. Granular material	9.65	Cum	1000.00	Rupees One Thousand Only	Per cubic metre	9650
Total Rs.							293688
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							


Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharm

Schedule Of Quantity

Estimated Cost:- 4,99,041.00

Earnest Money:- 10,000.00

Time:- One Months.

Name Of Work :- Construction of link road Himri Reog Mohal (BASP) (SH:- C/O
Breast wall at Rd 0/550 to 0/570) (Wire Crate)

S.No	Description of Work	No. of Qty.		Rate		Unit		Amount
		3	4	In figures 5	In words 6	7		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	102.40	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per Cubic metre	20379	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	65.00	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	23173	
3	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS 280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge	120.50	Cum	3780.00	Rupees Three Thousand Seven Hundred Eighty Only	Per Cubic metre	455490	
Total Rs.							499041	
Amount Quoted by the Contractor in Percentage								
Note :- All the material will procured by the contractor him self								

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharti.

Schedule Of Quantity

**Work:- R/R damages on Shakoh to Hanuman Mandir Road road Km 0/00 to 1/250. (SH: C/O
between Km 1/228 to Km 1/241.45)**

Estimated Cost:- 4,99,352.00
Earnest Money:- 10000.00

Time:- One Month.

Description of Work	No. of Qty.	Rate		Unit	Amount
		In figures	In words		
2 work in excavation in hilly area by manual/mechanical means i/c cutting and trimming and side slope structures as per drawing and technical specification clause 305.1 and disposal of surplus excavated upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated ble materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed er MORD Specification and as per the direction of Engineer-In- Charge	3				
	4	233.40	Rupees Two hundred thirty three and Paise fourty only	Per cubic metre	4834.00
3 work in excavation for structures as per drawing and technical specification clause 305.1 including ing out construction of shoring and bracing, removal of stumps and other deleterious materials and osal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated ble materials as per MORD Specification directed by Engineer-In- Charge	4	356.50	Rupees Three hundred fifty six and paise fifty only	Per cubic metre	14097.00
	5	4800.00	Rupees Four thousand six hundred only	Per cubic metre	453857.00
6 filling behind abutment, wing wall and retaining wall of granular material complete as per ings and technical specifications MORD clause 1204.3.8 including carriage of materials within all lifts and as per the direction of Engineer-In-Charge.	6	841.80	Rupees Eight hundred forty one and eighty Paise only	Per cubic metre	16304.00
	7	180.00	Rupees One hundred eighty only	Per running metre	10260.00
7 ding and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical cations MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as direction of Engineer-In-Charge.	8				
Amount Quoted by the Concrator in percentage					
ons:-(1) All the materials will be procured by the contractor himself and bills will be ed.					
Total:-					499352.00

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharam

Schedule of Quantity

NAME OF WORK :- ~~RD~~ R/D on Shogi Mehli road KM 0/000 to 12/375.
(SH : C/O R/Wall at RD 8/045 to 8/060).

Estimated Cost: 4,18,128 /- only

Earnest Money: 10000 /-only.

Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer -in- Charge .	40.20	Per Cum	233.40	Two hundred thirty three rupee forty Paísa only	Per Cum	9383.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction -in- Charge.	79.95	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	383760.00
3	Back filling behind Abutment , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	20.70	Per Cum	841.80	Eight Hundred forty one rupees eighty paísa only	Per Cum	17425.00
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	42.00	Per Rmt	180.00	One hundred eighty rupees only	Per Rmt	7560.00
				Total			418128.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer
Shimla Rural Division
HP.PWD, Dhaní



Schedule Of Quantity

M/O PWD Rest house house at TaraDevi (SH:- Providing Furnishing Items in H.P.P.W.D. rest

Estimated Cost:- 498030.00
Earnest Money:- 10000.00
Time:- One Month.

Sl. No.	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Providing & placing Quilt in superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	3	Nos	4200.00	Rupees Four Thousand & Two Hundred only.	Nos	176400.00
2	Providing & placing Pillow in superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	48.00	Nos	650.00	Rupees Six hundred & fifty only.	Nos	31200.00
3	Providing & placing Pillow Cover in superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	96.00	Nos	180.00	Rupees One hundred & eighty only.	Nos	17280.00
4	Providing & placing White Bed Sheed in superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	48.00	Nos	2800.00	Rupees Two Thousand & eight hundred	Nos	134400.00
5	Providing & placing Quilt Cover single in superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	36	Nos	2800.00	Rupees Two Thousand & eight hundred	Nos	100800.00
6	Providing & placing Bucket in superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	15	Nos	550.00	Rupees five hundred & fifty only.	Nos	8250.00
	Providing & placing Mug superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	15	Nos	80.00	Rupees eighty only.	Nos	1200.00
	Providing & placing Big Towel superior quality approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	30	Nos	950.00	Rupees Nine hundred & fifty only.	Nos	28500.00
	Total						498030.00

Amount Quated by the Contractor in Percentage.

Note:- All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami

Schedule Of Quantity

Estimated Cost - 2,94,762.00

Name Of Work - Special Repair to District Court Complex, Shimla (S/R) Painting - Discrepancy in Earnest Money - 10,000.00
 CRI Court & Miscellaneous work at Courts & Courts in Block-A)

Date - One Month

Sl. No.	Description of Work	No of Qty	Rate in figures	In words	Unit	Amount
1	Removal of old paint work on wall surface by using high pressure water jetting and removal of old paint work by using scraper and brush.	173.43	250/-	One hundred and seventy three and 43/100	Sq. metre	43357.50
2	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	373.43	50/-	Three hundred and seventy three and 43/100	Sq. metre	18671.50
3	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	373.43	50/-	Three hundred and seventy three and 43/100	Sq. metre	18671.50
4	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	126.04	40.00	One hundred and twenty six and 4/100	Sq. metre	5041.60
5	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	5.95	1150.00	Five and 95/100	Cubic metre	6837.50
6	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	14.66	40.00	Fourteen and 66/100	Sq. metre	586.40
7	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	5.13	550.00	Five and 13/100	Cubic metre	2821.50
8	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	20.52	1150.00	Twenty and 52/100	Sq. metre	23598.00
9	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	14.64	1170.00	Fourteen and 64/100	Sq. metre	17129.00
10	Application of 1st quality white emulsion paint on wall surface in 2 coats. The coats should be applied in alternate directions. The surface should be prepared by sanding and priming.	4.00	2200.00	Four and 00/100	Sq. metre	8800.00

12	Providing and fixing 250mm dia CP brass angle cock of approved quality with fittings complete including carriage of materials within all leads and lifts	2 00	No	250 00	Rupees Two Hundred Fifty Only	Each	1250
13	Providing and fixing 250mm dia CP brass angle cock of approved quality with fittings complete including carriage of materials within all leads and lifts	2 00	No	550 00	Rupees Five Hundred Fifty Only	Each	1100
14	Providing and fixing 250mm dia CP brass angle cock of approved quality with fittings complete including carriage of materials within all leads and lifts	2 00	No	550 00	Rupees Five Hundred Fifty Only	Each	1100
15	Providing and fixing 100mm dia chromium plated galv of approved quality for floor galv. complete including carriage of materials within all leads and lifts	12 00	No	105 00	Rupees One Hundred Five Only	Each	1260
16	Providing and fixing 100mm dia chromium plated galv of approved quality for floor galv. complete including carriage of materials within all leads and lifts	2 00	No	6250 00	Rupees Six Thousand Two Hundred Fifty Only	Each	12500
17	Providing and fixing 100mm dia chromium plated galv of approved quality for floor galv. complete including carriage of materials within all leads and lifts	2 00	No	1360 00	Rupees One Thousand Three Hundred Only	Each	2720
18	Providing and fixing 100mm dia chromium plated galv of approved quality for floor galv. complete including carriage of materials within all leads and lifts	2 00	No	150 00	Rupees One Hundred Fifty Only	Each	300
19	Providing and fixing 15mm dia CP brass angle cock of approved quality with fittings complete including carriage of materials in all leads and lifts	2 00	No	950 00	Rupees Nine Hundred Fifty Only	Each	1900
20	Providing and fixing 15mm dia CP brass bio cock of approved quality including carriage of materials within all leads and lifts	3 00	No	950 00	Rupees Nine Hundred Fifty Only	Each	2850
21	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work including cutting chases and making good the walls etc. 15mm nominal dia	25 00	Rmt	350 00	Rupees Three Hundred Fifty Only	Per running metre	8750
22	Providing and fixing 110mm high pressure PVC Finolex (Type-B) spigot and socket waste and ventilating pipes ISI marked including fitting with approved adhesive etc complete including carriage of materials within all leads and lifts	19 00	Rmt	650 00	Rupees Six Hundred Fifty Only	Per running metre	12350
23	Providing and fixing 75mm high pressure PVC Finolex (Type-B) spigot and socket waste and ventilating pipes ISI marked including fitting with approved adhesive etc complete including carriage of materials within all leads and lifts	20 00	Rmt	450 00	Rupees Four Hundred Fifty Only	Per running metre	9000

29	Providing and fixing 100mm thick G.I. pipes complete with 10 fittings and tanks for piping and making ready for use including carriage of materials within all leads and lifts.	2.00	No	20.00	Rupees Twenty Only		
30	Providing and fixing 100mm thick G.I. pipes complete with 10 fittings and tanks for piping and making ready for use including carriage of materials within all leads and lifts.	4.00	No	40.00	Rupees Forty Only		
31	Providing and fixing 100mm thick G.I. pipes complete with 10 fittings and tanks for piping and making ready for use including carriage of materials within all leads and lifts.	26.00	Rmt	150.00	Rupees Three Hundred Fifty Only	Per running metre	3750
32	Providing and fixing 100mm thick G.I. pipes complete with 10 fittings and tanks for piping and making ready for use including carriage of materials within all leads and lifts.	15.51	Sqm	240.00	Rupees One Thousand Fifty Only	Per square metre	15500
33	Providing and fixing 100mm thick G.I. pipes complete with 10 fittings and tanks for piping and making ready for use including carriage of materials within all leads and lifts.	34.52	Sqm	440.00	Rupees One Thousand Four Hundred Fifty Only	Per square metre	30000
34	Providing and fixing 100mm thick Commercial Board shutters for cupboard / ward robe including fixing with necessary hinges with screws etc complete including carriage of materials within all leads and lifts.	15.51	Sqm	1600.00	Rupees One Thousand Five Hundred Fifty Only	Per square metre	24000
35	Providing and fixing 100mm thick Commercial Board shutters for cupboard / ward robe including fixing with necessary hinges with screws etc complete including carriage of materials within all leads and lifts.	26.05	Sqm	890.00	Rupees Eight Hundred Ninety Only	Per square metre	23185
36	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters including fixing with necessary screws etc complete including carriage of materials within all leads and lifts.	28.00	No	55.00	Rupees Fifty Five Only	Each	1540
37	Providing and fixing bright finished brass handles with screws etc complete including carriage of materials within all leads and lifts (1) 100mm	23.00	No	180.00	Rupees One Hundred Eighty Only	Each	4140
38	Providing and fixing square edges cover fillets (beading) 19mmx6mm section dc mitring at junctions with wood screws and nails complete including carriage of materials within all leads and lifts. 1st class Indian teak wood	37.60	Rmt	40.00	Rupees Forty Only	Per running metre	1504
39	Providing and fixing bright finished hydraulic door closer of Godrej make or equivalent with screws etc complete including carriage of materials in all leads and lifts	6.00	No	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Each	13500

2/20/20

Schedule Of Quantity						Estimated Cost:- 2,34,260.00	
Name Of Work :- Restoration of Rain Damages on Phayal Rampuri Via Matholi Road km 0/00 to 5/200 (SH:- C/O Retaining wall at Rd. 0/975 to 0/985)						Earnest Money:- 4,700.00	
						Time:- One Month.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1503 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	9.80	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	2287
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	11.80	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	4207
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	44.80	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	215040
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	23.00	Rml	180.00	Rupees One Hundred Eighty Only	Per running metre	4140
5	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.P.W.D., specifications of 1990 volume-I including carriage of material within all leads and lifts	10.20	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	8586
Total Rs.							234260
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,P.W.D. Dhamsi

Schedule of Quantity

ne of work: RR Damages on Badmain to Basantpur road km 0/000 to 7/000.
: C/O R/Wall at RD 5/975 to 5/980).

Estimated Cost: 4,78,546 /- only

Earnest Money: 10000 /-only.

Time: - One month

No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
				5	6		
7	8						
	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other delcterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer -in- Charge .	20.20	Per Cum	356.50	Three hundred fifty six rupees fifty paisa only	Per Cum	7201.00
	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803.1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction -in- Charge.	93.28	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	447750.00
	Back filling behind Abutment , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	21.40	Per Cum	841.80	Eight Hundred forty one rupees eighty paisa only	Per Cum	18015.00
	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	31.00	Per Rmt	180.00	One hundred eighty rupees only	Per Rmt	5580.00
					Total		478546.00
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer
Shimla Rural Division
HP.PWD, Dhan

Schedule of Quantity

Name of work: RR Damages on Badmain to Basantpur road km 0/000 to 7/000.


SH : C/O R/Wall at RD 0/256 to 0/260).

Estimated Cost: 4,99,924 /- only

Earnest Money: 10000 /-only.

Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure 5	In word 6		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer -in- Charge .	23.32	Per Cum	233.40	Two hundred thirty three rupee forty Paisa only	Per Cum	5443.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction -in- Charge.	97.33	Per Cum	4800.00	Forty eight Hundred rupces only	Per Cum	467184.00
3	Back filling behind Abutment , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	26.44	Per Cum	841.80	Eight Hundred forty one rupees eighty paisa only	Per Cum	22257.00
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	28.00	Per Rmt	180.00	One hundred eighty rupees only	Per Rmt	5040.00
	Amount Quoted by the Contractor in Percentage				Total		499924.00
	Note :- All the material will procured by the contractor him self						


 Executive Engineer
 Shimla Rural Division
 HP.PWD, Dharmi

Schedule Of Quantity						Estimated Cost:- 3,43,849.00	
Name of Work :- R/R damages on Bag Kangri Road km 0/000 to 7/250 (SH:- C/O R/wall at RD 0/645 to 0/657)						Earnest Money:-7000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseing and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	7.56	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1765
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	28.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	10139
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	65.04	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	312192
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	29.00	No	190.00	Rupees One Hundred Ninety Only	Each	5510
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts	16.92	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	14243
Total Rs.							343849
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharti

Schedule Of Quantity

**NAME OF WORK :- RR Damages on Slapper tatapani Suni Luhri road Km 72/000 to 86/000,
(SI:-Hiring of JCB for removal of slips on RD 81/960 to 82/015).**

Estimated cost: 4,99,907 /-
Earnest Money: 10000 /-
Time : One Month

S.No	Description of Work	No.of Qty.	Unit	Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5	4097.60	Cum	122.00	One Hundred Twenty Two Rupees Only	Per Cubic Meter	499907.00
						Total	499907.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor himself							

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Schedule of Quantity

ame of work: RR Damages on Badmain to Basantpur road km 0/000 to 7/000.

SH : C O R/Wall at RD 0/260 to 2/63 (2/2/3)

Estimated Cost: 3,76,575 /- only

Earnest Money: 7600 /- only.

Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2			5	6	7	8
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer -in- Charge .	17.49	Per Cum	233.40	Two hundred thirty three rupee forty Paise only	Per Cum	4082.00
2	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803.1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction -in- Charge.	73.15	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	351120.00
3	Back filling behind Abutment , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	19.83	Per Cum	841.80	Eight Hundred forty one rupees eighty paise only	Per Cum	16693.00
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	26.00	Per Rmt	180.00	One hundred eighty rupees only	Per Rmt	4680.00
				Total			376575.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer
Shimla Rural Division
HP.PWD. Dharami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hari Devi Serl Road Km. 0/00 to 3/600 (Sh:- Construction of R-wall at R.D. 0/780 to 0/792)

Estimated Cost - Rs 268492/- only
 Earnest Money - Rs 5000/- only
 Time - One Month

Sl. No.	Sub head and Items of work	Qty.		Rate figures	Unit	Amount
		3	4			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.44	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	3137.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	16.20	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	5775.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	54.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	248400.00
1	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8. (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	9.00	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	7576.00
	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	21.20	Rmt.	170.00	Rupees One Hundred Seventy Only	3604.00
Total:						268492.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhaml

Work:- Restoration of rain damages on Banuti to Dayla Road In km. 0/00 to 1/00 (Sh: Constructin of Wire crate wall at Rd. 0/985 to 1/00) Job No -11

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 499136 /- only
 Earnest Money : - Rs. 10000 /-only
 Time: - One Month

Sub head and items of work	Qty.		Rate		Unit	Amount
	3	4	figures	In words		
2 Providing and laying of boulder apron laid in wire crates with 4 mm (four milimeter) dia GI wire conforming to IS:280 (two hundred eighty) and IS:4826 (four thousnad eight hundred twenty six) in 100 mm x 100 mm (one hundred into one hundred milimeter) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications clause 1301, (one thousand three hundred one) including carriage of all labour equipement and material to various location through all modes of transportation in all leads lifts all incidental charge.	132.81	Cum	3560.00	Rupees Three Thousand Five Hundred Sixty Only	Per Running Metre	472804.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	31.28	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	26332.00
					Total:	499136.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhani

SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain damages on Banuti Pahal Road via Nehwat Km. 0/00 to 17/105 (Sh: Correction layer Providing and laying stone soling Grade-III in various Rds.) Job - II

Estimated Cost - Rs 491639 / only
 Earnest Money - Rs 10000 / only
 Time - One Month

Sub head and items of work	Qty.		Rate figures		Unit	Amount
			4	5		
2	3		4	5	6	7
Scruffy existing granular surface to depth of 50 mm and disposal of scrified material with in all leads and lifts as per technical specification 301.4 as per the direction of Engineer in Charge.	3032.00	Sqm	12.15	Rupees Twelve and Paise Fifteen Only	Per Square Meter	36839.00
2	227.40	Cum	2000.00	Rupees Two Thousand Only	Per cubic metre	454800.00
					Total:	491639.00

Amount Quoted by the Contractor in Percentage					Rs.	
---	--	--	--	--	-----	--

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banuti Pahal Road via Nehwat Km. 0/00 to 17/105 (Sh: Correction layer
Providing and laying stone soling Grade-III In various Rds.) Job - I

Estimated Cost - Rs 491639/- only
Earnest Money - Rs 10000/-only
Time - One Month

Sub head and items of work	Qty.		Rate figures		Unit	Amount
	3	4	5	6	7	
Scruffyng existing granular surface to depth of 50 mm and disposal of scriified material with in all leads and lifts as per technical specification 301.4 as per the direction of Engineer in Charge.	3032.00	Sqm	12.15	Rupees Twelve and Paise Fifteen Only	Per Square Meter	36839.00
Providing laying spreading and compacting stone agg. of specific size to WBM specification i/c spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN. In stages to proper grade and camber. applying and brooming stone screening/binding material to fill up the interstices of course agg., watering and compacting to the required density grading-III as per technical specification clause 405 by manual means including entire carriage of materials upto all leads and lifts through all modes of transportation as per the direction of Engineer in Charge	227.40	Cum	2000.00	Rupees Two Thousand Only	Per cubic metre	454800.00
					Total:	491639.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

SCHEDULE OF QUANTITY


Work:- Annual Repair & Maintenance of Sangti Neri Road Km. 0/00 to 6/645 (Sh: Construction of V-Shape drain in Km. 0/200 to 1/200)

Estimated Cost. - Rs 442000 /- only
 Earnest Money - Rs 9000 /-only
 Time - One Month

Sub head and items of work	Qty.	Rate figures	Unit	Amount	
2	3	4	5	6	
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C grade M 10, (i) C.C. 1:3 6 20 mm nominal mix (Twenty Millimetre size) concrete mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	85.00 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	442000.00
				Total:	442000.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhamsi

Name of Work:- Construction of Link Road from Kiarty Gaushala to Mashobra in Km. 0/00 to 1/760 (Sh: Construction of Retaining Wall at Rd. 0/244 to 0/255.50)

SCHEDULE OF QUANTITY

Estimated Cost Rs 485645 /- only
 Earnest Money - Rs 10000 /- only
 Time - One Month

Sub head and items of work	Qty.		Rate figures	Unit	Amount	
2	3	4	5	6	7	
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	22.77	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5315.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	32.32	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	11522.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement: 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	97.06	Cum	4500.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	436735.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8, (I) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	14.15	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	11911.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v)20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	61.30	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	10421.00
Total:						485645.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhani

Name of Work:- Annual Repair & Maintenance of Type-II Quarter at Power House Totu (Sh: P/L tiles, Painting & Distemping etc.)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 403151 /- only
 Earnest Money - Rs 8000 /- only
 Time - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
		3	4	5	6		
1.00	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge in Cement mortaries	6.30	Cum	1011.75	Rupees One Thousand Eleven and Paise Seventy Five Only	Per Cubic Metre	6374.00
2.00	Demolishing R.C.C work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge	0.39	Cum	1465.35	Rupees One Thousand Four Hundred Sixty Five and Paise Thirty Five Only	Per Cubic Metre	571.00
3.00	Brick work with common burnt clay EPS (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in . in Cement mortar 1:6 (1 cement : 6 coarse sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	3.71	Cum	9570.00	Rupees Nine Thousand Five Hundred Seventy Only	Per Cubic Metre	35505.00
4.00	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	2.99	Sqm	555.00	Rupees Five Hundred Fifty Five Only	Per Square Metre	1659.00
5.00	Reinforced cement concrete work in basins, suspended floors, roofs landings, balconies, shelves, chajjas, lintels, bands, plain window sills, above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement: 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.30	Cum	9127.00	Rupees Nine Thousand One Hundred Twenty Seven Only	Per Cubic Metre	2738.00
6.00	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	32.87	Kg.	99.13	Rupees Ninety Nine and Paise Thirteen Only	Per Kilogramme	3258.00
7.00	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) complete including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	178.43	Sqm	259.00	Rupees Two Hundred Fifty Nine Only	Per Square Metre	46213.00
8.00	Providing and fixing 10mm thick anti-slip water proof stain and impetresistent heavy duty vetrified tiles or equivalent 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	52.15	Sqm	1550.00	Rupees One Thousand Five Hundred Fifty Only	Per Square Metre	80833.00
9.00	Providing and fixing 10 mm thick acid and/or alkali resistant tiles of approved make and colour using acid and/or alkali resisting mortar bedding, and joints filled with acid and/or alkali resisting cement as per IS : 4457, complete as per the direction of Engineer-in- Charge In dado/skirting on 12 mm thick mortar 1:4 (1 acid proof cement : 4 coarse sand) Acid and alkali resistant tile including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	6.45	Sqm	1650.00	Rupees One Thousand Six Hundred Fifty Only	Per Square Metre	10643.00
10.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600mm X 120mm /100x100 mm including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	5.98	Sqm	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square Metre	8671.00
1.00	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps) over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement and matching pigments etc. complete Size of Tile 600mm X 120mm /100x100 mm including carriage of material in all leads and lifts as per the direction of Engineer in Charge	20.09	Sqm	1500.00	Rupees One Thousand Five Hundred Only	Per Square Metre	30135.00

12.00	Providing and fixing granite stone in flooring, 20mm (average) thickness base of cement mortar 1:3 (Cement : Sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone i/c rubbing and polishing complete including carriage of materials upto all leads and lifts. 20mm thick.	3.99	Sqm	5500.00	Rupees Five Thousand Five Hundred Only	Per Square Metre	16445.00
13.00	Providing and fixing 40mm paneled / glazed or paneled and glazed partitions fixing to frame with iron screws etc complete (frame to be paid for separately) with 2nd class deodar wood including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	3.69	Sqm	3669.30	Rupees Three Thousand Six Hundred Sixty Nine and Paise Thirty Only	Per Square Metre	13540.00
14.00	Providing and fixing wire gauge shutters using galvanized MS wire gauge of 18 gauge designation B5 G with wire of dia 0.56 mm for doors windows and eaves-tory windows including bright finished black enameled iron hinges with necessary screws 30 mm thick 2nd class deodar wood including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	3.69	Sqm	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per Square Metre	11424.00
15.00	Providing and fixing 19 mm thick commercial board water proof in shelves, lining box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.44	Sqm	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square Metre	2088.00
16.00	Providing and fixing 10mm thick ply wood lining with butt jointing and nails (frame work and cover fillets to be measured and paid for separately complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.32	Sqm	1100.00	Rupees One Thousand One Hundred Only	Per Square Metre	4752.00
17.00	Providing and fixing 19 mm thick commercial board water proof shutter for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.32	Sqm	1650.00	Rupees One Thousand Six Hundred Fifty Only	Per Square Metre	7128.00
18.00	Providing and fixing 0.80 mm thick coloured or plain laminated sheet (sumatic) on boards / ply wood sheets with approved adhesive and nails complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.32	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Metre	3672.00
19.00	Providing and fixing stainless steel kitchen sink of approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted white including cutting holes and making good the same but excluding fitting. 610x510mm with bowl depth 200mm and as per the direction of Engineer-in-charge.	1.00	Each	3267.00	Rupees Three Thousand Two Hundred Sixty Seven Only	Each	3267.00
20.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps including carriage of materials upto all leads and lifts	1.00	Each	2402.95	Rupees Two Thousand Four Hundred Two and Paise Ninety Five Only	Each	2403.00
21.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc including carriage of material upto 15 mm nominal outer dia Pipes including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	40.00	Rmt.	293.80	Rupees Two Hundred Ninety Three and Paise Eighty Only	Per Running Metre	11752.00
22.00	Providing and fixing C.P. Brass Pillar cock of approval quality 15 mm nominal bore including carriage of material upto all leads and lifts	2.00	Each	750.00	Rupees Seven Hundred Fifty Only	Each	1500.00
23.00	Providing and fixing C.P. brass waste for wash basin or sink including carriage of materials within all leads and lifts :- 32 mm dia	2.00	Each	190.00	Rupees One Hundred Ninety Only	Each	380.00
24.00	Providing and fixing high pressure PVC flexex Type B spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete, including Carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge	0.00	0	0.00	Rupees NIL Only	0	0.00
0.00	110 mm dia	20.00	Rmt.	409.30	Rupees Four Hundred Nine and Paise Thirty Only	Per Running Metre	8186.00

25.00	Providing and fixing PVC door head with oval access door, insertion rubber washer, 4 mm thick hole, and not ISI marked complete including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts. 150mm dia.	0.00	0	0.00	Rupees Nil, Only	0	0.00
0.00	110 mm dia.	6.00	Each	328.25	Rupees Three Hundred Twenty Eight and Paise Twenty Five Only	Each	1968.00
26.00	Providing and fixing Chromium plated brass angle rock 15 mm dia. Weight 400 gms. including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	8.00	Each	950.00	Rupees Nine Hundred Fifty Only	Each	7600.00
27.00	Providing and fixing C.P. Connection ply 45cm Long 15mm hole including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	10.00	Each	200.00	Rupees Two Hundred Only	Each	2000.00
28.00	Providing & fixing Galuting. 100x100, including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	Each	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
29.00	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 5.0 mm thick glass including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	2.40	Sqm	848.00	Rupees Eight Hundred Forty Eight Only	Per Square Metre	2015.00
30.00	Providing and fixing ISI marked oxidised MS handles conforming to IS: 4992 with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.00	0	0.00	Rupees Nil, Only	0	0.00
30.01	300 mm	5.00	Each	125.00	Rupees One Hundred Twenty Five Only	Each	625.00
30.02	125 mm	5.00	Each	140.00	Rupees One Hundred Forty Only	Each	700.00
31.00	Providing and fixing ISI marked oxidised MS Tower Bolt conforming to IS:4992 with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.00	0	0.00	Rupees Nil, Only	0	0.00
31.01	100 mm	5.00	Each	130.00	Rupees One Hundred Thirty Only	Each	650.00
31.02	125 mm	5.00	Each	150.00	Rupees One Hundred Fifty Only	Each	750.00
32.00	Distemper (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give uneven shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	230.54	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square Metre	27670.00
33.00	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/ litre. With ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	42.83	Sqm	72.00	Rupees Seventy Two Only	Per Square Metre	3084.00
34.00	Painting two coats (excluding priming coat) on wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stoping With enamel paint other than white including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	42.83	Sqm	124.00	Rupees One Hundred Twenty Four Only	Per Square Metre	5311.00
35.00	Painting two coats (excluding priming coat) on Steel and Steel based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stoping With enamel paint other than white including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	5.22	Sqm	95.00	Rupees Ninety Five Only	Per Square Metre	496.00
6.00	Finishing walls with Acrylic Smooth exterior paint of required shade. New work (Two or more coat applied @ 1.60 lit/10 sqm over and including priming coat with exterior primer applied @ 2.20 kg/10 sqm) including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	30.60	Sqm	146.00	Rupees One Hundred Forty Six Only	Per Square Metre	4468.00

37.00	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	264.33	Sqm	75.00	Rupees Seventy Five Only	Per Square Metre	19825.00
38.00	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C pan with ISI marked white solid plastic seat and lid including carriage of materials upto all leads and lifts as per the direction of the Engineer-in-Charge.	1.00	Each	5660.60	Rupees Five Thousand Six Hundred Sixty and Paise Sixty Only	Each	5661.00
39.00	Providing and fixing 8mm dia C.P./S.S. Jet with flexible tube upto 1metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer-in-Charge.	1.00	Each	450.00	Rupees Four Hundred Fifty Only	Each	450.00
40.00	Providing and fixing charminium plated brass soap dish with C.P. brass brackets fixed to wooden cleats with C.P. brass screws including carriage of materials with in all leads and lifts.	3.00	Each	163.00	Rupees One Hundred Sixty Three Only	Each	489.00
41.00	Providing and fixing 600 x 120 x 5mm glass shelf with edges round off supported on anodised aluminum angle frame with CP brass brackets and guard rail complete fixed 40mm screws rawl plugs etc, complete including carriage of materials with in all leads and lifts.	2.00	Each	1265.00	Rupees One Thousand Two Hundred Sixty Five Only	Each	2530.00
42.00	Providing and fixing 750mm x 20mm size CP brass towel rail (heavy duty ISI marked) complete with CP brass brackets fixed to wooden plugs with CP brass screws including carriage of materials with in all leads and lifts.	2.00	Each	1050.00	Rupees One Thousand Fifty Only	Each	2100.00
Total:							403151.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Didoghatti Karechl Road Km. 0/00 to 8/825 (Sh: Construction of B-wall at Rd. 3/995 to 4/030)

Estimated Cost: - Rs 445733 /- only
 Earnest Money : - Rs. 9000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	39.90 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	9313.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	21.70 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	7738.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	90.96 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	418416.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	60.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	10268 00
0					Total:	445733.00

Amount Quoted by the Contractor In Percentage		Rs.
--	--	------------

Note : (1) All the material will procured by the contractor him self.

Executive Engineer
 Shimia Rural Division
 HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Link Road from Petrol Pump Hiranagar to village Jablog Km. 0/00 to 0/760 (Sh: Construction of B-wall at Rd. 0/738 to 0/760 and Edge wall at Rd. 0/725 to 0/760)

Estimated Cost - Rs 430252/- only
 Earnest Money - Rs 9000/- only
 Time - One Month

S. No.	Sub head and Items of work	Qty.		Rate figures		Unit	Amount
		3	4	5	6	7	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	6.48	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1512.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	51.63	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	18405.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	87.20	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	401120.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	54.20	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	9214.00
0						Total:	430252.00

Amount Quoted by the Contractor in Percentage		Rs.
---	--	-----

Note : (i) All the material willl procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhani

SCHEDULE OF QUANTITY

of Work:- Restoraton of rain damages on Banuti Pahal Road via Nehwat in Km. 0/00 to 17/105 (Sh: Construction of B-wall at Rd. 4/480 to 4/515)

Estimated Cost - Rs 440388 /- only
 Earnest Money - Rs 9000 /- only
 Time - One Month

Sub head and items of work	Qty.		Rate figures	Unit	Amount	
2	3	4	5	6	7	
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	18.90	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	4412.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	43.40	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	15472.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	91.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	418600.00
Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge	11.20	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1904.00
Total:					440388.00.	

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhama

SCHEDULE OF QUANTITY

Name of Work: - Restoration of Rain damages on Hiranagar Dhamoon Road Km. 0/00 to 8/00 (Sh: C/o R-wall at R.D. 6/680 to 6/690

Estimated Cost: - Rs 390509 /- only
 Earnest Money : - Rs. 8000 /-only
 Time: - One Month

S. No.	Sub head and Items of work	Qty.		Rate	Unit	Amount
				figures		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	14.40	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	3361.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	19.52	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	6959.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	79.55	Cum	4600.00	Rupees Four Thousand Six Hundred Only	365930.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.40	Rmt.	170.00	Rupees One Hundred Seventy Only	5168.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.80	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	9091.00
0					Total:	390509.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (I) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

me of Work:- Restoration of rain damages on various Roads under Totu Sub Division (Sh: Supplying and Stacking VI pot seal bag cold mix)

Estimated Cost: - Rs 297600 /- only
 Earnest Money : - Rs. 6000 /-only
 Time: - One Month

Sub head and items of work	Qty.	Rate		Unit	Amount
		figures			
2	3	4	5	6	7
Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge.	372.00 No.	800.00	Rupees Eight Hundred Only	Each	297600.00
				Total:	297600.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will pro cured by the contractor him self.


Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi



SCHEDULE OF QUANTITY					
Item of Work:- Restoration of rain damages on Devnagar Moolbari Road Km. 0/00 to 1/200 (Sh: Providing and laying WBM Grade-III for corrections in various Rds.)				Estimated Cost: - Rs 267430 /- only Earnest Money : - Rs. 5000 /-only Time: - One Month	
				Sub head and items of work	Qty.
2	3	4	5	6	7
Providing laying spreading and compacting stone agg. of specific size to WBM specification i/c spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN. In stages to proper grade and camber, applying and brooming stone screening/binding material to fill up the interstices of course agg., watering and compacting to the required density grading-III as per technical specification clause 405 by manual means including entire carriage of materials upto all leads and lifts through all modes of transportation as per the direction of Engineer in Charge.	113.80 Cum	2350.00	Rupees Two Thousand Three Hundred Fifty Only	Per cubic metre	267430.00
				Total:	267430.00

Amount Quoted by the Contractor in Percentage	Rs.
--	-----

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhama

Schedule Of Quantity

Estimated Cost:- 1,97,100.00

Name Of Work :- Restoration of rain Damages on Badheri Section Under Jutogh sub Division (SH:-Hiring of JCB for removal of snow/slips.

Earnest Money:- 4,000.00
Time:- One Months.

S.No	Description of Work	No of Qty.			Rate		Unit	Amount
		3	4	5	In figures	In words		
1	Hiring of JCB/Excavator cum loader for removal of Land slides snow /slips including the cost of fuel oil, lubricants, wages of operational staff. any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	180.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	197100	
Total Rs.								197100
Amount Quoted by the Contractor in Percentage								
Note :- All the material will procured by the contractor him self								

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhama

Schedule Of Quantity

Name Of Work :- C/O Ambulance Road to Uparli Fetechi km 0/00 to 0/750 road km 0/00 to 1/350 (SH:-C/O R/wall at RD 0/500 to 0/504 , 0/098 to 0/107)

Estimated Cost:- 4,09,576.00

Earnest Money:- 8,200.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate in figures	in words	Unit	Amount
		3	4				
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	18.72	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	4369
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	21.84	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	7786
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	78.98	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	379104
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	14.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	11819
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of 1(y) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	34.20	Nos	190.00	Rupees One Hundred ninety Only	Each	6498
Total Rs.							409576
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HPPWD, D.D.

Schedule Of Quantity

Estimated Cost:- 4,85,919.00

Name Of Work :- Restoration of Rain Damages on Hiranagar Sharog Road km 0/00 to 5/00 (SH:- C/O R/wall at Rd 0/681 to 0/690)

Earnest Money:- 10,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and dressing of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	15.84	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	3697
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	21.47	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	7554
3	Providing and Laying cement concrete for plain / reinforced concrete in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm nominal mix) including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	95.81	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	459888
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD specifications of 1990 volume-I including carriage of material within all leads and lifts	9.72	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	8182
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	34.20	No	190.00	Rupees One Hundred Ninety Only	Each	6498
Total Rs.							485919
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami

SCHEDULE OF QUANTITY


e of Work:- Restoration of rain damages on Didoghatti Karechi Road Km. 0/00 to 12/000 (Sh: Construction of R-wall at Rd. 3/986 to 3/993)

Estimated Cost: - Rs 198394 /- only
 Earnest Money : - Rs. 4000 /-only
 Time: - One Month

Sub head and items of work	Qty.	Rate		Unit	Amount
		3	4		
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	11.34	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	2647.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	13.58	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	4841.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	39.76	Cum	4600.00	Rupees Four Thousand Six Hundred Only	182896.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.83	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	4066.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	23.20	Rmt.	170.00	Rupees One Hundred Seventy Only	3944.00
				Total:	198394.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (I) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work: - Construction of Link Road from Pahal to Ghat in Km. 0/00 to 2/00 (SH: Formation Cutting in km. 0/855 TO 1/125)

Estimated Cost: - Rs 468111/- only

Earnest Money : - Rs. 9000/-only

Time- One Month

S.No.	Sub head and items of work	Qty.	In figure	Rate In words	Unit	Amount	
1	2 Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW, one sixth of SR and one third of HR. = 31.95 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreases in all cases recovered from the contractio @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	3 1597.65	293.00	Rupees Two Hundred Ninety Three Only	Per cubic meire	468111.00	
Amount Quoted by the Contractor in Percentage						Total:	468111.00

Executive Engineer,
Shimla Rural Division,
HPPWD Dharni

Form notified
17829/55(1) 86 cord dated

responsible for award
in any capacity for
the names of persons
& who are near relatives
of this condition by
department.

working or Administrative
as a contractor for
Government of Himachal
at any time to be
afore said before
days from the date of
individual cases as per
ctors, who himself
ld render tender of the
ater supply install
der and sign the
o an agreement for
1 agencies of the go
ulture.
arts from Executive
Illegal ignorance
in words and in

SCHEDULE OF QUANTITY

Name of Work: - Annual Repair & Maintenance of Gharahatti Bhajol Road Km. 0/000 to 14/000 (Sh: Improvement of Sharp Curve in various Rds. 0/000 to 1/225)

Estimated Cost: - Rs 479891/- only
Earnest Money: - Rs. 10000/-only
Time- One Month

Sl. No.	Sub head and items of work	Qty.	Cum	Rate		Unit	Amount	
				In figure	In words			
1	Curting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick- jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required), the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 24.43 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decrease in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be effected any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	2056.09	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	479891.00	
Amount Quoted by the Contractor in Percentage							Total:	479891.00

Executive Engineer,
Shimla Rural Division,
HPPWD Dhami

Correspondence
Object
Amount is not work
Many come
Conditions present
is may be or
s and order
Supervisors
any liable
f order

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Shimla Nalagarh Road Km. 7/00 to 22/00 (Sh: Construction of R-wall at Rd. 14/150 to 14/162) Estimated Cost: - Rs 324881/- only
 Earnest Money . - Rs 6000/-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	21.60 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5041.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	22.56 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	8043.00
	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	63.48 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	292008.00
	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	14.40 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	12122.00
	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	45.10 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	7667.00
					Total:	324881.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (I) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain damages on Ghanahatti Parech Road Km. 0/00 to 1/800 (Sh: Construction of R-wall at Rd. 1/725 to 1/742)

Estimated Cost - Rs 483149 /- only
 Earnest Money : - Rs. 10000 /-only
 Time: - One Month

Sub head and Items of work	Qty.	Rate		Unit	Amount
		4	5		
2	3	4	5	6	7
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	27.54 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6428.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	32.98 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	11757.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	96.56 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	444176.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.73 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	9874.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	64.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	10914.00
				Total:	483149.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

e of Work:- Restoration of rain damages on Link Road to village Panti in Km. 0/00 to 0/660 (Sh: Construction of R-wall in between Km. 0/340 to 0/352)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 340771 /- only
 Earnest Money: - Rs. 7000 /-only
 Time: - One Month

Sub head and items of work	Qty.		Rate figures		Unit	Amount
	3	4	5	6	7	
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	19.44	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	4537.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	23.28	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	8299.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	68.16	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	313536.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	8.28	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	6970.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	43.70	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	7429.00
					Total:	340771.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhama

DESCRIPTION OF WORK:- Restoration of Rain damages on Ghanahatti Nehra Bhukho Road Km. 0/00 to 8/825 (Sh: Construction of R-wall at Rd. 6/910 to 6/920)


SCHEDULE OF QUANTITY

Estimated Cost: - Rs 335966 /- only
 Earnest Money : - Rs. 7000 /-only
 Time: - One Month

Sub head and Items of work	Qty.	Rate figures		Unit	Amount
		3	4		
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	11.85 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	2766.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	30.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	10695.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	68.15 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	313490.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.60 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3030.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -In-Charge.	31.50 Rmt.	190.00	Rupees One Hundred Ninety Only	Per Running Metre	5985.00
Total:					335966.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimia Rural Division
 HPPWD,Dhami



SCHEDULE OF QUANTITY
Work:- Restoration of rain damages on Thachi Seri Shalli Road Km. 0/00 to 3/285 (Sh: Construction of Breast Wall at Rd. 0/380 to 0/380.50) from road level to Govt. Primary School Thachi Building)

Estimated Cost: - Rs 464367 /- only
 Earnest Money . - Rs. 9000 /-only
 Time: - One Month

Sub head and Items of work 2	Qty.		Rate	Unit	Amount
	3	4	figures	6	7
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	20.62	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	4813.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	13.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	4791.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	96.60	Cum	4600.00	Rupees Four Thousand Six Hundred Only	444350.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.30	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	5303.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.00	Rmt.	170.00	Rupees One Hundred Seventy Only	5100.00
				Total:	464367.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

of Work: - Restoration of Rain damages on Bhajyar Devidhar Road Km. 0/00 to 2/200 (Sh: Construction of R-wall at Rd.1/289 to 1/299/56)

Estimated Cost: - Rs 498519 /- only
 Earnest Money: - Rs. 10000 /-only
 Time: - One Month

Sub head and items of work	Qty.	Rate figures		Unit	Amount
		3	4		
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	13.02 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3039.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	54.81 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	19540.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	99.86 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	459356.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.34 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9546.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	41.40 Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	7038.00
0				Total:	498519.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Gharog Nalta Road Km. 0/00 to 7/00 (Sh: Construction of R-wall at Rd. 4/010 to 4/050)						
						Estimated Cost: - Rs 488184 /- only Earnest Money : - Rs. 10000 /-only Time: - One Month
2	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
3					6	7
	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	28.50 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6652.00
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	26.60 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	9483.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	98.42 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	452732.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.40 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9597.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	54.00 Rmt	180.00	Rupees One Hundred Eighty Only	Per Running Metre	9720.00
0					Total:	488184.00

Amount Quoted by the Contractor In Percentage		Rs.
---	--	-----

Note : (i) All the material will procured by the contractor him self.

Execd Engineer
 Shimla Rural Division
 HPPWD, Dhamla

SCHEDULE OF QUANTITY
Annual Repair & maintenance of Judicial Academy at Ghandal (Sh. Providing and fixing Railing , providing and applying putty and painting in Admn Blook etc.)

Sub head and Items of work

Estimated Cost - Rs 485895 /- only
 Earnest Money : - Rs 10000 /-only
 Time - One Month

1	2	3	4		5	6	7
			Qty.	Rate figures			
1	Steel work welded in built up sections/ framed work, including hollow section including cutting, hosting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required including carriage of material with in all lead and lifts as per the direction of Engineer-in-Charge. (ii) In gratings, framed, guards, bars ladders and railing, brackets and similar works :-	2847.20	Kg	115.00	Rupees One Hundred Fiteen Only	Per Kilogramme	304428.00
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material in all leads and lifts as per the direction of Engineer in Charge.	940.24	Sqm	78.00	Rupees Seventy Eight Only	Per Square Metre	73339.00
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour: Two Coats including carriage of materials upto all leads and lifts and as directed by the Engineer in Charge	940.24	Sqm	115.00	Rupees One Hundred Fiteen Only	Per Square Metre	108128.00
0	Total:						485895.00

Amount Quoted by the Contractor In Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhani


SCHEDULE OF QUANTITY						
Name of Work:- Rutine Mainteneace of Playground of Govt. Senior Secondary School Dargl Distt. Shimla (Sh: Construction of R-wall towards valley side protect the play ground of GSSS Dargl In Km. 0/012 to 0/017.60) Against Deposit					Estimated Cost: - Rs 495991 /- only Earnest Money : - Rs. 10000 /-only Time: - One Month	
S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	18.48 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	4313.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	26.88 Cum	358.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	9583.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	101.64 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	467544.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	8.40 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	7071.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v)20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	44.00 Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	7480.00
0					Total:	495991.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (I) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

Name of Work: - Routine Maintenance of Playground of Govt. Senior Secondary School Dargi Distt. Shimla (Sh: Construction of R-wall towards valley side protect the play ground of GSSS Dargi In Km. 0/00 to 0/011.50) Against Deposit

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 496791/- only
Earnest Money: - Rs. 10000/-only
Time: - One Month

0	Sub head and Items of work	Qty.	Rate		Unit	Amount	
			figures	5			
1	2	3	4	5	6	7	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORO specification directed by Engineer-in-Charge.	15.53	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3625.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORO specification directed by Engineer-in-Charge.	43.70	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	15579.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	98.90	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	454940.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	17.25	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	14521.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	47.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	8126.00
0							
Total:							496791.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Rs.

Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi

Schedule Of Quantity

Name Of Work :- A/R & M/O Judicial Academy at Ghandal, Distt Shimla (HP) (SH:- P/F of Cupboards in Library of Administrative Block & Painting work etc) Job no.1

Estimated Cost:- 4,97,917.00
 Earnest Money:- 10,000.00
 Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing 19 mm thick commercial board water proof in shelves, lining box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	176.00	Sqm	1700.00	Rupees One Thousand Seven Hundred Only	Per Square meter	299200
2	Providing and fixing 0.80 mm thick coloured or plain laminated sheet (sunmica) on boards ply wood sheets with approved adhesive and nails complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	176.00	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square meter	149600
3	Providing and fixing square edged cover fillets (beading) 19 x 6 mm section including mitring at junction with wooden screws / nails etc complete of hard wood including carriage of material in all leads and lifts	203.20	Rmt	65.00	Rupees Sixty Five Only	Per Running meter	13208
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood and steel work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	181.06	Sqm	150.00	Rupees One Hundred Fifty Only	Per Square meter	27159
5	Finishing walls with Acrylic Smooth exterior paint of required shade. New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	50.00	Sqm	175.00	Rupees One Hundred Seventy Five Only	Per Square meter	8750
Total Rs.							497917
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhandu

Schedule Of Quantity

Estimated Cost:- 4,99,387.00

Name Of Work :- A/R & M/O Judicial Academy at Ghandal, Distt Shimla (HP) (SH:- P/F of Cupboards in Library of Administrative Block & Painting work etc) Job no.2

Earnest Money:- 10,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing 19 mm thick commercial board water proof in shelves lining, box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	176 00	Sqm	1700 00	Rupees One Thousand Seven Hundred Only	Per Squar meter	299200
2	Providing and fixing 0.80 mm thick coloured or plain laminated sheet (Surmica) on boards ply wood sheets with approved adhesive and nails complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	176 00	Sqm	850 00	Rupees Eight Hundred Fifty Only	Per Squar meter	149500
3	Providing and fixing square edged cover litlets (beading) 19 x 6 mm section including mitring at junction with wooden screws / nails etc complete of hard wood including carriage of material in all leads and lifts	202 40	Sqm	65 00	Rupees Sixty Five Only	Per Squar meter	13156
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood and steel work with Deluxe Multi Surface Paint of required shade Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	202 87	Sqm	150 00	Rupees One Hundred Fifty Only	Per Squar meter	30431
5	Finishing walls with Acrylic Smooth exterior paint of required shade. New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	40 00	Sqm	175 00	Rupees One Hundred Seventy Five Only	Per Squar meter	7000
Total Rs.							499387
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD. Dhandi

SCHEDULE OF QUANTITY						
Work :- Constuction of Veterinary Hospital at Dargi, Distt Shimla (Sh: C/o additional room at first floor & Providing and fixing stairs from ground floor to first floor along with repair of rooms at ground floor of veterinary Hospital Building at Dargi) Deposit						
Sub head and Items of work	Qty.	Rate	Estimated Cost :- Rs 371764 /- only	Earmest Money :- Rs. 7000 /- only		7
				Unit	Amount	
2	3	4	5	6	6	7
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	0.29	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	103.00
Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure in Cement mortar 1:4 (1 cement: 4 coarse sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	9.81	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	10091.00
Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor 1 level in all shapes and sizes in: in Cement mortar 1:6 (1 cement: 6 coarse sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	5.15	Cum	9570.00	Rupees Nine Thousand Five Hundred Seventy Only	Per Cubic Meter	49286.00
Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdlasts etc complete and stacking within all leads and lifts as per the direction of Engineer in Charge. : Of area beyond 3 sq metres	2.00	No.	214.85	Rupees Two Hundred Fourteen and Paise Eighty Five Only	Each	430.00
Reinforced cement concrete work in beams, suspended floors, roofs landings, balconies, shelves, chajjas, lintels, bands, plain window sills, above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.76	Cum	9127.00	Rupees Nine Thousand One Hundred Twenty Seven Only	Per cubic metre	6937.00
Providing Mild Steel/for steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto two level. including carniage of material in all leads and lifts as per direction of the Engineer in Charge.	12.00	Kg.	95.00	Rupees Ninety Five Only	Per Kilogramm e	1140.00
Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 2nd class D/wood or Sal wood	0.12	Cum	125000.00	Rupees One Lakh Twenty Five Thousand Only	Per Cubic Metre	15000.00
Providing and fixing panelled or panelled and glazed shutters for windows and clerestory windows, including ISI marked M S pressed butt hinges bright finished of required size with necessary screws, /nails including fixing 4.00 mm thick glass with necessary screws, corners/mouldings complete in all respect and as per direction and satisfaction of Engineer in-charge. 2nd class deodar	8.31	Sqm	4150.00	Rupees Four Thousand One Hundred Fifty Only	Per Square Metre	34487.00

drilling and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 200x10 mm

drilling and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :125mm.

drilling and fixing aluminium sliding door bolts (Barrel type) anodized transparent or dyed to required shade colour with bolts and nuts etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. -300 X 16 mm

drilling and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600mm x 300mm/300x300 mm

drilling and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08% and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc, complete. Size of tile 600mm X 120mm./100x100 mm

steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.

Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.

Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.

15 mm cement plaster on the rough side of single or half brick wall of mix: 1:6 (1 cement: 6 fine sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.

6.00	No.	90.00	Rupees Ninety Only	Each	540.00
6.00	No.	80.00	Rupees Eighty Only	Each	480.00
10.00	No.	70.00	Rupees Seventy Only	Each	700.00
3.00	No.	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
15.17	Sqm	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square Meter	21997.00
1.56	Sqm	1500.00	Rupees One Thousand Five Hundred Only	Per Square Meter	2340.00
1099.63	Kg.	110.00	Rupees One Hundred Ten Only	Per Kilogram	120959.00
21.23	Sqm	130.00	Rupees One Hundred Thirty Only	Per Square Meter	2760.00
28.60	Sqm	125.00	Rupees One Hundred Twenty Five Only	Per Square Metre	3575.00
32.02	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Metre	8005.00

19	15 mm cement plaster on the Fair side of single or half brick wall of mix 1:6 (1 cement: 6 fine sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	32.02	Sqm	240.00	Rupees Two Hundred Forty Only	Per Square Metre	7685.00
20	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	338.43	Sqm	75.00	Rupees Seventy Five Only	Per Square Meter	25382.00
21	Distemping with Acrylic washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	169.22	Sqm	105.00	Rupees One Hundred Five Only	Per Square Meter	17768.00
22	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	169.22	Sqm	135.00	Rupees One Hundred Thirty Five Only	Per Square Meter	22845.00
23	Providing and fixing prelaminate board ceiling complete with all necessary screws and clamps 8 mm thick as per HPPWD specification 1990 volume-1 including carriage of material, labour, tool and plants through all modes of transportation with in all leads and lifts as per direction of the Engineer in Charge	15.17	Sqm	1200.00	Rupees One Thousand Two Hundred Only	Per Square Meter	18204.00
0							
Total:							371764.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhami

SCHEDULE OF QUANTITY

name of Work:- Construction of Link Road Palkari Makri Km. 0/00 to 1/600 (Sh: Construction of V-Shape drain in Km. 0/00 to 0/450 & 0/550 to 0/800)

Estimated Cost - Rs 448333 / only
 Earnest Money - Rs 9000 /only
 Time - One Month

Sub head and items of work	Qty	Rate figures	One Month			
			Unit	Amount		
2	3	4	5	6	7	
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	105.00	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	37433.00
Providing and laying compacting stone soling of specific size to properly hand packed tightly in under flooring as per drawing complete and technical specification by manual means (i) 100 mm. thickness including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	38.50	Cum	1400.00	Rupees One Thousand Four Hundred Only	Per cubic metre	53900.00
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P C C grade M 10, (i) C.C 1:3:6 20 mm nominal size (Twenty Millimetre size) concrete mix, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	70.00	Cum	5100.00	Rupees Five Thousand One Hundred Only	Per cubic metre	357000.00
					Total.	448333.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

~~Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhani~~

Schedule Of Quantity

NAME OF WORK :- RR Damages on various roads of Sunni Sub-Division, Shimla HP
(SH:-Hiring of JCB for removal of slips on various Rd's of various road).

Estimated cost: 4,73,970 /-
 Earnest Money: 9500 /-
 Time : One Month

S.No	Description of Work	No.of Qty.	Unit	Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5	3885.00	Cum	122.00	One Hundred Twenty Two Rupees Only	Per Cubic Meter	473970.00
						Total	473970.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor himself							

Executive Engineer
 Shimla Rural Division
 HPPWD Dhami

Schedule Of Quantity						Estimated Cost:- 4,77,016.00	
Name Of Work :- Construction of link road from chebri to Piplughat km 0/00 of 3/870. (SH:- C/O R/wall (Wire crate) at Rd 3/580 to 3/595) Under M.M.G.S.Y						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	28.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	6582
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	22.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	8021
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	45.00	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	216000
4	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	86.40	Cum	2852.00	Rupees Two Thousand Eight Hundred Fifty Two Only	Per Cubic metre	246413
Total Rs.							477016
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharm

Schedule Of Quantity

TIME OF WORK :- RR Damages on Shogi Salana road km 0/000 to 8/000.
AI:- Hiring of JCB for removal of slips on various Rd's of road).

Estimated cost: 3,55,496 /-

Earnest Money: 7100 /-

Time : One Month

S.No	Description of Work	No.of Qty.	Unit	Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5	2913.90	Cum	122.00	One Hundred Twenty Two Rupees Only	Per Cubic Meter	355496.00
						Total	355496.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor himself							

Executive Engineer
 Shimla Rural Division
 HPPWD Dham

Schedule Of Quantity						Estimated Cost:- 4,94,218.00	
Name of Work: Restoration of Rain Damages on Tara Devi Ghamber road, km 0/000 to 11/520 C/O R/Wall in between Km 9/300 to 9/312.5						(SH: Earnest Money:- 10,000.00 Time:- One Month	
Sr. No.	Description of work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	36.63	cum	₹ 233.40	Rupees Two Hundred Thirty Three and Fourty Paise Only	per cum	₹ 8,548.00
2	Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and braeing, removal of stumps & other deleterious material & disposal upto ahead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.	21.88	cum	₹ 356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	per cum	₹ 7,798.00
3	P/L concrete for plain/reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:4:8 nominal mix (1 Cement : 4 sand : 8 graded crushed stone aggregate 40mm nominal size).	94.50	cum	₹ 4,800.00	Rupees Four Thousand Eight Hundred Only	per cum	₹ 453,600.00
4	Providing weep holes in brick masonry/ stone masonry/ plain or reinforced concrete abutment, wing wall, return wall, with 100mm dia PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7	48.00	Rmt	₹ 190.00	Rupees One Hundred Ninty Only	per Rmt	₹ 9,120.00
5	Backfilling behind abutment, wing wall, and return wall complete as per drawing & technical specification clause 1204.3.8, Granular material.	18.00	cum	₹ 841.80	Rupees Eight Hundred Fourty One And Eighty Paise Only	per cum	₹ 15,152.00
Amount Quoted by the Contractor in percentage						Rs.	Total Amount= ₹ 494,218.00
Conditions:- All the Machinery/ Materials will be procured by the contractor himself and bills will be submitted							

Executive Engineer
Shimla Rural Division
HPPWD Dham

Schedule Of Quantity

Name of Work :- R/R damages on (i) Ghanahatti Nehra Shaltu Dargot road km 0/0 to 5/450 (ii) Ghanahatti Nehra Bhukhoo road km 0/00 to 8/00 (SH:- Construction of Unlined drain, Maintenance of Hume pipe Culvert ,earthen shoulder etc)

Estimated Cost:- 4,27,675.00

Earnest Money:- 8,600.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	5	6		
				In figures	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per the direction of in charge	1263.05	Cum	90.00	Rupees Ninety Only	Per cubic metre	113675
2	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materis within all leads and lifts and as per the direction of Engineer-In- Charge .	25.00	No	1600.00	Rupees One Thousand Six Hundred Only	Each	40000
3	Maintenance of earthen shoulder (stripping of excess soil) from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per specifications.	8000.00	Sqm	18.00	Rupees Eighteen Only	Per Square metre	144000
4	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	5000.00	Rmt	5.00	Rupees Five Only	Per running metre	25000
5	Construction of unlines surface drains of average cross-sectional area 0.40 Sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment with a lift upto 3m and lead Of 50m (average lead 25m) as per technical specification clause 207	2500.00	Rmt	42.00	Rupees Forty Two Only	Per running metre	105000
Total Rs							427675
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.