

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

No. PW-DPD-CB-Tender/2025-26-

19695

Dated:- 7.8.2026

To

The Executive Engineer(IT) Cell,  
HP.PWD,Nirman Bhawan, Nigam Vihar,  
HP.PWD,Shimla-2.

**Subject:**


**Regarding publication of Tender notice on department website.**

Sir,

With reference to the notification issued by the Secretary (PW) to the Government of Himachal Pradesh No. PBW(B) A(3)I/2024 dated 03/01/2024 , further corrigendum on dated 08/01/2025 and Under Secretary (PW) to the Government of Himachal Pradesh No. PWD-B-A0(3)/1/2024-241828 dated 02-02-2026 . Enclosed please find herewith the copy of tender notice for the publishing on departmental website.

**Certified that the work mentioned in the Tender Notice are urgenet in nature.**

DA:- As above

  
Executive Engineer,  
Dharampur Division,  
HP.PWD. Dharampur.

## H.P.P.W.D NOTICE INVITING TENDER

The **percentage** rate off line tender notice on the form 6 & 8 are invited by the Executive Engineer, Dharampur Division, HPPWD Dharampur on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

### TENDER SCHEDULE:


- |    |   |                           |
|----|---|---------------------------|
| 1  | Date and time of receipt of application for the tender form : | 12-03 -2026 upto 4.00 PM  |
| 2  | Date and time of issue of tender form :                       | 13-03 -2026 upto 4.00 PM  |
| 3  | Date and time of receipt of tenders:                          | 16-03 -2026 upto 11.00 AM |
| 4. | Date and time of opening of tenders:                          | 16-03 -2026 upto 11.30 AM |

The tender form will be issued against cash payment (non refundable), the **earnest money in the shape of NSC/FDR/Deposit** at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dharampur Division, HPPWD Dharampur must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

Sr. No	Name of Works	Estimated Cost (in Rs)	EMD (in Rs.)	Time Limit	Cost of Tender Form	Eligible class of Contractor
01.	A/R & M/O Nor Residential Building in HPPWD Division Dharampur (SH:- Painting of Porch and Providing and Fixing of glass panes)	95,182/-	2,000/-	Two months	350/-	"D"
02	A/R & M/O Nor Residential Buildings in HPPWD Dharampur (SH:- Supplying and Installation of CCTV Cameras in HPPWD Division Dharampur Campus)	68,960/-	1,500/-	Two Months	350/-	"D"
03	A/R & M/O Non Residential Building in HPPWD Division Dharampur (SH:- C/O Roof Truss for Poch)	83,355/-	2,000/-	Two Months	350/-	"D"
04	Repair of Residential Quarter HPPWD Division Dharampur (SH:- Repair of wall painting and Damp proofing etc.)	98,846/-	2,000/-	Two Months	350/-	"D"
05	A/R & M/O Rest House at Sidhpur (NR Building) (SH:- P/F Aluminium wardrobe and paint work etc.)	99,453/-	2,000/-	Two months	350/-	"D"

### Terms and Conditions:-

- 1 The contractors/firms should possess the following documents at the time of application (Photocopy to be attached):- i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.), (iii) Copy of GST registration. (iv) Copy of EPF Number, (v) Owned/Hired documentary proof of the machinery required for the work. (vi) Cost of tender, (vii) Earnest Money.
2. The Contractors/firms are required to quote their rates both in figures and words, failing which under-signed reserve the right to accept/reject any or all tenders without assigning any reasons.
3. 1% cess charges on the amount of work awarded will be recovered from the contractor and the contractor has to get registered with Labour Officer-cum-Registering Officer-cum- Cess Collector within one month from the issue of the award letter.
4. The contractor will give affidavit that he has not two or more works in hand for execution, failing which the application shall be rejected.
5. The offer of the tender shall remain valid upto 60 days after the opening.
6. The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).

  
Executive Engineer,  
Dharampur Division,  
HP.PWD, Dharampur,  
Distt: Mandi (H.P.)

No.PW-DPD-CB-Tender/2025-26/

19696-700

Dated:- 7.3.2026

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer, Hamirpur Zone HP.PWD, Hamirpur H.P.
2. The Superintending Engineer Dharampur Circle HP.PWD Dharampur.
3. The Executive Engineer (IT) O/o Engineer-In Chief HPPWD Shimla through [email-eeict-pwd-shi@hp.gov.in](mailto:email-eeict-pwd-shi@hp.gov.in) & [ee-pwd-hp@nic.in](mailto:ee-pwd-hp@nic.in) for uploading the same on HPPWD web portal.
4. Notice Board.
5. A/B, D/B. Of this office.

1  
Executive Engineer,  
Dharampur Division,  
HP.PWD, Dharampur,

234  
101

DRAFT SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O Non Residential building in HPPWD Division Dharampur (SH: Painting of Porch and  
ing and fixing of glass panes)

Estimated cost :- 95182  
Earnest Money :- 2000  
Time Limit Three Months  
Amount

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2	3	4	5	6	7
Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete after thoroughly brushing the surface free from mortar droops, dust, loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	80.53	90.00	Rupees Ninety Only	Per Square Metre	7248
Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture having VOC (Volatile Organic Compound) content less than 50 (fifty) grams per litre for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar drooping and other foreign matter and sand papered smooth including applying of putty a required for meting the surface complete including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	80.53	95.00	Rupees NinetyFive Only	Per Square Metre	7650
Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (One point nine liters per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (One point eight liters per ten square metre) of approved brand, Shalimar make on new steel and new steel surface under coat with ready mixed paint brushes to give an even shade including cleaning the surface of all dirt dust and other foreign metter complete upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	11.04	87.00	Rupees EightySeven Only	Per Square Metre	960
Supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary plain glass 4mm thick including carriage of materials within all leads and lifts and other incidentals charges.	22.65	850.00	(Rupees: Four hundred ninety four and paise sixty five) only	Per Square metre	19253
Providing and fixing high pressure 110 mm ( one hundred ten millimetre) dia PVC spigot and socket, waste and ventilating pipes of Finolex/Supreme/Astral make or equivalent ISI marked working pressure not less than 6.00 (six) kilogram per square centimeter including fixing with approved adhesive etc. complete including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	48.00	495	Rupees Four Hundred NinetyFive Only	Per Running Metre	23760

<p>Providing and fixing galvanized MS wire gauge of IS gauge designation 85G with wire of dia 0.56mm for doors, windows and clearstorey windows including mettaled beading with necessary steel screws including applying a priming coat of red lead paint complete including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.</p> <p>Providing and fixing tiled false ceiling of specified materials of size 595x395 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. he rates are inclusive of royalty, GST or other taxes imposed by the Government.</p>	24.20	750	Rupees Seven Hundred Fifty Only	Per Square Metre	18150
<p>Providing and fixing tiled false ceiling of specified materials of size 595x395 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. he rates are inclusive of royalty, GST or other taxes imposed by the Government.</p>	12.88	1410	Rupees One Thousand Four Hundred Ten Only	Per Square Metre	18161
				Total:	95182

*Our amount approved for Rs 95182/- vide s.n.m. 234*

*2025-26*

*[Signature]*  
 Executive Engineer,  
 Dharampur Division  
 H.P.W.D., Dharampur

230  
100

DRAFT SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O Non- Residential Buildings in HPPWD Dharampur. ( SH:- Supplying and installation of TV Cameras in HPPWD Division Dharampur Campus)

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Two Months Amount
		Earnest Money:-			
		In Figure	In words		
2 Supplying of 07 Nos ( seven numbers)HD 2.4 (two point four)MP Audio/ Night color vision Cameras, 1No ( one number). Solar Dual Camera with 128 (one hundred twenty eight) GB memory card including fitting and diagnosing of 16 ( sixteen ) numbers CCTV Cameras including BNC/DC Connectors ,3+1 (three plus one) Wireall ,Battans etc. complete in all respect as per direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 1.00	68960	Rupees SixtyEight Thousand Nine Hundred Sixty Only	6 Per Job	68960
Total:-					68960

*Duit amount approved for Rs 68960/- vide*

*Scr No 230*

*Executive Engineer,  
Dharampur Division  
H.P.P.W.D., Dharampur*

235  
102

DRAFT SCHEDULE OF QUANTITY

Name of Work :-A/R & M/O Non Residential building in HPPWD Division Dharampur (SH: C/O Roof truss for

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount
		Earnest Money:-			
		In Figure	In words		
	3	4	5	6	7
2 Structural steel work riveted, bolted or welded in builtup sections in trusses ,rafters and purlins in building framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including entire carriage of material with in all leads and lifts and as per drawings and technical specifications as per direction of Engineer-in-Charge including other incidentals. The rates are inclusive of royalty, GST or other taxes imposed by the Government.	220.50	115	Rupees One Hundred Fifteen Only	Per Kilogramme	25358
Structural steel work riveted, bolted or welded in builtup sections,, made of trusses ,rafters and purlins in building framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including entire carriage of material with in all leads and lifts and as per drawings and technical specifications as per direction of Engineer-in-Charge including other incidentals .The rates are inclusive of royalty, GST or other taxes imposed by the Government.	220.50	28 ( L.Rate)	Rupees TwentyEight Crore Only	Per Kilogramme	6174
Providing and fixing 0.60mm (Zero point sixty millimetres) thick preprinted steel sheet made of TATA,Durashine in roofing with hot dipped matallic Zinc coated sheet with the top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns 5 (five) micron over five micron's primer coating to back coat of polyester over 5 (five) microns primer coating including fixing with pre painted iron J or L hooks, bolts and nuts 6mm (six millimeters) dia meter with preprinted limpet and rubber washer complete with all accessories as required as per the direction of Engineer-in Charge upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. he rates are inclusive of royalty, GST or other taxes imposed by the Government.	12.25	1350	Rupees One Thousand Three Hundred Fifty Only	Per Square Metre	16538
Providing and fixing 0.60mm (Zero point sixty millimetres) thick preprinted steel sheet made of TATA,Durashine in roofing with hot dipped matallic Zinc coated sheet with the top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns 5 (five) micron over five micron's primer coating to back coat of polyester over 5 (five) microns primer coating including fixing with pre painted iron J or L hooks, bolts and nuts 6mm (six millimeters) dia meter with preprinted limpet and rubber washer complete with all accessories as required as per the direction of Engineer-in Charge upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. he rates are inclusive of royalty, GST or other taxes imposed by the Government.	17.64	118 ( L.Rate)	Rupees Eleven Crore Eight Lakh Only	Per Square Metre	2082

<p>Providing and fixing ridges or hips with proper gola 60cm (Sixty centimetres) overall with 0.60mm) Zero point six zero millimetres) thick prepainted steel sheets for roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyster organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating plus back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetres) dia and prepainted G.I. limpet and bitumen washer complete with all accessories as required upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. he rates are inclusive of royalty, GST or other taxes imposed by the Government.</p>	16.20	690	Rupees Six Hundred Ninety Only	Per Running Metre	11178
<p>Providing and fixing MS BP Sheet 1.66 to 2.00 (One point sixty six to two) millimetres thick to eaves board/ facia/ soffits/ ceiling including cutting fixing and welding to steel roof members and applying a coat of red lead primer complete upto all heights as per direction of Engineer in Charge ( base members of steel work shall be measured and paid separately ) upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. he rates are inclusive of royalty, GST or other taxes imposed by the Government</p>	11.04	1995	Rupees One Thousand Nine Hundred NinetyFive Only	Per Square Metre	22025
Total:-					83355

*0417 amount approved For Rs 83355/- vide S.M. 235  
2025-26*

*Executive Engineer,  
Dharampur Division  
H.P.P.W.D., Dharampur*

233

**DRAFT SCHEDULE OF QUANTITY**

Work:- Repair of Residential Quarter HPPWD Division Dharampur (Sh:- Repair of wall painting and Damp proofing

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2 Finishing Roofing with Damp proof smart care Asian paint with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 268.42	275	Rupees Two Hundred SeventyFive Only	6 Per Square metre	7 73816
2 Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including t thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for melling the surface including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	213.69	74.80	Rupees SeventyFour Paise Eighty Only	Per Square metre	15984
Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm(zero point nine liters per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm(zero point seven five liters per ten square metre) of approved brand and manufacture of ICI (Dulux Gloss), Nerolac, Berger (Luxol High Gloss), Asian Paints (Premium Apcolite Gloss), Shalimar. make including cleaning of all dirt, dust and other foreign matter sand papering and stopping complete upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	50.60	94.3	Rupees NinetyFour Paise Thirty Only	Per Square metre	4772
Providing and applying white cement based putty of average thickness 1 mm, (One millimetre) of approved brand and manufacturer JK wall putty/ Birla white Putty make over the plastered wall surface to prepare the surface even and smooth complete upto all floor level including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	53.42	80	Rupees Eighty Only	Per Square metre	4274
				<b>Total</b>	<b>98846</b>

*Draft schedule of quantity approved*  
*RS.98846/- vide no. 233/2025-26*

Executive Engineer,  
 Dharampur Division  
 H.P.P.W.D., Dharampur

241

## DRAFT SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O Rest House at Sidhpur ( SH :- Providing and fixing Aluminium Wardrobe and paint work		Estimated cost :-		99453	
		Earnest Money:-		2000	
Description of item/Sub Head		Time Limit		Two Months	
		In Figure	In words	Unit	Amount
Quantity					
3	2	4	5	6	7
61.8	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z-section and other section approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) as per direction of the Engineer-in-charge and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax , sale tax GST or other taxes imposed by the Government.	449.45	Rupees Four Hundred FortyNine Paise FortyFive Only	Per Kilogramme	27776
12.86	Providing and fixing 3 mm (three millimetre) thick ACP sheet approved shade and over GI frame work fixing with screws complete and the directions of Engineer-in-charge.( frame work to be paid seprately)as per direction of the Engineer-in-charge and other incidentals. The rate is includes of octroi, royalty, Malkana, toll tax , sale tax GST or other taxes imposed by the Government.	3067	Rupees Three Thousand SixtySeven Only	Per Square Metre	39442
3.12	Providing and fixing 6 mm thick Bakelite sheet approved shade and over aluminium frame work fixing with screws complete as per direction of the Engineer-in-charge and other incidentals. The rate is includes of octroi, royalty, Malkana, toll tax , sale tax GST or other taxes imposed by the Government.	1033.35	Rupees One Thousand ThirtyThree Paise ThirtvFive Only	Per Square Metre	3224
2	Providing and fixing 600x450mm (six hundred into four hundred fifty millimetre) beveled edge mirror of superior glass make of Atul Modi Guard, Golden fish mounted on 6mm (six millimetre) thick A.C. sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washer including the carriage of material within all leads, lifts through all modes of transportation upto all floor level as per direction of the Engineer-in-charge and other incidentals. The rate is includes of octroi, royalty, Malkana, toll tax , sale tax GST or other taxes imposed by the Government.	1547.4	Rupees One Thousand Five Hundred FortySeven Paise Forty Only	Each	3095
4	Providing and fixing of special quality bright finished brass cup board or ward robe locks with four levers of approved quality including necessary screws as per direction of the Engineer-in-charge and other incidentals. The rate is includes of octroi, royalty, Malkana, toll tax , sale tax GST or other taxes imposed by the Government.	191.6	Rupees One Hundred NinetyOne Paise Sixty Only	Each	766
14	Providing and fixing aluminium handles anodized transparent or dyed to required colour of shade with necessary screws etcetra complete 125mm (One hundred twenty five millimetre) nominal size. as per direction of the Engineer-in-charge and other incidentals. The rate is includes of octroi, royalty, Malkana, toll tax , sale tax GST or other taxes imposed by the Government.	43.8	Rupees FourtyThree Paise Eighty Only	Each	613
47.69	Removing dry oil bond distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax , sale tax , GST or other taxes imposed by the Government.	17	Rupees Seventeen Only	Per Square Metre	811

Description of work	47.69	119	Rupees One Hundred Nineteen Only	Per Square Metre	5675
Finishing wall with weather proof exterior grade emulsion of approved design (Apex Ultima, Asian Paints ICI Dulux Gloss, Nerolac, Burger (luxol) High Gloss, Premium Apcolite Gloss & Shalimar manufacture) on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surfaces to remove all dirt dust and other foreign matter etcetera including sand papered smooth complete upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8	316	Rupees Three Hundred Sixteen Only	Per Square Metre	2528
Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with in cement mortar 1:3 The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	46.26	98.00	Rupees Ninety Eight Only	Per Square Metre	4533
Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including t horoughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metling the surface including entire carriage of material with in all leads and lifts and including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	1.00	10990.00	Rupees Ten Thousand Nine Hundred Ninety Only	Each	10990
				Total:-	99453

*Only amount approved for Rs 99453/-  
vide S- No 241*

Executive Engineer,  
Dharampur Division  
H.P.P.W.D., Dharampur