

Himachal Pradesh
Public Works Department

No.PW/RGH/Estt-Tender/2025-26-
To

10846-95

Dated:- 12-03-2026


The Executive Engineer (IT) Cell,
Nigam Vihar HP. Shimla-2
cc-pwd-hp@nic.in

Subject:- Publication of Tender Notice.

Jai Hind.


Enclose please find herewith the Notice Inviting Tender to be opened on 19.03.2026 for uploading on departmental website as per notification Secy. (PW) to the Government of H.P. No. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the notice is urgent nature and public interest.

Encl: - As above


Executive Engineer,
Rajgarh Division,
HP.PWD, Rajgarh.

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. All the Assistant Engineers working under this Division.
5. All Head of Branches of this office.
6. All Intending Bidders/Contractors.
7. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office **19.03.2026 upto 10:30 AM** and shall be opened on the same day at **11:00 AM** in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Schedule					
1.	Last date for tender receipt of application for tender form		17.03.2026 upto 5:00 PM			
2.	Last date of sale of tender forms.		18.03.2026 upto 5:00 PM			
3.	Date of receipt of tender forms		19.03.2026 upto 10:30AM			
4.	Date of opening of tenders		19.03.2026 at 11:00 AM			
Sr. No.	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form	Eligible Class of contract or
1.	Restoration rain damage on Chaillia Neripul Yashwant Nagar Kumarhatti raod km 45/00 to 62/00 (SH:- Construction of Retaining walls Between km 57/944 to 57/948.50) Under PDNA Balance amount.	3,30,388/-	7,000/-	Two month	350/-	Class- "C&D"
2.	Restoration rain damage on Chaillia Neripul Yashwant Nagar Kumarhatti raod km 45/00 to 62/00 (SH:-ROFD Between km 57/920 to 57/960) Under PDNA Balance amount.	1,77,840/-	4,000/-	One month	350/-	Class- "C&D"
3.	Restoration rain damage on Banethi Bagthan Rajgarh Chandol road km 48 to 127/300 (SH:-C/O PCC Brest Walls Between Km 82/225 to 82/240) Under PDNA Balance amount.	2,24,489/-	5000/-	Two month	350/-	Class- "C&D"

Certificate :-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractor/bidder should quoted in percentage rates.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The offer shall remain valid upto 75 days.
7. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW)B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
8. The Executive Engineer reserve the right any or all the tenders without assigning any reason.
9. The contractor will have to submit the proof of machinery/JCB (hired/owned), RC alongwith opprater Mobile No. required for work.
10. Certificate of Registration for GST and acknowledgement of upto date filed return as per NIT stipulation.
11. Limit of work in Hand for the Contractor in HPPWD vide Nofication No. PWD-B-F0(1)/3/202-268025 dated 29.10.2025 and further circulate vide Engineer in Chief letter No.PW/CRT/32-20/Genl Inst./Tender Documents/ 2025 Class-A,B,C.



Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh
Tel. No. 01799-221023
Mail.ee-raj-hp@nic.in


SCHEDULE OF QUANTITY

Name of work :- Restoration rain damage on Chaillia Neripul Yashwant Nagar Kumarhatti raod km 45/00 to 62/00 (SH:-
Construction of Retaining walls Between km 57/944 to 57/948.50) Under PDNA Balance amount.

Estimated cost: - Rs.3,30,388.00/-
Earnest money: - Rs. 7,000/-
Time Limit: -Two Months

Sr.	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	32.40	Per Cubic Metre.	260.00	Two hundred sixty and paise nil only.	8424.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as par drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	53.39	Per Cubic Metre	5900.00	Rupees thousand hundred paise nil only.	315001.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.00	Each	278.00	Rupees two hundred seventy eight and paise nil only.	2780.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	5.39	Per Cubic Metre.	776.00	Rupees Seven hundred seventy six and paise nil only.	4183.00
					Total:	330388.00
	Quoted rates percentage in figure					
	Quoted rates percentage in word					


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work :- Restoration rain damage on Chaillia Neripul Yashwant Nagar Kumarhatti raod km 45/00 to 62/00 (SH:-ROFD Between km 57/920 to 57/960) Under PDNA Balance amount.

Estimated cost: - Rs.1,77,840.00,
Earnest money: - Rs. 4,000.00/-
Time Limit: -One Month

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 130 cum (one hundred thirty) in all cases, @ rupees 300/- only (Rupees Three hundred only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	780.00	Per Cubic Metre.	228.00	Rupees Two hundred twenty eight and paise nil only.	177840.00
					Total:	177840.00

Executive Engineer
Rajgarh Division
KDPWD Rajgarh


SCHEDULE OF QUANTITY

Name of work : - Restoration rain damage on Banethi Bagthan Rajgarh Chandol road km 48/00 to127/300 (SH:-
Construction of PCC Breast walls Between km 82/225 to 82/240) Under PDNA Balance amount

Estimated cost: - Rs.2,24,489,00/-
Earnest money: - Rs.5,000/-
Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	28.35	Per Cubic Metre.	260.00	Rupees Two hundred sixty and paise nil only.	7371.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as par drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	36.14	Per Cubic Metre	5900.00	Rupees Five thousand hundred and paise nil only.	213226.00

<p>Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,</p>	<p>14.00</p>	<p>Each</p>	<p>278.00</p>	<p>Rupees two hundred seventy eight and paise nil only.</p>	<p>3892.00</p>
<p>Quoted rates percentage in figure</p>	<p></p>	<p></p>	<p></p>	<p>Total:</p>	<p>224489.00</p>
<p>Quoted rates percentage in word</p>	<p></p>	<p></p>	<p></p>	<p></p>	<p></p>


 Executive Engineer
 Rajgarh Division
 JSPWD Rajgarh