

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **20-03-2026 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **18-03-2026 to 19-03-2026 up to 4:30 P.M** and the application for issue of tender form shall be received on **18-03-2026 up to 12.00 Noon.**

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	A/R and M/O Darini Khas to Bhaler Road km 0/00 to 5/330.(Under MMSRRY).(S:H:-Repair of Pot Hole / patch work km 2/00 to 3/00)	99,326.00	2,000.00	One Month	350/-
2	A/R and M/O Darini Khas to Bhaler Road km 0/00 to 5/330.(Under MMSRRY).(S:H:-Repair of Pot Hole / patch work km 4/050 to 5/330)	99,113.00	2,000.00	One Month	350/-
3	A/R and M/O Darini Khas to Bhaler Road km 0/00 to 5/330.(Under MMSRRY).(S:H:-Repair of Pot Hole / patch work km 3/030 to 4/010)	99,416.00	2,000.00	One Month	350/-
4	A/R and M/O Charri to Jhikli Ansui km 0/00 to 4/235.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 0/00 to 1/00)	99,549.00	2,000.00	One Month	350/-
5	A/R and M/O Link road from village Har to Village Kuther km 0/00 to 1/500.(Under MMSRRY)(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 0/00 to 0/400)	99,491.00	2,000.00	One Month	350/-
6	A/R and M/O Link road from village Har to Village Kuther km 0/00 to 1/500.(Under MMSRRY)(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 0/500 to 0/900)	98,800.00	2,000.00	One Month	350/-
7	A/R and M/O Link road from village Har to Village Kuther km 0/00 to 1/500.(Under MMSRRY)(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 1/00 to 1/500)	98,542.00	2,000.00	One Month	350/-
8	A/R and M/O Link to village Kiari Chatrer Chamdera km 0/00 to 9/00.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 0/00 to 0/600)	99,641.00	2,000.00	One Month	350/-
9	A/R and M/O Link to village Kiari Chatrer Chamdera km 0/00 to 9/00.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 0/700 to 1/300.)	99,791.00	2,000.00	One Month	350/-
10	A/R and M/O Link to village Kiari Chatrer Chamdera km 0/00 to 9/00.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 1/400 to 2/00.)	99,453.00	2,000.00	One Month	350/-
11	A/R and M/O Link to village Kiari Chatrer Chamdera km 0/00 to 9/00.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 2/100 to 2/700.)	97,623.00	2,000.00	One Month	350/-
12	A/R and M/O Link to village Kiari Chatrer Chamdera km 0/00 to 9/00.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 2/800 to 3/700)	98,316.00	2,000.00	One Month	350/-
13	A/R and M/O Link to village Kiari Chatrer Chamdera km 0/00 to 9/00.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 3/800 to 4/700)	98,822.00	2,000.00	One Month	350/-
14	A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 2/00 to 2/600)	98,336.00	2,000.00	One Month	350/-
15	A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 2/700 to 3/500)	97,979.00	2,000.00	One Month	350/-
16	A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 3/600 to 4/300)	97,484.00	2,000.00	One Month	350/-

17	A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 4/500 to 5/300)	98,993.00	2,000.00	One Month	350/-
18	A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 5/400 to 6/800.)	97,135.00	2,000.00	One Month	350/-
19	A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 7/00 to 8/00)	98,817.00	2,000.00	One Month	350/-
20	A/R and M/O Salli to Khari Behi Road km 0/00 to 9/570.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 0/900 to 2/00)	99,436.00	2,000.00	One Month	350/-
21	A/R and M/O Salli to Khari Behi Road km 0/00 to 9/570.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 2/200 to 3/100)	99,611.00	2,000.00	One Month	350/-
22	A/R and M/O Salli to Khari Behi Road km 0/00 to 9/570.(Under MMSRRY)(S:H:-Repair of Pot Hole / patch work km 3/200 to 4/500)	98,910.00	2,000.00	One Month	350/-
23	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 18/00 to 18/400).	98,904.00	2,000.00	One Month	350/-
24	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 21/00 to 21/500).	98,649.00	2,000.00	One Month	350/-
25	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 23/00 to 24/00).	98,190.00	2,000.00	One Month	350/-
26	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 24/00 to 25/00).	98,461.00	2,000.00	One Month	350/-
27	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 21/500 to 22/00).	98,888.00	2,000.00	One Month	350/-
28	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 18/400 to 19/00).	99,068.00	2,000.00	One Month	350/-
29	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 19/00 to 20/00).	99,232.00	2,000.00	One Month	350/-
30	C/o Jeepable Road with Culvert From Thamba Bridge to Palwala Dispensary Road.(S.H:- C/o 0.90 mtrs span culvert at RD 0/002 Providing and laying 1:3:6 & 1:2.5:5.)	92,732.00	2,000.00	One Month	350/-
31	Restoration of Rain Damage on various road under Sub-Shahpur (S.H:-Providing & Laying WBM G-III on Rait to Kohla road at RD 4/800 to 4/875.	98,730.00	2,000.00	Two Months	350/-
32	C/o Jeepable Road with Culvert From Thamba Bridge to Palwala Dispensary Road.(S.H:- C/o 0.90 mtrs span culvert at RD 0/002 1:4:8 ,Providing and laying 80 mm thick Interlocking Concrete paver block.	94,400.00	2,000.00	One Month	350/-
33	Restoration of Rain Damage on various road under Sub-Shahpur (S.H:-Providing & Laying WBM G-III on Rait to Kohla road at RD 4/950 to 5/025.	98,730.00	2,000.00	Two Months	350/-
34	C/o Jeepable Road with Culvert From Thamba Bridge to Palwala Dispensary Road.(S.H:- C/o 0.90 mtrs span culvert at RD 0/002 Providing and laying 1:2.5:5 ,1:2:4 ,Supplying fitting and placing HYSD & 1:4:8.	85,101.00	2,000.00	One Month	350/-
35	Restoration of Rain Damage on various road under HPPWD Shahpur Sub-Shahpur (S.H:- Hiring of Excavator cum loader for removal of slip under Rait Section.)	99,000.00	2,000.00	One Month	350/-
36	C/o Saddun to Prei road km 0/00 to 1/300 (S.H:- P/L C.C Pavement from RD 0/208.30 to 0/228 Under PDNA.)	97,149.00	2,000.00	Two Months	350/-
37	Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur Distt Kangra H.P. (S.H:-P/F G.S Sheet roofing, cirtain rods ,PVC Water Tank.	99,710.00	2,000.00	Two Months	350/-
38	Restoration of Rain damages on Harnera to Harnera Bag road KM 0/00 to 1/500.(S.H:- C/o Retaining wall at RD 0/792 to 0/979.10.)	99,664.00	2,000.00	Two Months	350/-

39	Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250.(S.H:- C/Ou-Shape Drain at RD 2/360 TO 2/385.)	94,711.00	2,000.00	One Month	350/-
40	Restoration of Rain damages on Harnera to Harnera Bag road KM 0/00 to 1/500.(S.H:- C/o Retaining wall at RD 0/820 to 0/825.10.)	99,314.00	2,000.00	Two Months	350/-
41	Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur . Distt Kangra H.P. (S.H:-P/F G.S Sheet roofing, and Cup board).	98,080.00	2,000.00	Two Months	350/-
42	Restoration of Rain damages on Charri to Bhitlu road KM 0/00 to 5/780.(S.H:- C/o Wire crate wall at RD 4/650 to 4/661.)	99,873.00	2,000.00	Two Months	350/-
43	Restoration of Rain damages on Charri to Ghera road KM 0/00 to 8/555 .(S.H:- C/o RCC Wall at RD 8/398 to 8/399.50).	98,599.00	2,000.00	Two Months	350/-
44	Recovery and Reconstruction On Chambi Bhanala Skou Khas Road km 0/00 to 8/500.(Under PDNA).(S.H:- C/o U-Shape Drain at RD 5/495 to 5/525.	90,796.00	2,000.00	One Month	350/-
45	Restoration of Rain damages on Charri to Ghera road KM 0/00 to 8/555 .(S.H:- C/o RCC Wall at RD 8/396 to 8/397.50.	99,696.00	2,000.00	One Month	350/-
46	C/O Shahpur Majiar road KM 0/00 to 1/500.(S.H:- C/o R /wall at rd 1/174.80 to 1/178.	92,057.00	2,000.00	One Month	350/-
47	Recovery and Reconstruction On Chambi Bhanala Skou Khas Road km 0/00 to 8/500.(Under PDNA).(S.H:- C/o Edge wall and U-Shape Drain at RD 1/900 to 1/913).	91,703.00	2,000.00	One Month	350/-
48	Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800..(S.H:- C/o Wire Crate wall with C.C.Pusta at RD 11/850 to 11/852.50.	98,510.00	2,000.00	Two Months	350/-
49	Recovery and Reconstruction on Shahpur Kiari Chatrer Road km 0/00 to 8/900 (Under PDNA) (SH:- C/o R/wall at RD 8/135 to 8/142.50)	91,413.00	2,000.00	Two Months	350/-
50	Recovery and Reconstruction on Shahpur Kiari Chatrer Road km 0/00 to 8/900 (Under PDNA) (SH:- C/o R/wall at RD 8/161.50 to 8/167)	91,099.00	2,000.00	Two Months	350/-
51	Recovery and Reconstruction on Shahpur Kiari Chatrer Road km 0/00 to 8/900 (Under PDNA) (SH:- C/o R/wall at RD 8/144.50 to 8/152)	91499.00	2,000.00	Two Months	350/-
52	Recovery and Reconstruction on Shahpur Kiari Chatrer Road km 0/00 to 8/900 (Under PDNA) (SH:- C/o R/wall at RD 8/154 to 8/159.50)	91423.00	2,000.00	Two Months	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions:-

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in H.P.P.W.D. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HPPWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

No.PWD/SD/Tender/NIT/2025-26/- 11071 79

Dated: 12/03/2026

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. Notice Board

Executive Engineer
Shahpur Division
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99326.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- A/R and M/O Darini Khas to Bhalor Road km 0/00 to 6/330, (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 2/00 to 3/00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	20363.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	248.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5580.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	248.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	73383.00
TOTAL :-						99326.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99113.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

NAME OF WORK :- A/R and M/O Darini Khas to Bhaler Road km 0/00 to 5/330. (Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 4/050 to 5/330

S. No.	Description of Items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	19035.00	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	251.50	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5659.00	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	251.50	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	74419.00	
TOTAL :-						99113.00	
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)	
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)	


 Executive Engineer,
 Shahpur Division,
 HPPWD Bhalpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99416.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- A/R and M/O Darini Khas to Bhaler Road km 0/00 to 5/330.(Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 3/030 to 4/010

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	6.26	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	14085.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	268.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6030.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	268.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79301.00
TOTAL :-						99416.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99549.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: Two Month

NAME OF WORK :- A/R and M/O Charri to Jhikii Ansui km 0/00 to 4/235.(Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 0/00 to 1/00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size (75mm) seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	1800.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	307.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6908.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	307.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	90841.00
TOTAL :-						99549.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99491.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

NAME OF WORK :- A/R and M/O Link road from village Har to Village Kuther km 0/00 to 1/500 (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 0/00 to 0/400

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3 18	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	7155.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6525.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85871.00
TOTAL :-						99491.00
Quoted Rate in Figure (%)		n	(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		n	(Amount to be quoted by the contractor in words)			

Nity Singh
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98800.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- AIR and M/O Link road from village Har-to Village Kuther km 0/00 to 1/500.(Under MMSRRV)
SUB-HEAD :- Repair of Pot Hole / patch work km 0/500 to 0/900

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3.58	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	8055.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6413.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	84332.00
TOTAL :-						98800.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98542.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

NAME OF WORK :- AVR and M/O Link road from village Har to Village Kuthor km 0/00 to 1/500, (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 1/00 to 1/500

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted (thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4613.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6638.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87291.00
TOTAL :-						98542.00
Quoted Rate in Figure (%)		0	(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		0	(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

7

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99641.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

NAME OF WORK :- A/R and M/O Link to village Kiarl Chattrer Chamdera km 0/00 to 9/00.(Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 0/00 to 0/600

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	4.52	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	10170.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	281.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6323.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	281.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	83148.00
TOTAL :-						99641.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99791.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- AIR and M/O Link to village Kharl Chattrer Chandera km 0/00 to 9/00.(Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 0/700 to 1/300.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6818.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6570.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86403.00
TOTAL :-						99791.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99453.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- A/R and M/O Link to village Kiari Chatter Chamdera km 0/00 to 9/00. (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 1/400 to 2/00.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3.87	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	8708.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6413.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.00	295.90	Rupees Two Hundred Ninely Five And Paise Ninely Only	Per square metre	84332.00
TOTAL :-						99453.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Subhanshu
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97623.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

NAME OF WORK :- A/R and M/O Link to village Klari Chattrer Chamdera km 0/00 to 9/00.(Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 2/100 to2/700.

S. No.	Description of items	Quantity		RATES		Unit	Amount
		In fig	In words	In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] (seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	5 18 00		2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	11655.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503; as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	270.000		22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6075.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	270.000		295.90	Rupees Two Hundred Ninely Five And Paise Ninely Only	Per square metre	79893.00
TOTAL :-							97623.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98316.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

12

NAME OF WORK :- A/R and W/O Link to village Kiari Chatter Chamdera km 0/00 to 9/00. (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 2/800 to 3/700

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size (75mm) seventy five millimeters) compacted thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	4.78	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	10735.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	275.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6188.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	275.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	81373.00
TOTAL :-						98316.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98822.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

18

NAME OF WORK :- A/R and M/O Link to village Klari Chater Chandra km 0/00 to 9/00. (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 3/800 to 4/700

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] (seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	6.42	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	14445.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of ₹ 275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	265.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5963.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ binder content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	265.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	78414.00
TOTAL :-						98822.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98336.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT Two Month

NAME OF WORK :- A/R and M/O Manal Bhandrelia Mawa Road km 0/00 to 8/160,(Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 2/00 to 2/600

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	13005.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	268.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6030.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	268.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79301.00
TOTAL :-						98336.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor In Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor In words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R and M/O Manal Bhandrella Mawa Road km 0/00 to 8/160, (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 2/700 to 3/500

ESTIMATED COST :- ₹ 97979.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT Two Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 5mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	364	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	8190.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	282.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6345.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	282.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	83444.00
TOTAL :-						97979.00
Quoted Rate in Figure (%)		0	(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		0	(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97484.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT Two Month

NAME OF WORK :- A/R and M/O Manai Bhandreliya Mawa Road km 0/00 to 8/160 (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 3/600 to 4/300.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, slope screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eightcun) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORPD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3.42	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	7695.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	282.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6345.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	282.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	83444.00
TOTAL :-						97484.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98993.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

(17)

NAME OF WORK :- A/R and M/O Manai Bhandrella Mawa Road km 0/00 to 8/160. (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 4/500 to 5/300

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6975.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	289.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6503.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer In Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	289.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85575.00
TOTAL :-						98993.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R and M/O Manal Bhandrella Mawa Road km 0/00 to 8/160 (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work km 5/400 to 6/800.

ESTIMATED COST :- ₹ 97135.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT Two Month

18

S No.	Description of items	Quantity	RATES		Unit	Amount
			In/fg	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-II size (75mm) seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, troling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, (applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 018cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	4.68	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	10530.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	272.00	2250	Rupees Twenty Two And Paise Fifty Only	Per square metre	6120.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm thickness composed of 11.2 mm to 0.59 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	272.00	295.90	Rupees Two Hundred Ninely Five And Paise Ninely Only	Per square metre	80485.00
TOTAL :-						97135.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98817.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Month

NAME OF WORK :- A/R and M/O Manai Bhandralia Mawa Road Km 0/00 to 8/160 (Under MMSRRY)
SUB-HEAD :- Repair of Pot Hole / patch work Km 7/00 to 8/00.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-II size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	4.72	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	10620.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	277.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6233.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	277.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	81964.00
TOTAL :-						98817.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor In Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor In words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99436.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- A/R and M/O Salli to Khari Behl Road km 0/00 to 9/570. (Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km 0/900 to 2/00

K S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interspaces of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	83.58	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	8055.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	887.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6458.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @10 binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	287.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	84923.00
TOTAL :-						99436.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shajapur Division,
 HPPWD Shajapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99611.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

21

NAME OF WORK :- A/R and M/O Salli to Khari Behi Road km 0/00 to 9/570.(Under MMSRRY)

SUB-HEAD :- Repair of Pot Hole / patch work km2/200 to 3/100

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.95	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6638.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 Kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6570.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86403.00
TOTAL :-						99611.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98910.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Month

NAME OF WORK :- A/R and M/O Sallit to Khari Bahi Road km 0/00 to 9/570. (Under MMSRRV)
SUB-HEAD :- Repair of Pot Hole / patch work km3/200 to 4/500

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6255.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	291.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6548.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetrating grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	291.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86107.00
TOTAL :-						98910.00
		Quoted Rate in Figure (%)				11
		Quoted Rate in Words (%)				11


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98904.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

23

NAME OF WORK :- A/R and M/O Ranitah 32 mile Kota road km 18/00 to 24/00. (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 18/00 to 18/400).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and travelling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	196.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	27773.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	223.40	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5027.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ the binders content @ 22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	223.40	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	66104.00
TOTAL :-						98904.00
				(Amount to be quoted by the contractor in Figure)		
				(Amount to be quoted by the contractor in Figure)		
				(Amount to be quoted by the contractor in words)		
				(Amount to be quoted by the contractor in words)		


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98649.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

25

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 21/00 to 21/500).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	25.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3543.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	298.70	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6721.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	298.70	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88385.00
TOTAL :-						98649.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shikhpur Division,
 HPPWD Shalpur

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98190.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

(Signature)

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 23/00 to 24/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBPM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and travelling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	27.25	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3861.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	296.26	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6666.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	296.26	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87663.00
TOTAL :-						98190.00

(Signature)
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98461.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

26

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 24/00 to 25/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface/damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	23.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3259.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6728.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5. 11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88474.00
TOTAL :-						98461.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				

N. V. Jaiswal
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98888.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

27

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 21/500 to 22/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	57.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	8077.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.21	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6417.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer In Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.21	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	84394.00
TOTAL :-						98888.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor In Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor In words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99068.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

28

NAME OF WORK :- A/R and M/O Ranikla 32 mile Kotla road km 18/00 to 26/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 19/00 to 20/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	36.50	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	5172.00	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.90	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6635.00	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.90	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87261.00	
TOTAL :-						99068.00	
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)	
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)	

Executive Engineer,
 Shahpur Division,
 APPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99232.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month



NAME OF WORK :- A/R and M/O Rantial 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).
 SUBHEAD :- Repair of Pot Hole / patch work between km 18/400 to 19/00).

Sl. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and travelling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	99.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	14028.00
2	Providing and applying tack coat with Bitumen emulsion (BS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	267.60	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6021.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer In Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	267.60	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79183.00
TOTAL :-						99232.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				

Kunj persh
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

32

ESTIMATED COST :- ₹ 92732.00
 EARNEST MONEY :- ₹ 21000.00
 TIME LIMIT : One Month

NAME OF WORK :- C/o Jeepable Road with Culvert From Thamba Bridge to Palwala Dispensary Road
SUB-HEAD :- Construction of 0.90 Mtrs Span culvert at RD 0/002 Providing and laying 1:3:6 & 1:2:5:5.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.05	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	27169.00
3	Providing and laying concrete mechanically mixed and vibrated PCC M-15(Fifteen) grade 1:2:5:5 in foundation (one cement: two point five sand :five graded stone aggregate 40mm(forty millimeter) nominal size for plain/reinforced concrete in sub structure or similar works complete as per drawings and technical specification clause 802,803,1202 and 1203 and curing complete including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer in charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.00	5550.00	Rupees Five Thousand Five Hundred Fifty Only	Per cubic metre	55500.00
TOTAL :-						92732.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

(Signature)
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(31)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98730.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damage on various roads under Shahpur Sub Division.

SUB-HEAD :- Providing and laying WBM G-III on Rait to Kohla Raod at RD 4/800 to 4/875.

S. No.	Description of items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five-millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government..	43.88	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	98730.00	
		3	4	5	6	7	
TOTAL :-						98730.00	
		(Amount to be quoted by the contractor in Figure)				ra	
		(Amount to be quoted by the contractor in words)				ra	

Yash Jangra
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

32

ESTIMATED COST:- ₹ 94400.00
 EARNEST MONEY :- ₹ 21000.00
 TIME LIMIT : One Month

NAME OF WORK :-

C/o Jeepable Road with Culvert From Thamba Bridge to Palwala Dispensary Road

SUB-HEAD :-

Construction of 0.90 Mtrs Span culvert at RD 0/002 C.C. 1:4:8, Providing and laying 80 mm thick Interlocking Concrete paver block.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	9500.00
2	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	53.25	1200.00	Rupees One Thousand Two Hundred Only	Per Sqm metre	63900.00
3	Provide & Fixing dual direction of reflective speed breaker / double strips plastic high impact resistance plastic body of size 275*150*32 mm having six glass large 12mm dia reflective lance to one side 12nos on both side provided with twp steel zinc plate hails of 12 mm and 120 mm length for fixing to road by hammering CAT/PART no.GPL. 0702 make green and equivalent has per direction by the Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	30	700	Rupees Seven Hundred Only	each	21000
TOTAL :-						94400.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate In Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shajapur

SCHEDULE OF QUANTITY


53

ESTIMATED COST :- ₹ 98730.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damage on various roads under Shahpur Sub Division.

SUB-HEAD :- Providing and laying WBM G-III on Raft to Kohla Raod at RD 4/950 to 5/025.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government..	43.88	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	98730.00
	TOTAL :-					98730.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

34

ESTIMATED COST :- ₹ 85101.00
 EARNEST MONEY :- ₹ 21000.00
 TIME LIMIT : One Month

NAME OF WORK :- C/o Jeepable Road with Culvert From Thamba Bridge to Palwala Dispensary Road

SUB-HEAD :- Construction of 0.90 Mtrs Span culvert at RD 0/002 Providing and laying 1:2.5:5, 1:2:4, Supplying fitting and placing HYSD & 1:4:8.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying concrete mechanically mixed and vibrated PCC M-15(Fifteen) grade 1:2.5:5 in foundation (one cement: two point five sand :five graded stone aggregate 40mm(forty millimeter) nominal size for plain/reinforced concrete in sub structure or similar works complete as per drawings and technical specification clause 802,803,1202 and 1203 and curing complete including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer in charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.14	5550.00	Rupees Five Thousand Five Hundred Fifty Only	Per cubic metre	11877.00
2	Providing and laying mechanically mixed and vibrated concrete for plain concrete in flooring of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.96	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	12054.00
3	Supplying fitting and placing HYSD bar reinforcement in super-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	235.00	95.00		Per kilogram	22325.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	27.03	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	22976.00
5	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. The rate is including per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	7.98	810.00	Rupees Eight Hundred Fifty Only	Per cubic metre	6464.00


35

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF Restoration of Rain damages on various roads under HP.PWD Shahpur Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips under Rait Section.

S. No	Description of Items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	63	4	1100.00	6	Per Hour	99000.00
TOTAL :-							
99000.00							
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					


Executive Engineer,
Shahpur Division,
HPPWD Shahpur

36

SCHEDULE OF QUANTITY

ESTIMATED ₹ 97149.00
 EARNEST ₹ 2000.00
 TIME LIMIT Two Months

NAME OF WORK :- C/o Saddun to Prei road KM 0/00 to 1/300.
 SUB-HEAD :- P/L C.C Pavement from RD 0/208.30 to 0/228. (Under PDVW)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.74	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	76791.00
	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.68	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	20358.00
TOTAL :-						97149.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

N. M. Jaiswal
 Executive Engineer,
 Shahpur Division

SCHEDULE OF QUANTITY

37

ESTIMATED COST :- ₹ 99710.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur . Distt Kangra H.P.
SUB-HEAD :- P/F G.S Sheet roofing, cirtain rods ,PVC Water Tank.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing & fixing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 0.63 mm thick with zinc coating not less than 275 gm/ m ² lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.12	1210.50	Rupees One Thousand Two Hundred Ten And Paise Fifty Only	Per Killograme	18303.00
2	Providing and fixing 25 mm (twenty millimetres) dia stainless steel curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete as per approved shade within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	16.60	450.00	Rupees Four Hundred Fifty Only	Per Running metre	7470.00
3	Providing and fixing wire gauge shutters using galvanized M.S wire gauge of average width of aperture 1.4 mm in both side directions with wire of dia 0.63 mm, for doors, windows and clerestory window with hinges and necessary screws 35 mm thick second class teak wood complete as per approved shade within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	2.15	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per square metre	9138.00
4	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / fascia / soffits / ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per square metre	5250.00
5	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	288.75	105.00	Rupees One Hundred Five Only	Per Killograme	30319.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
6	Providing and placing water tank make P.V.C. SINTEX three layer having capacity of 500 (Five hundred) liters each tank with necessary fittings including over flow pipe scour pipe etcetera and pads required for in let and out let ball valve with cover and locking arrangements complete in all respect within all leads, lifts of materials and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Each	5250.00
7	Making connection of galvanized mild steel distribution branch with galvanized mild steel main 20mm to 40mm (Twenty millimetres to Forty millimetres) nominal bore by providing and fixing tees including cutting and threading the pipe complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	99.50	241.00	Rupees Two Hundred Forty One Only	Per Running metre	23980.00
Total:-						99710.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY




ESTIMATED COST :- ₹ 99664.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain damages on Harnera to Harnera Bag road KM 0/00 to 1/500.

SUB-HEAD :- C/o Retaining wall at RD 0/792 to 0/797.10.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.33	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2216.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.32	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	87020.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.00	350.00	Rupees Three Hundred Fifty Only	Each	5600.00

Sl. No.	Description of Items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1							
2	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.68	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4828.00	
TOTAL :-						99664.00	
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)	
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)	


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 94711.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

59

NAME OF WORK :- Restoration of Rain damages on Shahpur Chakban Lapiana Road KM 0/00 to 20/250.
SUB-HEAD :- C/o U-Shape Drain a RD 2/360 to 2/385.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge. Including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	9.51	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	51164.00
3	Steel work welded in gratings including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	371.20	105.00	Rupees One Hundred Five Only	Per Killogram	38976.00
TOTAL :-						94711.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWP Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99314.00

EARNEST MONEY :- ₹ 2000.00


TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain damages on Harnera to Harnera Bag road KM 0/00 to 1/500.

SUB-HEAD :- C/o Retaining wall at RD 0/820 to 0/825.10.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.33	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2216.00
2	Providing and Laying mechanically mixed and vibrated plain concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.32	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	87020.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.00	350.00	Rupees Three Hundred Fifty Only	Each	5250.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3				
2						
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.68	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4828.00
TOTAL :-						99314.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98080.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Special Repair to Non Residential Building O/O Executive Engineer HPPWD Shahpur : Distt Kangra H.P.
SUB-HEAD :- P/F G.S Sheet roofing, and cup board.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing & fixing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 0.63 mm thick with zinc coating not less than 275 gm/ m ² lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.96	1210.50	Rupees One Thousand Two Hundred Ten And Paise Fifty Only	Per Killogramme	15688.00
2	Repair of Table including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.00	15000.00	Rupees Fifteen Thousand Only	Each	15000.00
3	Providing and fixing cup board shutters with 25 mm thick veneered particle board (IS : 3097 marked, exterior grade (Grade I), of approved make, including lind class teak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of Engineer-in-Charge. With decorative veneering on one side and commercial veneering on other side. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	34.56	1950.00	Rupees One Thousand Nine Hundred Fifty Only	Per square metre	67392.00
Total:-						98080.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

422

ESTIMATED COST :- ₹ 99873.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of Rain damages on Charri to Bhitlu road KM 0/00 to 5/780.
 SUB-HEAD :- Construction of Wire crate wall at RD 4/650 to 4/661.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5950.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.30	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	69225.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	2.30	7050.00	Rupees Seven Thousand Fifty Only	Per cubic metre	16215.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and laying mechanically mixed and vibrated plain cement concrete grade M-15 (M-Fifteen) nominal mix 1:2%:5 (One cement isto Two and half sand isto fiye graded crushed stone aggregate 40mm (Forty millimetres) nominal size) on ground or under water and curing complete including pumping or bailing out water complete for all heights/depths including cost of form work in craddle bedding Type- A as per drawing and MORD technical specification section 800, 900 and 1100 including carriage of materials with in all leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by	1.45	5850.00	Rupees Five Thousand Eight Hundred Fifty Only	Per cubic metre	8483.00
TOTAL :-						99873.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Skahpur Division,
 HPPWD Skahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- * 98599.00
 EARNEST MONEY :- * 2000.00
 TIME LIMIT : : Two Months

NAME OF WORK :- Restoration of Rain damages on Charri to Ghera road Km 0/00 to 8/555.
 SUB-HEAD :- C/o RCC Wall at RD 8/398 to 8/399.50.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.30	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1505.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.16	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	760.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.40	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	52910.00

123

4	Supplying fitting and placing HVSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	440.70	90.50	Rupees Ninety And Paise Fifty Only	Per Kilogram	39883.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MOR.D technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.93	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2491.00
TOTAL :-						98599.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 90796.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Recovery and Reconstruction On Chambi Bhanajia Skou Khas Road km 0/00 to 8/500. (Under PDNA)
 SUB-HEAD :- C/o U-Shape Drain at RD 5/495 to 5/525.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	1 Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	9450.00
2	2 Providing and laying mechanically mixed and vibrated plain concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.12	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	81346.00
TOTAL :-						90796.00
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in figure)
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)

Shahpur
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99696.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain damages on Charri to Ghera road Km 0/00 to 8/555.
 SUB-HEAD :- C/o RCC Wall at RD 8/396 to 8/397.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1547.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.19	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	903.00
3	Providing and Laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.40	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	52910.00

VS

4	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	450.40	90.50	Rupees Ninety And Paise Fifty Only	Per Killogram	40761.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.97	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2525.00
TOTAL :-						99696.00
	Quoted Rate in Figure (%)	h		(Amount to be quoted by the contractor in Figure)		
	Quoted Rate in Words (%)	h		(Amount to be quoted by the contractor in words)		


 Executive Engineer,
 Sakhpur Division,
 HPPWD Shshpur

SCHEDULE OF QUANTITY

47

ESTIMATED COST:- ₹ 91703.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK : Recovery and Reconstruction On Chambi Bhanala Skou Khas Road km 0/00 to 8/500.(Under PDNA)
SUB-HEAD :- C/o Edge wall and U-Shape Drain at RD 1/900 to 1/913.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24.21	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	8474.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.47	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	83229.00
TOTAL :-						91703.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

(Signature)
 Executive Engineer,
 Sijhpur Division,
 P.P.P.W.D. Shahpur.

SCHEDULE OF QUANTITY

128

Ser no - 383


128

ESTIMATED COST :- ₹ 98510.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages in Chambli to Dharamshala road (MDR) Km 0/00 to 12/800.

SUB-HEAD :- C/o Wire Crate wall with C.C.Pusta at RD 11/850 to 11/852.50. (Under PDNA)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and 35 per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.10	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1785.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete Grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34970.00
3	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.90	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	61755.00
TOTAL :-						98510.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shajpur Division,
 HPPWD Shajpur

SCHEDULE OF QUANTITY

~~74~~ 119

Sms - 370

ESTIMATED COST :- ₹ 91413.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Recovery and Reconstruction on Shahpur Kari Chatter Road Km 0/00 to 8/900 (Under PDNA)

SUB-HEAD :- C/o R/Wall at RD 8/135 to 8/142.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3675.00
2	Proving and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 200, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 150 five sand 150 ten graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / breast wall etcetera including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80525.00
3	Providing and laying 150mm (one Hundred millimetres) dia P.V.C pipe weep holes in brick masonry/stone masonry, stone / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V)/20(H)(One Vertical / Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.00	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5100.00
TOTAL :-						91413.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Handwritten signature

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 91099.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT : Two Months

50

NAME OF WORK :- Recovery and Reconstruction on Shahpur Kiarl Chattrer Road Km 0/00 to 8/900 (Under PDNA)

SUB-HEAD :- C/o R/Wall at RD 8/161.50 8/167.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3675.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1.5:1.0 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80538.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.63	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4786.00
TOTAL :-						91099.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				




 Executive Engineer,
 Shahpur Division,
 HPPWD Shikhar

SCHEDULE OF QUANTITY

51

Smo-34

ESTIMATED COST :- ₹ 57,43,00
 EARNEST MONEY :- ₹ 2000,00
 TIME LIMIT :- Two Months

NAME OF WORK :- Recovery and Reconstruction on Shahpur Kari Chater Road Km 0/00 to 8/900 (Under PDNA)

SUB-HEAD :- C/o R/Wall at RD 8/144.50 to 8/152.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressings of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3675.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80500.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H):(One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.63	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4786.00
TOTAL :-						91449.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				



HSE
 Executive Engineer,
 Shahpur Division,
 HPPWD Shikhar

SCHEDULE OF QUANTITY

67

86 no - 348

ESTIMATED COST:- ₹ 91423.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

52

NAME OF WORK :- Recovery and Reconstruction on Shajpur Kari Chatter Road Km 0/00 to 8/900 (Under PDNA)
 SUB-HEAD :- C/o R/Wall at RD 8/154 to 8/159.50.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3675.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten Graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80538.00
3	Providing and Laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.60	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4760.00
TOTAL :-						91423.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				




 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur