

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **13-03-2026 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **12-03-2026 up to 4:00 P.M** and the application for issue of tender form shall be received on **11-03-2026 up to 12.00 Noon.**

The earnest money in the shape of NSC/FDR/Saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 2/00 to 3/00.	97,392.00	2,000.00	One Month	350/-
2	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 3/00 to 4/00.	98,254.00	2,000.00	One Month	350/-
3	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 4/00 to 5/00.	96,440.00	2,000.00	One Month	350/-
4	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 6/00 to 7/00.	97,830.00	2,000.00	One Month	350/-
5	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 0/00 to 1/00.	95,406.00	2,000.00	One Month	350/-
6	A/R and M/O Shahpur Kiari Chattrer Road km 0/000 to 9/00. (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 0/00 to 1/00.	98,663.00	2,000.00	One Month	350/-
7	Land Mitigation on Blehar to Duli road Road KM 0/00 to 5/300.(S:H:-Clearing and Grubbing road Lnad ,C/o Earthen shoulder and Maintenance drain between KM 0/00 to 2/100.)	99,676.00	2,000.00	One Month	350/-
8	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 5/00 to 6/00.	98,690.00	2,000.00	One Month	350/-
9	Restoration to Rain Damages on Kutharana to Kareri road KM 0/000 to 8/720.(S.H:- Clearing and Grubbing road Lnad ,C/o Earthen shoulder and Maintenance drain between KM 0/00 to 2/100.)	99,676.00	2,000.00	One Month	350/-
10	Land Mitigation on Blehar to Duli road Road KM 0/00 to 5/300.(S:H:-Clearing and Grubbing road Lnad ,C/o Earthen shoulder and Maintenance drain between KM 2/300 to 4/300	99,296.00	2,000.00	One Month	350/-
11	A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 1/00 to 2/00.	96,429.00	2,000.00	One Month	350/-
12	Restoration to Rain Damages on Harnera to Badanj Tatwani road KM 0/000 to 9/00.(S.H:- Hiring of Excavator cum loader for removal od slips at RD 7/200 to 7/300.	99,000.00	2,000.00	One Month	350/-
13	Land Mitigation on Blehar to Duli road Road KM 0/00 to 5/300.(S:H:-Removal of slips at various Rds).	99,325.00	2,000.00	One Month	350/-
14	Land Mitigation on Rulehar to Lam road Road KM 0/00 to 4/00.(S:H:-Removal of slips at various Rds).	99,325.00	2,000.00	One Month	350/-
15	A/R and M/O Shahpur Kiari Chattrer Road km 0/000 to 9/00. (Under MMSRRY 2025-26).(S:H:-Repair of Pot Hole / patch work between km 1/00 to 2/00.	96,802.00	2,000.00	One Month	350/-
16	A/R and M/O Chambi to Dharamshala road km 0/00 to 12/800 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/00 to 3/00.	96,612.00	2,000.00	One Month	350/-

17	Recovery and Reconstruction On Chambi Bhanala Skou Khas Road km 0/00 to 8/500 (SH C/o U-Shape Drain at RD 3/885 to 3/915).	90,796.00	2,000.00	One Month	350/-
18	A/R and M/O Chambi to Dharamshala road km 0/00 to 12/800 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 7/00 to 8/00)..	97,025.00	2,000.00	One Month	350/-
19	Restoration of damages on Darini to Jhanyana km 0/00 to 2/00. (SH:-Hiring of Excavator cum loader for removal of slips at various RD).	99,000.00	2,000.00	One Month	350/-
20	A/R and M/O Chambi to Dharamshala road km 0/00 to 12/800 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 3/00 to 4/00.	97,217.00	2,000.00	One Month	350/-
21	Recovery and Reconstruction On Chambi Bhanala Skou Khas Road km 0/00 to 8/500 (SH C/o R/Wall at 2/105 to 2/112.50.)	92,866.00	2,000.00	One Month	350/-
22	Restoration to Rain Damages on Harnera to Badanaj Tatwani road KM 0/000 to 9/00.(S.H:- Hiring of Excavator cum loader for removal of slips at RD 4/800 to 5/300	99,000.00	2,000.00	One Month	350/-
23	A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900.(Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 0/00 to 0/400.	97,598.00	2,000.00	One Month	350/-
24	A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900.(Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 0/500 to 0/900.	99,486.00	2,000.00	One Month	350/-
25	A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900.(Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/00 to 1/400.	99,703.00	2,000.00	One Month	350/-
26	A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900.(Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/500 to 1/900	99,936.00	2,000.00	One Month	350/-
27	A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900.(Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/00 to 2/400	99,673.00	2,000.00	One Month	350/-
28	A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900.(Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/500 to 2/900.	99,808.00	2,000.00	One Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 05/03/2026

No.PWD/SD/Tender/NIT/2025-26/- 10676 to 84

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. Notice Board


Executive Engineer
Shahpur Division
HP.PWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97392.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Shahpur Chakhan Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 2/00 to 3/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	1.95	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4388.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.10	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6572.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of M1SS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.10	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86432.00
TOTAL :-						97392.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R and M/O Shahpur Chakkan Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 3/00 to 4/00.

ESTIMATED COST :- ₹ 98254.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted (thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.05	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4613.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.10	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6617.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.10	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87024.00
TOTAL :-						98254.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

2

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96440.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Shahpur Chakhan Lapiyana road km 0/00 to 20/250. (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 4/00 to 5/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] (seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6750.00	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.40	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6489.00	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.40	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85338.00	
		TOTAL :-					96440.00
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)	
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)	

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

3

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97830.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Shahpur Chakban Lapiyana road km 0/00 to 20/250. (Under NMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 6/00 to 7/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORO technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	3.05	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6863.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.70	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6428.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.70	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	84539.00
TOTAL :-						97830.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 95406.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT One Month

NAME OF WORK :- A/R and M/O Shahpur Chakhan Lappiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26) .
SUB-HEAD :- Repair of Pot Hole / patch work between km 0/00 to 1/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter) twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum/zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6527.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.10	2250.00	Rupees Twenty Two And Paise Fifty Only	Per square metre	85841.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ the binders content @ 22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.10	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85841.00
TOTAL :-						95406.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98663.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: One Month

NAME OF WORK :- A/R and M/O Shahpur Klari Chattror Road km 0/000 to 9/00. (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 0/00 to 1/00.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size (75mm) sevenly (five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of course aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	4.10	Ruppes Two Thousand Two Hundred Fifty Only	Per cubic metre	9225.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	280.90	22.50	Ruppes Twenty Two And Paise Fifty Only	Per square metre	6320.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-0 mm (Type-A) @0.2704 kg/por ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 g/mcc to required the, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	280.90	295.90	Ruppes Two Hundred Ninety Five And Paise Ninety Only	Per square metre	83118.00
TOTAL :-						90663.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- 99676.00
 EARNEST MONEY :- 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Land Mitigation on Blehar to Dull Road km 0/00 to 5/300.

SUB-HEAD :- Clearing and grubbing road land, C/O Earthen shoulder and Maintenance drain Between Km 0/000 to 2/100.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unservicable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidents	0.59	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	13240.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.	3360.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Square	24696.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.	2100.000	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running Metre	61740.00
TOTAL :-						99676.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.

8

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98690.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Shahpur Chakkan Lapiyana road km 0/00 to 20/250. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 5/00 to 6/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted (thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6863.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.40	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6489.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.40	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85338.00
TOTAL :-						98690.00
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				

Shahpur
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99676.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Restoration to Rain Damages on Kutharana to Kereri Road km 0/00 to 8/720.

SUB-HEAD :- Clearing and Grubbing road land, C/O Earthen shoulder and Maintenance drain Between Km 0/00 to 2/100..

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidenta	0.59	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hecter	13240.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.	3360.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Square metres	24696.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.	2100.000	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running Metre	61740.00
TOTAL :-						99676.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99296.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT:- One Months

NAME OF WORK :- Land Mitigation on Blehar to Duli Road km 0/00 to 5/300.

SUB-HEAD :- Clearing and Grubbing road land, C/O Earthen shoulder and Maintenance drain Between Km 2/300 to 4/300.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidents	0.56	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	12566.00	
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.	3800.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Square metres	27930.00	
3	Construction of unlined/surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.	2000.000	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running Metre	58800.00	
TOTAL :-						99296.00	
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)	
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)	



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96429.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- AIR and MIO Shahpur Chakhan Lapiyana road km 0/00 to 20/250 . (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 1/00 to 2/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted (thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3488.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	291.90	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6568.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	291.90	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86373.00
TOTAL :-						96429.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

(12)

NAME OF Restoration of Rain damages on Harnera Badarij Tatwani Road KM 0/00 to 9/00.

SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at RD 7/200 to 7/300.

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- 99325.00
 EARNEST MONEY :- 2000.00
 TIME LIMIT :- One Months

NAME OF WORK :- Land Mitigation on Blehar to Duli Road km 0/00 to 5/300.
SUB-HEAD :- Removal of Slips at Various RDS.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a lift up to 1.5 (one point five) metre and land upto 1000 (one thousand)meter as per technical specification 302 3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate includes octroi/royalty,Malkana,Tol tax, sale tax, GST or any other taxes imposed by the Government.	725.00	137.00	Rupees One Hundred Thirty Seven And Paise Fifteen Only	Per Cubic metre	99325.00
TOTAL :-						99325.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor In Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Bhabpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- 99325.00
 EARNEST MONEY :- 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Land Mitigation on Rulehar to Lam road km 0/00 to 4/00.

SUB-HEAD :- Removal of Slips at Various RDS.

Sr. No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a lift up to 1.5 (one point five) metre and land upto 1000 (one thousand) meter as per technical specification 302.3.5 and 1611 (one hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, sale tax, GST or any other taxes imposed by the Government.	725.00	137.00	Rupess One Hundred Thirty Seven And Paise Fifteen Only	Per Cubic metre	99325.00	
		TOTAL :-				99325.00	
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					


 Executive Engineer,
 Shyampur Division,
 HPPWD Shyampur.

(14)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96802.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Shahpur Kiarl Chattrer Road km 0/000 to 9/000. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 1/000 to 2/000.

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	2205.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	297.10	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6685.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	297.10	295.90	Rupees Two Hundred Ninely Five And Paise Ninely Only	Per square metre	87912.00
TOTAL :-						96802.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- 96612.00
 EARNEST MONEY :- 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Chambl to Dharamshala road km 0/00 to 12/800 . (Under MMSRRY 2025-26)

SUB-HEAD :- Repair of Pot Hole / patch work between km 2/00 to 3/00.

S No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250 00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	12713.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	263.50	22 50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5929.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	263.50	295 90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	77970.00
TOTAL :-						96612.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

16

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 90796.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Months

NAME OF WORK :- Recovery and Reconstruction On Chambi Bhanjala Skou Khas Road km 0/00 to 8/500. (Under PDNA)
 SUB-HEAD :- C/o U-Shape Drain at RD 3/885 to 3/915.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	9450.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.12	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	81346.00
TOTAL :-						90796.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.


19

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97025.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Chambl to Dharamshala road km 0/00 to 12/800 . (Under MMSRRY-2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 7/00 to 8/00.

S No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	12713.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	264.80	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5958.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	264.80	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	78354.00
TOTAL :-						97025.00
Quoted Rate In Figure (%)		F	(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		W	(Amount to be quoted by the contractor in words)			


 Executive Engineer
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT One Month

NAME OF Restoration of Rain damages on Darini to Jhaniyana KM 0/00 to 2/00.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various RD.

S No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

(Signature)
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

19

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97217.00
 EARNEST MONEY :- ₹ 20000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and W/O Chambl to Dharamshala road km 0/00 to 12/800 . (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 3/00 to 4/00.

S No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] (seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2290.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	12713.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	265.40	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5972.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 28 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	265.40	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	78532.00
TOTAL :-						97217.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 92866.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

21

NAME OF WORK :- Recovery and Reconstruction On Chambl Bhanala Skou Khas Road km 0/00 to 8/500 (Under PDNA)
 SUB-HEAD :- C/o R/wall at RD 2/105 TO 2/112.50.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earthwork in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.15	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4253.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto four sand isto eight/graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.55	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	83363.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.00	350.00	Rupees Three Hundred Fifty Only	Each	5250.00
TOTAL :-						92866.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD/Shahpur.

SCHEDULE OF QUANTITY

22

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Restoration of Rain damages on Harnera Badanji Tatwani Road KM 0/00 to 9/00.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at RD 4/800 to 5/300.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97598.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT One Month

NAME OF WORK :- A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900, (Under MMSRRY 2025-26),
SUB-HEAD :- Repair of Pot Hole / patch work between km 0/00 to 0/400.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the intersices of coarse aggregate, watering and compacting to the required density as per MORO technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	2205.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 Kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.60	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6741.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.60	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88652.00
TOTAL :-						97598.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99486.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: - One Month

NAME OF WORK :- A/R and M/O Odde to Lanjhani Road km 0/000 to 2/900 (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 0/500 to 0/900.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two pointfour millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound macadam Specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stonescreening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	2295.00
2	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	305.25	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6868.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @. 2704 kg/per ten square meter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including alsleads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	305.25	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	90323.00
TOTAL :-						99486.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99703.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT One Month

NAME OF WORK :- A/R and M/O Oder to Lanjhani Road Km 0/000 to 2/900 (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between Km 1/00 to 1/400.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) grading-III size (75mm) seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.18	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	2655.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause #03, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	304.80	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6858.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ 1e binders content @ 22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	304.80	295.90	Rupees Two Hundred Ninely Five And Paise Ninely Only	Per square metre	90190.00
TOTAL :-						99703.00
		Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)		
		Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)		


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99936.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT One Month

NAME OF WORK :- A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900, (Under MMSRRY 2025-26)
SUB-HEAD :- Repair of Pot Hole / patch work between km 1/500 to 1/900.

S No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORO technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250 00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	2745 00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	305.25	22 50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6868 00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	305.25	295 90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	90323.00
TOTAL :-						99936.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shajpur Division,
 HPPWD Shajpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99673.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900. (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 2/00 to 2/400.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm] seventy five millimeters) compacted [thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3038.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	303.50	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6829.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	303.50	295.90	Rupees Two Hundred Ninely Five And Paise Ninely Only	Per square metre	89806.00
TOTAL :-						99673.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahnur Division,
 HPPWD Shahnur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99808.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT One Month

NAME OF WORK :- A/R and M/O Oder to Lanjhani Road km 0/000 to 2/900. (Under MMSRRY 2025-26)

SUB-HEAD :- Repair of Pot Hole / patch work between km 2/500 to 2/900.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3555.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 603, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	302.30	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6802.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten squaremeter aggregates using penetration grade bitumen @the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	302.30	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	89451.00
TOTAL :-						99808.00
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur