

**Himachal Pradesh  
Public Works Department**

**NO/PW/SNG/CB/E-16/Tender/25-26-9211-35**

**Dated: - 11-03-2026**

To

The Executive Engineer (IT Cell),  
Nigam Vihar, H.P. Shimla-2.  
[cc-pwd-hp@nic.in](mailto:cc-pwd-hp@nic.in)


**Subject: -Publication of Tender Notice.**

Sir,

Enclosed please find herewith notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt of Himachal Pradesh Letter No. No. PWD-B-A0(3)/8/2025-300858 Dated: Shimla-2 the Notification 13<sup>th</sup> Nov., 2025 as the works mentioned in the tender Notice are urgent nature and public interest.

**Encl: -NIT and Schedule of Quantity**

Yours faithfully,

  
Executive Engineer  
Sangrah Division  
HPPWD Sangrah

**Copy forwarded to the following for information and necessary action :-**

1. The Engineer –in- Chief, , HPPWD Shimla-2 please.
2. The Chief Engineer (SZ), HPPWD Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. Sirmour at Nahan Please.
4. The SDM Sangrah please.
5. The Superintending Engineer, 12<sup>th</sup> Circle HPPWD Nahan please.
6. The BDO Sangrah please.
7. All the Assistant Engineers under this division to display on their respective Notice Boards.
8. The Notice Board.

  
Executive Engineer  
Sangrah Division  
HPPWD Sangrah

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
SHORT TERM NOTICE INVITING TENDERS**

Sealed **percentage rate tenders** on from 6 & 8 are hereby invited by the Executive Engineer, Sangrah Division, HP.PWD. Sangrah on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

**Tender Schedule:-**

**Date and time of receipt of application for tender form-18.03.2026 up to 04:00 PM**

**Date and time of issue/Sale of tender form-20.03.2026 up to 12:00 Noon**

**Date and time of receipt of tender form-20.03.2026 up to 02:30 PM**

**Date and time of opening tender form-20.03.2026 at 03:00 PM**

The tender form can be had from the office of the Executive Engineer against Cash (**Non-refundable**). The earnest money should be in the shape of **Fixed Deposit** duly **pledged in favour of the Executive Engineer Sangrah Division HPPWD Sangrah** must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for 75 days. **The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.**

Sr. No.	Name of work	Estimated cost in Rs.	EMD in Rs.	Cost of Tender	Time Allowed	Class of Contractor
1.	Restoration of Rain Damages on Nohradhar Devamanal Bharari punnerdhar Road km. 0/00 to 18/390 (SH:- C/O PCC Edge wall from RD. 7/865 to 7/945 and P/L WBM GSB and G-II from km. 7/865 to 7/945 and PCC V-shaped drain from km. 7/875 to 7/935 in damaged portion) Under PDNA 2023	4,78,829	9,600/-	Rs. 350/-	02 Months	Class C & D
2.	Restoration of rain damages on Various road under Haripurdhar section HP.PWD., Sub-Division Haripurdhar (SH:- Supplying and stacking of sand at site of work on various road under Haripurdhar Sub-Division).	97,396	2,000/-	Rs. 350/-	02 Months	Class C & D

3.	Restoration of rain damages on Various road under Gattadhar section HP.PWD., Sub-Division Haripurdhar (SH:- Supplying and stacking of sand at site of work on various road under Gattadhar Section).	97,396	2,000/-	Rs. 350/-	02 Months	Class C & D
4.	Restoration of Rain Damage on lik road to village Kajwa km. 0/00 to 2/165 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to 2/165)	96,603	2,000/-	Rs. 350/-	02 Months	Class C & D
5.	Restoration of Rain Damage on Maa Bhangayani to Mourach Kelvi Road km. 0/00 to 9/00 (SH:- Hiring of JCB for Removal of Snow and Slip between km. 0/00 to 9/00)	97,087	2,000/-	Rs. 350/-	02 Months	Class C & D
6.	Restoration of Rain Damage on Kuffer dadar Road km. 0/00 to 7/365 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to 7/365)	96,465	2,000/-	Rs. 350/-	02 Months	Class C & D
7.	Restoration of Rain Damage on link road Ratwa to Kuna via Tholla Jadna Balaina km. 0/00 to 6/500 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to 6/500)	97,060	2,000/-	Rs. 350/-	02 Months	Class C & D
8.	Restoration of Rain Damage on link road to village Gajwa km. 0/00 to 2/555 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to 2/555)	96,499	2,000/-	Rs. 350/-	02 Months	Class C & D
9.	Restoration of Rain Damage on Pullilani Bhalar Bhalona Road km. 0/00 to 16/00 (SH:- Repair of erthen shoulders between km. 0/00 to 14/00)	99,900	2,000/-	Rs. 350/-	02 Months	Class C & D
10.	Restoration of Rain Damage on Maa Bhangayani to Morach Kelvi Road km. 0/00 to 9/00 (SH:- Repair of earthen shoulders between km. 0/00 to 9/00 on essential reaches)	99,900	2,000/-	Rs. 350/-	02 Months	Class C & D
11.	Restoration of Rain Damage on Kuffer Dadar Koli Ka Bag Road km. 0/00 to 7/365 (SH:- Repair of earthen shoulders between km. 0/00 to 7/365 on essential reaches)	99,900	2,000/-	Rs. 350/-	02 Months	Class C & D
12.	Restoration of Rain Damage on Charna Bhawai Sangrah Road km. 0/00 to 14/00 (SH:- Removal of slips in km. 1/700 to 3/700 & 5/00 to 7/500)	94,899	2,000/-	Rs. 350/-	02 Months	Class C & D
13.	Restoration of Rain Damage on Bhatewari to Bhog Road km. 0/00 to 4/00 (SH:- Removal of slips in km. 0/00 to 2/00)	99,412	2,000/-	Rs. 350/-	02 Months	Class C & D

14.	Restoration of Rain Damage on Bhatewari to Bhog Road km. 0/00 to 4/00 (SH:- Removal of slips in km. 2/00 to 4/00)	99,705	2,000/-	Rs. 350/-	02 Months	Class C & D
15.	Restoration of Rain Damage on Bhanra Kadoli to Tontha Shilli Bhangari Choker Road km. 0/00 to 9/00 (SH:- Removal of slips in km. 1/00 to 3/00)	99,119	2,000/-	Rs. 350/-	02 Months	Class C & D
16.	Restoration of Rain Damage on Bhanra Kadoli to Tontha Shilli Bhangari Choker Road km. 0/00 to 9/00 (SH:- Removal of slips in km. 3/00 to 5/00)	91,317	2,000/-	Rs. 350/-	02 Months	Class C & D
17.	Restoration of Rain Damage on Borli Siun Road km. 0/00 to 12/00 (SH:- Hiring of JCB for removal of slip from km. 10/00 to 11/00)	99,750	2,000/-	Rs. 350/-	02 Months	Class C & D
18.	C/O ITI Building at Maina Bag ,Distt. Sirmaur (H.P.)(SH:- Painting of Interior Portion of Building i.e. Corridor from Ground floor to Third floor & in stair case area from Ground floor to Third floor of ITI Building at Maina Bag ).	99,814/-	2,000/-	Rs. 350/-	02 Months	Class C & D
19.	C/O ITI Building at Maina Bag ,Distt. Sirmaur (H.P.)(SH:- Painting of Steel Sufaces at ITI Building at Maina Bag ).	91,429/-	2,000/-	Rs. 350/-	02 Months	Class C & D

**Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.**

**Terms and conditions:-**

**The contractors shall produce their latest registration/ renewal of their registration/ up to date filed GST return form GSTR-3b along with certificate of GST registration as per condition no. 16-iii/ EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.**

2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected.
3. The offer shall remain valid up to **75 days**.
4. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
5. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.
6. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.

7. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.

8. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

9. The provisions of notification issued vide Secretary (PW) to the Govt. of HP. Shimla notification **No. PBW(B)A(3)1/2024 Dated: Shimla-2 the 03.01.2024** shall also be applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No. PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996-38095 dated 13.03.2023.

  
Executive Engineer,  
Sangrah Division,  
HP.PWD; Sangrah

**Copy forwarded for information & necessary action to:-**

1. The Engineer-in-Chief, HP.PWD, Shimla-2 please.
2. The Chief Engineer (SZ) HPPWD Shimla-2 please.
3. The Deputy Commissioner Distt. at Nahan please.
4. The Superintending Engineers 12<sup>th</sup> Circle HPPWD Nahan please.
5. The SDM/BDO, Sangrah please.
6. All the Assistant Engineers under this Division.
7. The Drawing Branch of this office.
8. Notice Board.

  
Executive Engineer,  
Sangrah Division,  
HP.PWD, Sangrah.



Schedule of Quantity		Job No. 1	Estimated Cost:			
Name of Work:- Restoration of Rain Damages on Nohradhar Devamandal Bharari punnerdhar Road km. 0/00 to 18/390 (SH:- C/O PCC Edge wall from RD. 7/865 to 7/945 and P/L WBM GSB and G-II from km. 7/865 to 7/945 and PCC V-shaped drain from km. 7/875 to 7/935 in damaged portion) Under PDNA 2023			Earnest Money:	478829		
			Time Limit:	Two Months		
Sr. No	Description of Item	Net Quantity	Unit	Rate	Amount	
				In Figure		In Words
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and specification clause 802.803, 1202 & 1203(PCC Grade M10 Nominal mix 1:3:6) (One cement : Three sand: Six graded stone aggregate) including all lead, lift and carriage of materials as per the direction of Engineer incharge .	5.25 Cum	Per Cubic meter	5264.00	Rupees. Five Thousand two Hundred sixty four & Paise zero Only	27636
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:4:8 (One Cement : Four Sand: Eight Graded Stone Aggregate ) 40mm (Forty Millimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	52.80 Cum	Per Cubic meter	4789.00	Rupees (Four Thousand seven hundred eighty nine & Paise zero) Only	252859
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of i(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 . including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	50 No's	Each	290.00	Rupees (Two Hundred ninety & Paise zero ) Only	14500
4	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres. including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	268.40 sqm	Per square meter	91.30	Rupees (Ninty One & Paise thirty ) Only	24505
5	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	46.97 Cum	Per Cubic meter	2250.00	Rupees (Two Thousand two hundred fifty & Paise zero) Only	105683

6	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with 3-wheeled static roller 80-100KN static roller in stages to proper grade and camber applying and brooming crushable screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading - II as per technical specification clause 404 . WBM Grading-II including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	20.13	Cum	Per Cubic meter	2665.00	Rupees (Two thousand six hundred sixty five & Paise zero) Only	53646
<b>Total</b>							<b>478829</b>

Quoted rate in figure (+/-) .....

Quoted rate in words (+/-) .....

.....%

  
 Executive Engineer,  
 Sangraha Division,  
 HP.PWD. Sangraha.

Signature of contractor with full address.

**Schedule of Quantity**      **Job No. 2**

Name of work:- Restoration of rain damages on Various road under Haripurdhar section  
 HP.PWD., Sub-Division Haripurdhar (SH:- Supplying and stacking of sand at site of  
 work on various road under Haripurdhar Sub-Division).

Estimated Cost:	97396
Earnest Money:	2,000/-
Time Limit:	Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Supplying and stacking at site of work course sand which should be free from disintegrated/delatarious pieces of material/leaves clays etc. including carriage of material, labour and equipments to various location of site of work through all modes of transportation in all leads, lifts other incidental charges and as per the direction of Engineer-in-charge.	78.00 Cum Per Cum	1248.67	Rupees One thousand Two Hundred Forty Eight Point Sixty Seven	97396.00
<b>Total:-</b>					<b>97396</b>

Quated rate in figure (+/-) .....

Quated rate (+/-) .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.



**Schedule of Quantity**

Job No. **4**

Name of work:- Restoration of Rain Damage on lik road to village Kajwa km. 0/00 to 2/165 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to 2/165)

Estimated Cost:	96603
Earnest Money:	2,000/-
Time Limit:	Two Months

S.No	Description of Item	Unit	Rate		Amount		
			In figure	in words			
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	1130.65	cum	85.44	(Rs. Eight Five & paise forty four)only	96603
<b>Total:-</b>						<b>96603</b>	

Quated rate in figure (+/-) .....

Quated rate .....

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangraha Division,  
 HPPWD Sangraha

**Schedule of Quantity**

Job No. 5

Name of work:- Restoration of Rain Damage on Maa Bhangayani to Mourach Kelvi Road km. 0/00 to 9/00 (SH:- Hiring of JCB for Removal of Snow and Slip between km. 0/00 to 9/00)

		<b>Estimated Cost: 97087</b>		
		<b>Earnest Money: 2,000/-</b>		
		<b>Time Limit: Two Months</b>		
S.No	Description of Item	Unit	Rate	
			In figure	in words
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	85.44	(Rs. Eight Five & paise forty four)only
	<b>Total:-</b>			
				<b>97087</b>

Quated rate in figure (+/-).....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. **6**

Name of work:- Restoration of Rain Damage on Kuffer dadar Road km. 0/00 to 7/365 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to 7/365)

Estimated Cost: 96465

Earnest Money: 2,000/-


Time Limit: Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	85.44	(Rs. Eight Five & paise forty four)only	96465
<b>Total:-</b>					<b>96465</b>

Quated rate in figure (+/-) .....

Quated rate .....

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangraha Division,  
 HPPWD Sangraha.

**Schedule of Quantity**

Job No. **7**

Name of work:- Restoration of Rain Damage on link road Ratwa to Kuna via Tholla Jadna Balaina km. 0/00 to 6/500 (SH:- Hiring of JCB for Removal of slips between km. 0/00 to ~~6/500~~)

Estimated Cost:	97060
Earnest Money:	2,000/-
Time Limit:	Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slops and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	1136.00	(Rs. Eight Five & paise forty four)only	97060
<b>Total:-</b>					<b>97060</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah

**Schedule of Quantity**

Job No. 8

Name of work:- Restoration of Rain Damage on link road to village Gaiwa km. 0/00 to 2/555 (SH:-  
Hiring of JCB for Removal of slips between km. 0/00 to 2/555)

Estimated Cost:	96499
Earnest Money:	2,000/-

Time Limit: Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	85.44	(Rs. Eight Five & paise forty four)only	96499
	<b>Total:-</b>				<b>96499</b>

Quated rate in figure (+/-) .....%)

Quated rate .....%)

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah

**Schedule of Quantity**

Job No. 9

Name of work:- Restoration of Rain Damage on Pullilani Bhalar Bhalarona Road km. 0/00 to 16/00 (SH:-  
Repair of earthen shoulders between km. 0/00 to 14/00)

Estimated Cost: 99900

Earnest Money: 2,000/-


Time Limit: Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Maintenance of Earthen Shoulder (Stripping of excess soil), Stripping excess soil from the shoulder surface to achieve the approval level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 as per the direction of Engineer -in - Charge.	per cum	15.00	(Rs. Fifteen )only	99900
<b>Total:-</b>					<b>99900</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. 10

Name of work: - Restoration of Rain Damage on Maa Bhangayani to Morach Kelvi Road km. 0/00 to 9/00 (SH: - Repair of earthen shoulders between km. 0/00 to 9/00 on essential reaches)


Estimated Cost:	99900
Earnest Money:	2,000/-
Time Limit:	Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Maintenance of Earthen Shoulder (Stripping of excess soil), Stripping excess soil from the shoulder surface to achieve the approval level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 as per the direction of Engineer -in - Charge.	cum per cum	6660.00 15.00	(Rs. Fifteen )only	99900
<b>Total:-</b>					<b>99900</b>

Quoted rate in figure (+/-) .....%

Quoted rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangraha

**Schedule of Quantity**

Job No. 11

Name of work:- Restoration of Rain Damage on Kuffer Dadar Koli Ka Bag Road km. 0/00 to 7/365 (SH:- Repair of earthen shoulders between km. 0/00 to 7/365 on essential reaches)

Estimated Cost: 99900

Earnest Money: 2,000/-

Time Limit: Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Maintenance of Earthen Shoulder (Stripping of excess soil), Stripping excess soil from the shoulder surface to achieve the approval level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 as per the direction of Engineer -in - Charge.	per cum	15.00	(Rs. Fifteen only)	99900
<b>Total:-</b>					<b>99900</b>

Quoted rate in figure (+/-) .....%

Quoted rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. 12


Name of work:- Restoration of Rain Damage on Charana Bhawai Sangraha Road km. 0/00 to 14/00 (SH:-  
Removal of slips in km. 1/700 to 3/700 & 5/00 to 7/500)

		Estimated Cost:	94899		
		Earnest Money:	2,000/-		
		Time Limit:	Two Months		
S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	1110.71 cum per cum	85.44	(Rs. Eight Five & paise forty four)only	94899
<b>Total:-</b>					<b>94899</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangraha Division,  
 HPPWD Sangraha.

**Schedule of Quantity**

Job No. **13**

Name of work:- Restoration of Rain Damage on Bhatewari to Bhog Road km. 0/00 to 4/00 (SH:- Removal of slips in km. 0/00 to 2/00)

Estimated Cost:	99412
Earnest Money:	2,000/-
Time Limit:	Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	1163.53	cum	99412
<b>Total:-</b>					<b>99412</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. 14

Name of work:- Restoration of Rain Damage on Bhatewari to Bhog Road km. 0/00 to 4/00 (SH:-  
Removal of slips in km. 2/00 to 4/00)

Estimated Cost:	99705
Earnest Money:	2,000/-
Time Limit:	Two Months

S.No	Description of Item	Unit	Rate		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	85.44	(Rs. Eight Five & paise forty four)only	99705
<b>Total:-</b>					<b>99705</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. 15

Name of work:- Restoration of Rain Damage on Bhanra Kadoli to Tontha Shilili Bhangari Choker Road  
km. 0/00 to 9/00 (SH:- Removal of slips in km. 1/00 to 3/00)

Estimated Cost:	99119
Earnest Money:	2,000/-

S.No	Description of Item	Unit	Time Limit:		Amount
			In figure	in words	
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slopes and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	per cum	85.44	(Rs. Eight Five & paise forty four)only	99119
<b>Total:-</b>					<b>99119</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. **16**


**Name of work:- Restoration of Rain Damage on Bhanra Kadoli to Tontha Shilli Bhangari Choker Road km. 0/00 to 9/00 (SH:- Removal of slips in km. 3/00 to 5/00)**

		<b>Estimated Cost:</b>	91317			
		<b>Earnest Money:</b>	2,000/-			
		<b>Time Limit:</b>	Two Months			
S.No	Description of Item	Unit	Rate		Amount	
			In figure	in words		
1	Removal of landslide in all kind of soils (including saturated soil, boulder and rocky portion requiring blasting by mechanical means including cutting and trimming of side slops and disposal unserviceable cut material in all leads,lifts as per technical satisfaction clause 302.3.5 and 161.10 including leads,lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	1068.78 cum	per cum	85.44	(Rs. Eight Five & paise forty four)only	91317
<b>Total:-</b>						<b>91317</b>

Quated rate in figure (+/-) .....%

Quated rate .....%

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

Job No. **17**

Name of work:- R/R Damages on Borli Siun Road Km. 0/00 to 12/00(SH:- Hiring of JCB for removal of Slip from Km.10/00 to 11/00)

Estimated Cost:	99750
Earnest Money:	₹,000/-
Time Limit:	Three Months

S.No	Description of Item	Unit	Rate		Amount	
			In figure	in words		
1	Hiring of excavator-cum-loader for removal of land slide, slip clearance including cutting and trimming of slops and disposal of cut materials of all kinds of soil with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. No breakdown will be included in hire charges due to any kind of hinderance. The work shall be executed as per the HP.PWD specifications within all leads, lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	Hrs	per Hour	950.00	(Rs Nine hundred fifty)only	99750
<b>Total:-</b>						<b>99750</b>

Quated rate in figure (+/-) .....

Quated rate .....

Signature of contractor with full address.

  
 Executive Engineer,  
 Sangrah Division,  
 HPPWD Sangrah.

**Schedule of Quantity**

**Job No. 18**

**Name of Work:-C/O ITI Building at Maina Bag ,Distt. Sirmaur (H.P.)(SH:- Painting of Interior Portion of Building i.e Corridor from Ground floor to Third floor & in stair case area from Ground floor to Third floor of ITI Building at Maina Bag ).**

**Estimated Cost: 99,814/-**

**Earnest Money: 2,000/-**

**Time Period: Two Months**

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Finishing walls with Acrylic Smooth interior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface (13.111.1)including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1153.92	Sqrm	86.50	Rupees Eighty six & Paise fifty Only	99814
<b>Total:-</b>						<b>99814</b>

Quated rate in figure (+/-) .....

Signature of contractor with full address.

Quated rate in words (+/-) .....

  
**Executive Engineer,**  
 Sangraha Division,  
 HP.PWD. Sangraha.

**Schedule of Quantity**

Job No. 19

Estimated Cost: 91,429/-

Name of Work:-C/O ITI Building at Maina Bag, Distt. Sirmaur (H.P.)(SH:- Painting of Steel Surfaces at ITI Building at Maina Bag ).

Earnest Money: 1,900/-

Time Period: Two Months

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work(13.99. 1)including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1697.84	Sqm	53.85	Rupees Fifty three & Paise eighty five Only	91429
Total:-						91429

Quated rate in figure (+/-) .....

Signature of contractor with full address.

Quated rate in words (+/-) .....

  
 Parul  
 Executive Engineer,  
 Sangraha Division,  
 HP.PWD. Sangraha.