



Office of the Executive Engineer
Tissa Division, HPPWD Bhanjraru, District Chamba (H.P.)-176316
Himachal Pradesh
Public Works Department

No. PWD-TD/TA/Tender/2025-26- 16407-409

Offline
Dated: 26-02-2026

To


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.

Certificate

Certified that the tenders called vide this office letter No. PWD-TD/TA/Tender /2025-26:- 16307-406 dated. 26-02-2026 is emergent nature due to heavy rain and clouds burst on several places and in Public interest.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"

Sealed Percentage/Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Tissa Division, HPPWD, Tissa behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

Date of issued/sale of tender form against

09-03-2026.

Date of opening of Tender:-

11-03-2026.

The tender shall be received upto 11.00 AM on 11-03-2026, and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against E-Challan as shown below (Nonrefundable) during the working hours on 09-03-2026.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Tissa Division, HPPWD, Tissa a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

Job No.	Name of Work	Estimated cost.	Earnest Money	Time Limit	Cost of Form	Eligible Class
1	Restoration of rain damages on various roads under Nakrot Sub-Division (SH:- Deployment/Hiring of Poclain excavator for removal of slips.	499200.00	10000	Three Month	350	D/C
2	Restoration of rain damages on Link road from Buin to Khakhari Dam site km 0/0 to 4/250. (SH:- Hiring of JCB for removal of slips at various Rd's	497000.00	10000	Three Month	350	D/C
3	Restoration of rain damages on various roads under Nakrot Sub-Division. (SH:- Hiring of JCB for removal of slips at various Rd's	498520.00	10000	Three Month	350	D/C
5	Restoration of rain damages on Tissa Seikothi Jhajjakothi road km 0/0 to 26/0 (SH:- C/o R/wall at Rd 12/330 to 12/339)	499671.00	10000	Three Month	350	D/C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
3. GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.


Executive Engineer
Tissa Division HPPWD
Tissa at Bhanjraru

Dated:- 26-02-2026

No.PW.TD.CB.TA.Tender Notice/2025-26-

16307-406

Copy to the following for information for information please:-

1. Engineer-in-Chief HPPWD Shimla.
2. Chief Engineer(KZ) HPPWD Dharamshala.
3. The Superintending Engineer 7th Circle HPPWD Dalhousie.
4. All Executive Engineers in HPPWD.
5. SDM Tissa.
6. All the Assistant Engineer working under Tissa Division.
7. Tehsildar/BDO Tissa.
8. SHO Tissa.
9. All the contractors.
10. Notice Board.


Executive Engineer
Tissa Division HPPWD
Tissa at Bhanjraru

D.N.I.T.

Name of work:- Restoration of rain damages on various roads under Nakrot Sub-Division (SH:- Deployment/Hiring of Poclain excavator for removal of slips.

Estimated Cost Rs.:= 499200.00
Earnest Money Rs.:= 9984.00
Time Limit = One Months

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of earth cutting/excavating machinery Poclain 140 of 1.5 cubic metre bucket capacity @90 cubic metre per hour loading capacity to be deployment for earth cutting/excavation/filling/removal of slips / boulders and clearance of blocked side drain etc. Any repair/breakage during operation will be carried out by the contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/ removal of slips in all kinds of soil including loading in Tippers/Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge.The rate including the octroi, royalty, Malkana, toll tax, sale tax,GST or any other taxes imposed by the Government.	156.00	3200.00	Rupees Three Thousand Two Hundred Only	Per Hour	499200.00
Total						499200.00

DMR Approval for Rs 499200/-

[Signature]
Executive Engineer
Poclain Division H.P.W.D
ZISSA

D.N.I.T.

Name of work:- Restoration of rain damages on Link road Buiin to Khakhari Dam site km 0//0 to 4/250. (SH:- Deployment/Hiring of Poclain excavator for removal of slips.

Estimated Cost Rs.= 497000.00
Earnest Money Rs.= 9940.00
Time Limit = One Months

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of earth cutting/excavating machinery Poclain 210 of 1.50 cubic metre bucket capacity @90 cubic metre per hour loading capacity to be deployment for earth cutting/excavation/filling/removal of slips / boulders and clearance of blocked side drain etc. Any repair/breakage during operation will be carried out by the contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/ removal of slips in all kinds of soil including loading in Tipppers/Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge.The rate including the octroi, royalty, Malkana, toll tax, sale tax,GST or any other taxes imposed by the Government.	142.00	3500.00	Rupees Three Thousand Five Hundred Only	Per Hour	497000.00
Total						497000.00

Bill approved for Rs 497000/-


Executive Engineer
Division Engineer

D.N.I.T.

Name of work:- Restoration of rain damages on various roads under Nakrol Sub-Division. (SH:-

Estimated Cost Rs.= 498520.00

Earnest Money Rs.= 9970.00

Hiring of JCB for removal of slips at various Rd's

Time Limit = One Months

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	484.00	1030.00	Rupees One Thousand Thirty Only	Per Hour	498520.00
Total						498520.00

DAIR APPROVED FOR Rs 498520 only

[Signature]
Assistant Engineer
Nakrol Division H.P.W.D.
2885A

**Percentage Book
PRICE SCHEDULE**

Name of work: Restoration of rain damages on Tissa Seikohi Hhajakohi road km 0/0 to 26/0 (SIH- C/o R/wall at Rd 12/330 to 12/339)

Sr. No.	Description /Items of work.	Quantity	Unit	Figures	Rate	Amount in	Amount in
					Words	figure	words
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORU technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	50.45	Per Cubic Metre	280.00	Rupees Two Hundred Eighty Only	14126.00	Rupees Fourteen Thousand One Hundred Twenty Six Only
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation for all type of structure such as Retaining walls, Breast walls etc of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten Graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and depths including cost of form work as per drawing and MORU technical specification clause 802,803,1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	92.00	Per Cubic Metre	5100.00	Rupees Five Thousand One Hundred Only	469200.00	Rupees Four Lakh(s) Sixty Nine Thousand Two Hundred Only
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Gov. nment.	28.00	Each	280.00	Rupees Two Hundred Eighty Only	7840.00	Rupees Seven Thousand Eight Hundred Forty Only

Estimated cost- 499671.00
Earnest money- 9993.42
Time limit- Three Month

4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.38 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	11.34	Per Cubic Metre	750.00	Rupees Seven Hundred Fifty Only	8505.00	Rupees Eight Thousand Five Hundred Five Only
					Total:-	499671.00	Rupees Four Lakh(s) Ninety Nine Thousand Six Hundred Seventy One Only
					(To be quoted by Contractor)		
					(To be quoted by Contractor)		
	Quoted Rate in figure (%)						
	Quoted Rate in Words (%)						

Dmit Approved for 499671/-

[Signature]
 Associate Engineer
 District Division
 2132/A