




OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 11302-11 dated 09/03/2026.


Executive Engineer
Jaisinghpur Division
HPPWD., Jaisinghpur.



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095, Telephone No. 01894-228030,
Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **16.03.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **13.03.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **12.03.2026 up to 11:00 AM.** The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Paplah bandahu Odri road Km 0/00 to 6/500 (SH:-C/O R/wall at Rd 5/690 to 5/702)	208274.00	4200.00	Two Month	350/-
2	Restoration of rain Damages on Tinbar Jaisinghpur road Km 0/00 to 18/500 (SH:-C/O R/wall at RD 8/415 to 8/423)	95319.00	2000.00	Two Month	350/-
3	Restoration of rain Damages on various roads under Balakrupi Sub-Division (SH:-C/O Unlined drain and maintenance of earthen Shoulders on various Roads Under Alampur Section))	99932.00	2000.00	Two Month	350/-
4	Restoration of rain Damages on Kutballah to Pantehr road Km 0/00 to 1/660 (SH:-P/L Cement concrete pavement from 1/485 to 1/540 including protection wall adjoining Nalla & 1/075 to 1/100) Under PDNA	499712.00	10000.00	Two Month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 11302-11

Dated: 09/03/2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineers under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Paplah bandahu Odri road Km 0/00 to 6/500 (SH:-C/O R/wall at Rd 5/690 to 5/702)	Estimated cost Rs.	208274.00
	Earnest Money Rs.	4200.00
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25.44	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	5724.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	52.68	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	197550.00

4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	20.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5000.00	
Total						208274.00	
Quoted Rate (in Figures) Percentage						Excess (+)	%
G.Total in Figures						Less (-)	%
G.Total in Words							

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Tinbar Jaisinghpur road Km 0/00 to 18/500 (SH:-C/O R/wall at RD 8/415 to 8/423)	Estimated cost Rs.	95319.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.28	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	2538.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	23.06	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	88781.00

4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4000.00
	Total					95319.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY							
Name of work :-Restoration of rain Damages on various roads under Balakrupi Sub-Division (SH:-C/O Unlined drain and maintenance of earthen Shoulders on various Roads Under Alampur Section))					Estimated cost Rs.		99932.00
					Earnest Money Rs.		2000.00
					Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	622.00	56.00	Rupees Fifty Six Only	Per square metre.	34832.00	
2	Const, of unlined surface drains of average cross sanctioned area 0.40 SQm in soil to specified lines grades level and diamensions, Excavated material to be used in embankment within all leads and lifts as per technical specification clause 307 and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	700.00	93.00	Rupees Ninety Three Only	Per Running metre	65100.00	
Total						99932.00	
Quoted Rate (in Figures) Percentage		Excess (+)			%		
		Less (-)			%		
G.Total in Figures							
G.Total in Words							

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Kutballah to Pantehr road Km 0/00 to 1/660 (SH:-P/L Cement concrete pavement from 1/485 to 1/540 including protection wall adjoining Nalla & 1/075 to 1/100) Under PDNA

Estimated cost Rs.	499712.00
Earnest Money Rs.	10000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.99	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	5173.00

2	<p>Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government</p>	15.47	2050.00	Rupees Two Thousand Fifty Only	Per Cubic Metre	31714.00
3	<p>Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.</p>	54.3	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	230775.00

4	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement thickness as per design and laid over a prepared sub base with 43(forty three) grade cement or any type as per clause 1501 M-30 (M- thirty) grade, design mix cement concrete, coarse and fine aggregates conforming to IS:383(three hundred eighty three), maximum size of coarse aggregate not exceeding 25mm(twenty five millimetre) mixed in a concrete mixer of not less than 0.2 (zero point two) cubic meter capacity and appropriate weight batcher using approved mix design, laid in approved fixed side form work (steel channel), laying and fixing of 125(one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing, spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs using curing compound (where specified) and water, finishing to line and grade as per drawing and M.O.R.D. technical specification clause 1501 as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	30.94	7500.00	Rupees Seven Thousand Five Hundred Only	Per Cubic Metre	232050.00
	Total					499712.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
H.P.WD Jaisinghpur