



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP PWD, Joginder Nagar District Mandi (H P) from the eligible contractors of the appropriate class registered in HP PWD as per revised enlistment rules so as to reach in the office of under signed on **20.03.2026** up to 11 30 A.M. and will be opened on the same day at (12.00 noon) in the presence of intending contractors. The tender application will be received in this office on **18.03.2026** up to 10.00 A.M. to 12.00 P.M. and tender form can be had from this office on **19.03.2026** from 2.00 P.M. to 5.00 P.M. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment. GST Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours


Sr No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1.	Restoration of rain damages on Machhyal Bhararu Bihun road km. 0/0 to 12/00 (SH:- Construction of Breast wall at RD. 5/975 to 5/987.50).	Rs.1,24,867/-	Rs. 2,500/-	Rs. 350/-	Class "D"	Three Months
2.	Construction of New road from main road to Village Sanogi in GP Galu (SH:- Providing and laying Kharanja Soling and Cement Concrete pavement in km. 0/00 to 0/029 under SDP deposit scheme ID: SDP/2020/289).	Rs. 97,177	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
3.	Construction of New road from main road to Village Sanogi in GP Galu (SH:- Providing and laying Kharanja soling and Cement Concrete pavement in km. 0/030 to 0/059 under SDP deposit scheme ID: SDP/2020/289).	Rs. 97,591/-	RS. 2,000/-	Rs. 350/-	Class "D"	Two Months
4.	R/R Damages on link road from Bhala-Ka-Rihra to Harizan Basti Bharola Sainthal km. 0/0 to 2/500. (SH:- Providing and Laying Kharanja Stone Soling & Cement Concrete Pavement at km. 0/631 to 0/656).	Rs. 97,581/-	RS. 2,000/-	Rs. 350/-	Class "D"	Two Months
5.	Restoration of rain damages on Construction & M/T of Ghataani Bhordehar road km. 0/0 to 3/500. (SH:- Construction of 900mm dia RCC hume pipe Culvert at km. 2/800. Job No.I)	Rs. 87,690/-	RS. 1,800/-	Rs. 350/-	Class "D"	Three Months
6.	Restoration of rain damages on Construction & M/T of Ghataani Bhordehar road km. 0/0 to 3/500. (SH:- Construction of 900mm dia RCC hume pipe Culvert at km. 2/800. Job No.II)	Rs. 75,951/-	RS. 1,500/-	Rs. 350/-	Class "D"	Three Months
7.	Restoration of rain Damages on Primary School Sarli to Harizan Basti Nichli Sarli km. 0/00 to 1/0. (SH:- Construction of Wire Crated Breast wall at km. 0/255 to 0/262.50).	Rs. 92,837/-	RS. 1,700/-	Rs. 350/-	Class "D"	Two Months
8.	Restoration of rain Damages on Primary School Sarli to Harizan Basti Nichli Sarli km. 0/00 to 1/0. (SH:- Construction of Wire Crated Breast wall at km. 0/300 to 0/307.50).	Rs. 92,837/-	RS. 1,700/-	Rs. 350/-	Class "D"	Two Months
9.	Restoration of rain damages on Various road under Lad-Bharol, Sub Division HPPWD Lad-Bharol (Tullah Section) (SH:- Hiring of Chain Excavator for removal of Land Slide/Slips i/c all classification of soil and boulders, debris and C/O of road side katcha drain)	Rs. 98,600/-	RS. 2000/-	Rs. 350/-	Class "D"	One Months
10.	Restoration of rain damages on Various road under Lad-Bharol, Sub Division HPPWD Lad-Bharol (Tullah Section) (SH:- Hiring of Chain Excavator for removal of Land Slide/Slips i/c all classification of soil and boulders, debris and C/O of road side katcha drain)	Rs. 98,600/-	RS. 2000/-	Rs. 350/-	Class "D"	One Months
11.	Restoration of rain Damages on Various road under Joginder Nagar Sub Division No.II HP.PWD Joginder Nagar (Ladruhin Section). (SH:- Hiring of Tipper for Shifting and Carriage of various types of materials etc).	Rs. 99,000/-	RS. 2000/-	Rs. 350/-	Class "D"	One Months
12.	Restoration of rain damages Draman Kun Ka Tar road km. 0/0 to 7/225. (SH:- Removal of Slips in various kms. 7/190 to 7/217.50).	Rs. 99,468/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
13.	Restoration of JNSG road km. 0/0 to 3/300. (SH:- Construction of PCC Breast wall at RD. 4/570 to 4/585).	Rs.1,78,724/-	Rs. 3,600/-	Rs. 350/-	Class "D"	Three Months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
3. For on behalf of Governor of Himachal Pradesh the Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
7. The contractor shall be responsible for rectifying defects noticed within six months from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.

9. providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.



Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No PW-JND-B&R-EA-I/NIT/Press/2025-26-

34235-84

Dated - 07/03/26

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Account Branch in this office.
9. Notice Board.
10. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.


Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Job No. 1

Eno. 560

641

Name of work:- Restoration of Rain Damages on Machhyal Bhararu Bihun Road Km 0/0 to 12/0
(SH: Construction of Breast wall at RD 5/975 to 5/987.50)

PERCENTAGE RATE BILL OF QUANTITY

Contact No:

Name of the Bidder/Bidding Firm/Company		Estimated Cost : Rs. 124967.00/- only		Earnest Money Cost : Rs. 2500.00/- only		Time:- Three months	
Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words	
1	2	3	4	5	6	7	
1	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	19.77	Per Cubic metre	6,137.65	1,21,341.00	Rupees One Lakh(s) Twenty One Thousand Three Hundred Forty One Only	
2	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time including GST.	11.00	each	329.65	3,626.00	Rupees Three Thousand Six Hundred Twenty Six Only	
Total				1,24,967.00			

Draft Schedule of Quantity approved for F 124967/- (one Lacs Twenty four Thousand Nine Hundred Sixty seven) only -

641

Executive Engineer,
B&R Division HP.PWD.,
Joginder Nagar.

(Sanogi)

254


Job No. 2

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of New road from main road to Village Sanogi in GP Galu (SH: Providing and laying Kharanja Soling and Cement Concrete pavement in km 0/030 to 0/059 under SDP deposit scheme ID: SDP/2020/289)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	97,591.00 2,000.00 Two Months
				Figures	Words		
				Rs.	P		
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	13.70	Per Cubic metre	1.751.80	Rupees One Thousand Seven Hundred Fifty One And Paise Eighty Only		24,000.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383. maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge The rate is inclusive all taxes levy by the government time to time including GST.	9.14	Per Cubic metre	8.051.50	Rupees Eight Thousand Fifty One And Paise Fifty Only		73,591.00
Total							97,591.00

Draft schedule of quantity approved for ₹ 97591.00/-
(₹ Ninety Seven thousand five hundred ninety one Rupee)


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

E No. 176/25-26

252

Job No. 3

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of New road from main road to Village Sanogi in GP Galu (SH: Providing and laying Kharanja Soling and Cement Concrete pavement in km 0/00 to 0/029 under SDP deposit scheme ID: SDP/2020/289)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: 97,591.00 Earnest Money: 2,000.00 Time Limit : Two Months
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in-Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	13.70	Per Cubic metre	1.751.80	Thousand Seven Hundred Fifty One And Paise Eighty Only	24,000.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	9.14	Per Cubic metre	8,051.50	Rupees Eight Thousand Fifty One And Paise Fifty Only	73,591.00
Total						97,591.00

*Draft schedule of quantity approved for ₹ 97,591.00/-
(Ninety seven thousand five hundred ninety one rupees only)*

~~Executive Engineer~~
B & R Division HP, PWD,
Joginder Nagar

Job No. 4

EoNo - 441

618

DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.		Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Figures	Words	
Name of Work : R/R on link road from Bhala-Ka-Rihra to Harizan Basti Bharola Sainthal km.0/0 to 2/500 under SCSP (Sub Head:- Providing and laying kharanja stone Soling & cement concrete pavement at km 0/631 to 0/656)							
							Estimate Cost: 97,581.00 Earnest Money: 2,000.00 Time Limit : Two Months
1		Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	10.58	Per Cubic metre	2,098.90	Rupees Two Thousand Ninety Eight And Paise Ninety Only	22,206.00
2		Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	9.19	Per Cubic metre	8,201.90	Rupees Eight Thousand Two Hundred One And Paise Ninety Only	75,375.00
		Total					97,581.00

618

Draft Schedule of Quantity approved for F 97,581/-
(Ninety Seven Thousand Five Hundred Eight One) only~~Executive Engineer~~B & R Division HP.PWD,
Joginder Nagar

Job No. 5

6 No. 474

655

DNIT/DRAFT SCHEDULE OF QUANTITY

Work of Work : Restoration of rain damages on Construction & M/T of Ghatasni Bhoradhar road km.0/0 to 3/500
(Site: Construction of 900mm dia RCC hume pipe culvert at Km 2/800.) Job No.-1

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT Rs. P
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	32.90	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	87,690.00 1,800.00 Three Months	21,319.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	0.97	Per cubic metre	6,090.20	Rupees Six Thousand Ninety And Paise Twenty Only		5,907.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	3.35	Per cubic metre	6,505.90	Rupees Six Thousand Five Hundred Five And Paise Ninety Only		21,795.00

4	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	7.50	Per running metre	5,155.90	Rupees Five Thousand One Hundred Fifty Five And Paise Ninety Only	38,669.00
	Total					87,690.00

Draft schedule of quantity approved for 87,690/- (Eighty seven thousand six hundred ninety only)

Executive Engineer

B & R Division HP.PWD,

Joginder Nagar

Job No. 6

E No 475

856

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Construction & M/T of Ghatasni Bhardhar road km.0/0 to 3/500
(Sh:- Construction of 900mm dia RCC hume pipe culvert at Km 2/800.) Job No.-II

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	9.73	Per cubic metre	7,509.75	Rupees Seven Thousand Five Hundred Nine And Paise Seventy Five Only	73,070.00
2	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	0.49	Per cubic metre	5,879.80	Rupees Five Thousand Eight Hundred Seventy Nine And Paise Eighty Only	2,881.00
Total						75,951.00

Draft schedule of quantity approved for ₹ 75,951/-
(Seventy five thousand nine hundred fifty one) only



Executive Engineer

B & R Division HP.PWD,

Joginder Nagar

Job No. 7

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Primary school Sarli to Harizan Bastii Nichli Sarli km.0/0 to 1/0
(SH: Construction of wire crated breast wall at km 0/255 to 0/262.50)

Estimate Cost: 92,837.00
Earnest Money: 1,900.00
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	8.48	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	5,495.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	23.44	Per Cubic metre	3,726.20	Rupees Three Thousand Seven Hundred Twenty Six And Paise Twenty Only	87,342.00
Total						92,837.00

*Draft schedule of quantity approved for
 ₹ 92,837 (Ninety two thousand eight hundred
 thirty seven) only*

Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

636

Job No.8

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Primary school Sarli to Harizan Bastii Nichli Sarli km.0/0 to 1/0 (SH: Construction of wire crated breast wall at km 0/300 to 0/307.50)		Estimate Cost: 1,900.00 Earnest Money: Two Months Time Limit :				
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	8.48	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	5,495.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	23.44	Per Cubic metre	3,726.20	Rupees Three Thousand Seven Hundred Twenty Six And Paise Twenty Only	87,342.00
Total						92,837.00

*Draft schedule of quantity approved for 92837/-
CN Ninety two thousand eight hundred thirty seven only*

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

637

Job No. 9

564

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain damages on various roads under Lad-Bharol Sub division HPPWD Lad Bharol (Tullah Section) (SH:- Hiring of chain excavator for removal of Land Slide/ Slips i/c all Classification of soil and boulders, debris and C/O road side katcha drain) <i>(No 4)</i>		Estimate Cost: 98,600.00	
		Earnest Money: 2,000.00	
		Time Limit : One Month	
Sr. No.	Description of work	Rate	
		Figures	Words
1	Hiring of Hydraulic Chain/ track Excavator JCB-140 having capacity of 0.63 to 0.72 (zero point six three to zero point seven two) cubic meter bucket capacity for haulage, and stacking of boulders on the vally side of the ground in form of boulder pitching to protect earthen slopes i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive all taxes including GST levy by the government time to time.	3,400.00	Rupees Three Thousand Four Hundred Only
Total			98,600.00

Draft Schedule of Quantity approved for ₹- 98,600/- (Ninety Eight, Thous and Six Hundred) only/-

564

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Assistant Engineer
Lad Bharol Sub-Division
HPPWD, Lad-Bharol

Job No. 10

565

DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.		Description of work	No. or Qty.	Unit	Estimate Cost:			
					Earnest Money:			
					Rate	AMOUNT		
					Figures	Words	Rs.	P
1		Hiring of Hydraulic Chain/ track Excavator JCB-140 having capacity of 0.63 to 0.72 (zero point six three to zero point seven two) cubic meter bucket capacity for haulage, and stacking of boulders on the vally side of the ground in form of boulder pitching to protect earthen slopes i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive all taxes including GST levy by the government time to time.	29.00	Per working hour	3,400.00	Rupees Three Thousand Four Hundred Only	98,600.00	
		Total					98,600.00	

Draft Schedule of Quantity approved for Rs. 98,600/-
(Ninety Eight Thousand Six Hundred) only/-

565

~~Assistant Engineer
Lad-Bharol Sub-Division
HPPWD, Lad-Bharol~~

~~Executive Engineer
B & R Division HP.PWD,
Joginder Nagar~~

Job No. 11

6295

Draft Schedule of Quantity

Estimated Cost:- 99000.00
Earnest Money:- 2000.00
Time:- One month

Name of work:- Restoration of Rain damages on various roads under Joginder Nagar Sub Division No.11 HP, PWD Joginder Nagar (Ladruhin Section).
Sub Head:- Hiring of Tipper for shifting and carriage of various types of materials etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/owner of tipper shall bear the-expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00	4500.00	Rupees Four thousand five hundred and paise nil only	Per day	99000.00
					Total:-	99000.00

6295

[Signature]

[Signature]
Assistant Engineer,
B&R Sub Division No.11,
HP.PWD, Joginder Nagar

Draft schedule of quantity approved for ₹ 99000/-
(₹ Ninety nine thousand) only

[Signature]
Executive Engineer
B&R Division, HPPWD
Joginder Nagar (H.P.)

Job No. 12

ENo 396

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Draman Kun Ka Tar road Km.0/0 to 7/225 (Sub Head:- Removal of slips in various km.s 7/190 to 7/217.50)

Estimate Cost: 99,468.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time including GST.	515.38	Per cubic metre	193.00	Rupees One Hundred Ninety Three Only	99,468.00
Total						99,468.00

*Draft schedule of quantity approved for ₹ 99468.00/-
(Ninety eight thousand four hundred sixty eight Rupees)*

595

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

537

Job No. 13

PERCENTAGE RATE BILL OF QUANTITY

Restoration of rain damages
 Name of work:- ~~Construction~~ On JNSG road km 0/0 to 3 1/2/300
 (CH) :- Construction of PCC Breast Wall at RD. 4/570 to 4/585)
 Contact No:

Estimated Cost : Rs. 178724.00/- only
 Earnest Money Cost : Rs. 3600.00/- only
 Time:- Three months

Name of the Bidder/Bidding Firm/Company						
Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	16.35	Per Cubic metre	201.75	3,299.00	Rupees Three Thousand Two Hundred Ninety Nine Only
		3	4	5	6	7

Sr. No. Item Description

Sr. No.	Item Description	Quantity	Unit	Estimated rate with all taxes including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1		3		5	6	7
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	28.20	Per Cubic metre	6,068.80	1,71,140.00	Rupees One Lakh(s) Seventy One Thousand One Hundred Forty Only
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (V): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	13.00	each	329.65	4,285.00	Rupees Four Thousand Two Hundred Eighty Five Only
	Total				1,78,724.00	

*Draft schedule of quantity approved for 178724/-
(i.e. one lac seventy eight thousand seven hundred and twenty four only)*

*Executive Engineer,
B&R Division HP.PWD.,
Joginder Nagar.*