



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

1. Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2026-27- 582-91 dated 25-04-2026.
2. Certified that the works falls under Panchayats areas for which tenders are being called.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur
Himachal Pradesh Works Department Jaisinghpur 176095 Phone No. 01894-228030,
Email ee-jaipwd-hp@gov.in


"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **02.05.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **30.04.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **30.04.2026 up to 11:00 AM.** The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the Earnest Money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:- Providing and fixing crash barrier at damaged Portion)	495776.00	10000.00	Two month	350/-
2	Restoration of rain Damages on Kuru Kelan to Kotlu road Km 0/00 to 1/550 (SH:-C/O Earth filling)	499067.00	10000.00	Two month	350/-
3	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O Crate wall 3rd step and C/O R/wall at Km 19/580 to 19/590 Bye pass road from Jaisinghpur Bazaar)	199546.00	4000.00	Two month	350/-
4	Repair of draman Amb Nee malli road Km 0/00 to 2/500 (SH:- maintenance of Gravel road and C/O Un-lined drain) Deposit VKVNY	249579.00	5000.00	Two month	350/-
5	Restoration of rain Damages on Andretta to Bahroo road Km 0/00 to 1/800 (SH:-C/O R/wall from RD 0/800 to 0/837)	190775.00	3900.00	Two month	350/-
6	A/R & M/O various roads under Sub-Division Panchrukhi Section Panchrukhi (SH:-Painting of boards and writing letters Kms stone etc.)	99994.00	2000.00	Two month	350/-
7	Restoration of rain damages on Tinbar jaisinghpur road Km 0/00 to 18/300 (SH:-Painting writing letters figures, sign boardsm caution boards, Kms stone etc.)	99727.00	2000.00	Two month	350/-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.


Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
On behalf of Governor of Himachal Pradesh)

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineers under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.




SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:- Providing and fixing crash barrier at damaged Portion)

Estimated cost Rs.	495776.00
Earnest Money Rs.	10000.00
Time Limits	Two Month


S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.98	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	2246.00
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (One cement : Two coarse sand : four graded stone aggregate 20mm (Twenty milimetre) nominal size) in foundation and footing including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	9.15	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	56730.00

3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm (Three millimetre) thick corrugated sheet metal beam rail, 70cm (Seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into five millimetre) spaced 2 m (Two metre) centre to centre, 1.8 m (One decimal eight metre) high, 1.1 m (One decimal one metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (One hundred fifty into seventy five into five millimetre), 330 mm (Three hundred thirty millimetre) long complete as per MORTH technical Specification section 800, as direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	104.00	4200.00	Rupees Four Thousand Two Hundred Only	Per Running Metre	436800.00
	Total					495776.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P.W.D Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Kuru Kelan to Kotlu road Km 0/00 to 1/550 (SH:-C/O Earth filling)		Estimated cost Rs.		499067.00		
		Earnest Money Rs.		10000.00		
		Time Limits		Two Month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of all other structures or other source spreading, grading to required slope and compacted in 200 mm (two hundred millimetre) thickness with three wheel 80-100 (Eighty - one Hundred) K.N static weight road roller to meet requirement of table 300.1 and 300.2 as per M.O.R.D. technical specification section 300 and 1600 and as per the direction of Engineer-in-Charge . including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2145.60	232.60	Rupees Two Hundred Thirty Two And Paise Sixty Only	Per cubic Metre	499067.00
	Total					499067.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)				%
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
H.P.WD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O
Crate wall 3rd stepand C/O R/wall at Km 19/580 to 19/590 Bye pass road from Jaisinghpur Bazaar)


Estimated cost Rs. 199546.00

Earnest Money Rs. 4000.00

Time Limits Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	31.68	3100.00	Rupees Three Thousand One Hundred Only	Per cubic metre	98208.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.50	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	95625.00
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00

4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.50	275.00	Rupees Two Hundred Seventy Five Only	Per cubic Metre	3713.00
	Total					199546.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Repair of draman Amb Nee malli road Km 0/00 to 2/500 (SH:-maintenance of Gravel road and C/O Un-lined drain) Deposit VKVNY				Estimated cost Rs.	249579.00	
				Earnest Money Rs.	5000.00	
				Time Limits	Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Const. of unlined surface drains of average cross sanctioned area 0.40 SQm in soil to specified lines grades level and dimensions. Excavated material to be used in embankment within all leads and lifts as per technical specification clause 307 and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	285.00	93.00	Rupees Ninety Three Only	Per Running metre	26505.00
2	Maintenance of gravel road including making up the loss of profile, rectifying corrugated surface, filling up of depressions, pot holes and erosion gullies by ading fresh material and compacting it with appropriate equipment or to strip excess of material from the road surface as per drawing and technical specification Clause 1905 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	918.00	243.00	Rupees Two Hundred Forty Three Only	Per square metre.	223074.00
Total						249579.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Andretta to Bahroo road Km 0/00 to 1/800 (SH-C/O R/wall from RD 0/800 to 0/837)

Estimated cost Rs.	190775.00
Earnest Money Rs.	3900.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.74	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	3992.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	40.45	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	155733.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	27.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	6750.00
4	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the	4.50	5400.00	Rupees Five Thousand Four Hundred Only	Per cubic metre	24300.00
	Total					190775.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
H.P.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O various roads under Sub-Division Panchrukhi Section Panchrukhi (SH:-
Painting of boards and writing letters Kms stone etc.)


Estimated cost Rs. 99994.00

Earnest Money Rs. 2000.00

Time Limits Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Supplying and stacking 1500x900mm (One thousand five hundred into nine hundred) size direction and place identification retro-reflective sign board as per IRC made of 1.5mm (One decimal five millimetre) thick sheeting and supported on 40mm (Forty millimetre) dia pipe painted with red lead primer as per approved drawing and technical specification clause vide clause 1701.2.3 and entire satisfaction / directions of Engineer-in-charge including hauling of materials in all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	3.00	5000.00	Rupees Five Thousand Only	Each	15000.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	68.04	10.00	Rupees Ten Only	Per square metre	680.00
3	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters with enamel paint of approval shade as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	72.09	60.00	Rupees Sixty Only	Per square metre	4325.00

4	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	41020.00	1.95	Rupees One And Paise Ninety Five Only	Per letter per centimetre	79989.00
	Total					99994.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Tinbar jaisinghpur road Km 0/00 to 18/300 (SH:-
Painting writing letters figures, sign boardsm caution boards, Kms stone etc.)

Estimated cost Rs.	99727.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34870.00	1.95	Rupees One And Paise Ninety Five Only	Per letter per centimetre	67997.00
2	Painting two coats (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brusing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering as required as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	190.00	81.00	Rupees Eighty One Only	Per square metre	15390.00
3	Painting two coats (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint of Asian/ Nerolac for use on floors to give an any shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering as required as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	190.00	86.00	Rupees Eighty Six Only	Per square metre	16340.00
Total						99727.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						



Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur